


TRANSPORTATION

DRAFT DESIGN REPORT / ENVIRONMENTAL IMPACT STATEMENT

Appendix F – Traffic Analysis

January 2014

Highway Project
P.I.N. 1721.51
BINs: 1033141 / 1033142
Interstate 87 (I-87) Exit 4 Access
Improvements
Albany County



U.S. Department of Transportation Federal Highway Administration

NEW YORK STATE DEPARTMENT OF TRANSPORTATION
ANDREW M. CUOMO, Governor

JOAN MCDONALD, Commissioner

PROJECT REPORT



Traffic Analysis

Table of Contents

1.0	DESIGN YEAR.....	2
2.0	GROWTH RATES.....	2
3.0	STUDY AREA.....	2
4.0	TRAFFIC DATA	3
4.1	Traffic Speeds	3
4.2	Travel Time & Delays	3
4.3	Traffic Volume Source	4
4.4	Traffic Flow Diagrams.....	5
5.0	TRAFFIC CHANGES DUE TO BUILD ALTERNATIVES	7
5.1	Diamond Alternative	7
5.2	Flyover Alternative.....	8
6.0	TRUCK TRAFFIC.....	9
7.0	ANALYSIS	9
8.0	CALIBRATION	9
8.1	Field Data Collection	10
8.2	Model Calibration	10
9.0	LEVEL OF SERVICE CRITERIA	12
10.0	LEVEL OF SERVICE, TRAVEL TIME AND DELAYS.....	12
10.1	Existing and No-Build	12
10.2	Level of Service for Build Alternatives	27
10.3	Travel Time	49
10.4	Network Delay and Distance Traveled	50
10.5	Ramp Queues	50
11.0	Safety Considerations, Accident History and Analysis.....	53

ATTACHMENT A: Figures
ATTACHMENT B: Traffic Count Data
ATTACHMENT C: Microsimulation Calibration Guidelines
ATTACHMENT D: Level of Service Criteria
ATTACHMENT E: Level of Service Worksheets
ATTACHMENT F: Accident Analysis
ATTACHMENT G: Pedestrian Generator Checklist

Traffic Analysis

The following discussion describes the traffic data used for this project and the methods used to analyze existing and future conditions. The exhibits that are also printed in the main body of the design report follow the design report naming convention. Exhibits unique to this appendix begin with the letter “F”.

1.0 DESIGN YEAR

The following design years are used in accordance with the NYSDOT Project Development Manual Appendix 5:

- Existing (2009)
- Estimated time of completion (ETC) (2016)
- ETC + 10 years (2026)
- ETC + 20 years (2036)
- ETC + 30 years (2046) at intersections adjacent to bridge structures and freeway segment underpasses or overpasses

2.0 GROWTH RATES

Traffic volume projections for the project study area were conducted by the Capital District Transportation Committee (CDTC) using their regional travel demand model. CDTC is the designated Metropolitan Planning Organization (MPO) for the Albany-Schenectady-Troy-Saratoga metropolitan area. The model incorporates existing traffic counts, planned development and transportation projects, and growth projections to estimate future traffic volumes with and without the implementation of this project.

Since the volume projections derived from the regional demand model reflect changes associated with regional land use, demographics and travel, the resulting peak hour volumes do not represent a uniform growth rate applied throughout the project area network. In general, CDTC’s volume projections show little to no growth for the No-Build scenario out to ETC+20. The growth and traffic diversions to the Exit 4 area vary for each of the Build Alternatives.

3.0 STUDY AREA

The traffic study area includes the project limits described in Section 1.2.1 of the design report. Within this study area, the following intersections and freeway facilities are included in the traffic operations evaluations:

Signalized Intersections:

- Central Avenue & Wolf Road
- Wolf Road & Sand Creek Road
- Wolf Road & Metro Park Road
- Wolf Road & I-87 Exit 4 northbound (NB) off-ramp
- Albany-Shaker Road & Wolf Road / I-87 Exit 4 NB on-ramp
- Albany-Shaker Road & Old Wolf Road / I-87 Exit 4 southbound (SB) on-ramp
- Old Wolf Road & I-87 Exit 4 SB off-ramp
- Watervliet-Shaker Road & I-87 Exit 5 SB off- and on-ramps
- Watervliet-Shaker Road & I-87 Exit 5 NB off- and on-ramps / Holly Lane

I-87 (Northway): All freeway segments, ramp junctions and weaves from Exit 2 to Exit 6.

4.0 TRAFFIC DATA

4.1 Traffic Speeds

The posted speed limit on I-87 within the project limits is 55 mph. The posted speed limit on Albany-Shaker Road, Wolf Road, Old Wolf Road, and Watervliet-Shaker Road within the project limits is 40 mph.

Actual operating speeds during the AM and PM peak hours were compiled from data provided by NYSDOT and by information published by NYSDOT Highway Data Services. The average speed and 85th percentile operating speeds (where available) within the study area are provided in Exhibit 2.3.1.5 b.

Exhibit 2.3.1.5 b						
Existing Peak Hour Traffic Speeds (mph)						
Roadway: Segment	Direction	Average		85th Percentile		Source ¹
		AM	PM	AM	PM	
I-87: Exit 2 to Exit 4	NB	57	51	-	-	A
	SB	56	56	-	-	
I-87: Exit 4 to Exit 5	NB	57	45	-	-	A
	SB	56	57	-	-	
I-87: Exit 5 to Exit 6	NB	52	41	-	-	A
	SB	56	56	-	-	
Albany-Shaker Road: Airport to Old Wolf Road	WB ²	30	29	-	-	B
Wolf Road: Metro Park Road to Exit 4 NB off-ramp	NB	34	26	-	-	B
	SB	37	34	-	-	
Old Wolf Road: Exit 4 ramp to Old Niskayuna Road	NB	33	27	43	42	C
	SB	33	23	41	41	
Watervliet-Shaker Road: Exit 5 SB off-ramp to Exit 5 NB ramps	EB	27	23	-	-	B
	WB	35	34	-	-	

¹ Sources of speed data:

- A. Continuous count stations via NYSDOT Region 1
- B. Running speeds from travel time study
- C. NYSDOT Highway Data Services

² Travel times were not measured in the eastbound direction from the Airport.

4.2 Travel Time & Delays

Field travel time data was collected in January 2009 on the study area roadways. Data was collected using the average-car method, where a vehicle is driven along the route traveling with traffic while distance, travel time and delay are recorded. The data collected was used as the basis for microsimulation modeling calibration (see Section 8.0).

Travel time and delay runs were conducted during the AM (7am to 9am) and PM (4pm to 6pm) peak hours. The study area was broken up into segments for the data collection. The sample size was nine to 15 runs in each direction on the local system (Wolf Road, Albany-Shaker Road, Old Wolf Road) and six to eight runs in each direction on I-87. The average travel time and delay collected from this study are summarized in Exhibit 2.3.1.5 a.

Exhibit 2.3.1.5 a Travel Time and Delay Summary				
Roadway: Segment	AM		PM	
	Overall Travel Time (seconds)	Delay (seconds)	Overall Travel Time (seconds)	Delay (seconds)
Northbound				
Wolf Road: Central to Metro Park	185	44	238	73
Wolf Road/ASR: Metro Park to Old Wolf	159	65	335	198
I-87: Sand Creek Overpass to Airport	414	144	403	102
Southbound				
WSR/CD Road/Old Wolf: Exit 5 NB Ramps to ASR	209	69	201	63
ASR/Wolf Rd: Old Wolf to Metro Park	104	18	92	5
Wolf Road: Metro Park to Central Ave	133	72	306	127
I-87: Exit 6 On-Ramp to Airport	206	52	303	35

The cause of the majority of the delay time experienced along the routes was related to traffic signal delay.

4.3 Traffic Volume Source

Existing AM and PM peak hour turning movement volumes were collected at many of the study area intersections in June and July of 2006 and January 2009. Traffic data was collected in years prior for the entire study area. The data collection conducted in 2009 was focused at key intersections in order to provide an update to data collected in 2006. All data collected in 2006 and 2009 was provided to CDTC to be used as a base in their regional demand model. Exhibit F.4.3-1 provides a summary of the data collection locations.

Exhibit F.4.3-1 Traffic Data Collection Locations		
Intersections	2006	2009
Wolf Road & Central Avenue	X	
Wolf Road & Sand Creek Road	X	X
Wolf Road & Metro Park Road	X	
Wolf Road & NB off-ramp	X	X
Albany-Shaker Road & Wolf Road	X	X
Albany-Shaker Road & Old Wolf Road	X	X
Old Wolf Road & Exit 4 SB off-ramp	X	
Watervliet-Shaker Road & Exit 5 SB Ramps		X
Watervliet-Shaker Road & Albany-Shaker Road	X	
Albany-Shaker Road & Airport Access	X	

The raw traffic count data from 2006 and 2009 is provided in Attachment B of this Appendix.

With the data collected as a base, CDTC forecasted volumes for a seasonally adjusted Existing (2009) condition, ETC (2016) No-Build, ETC+10 (2026) No-Build, ETC+20 (2036) No-Build and ETC+30 (2046) No-Build conditions.

4.4 Traffic Flow Diagrams

Exhibit 2.3.1.6 b presents the Existing (2009) traffic volumes for the study roadways. Exhibit F.4.4-1 presents the estimated future No-Build traffic volumes on these roadways for the four design horizons of the project. As shown in the exhibits, there is very little growth projected through the design years under the No-Build condition. The I-87 growth rates vary from 0.0% to 0.3% per year through ETC+30. The growth rates on the local system range from 0.1% to 1.1% per year through ETC+30.

The AM and PM peak hour traffic flow diagrams are presented in Attachment A of this Appendix. The AM and PM peak hours represent the periods of recurring peak hourly flows on the roadway network. The Existing and No-Build turning movement volumes at study intersections are presented on Figures F-1 through F-10. The Existing and No-Build I-87 mainline and ramp volumes are presented on Figures F-11 through F-20. Note that the I-87 and ramp volumes do not balance all the way through the corridor. This was done to maintain the source data provided by CDTC for the freeway segments and ramps.

Exhibit 2.3.1.6 b Existing Traffic Volumes		
Roadway: Segment	Existing (2009)	
	AADT¹	AM Peak PM Peak
I-87: Exit 2 to Exit 4 Northbound	56,700	3000 5100
I-87: Exit 4 to Exit 2 Southbound	56,700	5150 3750
I-87: Exit 4 to Exit 5 Northbound	64,400	2700 5800
I-87: Exit 5 to Exit 4 Southbound	48,900	4400 2500
I-87: Exit 5 to Exit 6 Northbound	66,700	2500 6000
I-87: Exit 6 to Exit 5 Southbound	67,800	6100 3300
Albany-Shaker Rd: West of Old Wolf	26,000	2300 2600
Wolf Rd: South of Exit 4	25,000	1950 2500

(1) AADT is the Average Annual Daily Traffic.

Exhibit F.4.4-1 Forecast No-Build Traffic Volumes								
Roadway: Segment	ETC (2016)		ETC+10 (2026)		ETC+20 (2036)		ETC+30 (2046)	
	AADT ¹	AM Peak	AADT	AM Peak	AADT	AM Peak	AADT	AM Peak
		PM Peak		PM Peak		PM Peak		PM Peak
I-87: Exit 2 to Exit 4 Northbound	56,700	3000 5100	57,200	3000 5150	57,800	3000 5200	58,300	3000 5250
I-87: Exit 4 to Exit 2 Southbound	57,800	5200 3850	58,300	5250 3950	58,900	5300 4100	59,400	5350 4250
I-87: Exit 4 to Exit 5 Northbound	65,600	2750 5900	66,100	2750 5950	66,700	2800 6050	67,200	2850 6050
I-87: Exit 5 to Exit 4 Southbound	48,900	4400 2550	49,400	4450 2600	50,000	4550 2750	50,600	4550 2800
I-87: Exit 5 to Exit 6 Northbound	67,800	2500 6100	68,300	2550 6150	69,400	2600 6250	-	- -
I-87: Exit 6 to Exit 5 Southbound	67,800	6100 3450	67,200	6050 3650	67,200	6050 3800	-	- -
Albany-Shaker Rd: West of Old Wolf	33,000	2450 3300	35,000	2550 3500	37,500	2600 3750	39,500	2800 3950
Wolf Rd: South of Exit 4	20,000	2050 2000	21,000	2000 2100	22,500	2000 2250	-	- -

(1) AADT is the Average Annual Daily Traffic.

5.0 TRAFFIC CHANGES DUE TO BUILD ALTERNATIVES

Two feasible alternatives were evaluated: Diamond Alternative and Flyover Alternative. Refer to Section 3.2 for descriptions of the alternatives. As stated previously, CDTC used their regional demand model to estimate future traffic volumes for the project study area with and without the project alternatives. For the build alternatives, they incorporated the proposed connections and geometry into the roadway network to establish the traffic patterns.

5.1 Diamond Alternative

There are several elements of the Diamond Alternative that will change the existing traffic patterns:

- Existing elements removed
 - Exit 4 SB off-ramp
 - Exit 5 SB on-ramp
 - C-D road between Exits 5 and 4
 - Exit 4 SB on-ramp
 - Exit 4 NB off-ramp
 - Exit 4 NB on-ramp
- New ramp facilities
 - Exit 5 SB on-ramp from Watervliet-Shaker Road (creating a “diamond” configuration with the Exit 5 SB off-ramp)
 - Exit 4 NB and SB on- and off-ramps to a new connector road (creating a new “diamond” interchange)
- New roadway
 - Connector Road from Wolf Road at Metro Park Road to Albany-Shaker Road (crossing over I-87)

All of these modifications to the existing system change the traffic patterns on segments of I-87 and the local roadway system. The addition of the Connector Road and Exit 4 Diamond ramps change patterns on the Exit 2 and Exit 5 ramps, especially for those with Wolf Road origins or destinations.

The AM and PM peak hour traffic flow diagrams are presented in Attachment A of this Appendix. The turning movement volumes at study intersections are presented on Figures F-21 through F-28. The Existing and No-Build I-87 mainline and ramp volumes are presented on Figures F-29 through F-36.

Compared to the No-Build condition, the Diamond Alternative is estimated to divert approximately 400 vehicles in the AM and 1,100 vehicles in the PM to the study area roadways from other roadways. This is a result of better access to the Airport, reduced congestion and shorter duration trips.

Exhibit F.5.1-1 presents the projected ETC (2016), ETC+10 (2026), ETC+20(2036), and ETC+30 (2046) Diamond Alternative traffic volumes for the study area. The Diamond Alternative sustains slight growth on I-87 at 0.5% per year or less.

Exhibit F.5.1-1 Forecast Build Alternative Traffic Volumes Diamond Alternative								
Roadway: Segment	ETC (2016)		ETC+10 (2026)		ETC+20 (2036)		ETC+30 (2046)	
	AADT ¹	AM Peak PM Peak	AADT	AM Peak PM Peak	AADT	AM Peak PM Peak	AADT	AM Peak PM Peak
I-87: Exit 2 to Exit 4 NB	60,000	3300 5400	60,600	3500 5450	61,100	3650 5500	61,100	3650 5500
I-87: Exit 4 to Exit 2 SB	57,800	5200 3850	58,300	5250 3950	58,900	5300 4050	59,400	5350 4050
I-87: Exit 4 to Exit 5 NB	62,800	2500 5650	63,300	2600 5700	63,900	2650 5750	64,400	2650 5800
I-87: Exit 5 to Exit 4 SB	59,400	5350 3650	62,200	5600 3800	65,000	5850 3900	65,000	5850 3900
I-87: Exit 5 to Exit 6 Northbound	63,900	2400 5750	65,600	2550 5900	67,200	2550 6050	-	-
I-87: Exit 6 to Exit 5 Southbound	67,800	6100 3500	68,900	6200 3625	70,000	6300 3750	-	-
Albany-Shaker Rd: West of Old Wolf	18,000	1100 1800	18,500	1250 1850	19,500	1400 1950	20,000	1600 2000
Wolf Rd: South of Exit 4	14,000	900 1400	15,000	950 1500	16,500	1050 1650	-	-

(1) AADT is the Average Annual Daily Traffic.

5.2 Flyover Alternative

There are several elements of the Flyover Alternative that will change the existing traffic patterns:

- Existing elements removed
 - Exit 4 SB off-ramp
 - Exit 5 SB on-ramp
 - C-D road between Exits 5 and 4
 - Exit 4 SB on-ramp
- Existing elements modified
 - Exit 4 NB off-ramp restricted to right-turn only onto Wolf Road SB
- New ramp facilities
 - Exit 4 NB off-ramp to new intersection on Albany-Shaker Road
 - Exit 5 SB on-ramp relocated to north (creates “half-diamond” with SB off-ramp)
 - Exit 4 SB off-ramp to new intersection on Albany-Shaker Road
 - Exit 4 SB on-ramp, accessed from new intersection on Albany-Shaker Road

All of these modifications to the existing system change the traffic patterns on segments of I-87 and the local roadway system. The removal of the C-D road and the Exit 4 SB off-ramp to Old Wolf Road significantly reduces the volumes on Old Wolf Road. Providing ramps to the new intersection on Albany-Shaker Road reduces the number of intersections that vehicles destined for Albany International Airport have to drive through.

The AM and PM peak hour traffic flow diagrams for this alternative are presented in Attachment A of this Appendix. The turning movement volumes at study intersections are presented on Figures F-37 through F-44 and the I-87 mainline and ramp volumes are presented on Figures F-45 through F-52.

Compared to the No-Build condition, the alternative is estimated to divert approximately 100 vehicles in the AM and 900 vehicles in the PM to the study area roadways from other roadways. This is a result of better access to the Airport, reduced congestion and shorter duration trips.

Exhibit F.5.2-1 presents the projected traffic volumes for the Flyover Alternative for each of the project's design-year horizons. The Flyover Alternative sustains slight growth on I-87 at 0.5% per year or less.

Exhibit F.5.2-1 Forecast Build Alternative Traffic Volumes Flyover Alternative								
Roadway: Segment	ETC (2016)		ETC+10 (2026)		ETC+20 (2036)		ETC+30 (2046)	
	AADT ¹	AM Peak PM Peak	AADT	AM Peak PM Peak	AADT	AM Peak PM Peak	AADT	AM Peak PM Peak
I-87: Exit 2 to Exit 4 NB	61,100	3250 5500	62,200	3350 5600	62,800	3500 5650	63,300	3550 5700
I-87: Exit 4 to Exit 2 SB	59,400	5350 3900	60,000	5400 4000	60,600	5450 4150	61,100	5500 4100
I-87: Exit 4 to Exit 5 NB	65,600	2700 5900	66,100	2750 5950	66,100	2800 5950	66,100	2800 5950
I-87: Exit 5 to Exit 4 SB	58,900	5300 3650	62,200	5600 3800	65,000	5850 3900	65,000	5850 3900
I-87: Exit 5 to Exit 6 Northbound	68,300	2550 6150	68,600	2600 6175	68,900	2650 6200	-	-
I-87: Exit 6 to Exit 5 Southbound	66,700	6000 3500	67,800	6100 3650	68,300	6150 3800	-	-
Albany-Shaker Rd: West of Old Wolf	19,000	1800 1900	20,500	2000 2050	22,000	2200 2200	24,500	2300 2450
Wolf Rd: South of Exit 4	18,500	1600 1850	19,000	1700 1900	19,500	1800 1950	20,500	1950 2050

(1) AADT is the Average Annual Daily Traffic.

6.0 TRUCK TRAFFIC

Heavy vehicle (truck) traffic for the study area roadways and intersections was compiled and used in the VISSIM and HCS analyses. Exhibit F.6.0-1 provides a summary of the truck percentages used. Daily truck percentage was not available for Wolf Road.

Exhibit F.6.0-1 Truck Data			
Route	I-87	Albany-Shaker Rd	Wolf Rd
% Peak Hour Trucks	2% AM, 2% PM	3% AM, 2% PM	1% AM, 1% PM
% Daily Trucks	8%	7%	-

7.0 ANALYSIS

A VISSIM microsimulation model was used to analyze the study area roadway network. The model was used to evaluate travel times, intersection delays and overall network delay. The LOS applied to the intersections are based on the criteria set forth in the 2000 Highway Capacity Manual (HCM) published by the Transportation Research Board (TRB). Freeway and ramp junction LOS were evaluated using Highway Capacity Software (HCS). LOS criteria from the HCM are provided in Attachment D of this Appendix.

8.0 CALIBRATION

The Existing condition VISSIM model was calibrated to field conditions in order to provide a base model from which all future No-Build and Build alternative models could be developed. This calibration involved

a program of field samples of applicable observable metrics such as vehicle queuing, volumes and travel times. Model attributes and input variables were developed to replicate operations based on these field conditions.

8.1 Field Data Collection

In January 2009, turning movement traffic counts were conducted at key intersections within the study area to update data that was collected in 2006. Traffic counts were conducted during the weekday morning and evening peak periods of 7 am to 9 am and 4 pm to 6pm. While the turning movement counts were conducted, spot queue length observations were also taken to establish the average and max queue lengths at the intersections.

Travel times through the study area were also collected, as described and presented in Section 4.2. The travel time data collection was broken up between for five different segments of the study area. Times were also recorded at intersections along the route in order to provide the time between intersections and the delay experienced.

Existing roadway and intersection geometry was documented as well as traffic control devices. Traffic signal timing and phasing records were obtained from NYSDOT for the signalized intersections within the project study area.

8.2 Model Calibration

The data collected was used as a basis to calibrate the base model to replicate existing conditions. The field collected volumes, geometry and traffic control devices were input into the model. Travel times were collected from the model for the same limits and segments as was collected in the field.

In order to replicate existing conditions on congested roadways and ramps, driving behavior parameters had to be customized from the standard default values for some parts of the study area. Parameters such as look ahead/back distance, headway time, maximum deceleration, safety distance and waiting time before diffusion were adjusted to replicate the more aggressive driving behaviors in these areas. Speeds were also adjusted to match the existing speeds of vehicles entering and exiting the network. Information from the travel time field samples as well as posted speeds were used to determine appropriate speeds for the network, especially in areas where congestion is experienced outside of the modeled network but results in slowdowns within the modeled network. Speed reductions were used on roadway segments that contain multiple mid-block driveways and/or other traffic signals that were not included in the study. A model seeding interval of 550 seconds was utilized to ensure that the entire network is populated with vehicles prior to the evaluation of the peak hour.

An FHWA publication, *Traffic Analysis Toolbox Volume III: Guidelines for Applying Traffic Microsimulation Modeling Software*, provides some guidance on calibration targets. A summary of these targets is shown in Attachment C. For this model, a target of 10% variation from the field collected travel time for each overall run was used, which is a more refined calibration than the FHWA guidance (15%).

Exhibits F.8.2-1 and F.8.2-2 summarize the comparison between the field collected travel times and the times extracted from the calibrated VISSIM models. As shown, the travel times in the models are all within the 10% variation target from the field collected times.

Exhibit F.8.2-1
VISSIM Calibration Results
AM Peak Travel Time Calibration

Travel Time Segment	Field Time *	Model Time *	% Difference
Northbound			
Wolf Road: Central to Sand Creek	119	114	
Wolf Road: Sand Creek to Metro Park	66	63	
Wolf Road: Central to Metro Park	185	177	-4.6%
Wolf Road: Metro Park to Exit 4 NB Off	63	64	
Wolf Road: Exit 4 NB Off to ASR	57	40	
ASR: Wolf to Old Wolf	39	45	
Wolf Road/ASR: Metro Park to Old Wolf	159	154	-3.4%
I-87: Sand Creek Overpass to Exit 4 NB Off-Ramp	154	180	
Wolf Road: Exit 4 NB Off to ASR	57	40	
ASR: Wolf to Old Wolf	39	45	
ASR: Old Wolf to Airport	116	110	
I-87: Sand Creek Overpass to Airport	414	428	3.4%
Southbound			
WSR: Exit 5 NB Ramps to SB Ramps	39	49	
CD Road: Exit 5 SB Ramps to Old Wolf	83	73	
Old Wolf Road: CD Road to ASR	86	80	
WSR/CD Road/Old Wolf: Exit 5 NB Ramps to ASR	209	208	-0.6%
ASR: Old Wolf to Wolf	22	36	
Wolf Road: ASR to Exit 4 NB Off Ramp	33	17	
Wolf Road: Exit 4 NB Off to Metro Park	49	53	
ASR/Wolf Road: Old Wolf to Metro Park	104	106	1.8%
Wolf Road: Metro Park to Sand Creek	92	95	
Wolf Road: Sand Creek to Central	121	115	
Wolf Road: Metro Park to Central	213	211	-1.0%
I-87/CD Road: Exit 6 to Old Wolf	145	148	
Old Wolf Road: CD Road to ASR	86	80	
ASR: Old Wolf to Airport	122	110	
I-87: Exit 6 On-Ramp to Airport	326	341	4.5%

* Travel Time provided in seconds.

Exhibit F.8.2-2
VISSIM Calibration Results
PM Peak Travel Time Calibration

Travel Time Segment	Field Time *	Model Time *	% Difference
Northbound			
Wolf Road: Central to Sand Creek	148	146	
Wolf Road: Sand Creek to Metro Park	91	86	
Wolf Road: Central to Metro Park	238	232	-2.4%
Wolf Road: Metro Park to Exit 4 NB Off	202	161	
Wolf Road: Exit 4 NB Off to ASR	111	91	
ASR: Wolf to Old Wolf	43	42	
Wolf Road/ASR: Metro Park to Old Wolf	335	311	-7.0%
I-87: Sand Creek Overpass to Exit 4 NB Off-Ramp	154	166	
Wolf Road: Exit 4 NB Off to ASR	111	91	
ASR: Wolf to Old Wolf	43	42	
ASR: Old Wolf to Airport	132	101	
I-87: Sand Creek Overpass to Airport	403	403	-0.1%
Southbound			
WSR: Exit 5 NB Ramps to SB Ramps	53	57	
CD Road: Exit 5 SB Ramps to Old Wolf	76	69	
Old Wolf Road: CD Road to ASR	71	96	
WSR/CD Road/Old Wolf: Exit 5 NB Ramps to ASR	201	211	5.1%
ASR: Old Wolf to Wolf	19	33	
Wolf Road: ASR to Exit 4 NB Off Ramp	18	15	
Wolf Road: Exit 4 NB Off to Metro Park	56	52	
ASR/Wolf Road: Old Wolf to Metro Park	92	99	8.1%
Wolf Road: Metro Park to Sand Creek	125	124	
Wolf Road: Sand Creek to Central	181	180	
Wolf Road: Metro Park to Central	306	305	-0.4%
I-87/CD Road: Exit 6 to Old Wolf	129	144	
Old Wolf Road: CD Road to ASR	71	96	
ASR: Old Wolf to Airport	121	101	
I-87: Exit 6 On-Ramp to Airport	303	328	8.2%

* Travel Time provided in seconds.

9.0 LEVEL OF SERVICE CRITERIA

LOS is presented as a letter from A to F with A representing free flowing, unimpeded traffic with little or no delay and F representing highly congested traffic flow with long delays.

Standard design objectives for urban street systems is to achieve a LOS D on all intersection approaches during peak hours (NYSDOT Highway Design Manual, Chapter 5.9.2). However, it is recognized that there are many competing objectives and considerations, especially in urban areas, that may affect the desirability and feasibility of achieving this goal for peak hours. In these cases, peak-hour LOS E or F may be acceptable.

10.0 LEVEL OF SERVICE, TRAVEL TIME AND DELAYS

10.1 Existing and No-Build

10.1.1 Intersection Level of Service

Summaries of the LOS for the Existing and future No-Build conditions are presented in Exhibits F.10.1.1-1 through F.10.1.1-10. As shown in these analyses, the following study area intersections have one or more movement that experience LOS E or worse during the Existing studied peak hours:

- Central Avenue & Wolf Road (PM)
- Sand Creek Road & Wolf Road (PM)
- Exit 4 NB off-ramp & Wolf Road (AM & PM)
- Albany-Shaker Road & Wolf Road (AM & PM)
- Albany-Shaker Road & Old Wolf Road (AM & PM)
- Old Wolf Road & C-D Road (AM)

The intersections experience higher delay levels during the PM peak hour as volumes are higher on Wolf Road and at the intersections.

Delay is estimated to increase through the ETC+20 design horizon due to background traffic growth. For the ETC+20 No-Build condition, the following study area intersections will experience LOS E or worse for one or more movements during the studied peak hours:

- Central Avenue & Wolf Road (PM)
- Sand Creek Road & Wolf Road (PM)
- Exit 4 NB off-ramp & Wolf Road (AM & PM)
- Albany-Shaker Road & Wolf Road (PM)
- Albany-Shaker Road & Old Wolf Road (AM & PM)
- Old Wolf Road & C-D Road (AM)
- Exit 5 SB Ramps & Watervliet-Shaker Road (PM)

The LOS for some improvements improved at the intersection of Albany-Shaker Road & Wolf Road when comparing Existing to No-Build. This is related to the change in volume distribution at the intersection due to the opening of the final phase of the Wolf Road parallel connector road, which will create a connection from Albany-Shaker Road to Aviation Road.

Exhibit F.10.1.1-1
VISSIM Analysis Results
Intersection Level of Service
2009 Existing AM

Intersection/Approach		Delay *	LOS	Intersection/Approach		Delay *	LOS
Central Avenue & Wolf Road				Albany Shaker Road & Wolf Road			
Central Avenue	EB LL	39.9	D	Albany Shaker Road	EB L	32.2	C
	EB TT	19.5	B		EB TT/R	32.7	C
Central Avenue	WB TTT	38.5	D		EB R	17.2	B
	WB R	7.4	A	Albany Shaker Road	WB L	51.4	D
Exit 2 NB Off-Ramp	NB TTT	40.2	D		WB TT	25.9	C
Wolf Road	SB LL	46.6	D		WB R	5.3	A
	SB RR	5.9	A	Wolf Road	NB L	64.4	E
OVERALL		29.2	C		NB L/TT	41.4	D
					NB R	19.0	B
Sand Creek Road & Wolf Road				OVERALL			
Sand Creek Road	EB L	33.7	C			32.3	C
	EB T	32.6	C	Albany Shaker Road & Old Wolf Road			
	EB R	4.3	A	Albany Shaker Road	EB L	43.2	D
Sand Creek Road	WB L	39.1	D		EB TT	43.6	D
	WB T	37.7	D		EB R	26.9	C
	WB R	6.8	A	Albany Shaker Road	WB L	29.2	C
Wolf Road	NB L	47.4	D		WB TT/R	40.2	D
	NB TT	21.9	C	Old Wolf Road	SB LL/T	56.8	E
	NB R	7.8	A		SB R	49.4	D
Wolf Road	SB L	46.7	D	OVERALL			
	SB TT	21.8	C			44.3	D
	SB R	5.7	A	Old Wolf Road & CD Road			
OVERALL		25.8	C	Site Driveway	EB L/T/R	9.9	A
Metro Park & Wolf Road				CD Road	WB L/T/R	34.7	C
Hess Station	EB L/T/R	26.6	C	Old Wolf Road	NB L/T/R	37.5	D
Metro Park Drive	WB L	36.1	D	Old Wolf Road	SB L/T/R	64.3	E
	WB T/R	8.1	A	OVERALL			
Wolf Road	NB L	3.0	A			39.2	D
	NB TT	3.2	A	Exit 5 SB Ramps & Watervliet Shaker Road			
	NB R	3.7	A	Watervliet Shaker Road	EB L/TT/R	15.4	B
Wolf Road	SB L	9.9	A	Watervliet Shaker Road	WB LT	16.6	B
	SB TT/R	4.5	A	Exit 5 SB Off-Ramp	SB L	24.3	C
					SB T/R	14.5	B
OVERALL		5.7	A	Sherwood Drive	SB L/T/R	24.9	C
Exit 4 NB Off-Ramp & Wolf Road				OVERALL			
Exit 4 NB Off-Ramp	EB LL	76.6	E			17.6	B
	EB R	31.4	C	Exit 5 NB Ramps & Watervliet Shaker Road			
Wolf Road	NB TTT	11.7	B	Watervliet Shaker Road	EB L	19.6	B
	SB TT	6.7	A	EB T/R	6.3	A	
OVERALL		26.0	C	Watervliet Shaker Road	WB L	12.9	B
					WB TT/R	12.1	B
				Holly Lane	NB L/T/R	34.6	C
				Exit 5 NB Off-Ramp	SB L	22.7	C
					SB T/R	10.4	B
				OVERALL			
						13.0	B

* Delay provided in seconds per vehicle.

L=Left, T=Through, R=Right, L/T=shared Left/Through, T/R=shared Through/Right

Exhibit F.10.1.1-2
VISSIM Analysis Results
Intersection Level of Service
2009 Existing PM

Intersection/Approach		Delay *	LOS	Intersection/Approach		Delay *	LOS
Central Avenue & Wolf Road				Albany Shaker Road & Wolf Road			
Central Avenue	EB LL	55.5	E	Albany Shaker Road	EB L	92.8	F
	EB TT	20.3	C		EB TT/R	50.4	D
Central Avenue	WB TTT	40.5	D		EB R	19.6	B
	WB R	19.3	B	Albany Shaker Road	WB L	55.6	E
Exit 2 NB Off-Ramp	NB TTT	54.3	D		WB T T	41.3	D
Wolf Road	SB LL	63.7	E		WB R	27.0	C
	SB RR	27.6	C	Wolf Road	NB L	57.6	E
OVERALL		36.6	D		NB L/TT	62.4	E
					NB R	36.2	D
Sand Creek Road & Wolf Road				OVERALL		48.9	D
Sand Creek Road	EB L	110.8	F	Albany Shaker Road & Old Wolf Road			
	EB T	98.2	F	Albany Shaker Road	EB L	128.9	F
	EB R	49.8	D		EB TT	119.6	F
Sand Creek Road	WB L	64.4	E		EB R	108.5	F
	WB T	67.9	E	Albany Shaker Road	WB L	84.1	F
	WB R	16.3	B		WB TT/R	27.8	C
Wolf Road	NB L	65.0	E	Old Wolf Road	SB LL/T	76.4	E
	NB TT	36.7	D		SB R	49.9	D
	NB R	13.8	B	OVERALL		80.3	F
Wolf Road	SB L	70.9	E	Old Wolf Road & CD Road			
	SB TT	37.9	D	Site Driveway	EB L/T/R	6.3	A
	SB R	19.0	B	CD Road	WB L/T/R	34.7	C
OVERALL		54.1	D	Old Wolf Road	NB L/T/R	14.4	B
Metro Park Drive & Wolf Road				Old Wolf Road	SB L/T/R	39.1	D
Hess Station	EB L/T/R	36.0	D	OVERALL		31.6	C
Metro Park Drive	WB L	43.5	D	Exit 5 SB Ramps & Watervliet Shaker Road			
	WB T/R	22.8	C	Watervliet Shaker Road	EB L/TT/R	34.0	C
Wolf Road	NB L	10.1	B	Watervliet Shaker Road	WB LT	21.2	C
	NB TT	14.2	B	Exit 5 SB Off-Ramp	SB L	33.6	C
	NB R	9.5	A		SB T/R	6.1	A
Wolf Road	SB L	26.1	C	Sherwood Drive	SB L/T/R	38.7	D
	SB TT/R	6.0	A	OVERALL		28.4	C
OVERALL		14.4	B	Exit 5 NB Ramps & Watervliet Shaker Road			
Exit 4 NB Off-Ramp & Wolf Road				Watervliet Shaker Road	EB L	30.6	C
Exit 4 NB Off-Ramp	EB LL	107.9	F		EB T/R	9.1	A
	EB R	19.8	B	Watervliet Shaker Road	WB L	19.1	B
Wolf Road	NB TTT	100.6	F		WB TT/R	19.6	B
	SB TT	4.1	A	Holly Lane	NB L/T/R	42.2	D
OVERALL		68.6	E	Exit 5 NB Off-Ramp	SB L	32.5	C
					SB T/R	10.5	B
				OVERALL		21.4	C

* Delay provided in seconds per vehicle.

L=Left, T=Through, R=Right, L/T=shared Left/Through, T/R=shared Through/Right

Exhibit F.10.1.1-3
VISSIM Analysis Results
Intersection Level of Service
2016 (ETC) No-Build AM

Intersection/Approach		Delay *	LOS	Intersection/Approach		Delay *	LOS
Central Avenue & Wolf Road				Albany Shaker Road & Wolf Road			
Central Avenue	EB LL	40.4	D	Albany Shaker Road	EB L	41.7	D
	EB TT	20.5	C		EB TT/R	23.0	C
Central Avenue	WB TTT	38.6	D		EB R	12.7	B
	WB R	8.8	A	Albany Shaker Road	WB L	33.8	C
Exit 2 NB Off-Ramp	NB TTT	40.4	D		WB TT	22.2	C
Wolf Road	SB LL	47.5	D		WB R	5.2	A
	SB RR	7.0	A	Wolf Road	NB L	51.4	D
OVERALL		29.2	C		NB L/TT	38.5	D
					NB R	7.9	A
Sand Creek Road & Wolf Road				OVERALL			
Sand Creek Road	EB L	31.1	C	Albany Shaker Road & Old Wolf Road			
	EB T	28.1	C	Albany Shaker Road	EB L	47.4	D
	EB R	2.4	A		EB TT	45.5	D
Sand Creek Road	WB L	35.8	D		EB R	32.8	C
	WB T	32.0	C	Albany Shaker Road	WB L	67.2	E
	WB R	5.2	A		WB TT/R	24.4	C
Wolf Road	NB L	42.9	D	Old Wolf Road	SB LL/T	81.6	F
	NB TT	13.1	B		SB R	66.9	E
	NB R	6.1	A	OVERALL			
Wolf Road	SB L	47.9	D	Old Wolf Road & CD Road			
	SB TT	19.7	B	Site Driveway	EB L/T/R	8.9	A
	SB R	9.8	A	CD Road	WB L/T/R	70.0	E
OVERALL		20.4	C	Old Wolf Road	NB L/T/R	42.9	D
Metro Park & Wolf Road				Old Wolf Road	SB L/T/R	243.3	F
Hess Station	EB L/T/R	33.9	C	OVERALL			
Metro Park Drive	WB L	42.9	D	Exit 5 SB Ramps & Watervliet Shaker Road			
	WB T/R	9.3	A	Watervliet Shaker Road	EB L/TT/R	16.4	B
Wolf Road	NB L	3.3	A	Watervliet Shaker Road	WB LT	18.8	B
	NB TT	2.0	A	Exit 5 SB Off-Ramp	SB L	24.5	C
	NB R	3.9	A		SB T/R	13.8	B
Wolf Road	SB L	4.5	A	Sherwood Drive	SB L/T/R	25.8	C
	SB TT/R	2.9	A	OVERALL			
OVERALL		3.7	A	Exit 5 NB Ramps & Watervliet Shaker Road			
Exit 4 NB Off-Ramp & Wolf Road				Watervliet Shaker Road	EB L	20.2	C
Exit 4 NB Off-Ramp	EB LL	56.4	E	EB T/R	10.4	B	
	EB R	16.6	B	Watervliet Shaker Road	WB L	10.7	B
Wolf Road	NB TTT	11.6	B		WB TT/R	12.2	B
	SB TT	9.1	A	Holly Lane	NB L/T/R	30.7	C
OVERALL		20.5	C	Exit 5 NB Off-Ramp	SB L	23.3	C
					SB T/R	10.7	B
				OVERALL		13.6	B

* Delay provided in seconds per vehicle.

L=Left, T=Through, R=Right, L/T=shared Left/Through, T/R=shared Through/Right

Exhibit F.10.1.1-4
VISSIM Analysis Results
Intersection Level of Service
2016 (ETC) No-Build PM

Intersection/Approach		Delay *	LOS	Intersection/Approach		Delay *	LOS
Central Avenue & Wolf Road				Albany Shaker Road & Wolf Road			
Central Avenue	EB LL	55.0	D	Albany Shaker Road	EB L	132.3	F
	EB TT	19.5	B		EB TT/R	27.0	C
Central Avenue	WB TTT	43.6	D		EB R	10.1	B
	WB R	18.8	B	Albany Shaker Road	WB L	24.5	C
Exit 2 NB Off-Ramp	NB TTT	54.0	D		WB T T	36.8	D
Wolf Road	SB LL	58.1	E		WB R	33.2	C
	SB RR	27.3	C	Wolf Road	NB L	67.4	E
OVERALL		37.4	D		NB L/TT	72.3	E
					NB R	12.9	B
Sand Creek Road & Wolf Road				OVERALL		48.5	D
Sand Creek Road	EB L	128.3	F	Albany Shaker Road & Old Wolf Road			
	EB T	101.5	F	Albany Shaker Road	EB L	416.1	F
	EB R	55.0	D		EB TT	330.6	F
Sand Creek Road	WB L	158.4	F		EB R	242.7	F
	WB T	170.3	F	Albany Shaker Road	WB L	85.6	F
	WB R	90.0	F		WB TT/R	31.4	C
Wolf Road	NB L	68.4	E	Old Wolf Road	SB LL/T	70.0	E
	NB TT	36.5	D		SB R	46.1	D
	NB R	14.4	B	OVERALL		149.7	F
Wolf Road	SB L	66.3	E	Old Wolf Road & CD Road			
	SB TT	36.8	D	Site Driveway	EB L/T/R	6.3	A
	SB R	19.0	B	CD Road	WB L/T/R	27.0	C
OVERALL		71.0	E	Old Wolf Road	NB L/T/R	14.2	B
Metro Park Drive & Wolf Road				Old Wolf Road	SB L/T/R	27.5	C
Hess Station	EB L/T/R	40.6	D	OVERALL		24.4	C
Metro Park Drive	WB L	48.9	D	Exit 5 SB Ramps & Watervliet Shaker Road			
	WB T/R	38.1	D	Watervliet Shaker Road	EB L/TT/R	43.2	D
Wolf Road	NB L	25.0	C	Watervliet Shaker Road	WB LT	22.8	C
	NB TT	28.8	C	Exit 5 SB Off-Ramp	SB L	34.2	C
	NB R	25.8	C		SB T/R	22.0	C
Wolf Road	SB L	11.7	B	Sherwood Drive	SB L/T/R	43.9	D
	SB TT/R	5.2	A	OVERALL		32.1	C
OVERALL		21.0	C	Exit 5 NB Ramps & Watervliet Shaker Road			
Exit 4 NB Off-Ramp & Wolf Road				Watervliet Shaker Road	EB L	27.0	C
Exit 4 NB Off-Ramp	EB LL	80.5	F	EB T/R	10.0	B	
	EB R	7.6	A	Watervliet Shaker Road	WB L	14.1	B
Wolf Road	NB TTT	182.9	F		WB TT/R	19.2	B
	SB TT	6.4	A	Holly Lane	NB L/T/R	41.0	D
OVERALL		105.6	F	Exit 5 NB Off-Ramp	SB L	31.0	C
					SB T/R	10.0	A
				OVERALL		20.3	C

* Delay provided in seconds per vehicle.

L=Left, T=Through, R=Right, L/T=shared Left/Through, T/R=shared Through/Right

Exhibit F.10.1.1-5
VISSIM Analysis Results
Intersection Level of Service
2026 (ETC+10) No-Build AM

Intersection/Approach		Delay *	LOS	Intersection/Approach		Delay *	LOS
Central Avenue & Wolf Road				Albany Shaker Road & Wolf Road			
Central Avenue	EB LL	41.8	D	Albany Shaker Road	EB L	32.2	C
	EB TT	21.0	C		EB TT/R	22.6	C
Central Avenue	WB TTT	39.5	D		EB R	12.3	B
	WB R	9.0	A	Albany Shaker Road	WB L	31.4	C
Exit 2 NB Off-Ramp	NB TTT	40.4	D		WB TT	22.2	C
Wolf Road	SB LL	46.6	D		WB R	5.2	A
	SB RR	7.0	A	Wolf Road	NB L	52.0	D
OVERALL		29.6	C		NB L/TT	37.4	D
					NB R	8.3	A
Sand Creek Road & Wolf Road				OVERALL		24.4	C
Sand Creek Road	EB L	31.1	C	Albany Shaker Road & Old Wolf Road			
	EB T	28.0	C	Albany Shaker Road	EB L	46.3	D
	EB R	2.5	A		EB TT	44.1	D
Sand Creek Road	WB L	37.5	D		EB R	31.4	C
	WB T	32.9	C	Albany Shaker Road	WB L	71.9	E
	WB R	5.1	A		WB TT/R	25.8	C
Wolf Road	NB L	44.9	D	Old Wolf Road	SB LL/T	81.5	F
	NB TT	14.4	B		SB R	70.9	E
	NB R	6.6	A		OVERALL		51.4
Wolf Road	SB L	52.0	D	Old Wolf Road & CD Road			
	SB TT	20.5	C	Site Driveway	EB L/T/R	8.9	A
	SB R	9.4	A	CD Road	WB L/T/R	73.9	E
OVERALL		21.3	C	Old Wolf Road	NB L/T/R	46.6	D
Metro Park & Wolf Road				Old Wolf Road	SB L/T/R	262.3	F
Hess Station	EB L/T/R	33.7	C	OVERALL		102.8	F
Metro Park Drive	WB L	39.5	D	Exit 5 SB Ramps & Watervliet Shaker Road			
	WB T/R	7.9	A	Watervliet Shaker Road	EB L/TT/R	16.1	B
Wolf Road	NB L	2.9	A	Watervliet Shaker Road	WB LT	18.2	B
	NB TT	2.1	A	Exit 5 SB Off-Ramp	SB L	26.7	C
	NB R	4.3	A		SB T/R	15.7	B
Wolf Road	SB L	5.0	A	Sherwood Drive	SB L/T/R	26.4	C
	SB TT/R	3.1	A	OVERALL		19.5	B
OVERALL		4.0	A	Exit 5 NB Ramps & Watervliet Shaker Road			
Exit 4 NB Off-Ramp & Wolf Road				Watervliet Shaker Road	EB L	22.4	C
Exit 4 NB Off-Ramp	EB LL	58.4	E	EB T/R	10.9	B	
	EB R	18.1	B	Watervliet Shaker Road	WB L	10.8	B
Wolf Road	NB TTT	12.1	B		WB TT/R	14.1	B
	SB TT	8.6	A	Holly Lane	NB L/T/R	37.4	D
OVERALL		21.4	C	Exit 5 NB Off-Ramp	SB L	23.6	C
					SB T/R	11.3	B
				OVERALL		15.0	B

* Delay provided in seconds per vehicle.

L=Left, T=Through, R=Right, L/T=shared Left/Through, T/R=shared Through/Right

Exhibit F.10.1.1-6
VISSIM Analysis Results
Intersection Level of Service
2026 (ETC+10) No-Build PM

Intersection/Approach		Delay *	LOS	Intersection/Approach		Delay *	LOS
Central Avenue & Wolf Road				Albany Shaker Road & Wolf Road			
Central Avenue	EB LL	55.7	E	Albany Shaker Road	EB L	132.4	F
	EB TT	20.1	C		EB TT/R	30.4	C
Central Avenue	WB TTT	47.8	D		EB R	11.2	B
	WB R	23.1	C	Albany Shaker Road	WB L	27.2	C
Exit 2 NB Off-Ramp	NB TTT	55.0	D		WB T T	39.5	D
Wolf Road	SB LL	63.5	E		WB R	40.2	D
	SB RR	29.8	C	Wolf Road	NB L	67.6	E
OVERALL		40.1	D		NB L/TT	73.4	E
					NB R	12.7	B
Sand Creek Road & Wolf Road				OVERALL		49.8	D
Sand Creek Road	EB L	130.9	F	Albany Shaker Road & Old Wolf Road			
	EB T	111.9	F	Albany Shaker Road	EB L	510.2	F
	EB R	64.6	E		EB TT	420.7	F
Sand Creek Road	WB L	183.9	F		EB R	358.8	F
	WB T	197.0	F	Albany Shaker Road	WB L	88.3	F
	WB R	112.8	F		WB TT/R	32.4	C
Wolf Road	NB L	70.5	E	Old Wolf Road	SB LL/T	73.9	E
	NB TT	41.4	D		SB R	49.4	D
	NB R	20.4	C	OVERALL		190.0	F
Wolf Road	SB L	67.9	E	Old Wolf Road & CD Road			
	SB TT	37.0	D	Site Driveway	EB L/T/R	6.4	A
	SB R	19.1	B	CD Road	WB L/T/R	30.1	C
OVERALL		76.9	E	Old Wolf Road	NB L/T/R	16.2	B
Metro Park Drive & Wolf Road				Old Wolf Road	SB L/T/R	24.1	C
Hess Station	EB L/T/R	41.6	D	OVERALL		25.5	C
Metro Park Drive	WB L	49.4	D	Exit 5 SB Ramps & Watervliet Shaker Road			
	WB T/R	35.0	C	Watervliet Shaker Road	EB L/TT/R	53.0	D
Wolf Road	NB L	41.0	D	Watervliet Shaker Road	WB LT	24.0	C
	NB TT	44.6	D	Exit 5 SB Off-Ramp	SB L	35.2	D
	NB R	39.4	D		SB T/R	24.9	C
Wolf Road	SB L	13.3	B	Sherwood Drive	SB L/T/R	48.8	D
	SB TT/R	5.3	A	OVERALL		36.6	D
OVERALL		29.9	C	Exit 5 NB Ramps & Watervliet Shaker Road			
Exit 4 NB Off-Ramp & Wolf Road				Watervliet Shaker Road	EB L	30.0	C
Exit 4 NB Off-Ramp	EB LL	86.0	F		EB T/R	11.0	B
	EB R	8.0	A	Watervliet Shaker Road	WB L	14.6	B
Wolf Road	NB TTT	193.7	F		WB TT/R	20.2	C
	SB TT	6.0	A	Holly Lane	NB L/T/R	33.9	C
OVERALL		111.0	F	Exit 5 NB Off-Ramp	SB L	32.1	C
					SB T/R	10.5	B
				OVERALL		21.7	C

* Delay provided in seconds per vehicle.

L=Left, T=Through, R=Right, L/T=shared Left/Through, T/R=shared Through/Right

Exhibit F.10.1.1-7
VISSIM Analysis Results
Intersection Level of Service
2036 (ETC+20) No-Build AM

Intersection/Approach		Delay *	LOS	Intersection/Approach		Delay *	LOS
Central Avenue & Wolf Road				Albany Shaker Road & Wolf Road			
Central Avenue	EB LL	43.9	D	Albany Shaker Road	EB L	39.8	D
	EB TT	21.4	C		EB TT/R	22.9	C
Central Avenue	WB TTT	39.1	D		EB R	12.0	B
	WB R	9.3	A	Albany Shaker Road	WB L	24.3	C
Exit 2 NB Off-Ramp	NB TTT	42.0	D		WB TT	21.3	C
Wolf Road	SB LL	46.9	D		WB R	3.4	A
	SB RR	7.3	A	Wolf Road	NB L	49.8	D
OVERALL		30.4	C		NB L/TT	38.2	D
					NB R	8.6	A
Sand Creek Road & Wolf Road				OVERALL		24.4	C
Sand Creek Road	EB L	34.4	C	Albany Shaker Road & Old Wolf Road			
	EB T	30.5	C	Albany Shaker Road	EB L	49.7	D
	EB R	2.7	A		EB TT	42.3	D
Sand Creek Road	WB L	35.4	D		EB R	28.2	C
	WB T	32.8	C	Albany Shaker Road	WB L	28.0	C
	WB R	5.9	A		WB TT/R	42.0	D
Wolf Road	NB L	46.4	D	Old Wolf Road	SB LL/T	83.9	F
	NB TT	15.2	B		SB R	72.1	E
	NB R	8.0	A		OVERALL		53.7
Wolf Road	SB L	45.6	D	Old Wolf Road & CD Road			
	SB TT	22.0	C	Site Driveway	EB L/T/R	9.4	A
	SB R	10.0	B	CD Road	WB L/T/R	69.3	E
OVERALL		22.5	C	Old Wolf Road	NB L/T/R	44.8	D
Metro Park & Wolf Road				Old Wolf Road	SB L/T/R	328.7	F
Hess Station	EB L/T/R	30.2	C	OVERALL		115.2	F
Metro Park Drive	WB L	44.9	D	Exit 5 SB Ramps & Watervliet Shaker Road			
	WB T/R	9.1	A	Watervliet Shaker Road	EB L/TT/R	17.6	B
Wolf Road	NB L	3.1	A	Watervliet Shaker Road	WB LT	18.3	B
	NB TT	2.1	A	Exit 5 SB Off-Ramp	SB L	26.3	C
	NB R	4.1	A		SB T/R	17.1	B
Wolf Road	SB L	3.2	A	Sherwood Drive	SB L/T/R	26.5	C
	SB TT/R	2.6	A	OVERALL		19.6	B
OVERALL		3.7	A	Exit 5 NB Ramps & Watervliet Shaker Road			
Exit 4 NB Off-Ramp & Wolf Road				Watervliet Shaker Road	EB L	24.2	C
Exit 4 NB Off-Ramp	EB LL	59.9	E		EB T/R	10.0	A
	EB R	17.2	B	Watervliet Shaker Road	WB L	13.0	B
Wolf Road	NB TTT	13.2	B		WB TT/R	15.1	B
	SB TT	9.3	A	Holly Lane	NB L/T/R	38.7	D
OVERALL		22.6	C	Exit 5 NB Off-Ramp	SB L	25.4	C
					SB T/R	12.1	B
				OVERALL		15.8	B

* Delay provided in seconds per vehicle.

L=Left, T=Through, R=Right, L/T=shared Left/Through, T/R=shared Through/Right

Exhibit F.10.1.1-8
VISSIM Analysis Results
Intersection Level of Service
2036 (ETC+20) No-Build PM

Intersection/Approach		Delay *	LOS	Intersection/Approach		Delay *	LOS
Central Avenue & Wolf Road				Albany Shaker Road & Wolf Road			
Central Avenue	EB LL	58.0	E	Albany Shaker Road	EB L	111.8	F
	EB TT	21.0	C		EB TT/R	29.2	C
Central Avenue	WB TTT	42.7	D		EB R	11.1	B
	WB R	25.3	C	Albany Shaker Road	WB L	28.2	C
Exit 2 NB Off-Ramp	NB TTT	56.5	E		WB T T	38.6	D
Wolf Road	SB LL	64.8	E		WB R	34.8	C
	SB RR	30.5	C	Wolf Road	NB L	55.3	E
OVERALL		39.3	D		NB L/TT	70.8	E
					NB R	12.0	B
Sand Creek Road & Wolf Road				OVERALL		44.8	D
Sand Creek Road	EB L	142.4	F	Albany Shaker Road & Old Wolf Road			
	EB T	124.3	F	Albany Shaker Road	EB L	518.3	F
	EB R	74.7	E		EB TT	459.7	F
Sand Creek Road	WB L	190.3	F		EB R	447.0	F
	WB T	203.3	F	Albany Shaker Road	WB L	88.7	F
	WB R	120.4	F		WB TT/R	33.8	C
Wolf Road	NB L	70.9	E	Old Wolf Road	SB LL/T	72.3	E
	NB TT	39.4	D		SB R	48.0	D
	NB R	18.5	B	OVERALL		212.1	F
Wolf Road	SB L	66.7	E	Old Wolf Road & CD Road			
	SB TT	37.9	D	Site Driveway	EB L/T/R	6.3	A
	SB R	21.1	C	CD Road	WB L/T/R	37.5	D
OVERALL		78.6	E	Old Wolf Road	NB L/T/R	15.9	B
Metro Park Drive & Wolf Road				Old Wolf Road	SB L/T/R	28.7	C
Hess Station	EB L/T/R	45.4	D	OVERALL		30.7	C
Metro Park Drive	WB L	54.0	D	Exit 5 SB Ramps & Watervliet Shaker Road			
	WB T/R	39.0	D	Watervliet Shaker Road	EB L/TT/R	63.3	E
Wolf Road	NB L	54.2	D	Watervliet Shaker Road	WB LT	25.9	C
	NB TT	43.8	D	Exit 5 SB Off-Ramp	SB L	36.1	D
	NB R	32.4	C		SB T/R	28.0	C
Wolf Road	SB L	12.1	B	Sherwood Drive	SB L/T/R	56.0	E
	SB TT/R	4.5	A	OVERALL		41.5	D
OVERALL		29.5	C	Exit 5 NB Ramps & Watervliet Shaker Road			
Exit 4 NB Off-Ramp & Wolf Road				Watervliet Shaker Road	EB L	30.4	C
Exit 4 NB Off-Ramp	EB LL	99.3	F		EB T/R	10.8	B
	EB R	10.1	B	Watervliet Shaker Road	WB L	18.9	B
Wolf Road	NB TTT	198.5	F		WB TT/R	21.5	C
	SB TT	5.7	A	Holly Lane	NB L/T/R	39.5	D
OVERALL		115.2	F	Exit 5 NB Off-Ramp	SB L	32.5	C
					SB T/R	10.9	B
				OVERALL		22.2	C

* Delay provided in seconds per vehicle.

L=Left, T=Through, R=Right, L/T=shared Left/Through, T/R=shared Through/Right

Exhibit F.10.1.1-9
VISSIM Analysis Results
Intersection Level of Service
2046 (ETC+30) No-Build AM

Intersection/Approach		Delay *	LOS	Intersection/Approach		Delay *	LOS
Exit 4 NB Off-Ramp & Wolf Road				Albany Shaker Road & Old Wolf Road			
Exit 4 NB Off-Ramp	EB LL	104.5	F	Albany Shaker Road	EB L	64.3	E
	EB R	49.6	D		EB TT	53.3	D
Wolf Road	NB TTT	18.5	B		EB R	49.8	D
	SB TT	9.1	A	Albany Shaker Road	WB L	26.7	C
OVERALL		38.5	D		WB TT/R	42.1	D
Albany Shaker Road & Wolf Road				Old Wolf Road	SB LL/T	89.3	F
Albany Shaker Road	EB L	32.8	C		SB R	76.5	E
	EB TT/R	23.2	C	OVERALL		58.7	E
	EB R	12.7	B				
Albany Shaker Road	WB L	28.8	C				
	WB TT	23.4	C				
	WB R	5.5	A				
Wolf Road	NB L	51.2	D				
	NB L/TT	44.5	D				
	NB R	8.5	A				
OVERALL		25.5	C				

* Delay provided in seconds per vehicle.

L=Left, T=Through, R=Right, L/T=shared Left/Through, T/R=shared Through/Right

Exhibit F.10.1.1-10
VISSIM Analysis Results
Intersection Level of Service
2046 (ETC+30) No-Build PM

Intersection/Approach		Delay *	LOS	Intersection/Approach		Delay *	LOS
Exit 4 NB Off-Ramp & Wolf Road				Albany Shaker Road & Old Wolf Road			
Exit 4 NB Off-Ramp	EB LL	137.7	F	Albany Shaker Road	EB L	469.8	F
	EB R	25.9	C		EB TT	424.4	F
Wolf Road	NB TTT	339.6	F		EB R	500.6	F
	SB TT	5.9	A	Albany Shaker Road	WB L	96.1	F
OVERALL		169.6	F		WB TT/R	41.8	D
Albany Shaker Road & Wolf Road				Old Wolf Road	SB LL/T	95.5	F
Albany Shaker Road	EB L	95.4	F		SB R	73.8	E
	EB TT/R	36.3	D	OVERALL		214.6	F
	EB R	14.7	B				
Albany Shaker Road	WB L	35.0	D				
	WB T T	44.0	D				
	WB R	29.3	C				
Wolf Road	NB L	61.0	E				
	NB L/TT	55.3	E				
	NB R	10.2	B				
OVERALL		43.0	D				

* Delay provided in seconds per vehicle.

L=Left, T=Through, R=Right, L/T=shared Left/Through, T/R=shared Through/Right

10.1.2 Freeway Level of Service

Freeway analyses for I-87 were conducted in accordance with the Highway Capacity Manual (HCM2000) using HCS+. The analyses were conducted for the freeway segments between Exits 2 and 4, Exits 4 and 5, Exits 5 and 6, and on the segments on the bridge over Albany-Shaker Road. Ramp junctions were evaluated at Exits 2, 4 and 5. Weave areas were evaluated at Exit 2. All of these analyses were conducted for Existing, ETC, ETC+10 and ETC+20. The freeway segment over Albany-Shaker Road was also evaluated for ETC+30. The level of service worksheets for all of the freeway analyses are provided in Attachment E.

The results of the AM and PM peak hour Existing and No-Build freeway analyses are summarized in Exhibits 2.3.1.7 c, 2.3.1.7 d, F.10.1.2-1 and F.10.1.2-2.

Exhibit 2.3.1.7 c Freeway Level of Service 2009 Existing AM Peak Hour			
Direction	Segment/Junction	Existing (2009)	
		Density pc/mi/ln	LOS
FREEWAY SEGMENTS			
NB	Exit 2W on to Exit 4 off	19.6	C
	Exit 4 off to Exit 4 on	14.4	B
	Exit 4 on to Exit 5 off	17.6	B
	Exit 5 on to Exit 6 off	12.3	B
SB	Exit 6 on to Exit 5 off	29.9	D
	Exit 4 off to Exit 5 on	28.8	D
	Exit 5 on to Exit 4 on	30.1	D
	Exit 4 on to Exit 2W off	33.8	D
RAMP JUNCTIONS			
NB	Exit 2W on-ramp	16.5	B
	Exit 4 off-ramp	22.2	C
	Exit 4 on-ramp	15.6	B
	Exit 5 off-ramp	21.2	C
SB	Exit 4 off-ramp	33.3	D
	Exit 5 on-ramp	26.5	C
	Exit 4 on-ramp	27.9	C
	Exit 2W off-ramp	33.0	D
WEAVE AREAS			
NB	Exit 2E on-ramp to Exit 2W off-ramp	22.0	C
SB	Exit 2W on-ramp to Exit 2E off-ramp	28.5	D

pc/mi/lane = passenger cars per mile per lane

Exhibit 2.3.1.7 d Freeway Level of Service 2009 Existing PM Peak Hour			
Direction	Segment/Junction	Existing (2009)	
		Density pc/mi/ln ¹	LOS
FREEWAY SEGMENTS			
NB	Exit 2W on to Exit 4 off	36.3	E
	Exit 4 off to Exit 4 on	31.5	D
	Exit 4 on to Exit 5 off	**	F
	Exit 5 on to Exit 6 off	31.5	D
SB	Exit 6 on to Exit 5 off	16.2	B
	Exit 4 off to Exit 5 on	16.3	B
	Exit 5 on to Exit 4 on	17.6	B
	Exit 4 on to Exit 2W off	24.5	C
RAMP JUNCTIONS			
NB	Exit 2W on-ramp	29.4	D
	Exit 4 off-ramp	33.4	D
	Exit 4 on-ramp	35.8	F
	Exit 5 off-ramp	45.0	F
SB	Exit 4 off-ramp	20.1	C
	Exit 5 on-ramp	16.9	B
	Exit 4 on-ramp	22.1	C
	Exit 2W off-ramp	25.5	C
WEAVE AREAS			
NB	Exit 2E on-ramp to Exit 2W off-ramp	39.2	E
SB	Exit 2W on-ramp to Exit 2E off-ramp	29.4	D

1 - pc/mi/ln = passenger cars per mile per lane

** - Density is greater than 45 pc/mi/ln and can no longer be calculated with the basic freeway analysis. Segment is oversaturated.

Exhibit F.10.1-1 Freeway Level of Service No-Build AM Peak Hour									
Direction	Segment/Junction	ETC (2016)		ETC+10 (2026)		ETC+20 (2036)		ETC+30 (2046)	
		Density pc/mi/ln	LOS	Density pc/mi/ln	LOS	Density pc/mi/ln	LOS	Density pc/mi/ln	LOS
FREEWAY SEGMENTS									
NB	Exit 2W on to Exit 4 off	19.6	C	19.6	C	19.6	C	-	-
	Exit 4 off to Exit 4 on	14.7	B	14.7	B	14.4	B	13.7	B
	Exit 4 on to Exit 5 off	18.0	B	18.0	B	18.3	C	-	-
	Exit 5 on to Exit 6 off	12.3	B	12.5	B	12.8	B	-	-
SB	Exit 6 on to Exit 5 off	29.9	D	29.6	D	29.6	D	-	-
	Exit 4 off to Exit 5 on	28.8	D	29.1	D	29.7	D	-	-
	Exit 5 on to Exit 4 on	30.4	D	31.0	D	31.4	D	31.4	D
	Exit 4 on to Exit 2W off	34.2	D	34.6	D	35.0	D	-	-
RAMP JUNCTIONS									
NB	Exit 2W on-ramp	16.6	B	16.7	B	16.6	B	-	-
	Exit 4 off-ramp	22.0	C	22.0	C	22.1	C	-	-
	Exit 4 on-ramp	16.8	B	16.7	B	16.3	B	-	-
	Exit 5 off-ramp	22.0	C	21.9	C	22.2	C	-	-
SB	Exit 4 off-ramp	32.8	D	32.8	D	32.8	D	-	-
	Exit 5 on-ramp	25.5	C	25.8	C	26.5	C	-	-
	Exit 4 on-ramp	28.1	D	28.5	D	28.6	D	-	-
	Exit 2W off-ramp	33.0	D	33.2	D	33.4	D	-	-
WEAVE AREAS									
NB	Exit 2E on-ramp to Exit 2W off-ramp	21.4	C	21.6	C	21.6	C	-	-
SB	Exit 2W on-ramp to Exit 2E off-ramp	31.1	D	32.0	D	32.8	D	-	-

pc/mi/lane = passenger cars per mile per lane

Exhibit F.10.1-2 Freeway Level of Service No-Build PM Peak Hour									
Direction	Segment/Junction	ETC (2016)		ETC+10 (2026)		ETC+20 (2036)		ETC+30 (2046)	
		Density pc/mi/ln ¹	LOS	Density pc/mi/ln	LOS	Density pc/mi/ln	LOS	Density pc/mi/ln	LOS
FREEWAY SEGMENTS									
NB	Exit 2W on to Exit 4 off	36.3	E	36.8	E	37.3	E	-	-
	Exit 4 off to Exit 4 on	31.5	D	31.5	D	32.2	D	31.8	D
	Exit 4 on to Exit 5 off	**	F	**	F	**	F	-	-
	Exit 5 on to Exit 6 off	32.0	D	32.3	D	32.8	D	-	-
SB	Exit 6 on to Exit 5 off	16.9	B	17.9	B	18.6	C	-	-
	Exit 4 off to Exit 5 on	16.7	B	17.0	B	18.0	B	-	-
	Exit 5 on to Exit 4 on	18.3	C	18.6	C	19.3	C	19.9	C
	Exit 4 on to Exit 2W off	25.2	C	25.8	C	26.8	D	-	-
RAMP JUNCTIONS									
NB	Exit 2W on-ramp	29.6	D	29.6	D	29.9	D	-	-
	Exit 4 off-ramp	33.5	D	33.7	D	33.9	D	-	-
	Exit 4 on-ramp	36.7	F	37.0	F	37.8	F	-	-
	Exit 5 off-ramp	46.6	F	47.3	F	48.1	F	-	-
SB	Exit 4 off-ramp	19.3	B	20.4	C	20.9	C	-	-
	Exit 5 on-ramp	16.7	B	17.1	B	18.0	B	-	-
	Exit 4 on-ramp	22.7	C	23.5	C	24.5	C	-	-
	Exit 2W off-ramp	26.2	C	26.8	C	27.7	C	-	-
WEAVE AREAS									
NB	Exit 2E on-ramp to Exit 2W off-ramp	39.1	E	38.8	E	38.9	E	-	-
SB	Exit 2W on-ramp to Exit 2E off-ramp	26.8	C	27.6	C	28.6	D	-	-

1 - pc/mi/ln = passenger cars per mile per lane

** - Density is greater than 45 pc/mi/ln and can no longer be calculated with the basic freeway analysis. Segment is oversaturated.

During the AM peak hour, all of the freeway segments, ramp junctions and weave areas are estimated to operate at LOS D or better through ETC+20. There are some locations where the analysis of future No-Build conditions shows a decrease in vehicle density from the Existing conditions. This is related to the projected regional changes in travel patterns and mode choice of CDTC's regional travel demand model, which indicate either no growth of mainline traffic combined with slight growth on the ramp or slight decreases in ramp volumes.

During the PM peak hour, the following locations operate at LOS E or worse under the Existing condition in the northbound direction:

- Freeway Segments
 - Exit 2W on to Exit 4 off
 - Exit 4 on to Exit 5 off
- Ramp Junctions
 - Exit 4 on-ramp
 - Exit 5 off-ramp
- Weave Areas
 - Exit 2E on to Exit 2W off

Through the ETC+20 design year, the same freeway facilities are estimated to continue to operate at LOS E or F. There is no substantial degradation in these operations beyond the Existing condition because there is little growth estimated in peak hour traffic on I-87. Similar to the AM peak hour, there are a few

instances where the density reported decreases in a future year; these instances are related to slight decreases in ramp volumes from the regional demand model.

10.2 Level of Service for Build Alternatives

Two build alternatives were evaluated for the purpose of this study: the Diamond Alternative and Flyover Alternative.

Summaries of the LOS for each build alternative for the ETC, ETC+10, ETC+20, and ETC+30 future year conditions are presented in the subsequent sections. Note that the ETC+30 condition was only evaluated for the intersections adjacent to the bridges.

10.2.1 Diamond Alternative

10.2.1.1 Intersection Level of Service

Summaries of the LOS for the future design years, for the Diamond Alternative, are presented in Exhibits F.10.2.1.1-1 through F.10.2.1.1-8. As shown in these analyses, there are intersections within the study area, but outside the project area, that continue to have movements that experience LOS E or worse at ETC+20 during the studied peak hours. These intersections are:

- Central Avenue & Wolf Road (PM)
- Sand Creek Road & Wolf Road (PM)
- Exit 5 SB Ramps & Watervliet-Shaker Road (PM)

At the project area intersections, all intersection approaches are estimated to operate at LOS D or better through ETC+20. There is one movement, the westbound left-turn at the Albany-Shaker Road & Connector Road intersection that operates at LOS E during both peak hours. This is relatively low volume movement and the LOS E is a result of signal timing priority given to the major through movements on Albany-Shaker Road and the Exit 4 ramps. Observation of other factors such as vehicle queue and volume-to-capacity ratio show that there is reserve capacity for the movement and the delay level is related to the cycle length used to serve the other major movements at the intersection.

The ETC+30 design year was also evaluated for the intersections adjacent to bridge structures that will be replaced as part of the project (I-87 over Albany-Shaker Road). All intersection approaches, at the intersections adjacent to the bridge structures, are estimated to operate at LOS D or better. The westbound left-turn at the Albany-Shaker Road & Connector Road intersection will continue to operate at LOS E during both peak hours.

Exhibit F.10.2.1.1-1
VISSIM Analysis Results
Intersection Level of Service
2016 (ETC) Diamond Alternative AM

Intersection/Approach		Delay *	LOS	Intersection/Approach		Delay *	LOS
Central Avenue & Wolf Road				Albany Shaker Road & Old Wolf Road			
Central Avenue	EB LL	40.4	D	Albany Shaker Road	EB L	22.1	C
	EB TT	19.9	B		EB TT	10.3	B
Central Avenue	WB TTT	37.9	D	Albany Shaker Road	WB TT/R	15.6	B
	WB R	7.6	A		Old Wolf Road	SB LL	28.4
Exit 2 NB Off-Ramp	NB TTT	40.2	D	SB R		21.1	C
Wolf Road	SB LL	43.7	D	OVERALL		18.3	B
	SB RR	6.1	A	Exit 5 SB Ramps & Watervliet Shaker Road			
OVERALL		28.3	C	Watervliet Shaker Road	EB L/TT/R	25.8	C
Sand Creek Road & Wolf Road				Watervliet Shaker Road	WB LT	20.8	C
Sand Creek Road	EB L	30.0	C	Exit 5 SB Off-Ramp	SB L	27.7	C
	EB T	26.2	C		SB T/R	22.4	C
	EB R	2.6	A		Sherwood Drive	SB L/T/R	31.7
Sand Creek Road	WB L	31.6	C	OVERALL		23.7	C
	WB T	28.6	C	Exit 5 NB Ramps & Watervliet Shaker Road			
	WB R	4.9	A	Watervliet Shaker Road	EB L	27.0	C
Wolf Road	NB L	42.1	D	EB T/R	13.7	B	
	NB TT	14.6	B	Watervliet Shaker Road	WB L	13.4	B
	NB R	8.3	A		WB TT/R	16.5	B
Wolf Road	SB L	42.7	D	Holly Lane	NB L/T/R	38.3	D
	SB TT	15.7	B	Exit 5 NB Off-Ramp	SB L	26.6	C
	SB R	9.0	A		SB T/R	11.2	B
OVERALL		19.0	B	OVERALL		17.6	B
Metro Park Drive/Airport Connector & Wolf Road				Airport Connector & Albany Shaker Road			
Airport Connector	EB L	23.7	C	Albany Shaker Road	EB TT	8.2	A
	EB T	17.0	B		EB RR	3.7	A
	EB R	6.9	A	Albany Shaker Road	WB L	42.8	D
Metro Park Drive	WB L	26.3	C		WB TT	5.2	A
	WB T/R	29.4	C	Airport Connector	NB LL	34.9	C
Wolf Road	NB L	31.6	C		NB R	5.4	A
	NB TT	13.9	B	OVERALL		13.9	B
	NB R	6.8	A	Diamond NB Ramps & Airport Connector			
Wolf Road	SB L	16.3	B	Diamond NB Off-Ramp	NB L	19.6	B
	SB TT	19.8	B		NB R	11.0	B
	SB R	6.9	A	Airport Connector	WB T	16.8	B
OVERALL		17.7	B	Airport Connector	EB L	15.4	B
Albany Shaker Road & Wolf Road					EB T	4.7	A
Albany Shaker Road	EB TT/R	2.8	A	OVERALL		13.0	B
	EB R	4.1	A	Diamond SB Ramps & Airport Connector			
Albany Shaker Road	WB L	10.1	B	Diamond SB Off-Ramp	SB L	23.2	C
	WB T T	4.9	A		SB R	4.9	A
Wolf Road	NB L	31.3	C	Airport Connector	WB L	12.0	B
	NB R	8.7	A		WB T	6.8	A
OVERALL		6.7	A	Airport Connector	EB T	14.7	B
					EB R	1.4	A
				OVERALL		10.1	B

* Delay provided in seconds per vehicle.

L=Left, T=Through, R=Right, L/T=shared Left/Through, T/R=shared Through/Right

Exhibit F.10.2.1.1-2
VISSIM Analysis Results
Intersection Level of Service
2016 (ETC) Diamond Alternative PM

Intersection/Approach		Delay *	LOS	Intersection/Approach		Delay *	LOS
Central Avenue & Wolf Road				Albany Shaker Road & Old Wolf Road			
Central Avenue	EB LL	54.2	D	Albany Shaker Road	EB L	30.9	C
	EB TT	19.2	B		EB TT	11.6	B
Central Avenue	WB TTT	37.2	D	Albany Shaker Road	WB TT/R	15.4	B
	WB R	19.7	B		Old Wolf Road	SB LL	29.5
Exit 2 NB Off-Ramp	NB TTT	52.6	D	SB R		24.4	C
Wolf Road	SB LL	62.0	E	OVERALL		19.4	B
	SB RR	26.0	C	Exit 5 SB Ramps & Watervliet Shaker Road			
OVERALL		35.5	D	Watervliet Shaker Road	EB L/TT/R	51.8	D
Sand Creek Road & Wolf Road				Watervliet Shaker Road	WB LT	27.0	C
Sand Creek Road	EB L	108.3	F	Exit 5 SB Off-Ramp	SB L	37.6	D
	EB T	92.0	F		SB T/R	8.6	A
	EB R	48.8	D		Sherwood Drive	SB L/T/R	48.5
Sand Creek Road	WB L	161.0	F	OVERALL		38.2	D
	WB T	171.4	F	Exit 5 NB Ramps & Watervliet Shaker Road			
	WB R	92.5	F	Watervliet Shaker Road	EB L	26.7	C
Wolf Road	NB L	63.2	E		EB T/R	13.1	B
	NB TT	33.3	C	Watervliet Shaker Road	WB L	18.5	B
	NB R	12.3	B		WB TT/R	20.5	C
Wolf Road	SB L	62.3	E	Holly Lane	NB L/T/R	35.3	D
	SB TT	35.8	D	Exit 5 NB Off-Ramp	SB L	28.9	C
	SB R	18.4	B		SB T/R	11.7	B
OVERALL		70.0	E	OVERALL		20.6	C
Metro Park Drive/Airport Connector & Wolf Road				Airport Connector & Albany Shaker Road			
Airport Connector	EB L	30.0	C	Albany Shaker Road	EB TT	23.5	C
	EB T	30.5	C		EB RR	7.5	A
	Metro Park Drive	EB R	18.2	B	Albany Shaker Road	WB L	40.9
WB L		20.7	C	WB TT		8.5	A
Wolf Road		WB T/R	35.8	D	Airport Connector	NB LL	31.4
	NB L	40.8	D	NB R		8.0	A
	Wolf Road	NB TT	20.8	C	OVERALL		19.1
NB R		7.8	A	Diamond NB Ramps & Airport Connector			
Wolf Road		SB L	24.0	C	Diamond NB Off-Ramp	NB L	18.9
	SB TT	27.6	C	NB R		6.8	A
	SB R	12.0	B	Airport Connector	WB T	41.3	D
OVERALL		24.8	C	Airport Connector	EB L	14.9	B
Albany Shaker Road & Wolf Road					EB T	15.1	B
Albany Shaker Road	EB TT/R	17.0	B	OVERALL		20.1	C
	EB R	5.9	A	Diamond SB Ramps & Airport Connector			
Albany Shaker Road	WB L	18.6	B	Diamond SB Off-Ramp	SB L	20.5	C
	WB T T	7.7	A		SB R	11.6	B
Wolf Road	NB L	28.1	C	Airport Connector	WB L	10.4	B
	NB R	8.7	A		WB T	25.7	C
OVERALL		13.1	B	Airport Connector	EB T	33.2	C
					EB R	7.1	A
				OVERALL		17.2	B

* Delay provided in seconds per vehicle.

L=Left, T=Through, R=Right, L/T=shared Left/Through, T/R=shared Through/Right

Exhibit F.10.2.1.1-3
VISSIM Analysis Results
Intersection Level of Service
2026 (ETC+10) Diamond Alternative AM

Intersection/Approach		Delay *	LOS	Intersection/Approach		Delay *	LOS
Central Avenue & Wolf Road				Albany Shaker Road & Old Wolf Road			
Central Avenue	EB LL	39.3	D	Albany Shaker Road	EB L	23.5	C
	EB TT	20.0	B		EB TT	11.0	B
Central Avenue	WB TTT	37.2	D	Albany Shaker Road	WB TT/R	15.9	B
	WB R	8.2	A		Old Wolf Road	SB LL	28.9
Exit 2 NB Off-Ramp	NB TTT	39.6	D	SB R		21.1	C
Wolf Road	SB LL	45.1	D	OVERALL		18.9	B
	SB RR	6.8	A	Exit 5 SB Ramps & Watervliet Shaker Road			
OVERALL		28.2	C	Watervliet Shaker Road	EB L/TT/R	34.8	C
Sand Creek Road & Wolf Road				Watervliet Shaker Road	WB LT	23.9	C
Sand Creek Road	EB L	32.3	C	Exit 5 SB Off-Ramp	SB L	30.8	C
	EB T	28.1	C		SB T/R	26.9	C
	EB R	2.5	A		Sherwood Drive	SB L/T/R	35.1
Sand Creek Road	WB L	33.5	C	OVERALL		27.8	C
	WB T	29.9	C	Exit 5 NB Ramps & Watervliet Shaker Road			
	WB R	5.0	A	Watervliet Shaker Road	EB L	30.4	C
Wolf Road	NB L	42.5	D		EB T/R	14.3	B
	NB TT	15.1	B	Watervliet Shaker Road	WB L	16.1	B
	NB R	9.0	A		WB TT/R	16.2	B
Wolf Road	SB L	45.7	D	Holly Lane	NB L/T/R	39.3	D
	SB TT	17.0	B	Exit 5 NB Off-Ramp	SB L	27.2	C
	SB R	9.3	A		SB T/R	12.2	B
OVERALL		20.2	C	OVERALL		18.2	B
Metro Park Drive/Airport Connector & Wolf Road				Airport Connector & Albany Shaker Road			
Airport Connector	EB L	25.6	C	Albany Shaker Road	EB TT	9.2	A
	EB T	18.2	B		EB RR	3.7	A
	EB R	6.8	A	Albany Shaker Road	WB L	42.4	D
Metro Park Drive	WB L	21.4	C		WB TT	5.5	A
	WB T/R	28.5	C	Airport Connector	NB LL	32.9	C
Wolf Road	NB L	32.0	C		NB R	5.7	A
	NB TT	15.0	B	OVERALL		14.4	B
	NB R	7.0	A	Diamond NB Ramps & Airport Connector			
Wolf Road	SB L	16.1	B	Diamond NB Off-Ramp	NB L	19.3	B
	SB TT	21.8	C		NB R	10.8	B
	SB R	6.8	A	Airport Connector	WB T	22.9	C
OVERALL		18.7	B	Airport Connector	EB L	15.9	B
Albany Shaker Road & Wolf Road					EB T	12.0	B
Albany Shaker Road	EB TT/R	3.2	A	OVERALL		15.5	B
	EB R	4.3	A	Diamond SB Ramps & Airport Connector			
Albany Shaker Road	WB L	11.4	B	Diamond SB Off-Ramp	SB L	19.2	B
	WB T T	4.9	A		SB R	5.2	A
Wolf Road	NB L	29.8	C	Airport Connector	WB L	12.0	B
	NB R	8.7	A		WB T	14.7	B
OVERALL		6.9	A	Airport Connector	EB T	19.4	B
					EB R	1.5	A
				OVERALL		12.2	B

* Delay provided in seconds per vehicle.

L=Left, T=Through, R=Right, L/T=shared Left/Through, T/R=shared Through/Right

Exhibit F.10.2.1.1-4
VISSIM Analysis Results
Intersection Level of Service
2026 (ETC+10) Diamond Alternative PM

Intersection/Approach		Delay *	LOS	Intersection/Approach		Delay *	LOS
Central Avenue & Wolf Road				Albany Shaker Road & Old Wolf Road			
Central Avenue	EB LL	56.4	E	Albany Shaker Road	EB L	34.0	C
	EB TT	20.0	C		EB TT	15.3	B
Central Avenue	WB TTT	39.6	D	Albany Shaker Road	WB TT/R	17.2	B
	WB R	21.2	C		Old Wolf Road	SB LL	29.3
Exit 2 NB Off-Ramp	NB TTT	53.5	D	SB R		23.8	C
Wolf Road	SB LL	62.4	E	OVERALL		21.0	C
	SB RR	27.7	C	Exit 5 SB Ramps & Watervliet Shaker Road			
OVERALL		37.0	D	Watervliet Shaker Road	EB L/TT/R	63.2	E
Sand Creek Road & Wolf Road				Watervliet Shaker Road	WB LT	26.2	C
Sand Creek Road	EB L	116.6	F	Exit 5 SB Off-Ramp	SB L	39.1	D
	EB T	108.4	F		SB T/R	9.1	A
	EB R	61.5	E		Sherwood Drive	SB L/T/R	46.0
Sand Creek Road	WB L	169.2	F	OVERALL		43.1	D
	WB T	180.5	F	Exit 5 NB Ramps & Watervliet Shaker Road			
	WB R	99.9	F	Watervliet Shaker Road	EB L	32.1	C
Wolf Road	NB L	66.9	E	EB T/R	10.1	B	
	NB TT	35.2	D	Watervliet Shaker Road	WB L	19.3	B
	NB R	14.4	B		WB TT/R	21.0	C
Wolf Road	SB L	64.4	E	Holly Lane	NB L/T/R	40.7	D
	SB TT	38.3	D	Exit 5 NB Off-Ramp	SB L	31.6	C
	SB R	20.6	C		SB T/R	9.1	A
OVERALL		74.9	E	OVERALL		21.5	C
Metro Park Drive/Airport Connector & Wolf Road				Airport Connector & Albany Shaker Road			
Airport Connector	EB L	32.1	C	Albany Shaker Road	EB TT	23.2	C
	EB T	31.4	C		EB RR	7.4	A
	Metro Park Drive	EB R	19.3	B	Albany Shaker Road	WB L	47.2
WB L		22.0	C	WB TT		6.6	A
Wolf Road	WB T/R	36.5	D	Airport Connector	NB LL	29.3	C
	NB L	43.7	D		NB R	6.0	A
	NB TT	23.8	C	OVERALL		18.2	B
Wolf Road	NB R	8.7	A	Diamond NB Ramps & Airport Connector			
	SB L	16.5	B	Diamond NB Off-Ramp	NB L	19.0	B
	SB TT	30.0	C		NB R	7.1	A
SB R	13.9	B	Airport Connector	WB T	51.7	D	
OVERALL		27.0	C	Airport Connector	EB L	17.2	B
Albany Shaker Road & Wolf Road					EB T	15.9	B
Albany Shaker Road	EB TT/R	18.1	B	OVERALL		22.8	C
	EB R	6.5	A	Diamond SB Ramps & Airport Connector			
Albany Shaker Road	WB L	26.2	C	Diamond SB Off-Ramp	SB L	21.4	C
	WB T T	7.8	A		SB R	13.5	B
Wolf Road	NB L	26.4	C	Airport Connector	WB L	11.0	B
	NB R	9.1	A		WB T	26.8	C
OVERALL		14.4	B	Airport Connector	EB T	33.0	C
					EB R	7.4	A
				OVERALL		18.1	B

* Delay provided in seconds per vehicle.

L=Left, T=Through, R=Right, L/T=shared Left/Through, T/R=shared Through/Right

Exhibit F.10.2.1.1-5
VISSIM Analysis Results
Intersection Level of Service
2036 (ETC+20) Diamond Alternative AM

Intersection/Approach		Delay *	LOS	Intersection/Approach		Delay *	LOS
Central Avenue & Wolf Road				Albany Shaker Road & Old Wolf Road			
Central Avenue	EB LL	42.8	D	Albany Shaker Road	EB L	23.8	C
	EB TT	20.6	C		EB TT	11.1	B
Central Avenue	WB TTT	36.5	D	Albany Shaker Road	WB TT/R	16.9	B
	WB R	8.8	A		Old Wolf Road	SB LL	28.6
Exit 2 NB Off-Ramp	NB TTT	41.5	D	SB R		21.2	C
Wolf Road	SB LL	46.7	D	OVERALL		19.2	B
	SB RR	7.0	A	Exit 5 SB Ramps & Watervliet Shaker Road			
OVERALL		29.0	C	Watervliet Shaker Road	EB L/TT/R	43.2	D
Sand Creek Road & Wolf Road				Watervliet Shaker Road	WB LT	26.1	C
Sand Creek Road	EB L	32.1	C	Exit 5 SB Off-Ramp	SB L	34.6	C
	EB T	26.9	C		SB T/R	32.8	C
	EB R	2.5	A		Sherwood Drive	SB L/T/R	35.6
Sand Creek Road	WB L	33.2	C	OVERALL		31.8	C
	WB T	30.3	C	Exit 5 NB Ramps & Watervliet Shaker Road			
	WB R	5.2	A	Watervliet Shaker Road	EB L	30.9	C
Wolf Road	NB L	44.0	D		EB T/R	15.2	B
	NB TT	16.5	B	Watervliet Shaker Road	WB L	15.6	B
	NB R	7.4	A		WB TT/R	17.1	B
Wolf Road	SB L	44.5	D	Holly Lane	NB L/T/R	36.3	D
	SB TT	18.2	B	Exit 5 NB Off-Ramp	SB L	28.3	C
	SB R	9.6	A		SB T/R	12.3	B
OVERALL		21.1	C	OVERALL		18.9	B
Metro Park Drive/Airport Connector & Wolf Road				Airport Connector & Albany Shaker Road			
Airport Connector	EB L	25.5	C	Albany Shaker Road	EB TT	10.6	B
	EB T	24.3	C		EB RR	3.7	A
	EB R	6.9	A	Albany Shaker Road	WB L	61.0	E
Metro Park Drive	WB L	21.9	C		WB TT	6.5	A
	WB T/R	26.6	C	Airport Connector	NB LL	31.4	C
Wolf Road	NB L	33.8	C		NB R	6.4	A
	NB TT	15.4	B	OVERALL		15.3	B
	NB R	7.7	A	Diamond NB Ramps & Airport Connector			
Wolf Road	SB L	13.1	B	Diamond NB Off-Ramp	NB L	21.0	C
	SB TT	21.6	C		NB R	10.6	B
	SB R	6.9	A	Airport Connector	WB T	25.4	C
OVERALL		18.9	B	Airport Connector	EB L	22.6	C
Albany Shaker Road & Wolf Road					EB T	18.2	B
Albany Shaker Road	EB TT/R	3.6	A	OVERALL		18.9	B
	EB R	4.4	A	Diamond SB Ramps & Airport Connector			
Albany Shaker Road	WB L	12.9	B	Diamond SB Off-Ramp	SB L	20.7	C
	WB T T	5.4	A		SB R	5.9	A
Wolf Road	NB L	29.8	C	Airport Connector	WB L	11.8	B
	NB R	8.7	A		WB T	21.7	C
OVERALL		7.3	A	Airport Connector	EB T	25.1	C
					EB R	1.4	A
				OVERALL		15.6	B

* Delay provided in seconds per vehicle.

L=Left, T=Through, R=Right, L/T=shared Left/Through, T/R=shared Through/Right

Exhibit F.10.2.1.1-6
VISSIM Analysis Results
Intersection Level of Service
2036 (ETC+20) Diamond Alternative PM

Intersection/Approach		Delay *	LOS	Intersection/Approach		Delay *	LOS
Central Avenue & Wolf Road				Albany Shaker Road & Old Wolf Road			
Central Avenue	EB LL	56.9	E	Albany Shaker Road	EB L	46.3	D
	EB TT	20.3	C		EB TT	2.0	A
Central Avenue	WB TTT	41.4	D	Albany Shaker Road	WB TT/R	10.2	B
	WB R	25.7	C		Old Wolf Road	SB LL	38.9
Exit 2 NB Off-Ramp	NB TTT	54.9	D	SB R		31.0	C
Wolf Road	SB LL	60.3	E	OVERALL		18.2	B
	SB RR	27.4	C	Exit 5 SB Ramps & Watervliet Shaker Road			
OVERALL		38.0	D	Watervliet Shaker Road	EB L/TT/R	69.4	E
Sand Creek Road & Wolf Road				Watervliet Shaker Road	WB LT	31.4	C
Sand Creek Road	EB L	133.6	F	Exit 5 SB Off-Ramp	SB L	41.4	D
	EB T	122.6	F		SB T/R	11.0	B
	EB R	73.2	E	Sherwood Drive	SB L/T/R	52.0	D
Sand Creek Road	WB L	177.5	F	OVERALL		47.7	D
	WB T	190.7	F	Exit 5 NB Ramps & Watervliet Shaker Road			
	WB R	109.0	F	Watervliet Shaker Road	EB L	31.6	C
Wolf Road	NB L	68.2	E	EB T/R	12.1	B	
	NB TT	36.1	D	Watervliet Shaker Road	WB L	21.3	C
	NB R	15.8	B		WB TT/R	20.8	C
Wolf Road	SB L	66.3	E	Holly Lane	NB L/T/R	39.3	D
	SB TT	37.5	D	Exit 5 NB Off-Ramp	SB L	33.3	C
	SB R	21.0	C		SB T/R	11.0	B
OVERALL		79.1	E	OVERALL		22.0	C
Metro Park Drive/Airport Connector & Wolf Road				Airport Connector & Albany Shaker Road			
Airport Connector	EB L	36.2	D	Albany Shaker Road	EB TT	28.6	C
	EB T	30.8	C		EB RR	7.8	A
	EB R	19.9	B	Albany Shaker Road	WB L	59.0	E
Metro Park Drive	WB L	26.5	C		WB TT	25.0	C
	WB T/R	41.5	D	Airport Connector	NB LL	34.8	C
Wolf Road	NB L	47.9	D		NB R	9.7	A
	NB TT	23.6	C	OVERALL		24.6	C
	NB R	9.2	A	Diamond NB Ramps & Airport Connector			
Wolf Road	SB L	20.7	C	Diamond NB Off-Ramp	NB L	22.5	C
	SB TT	31.9	C		NB R	7.1	A
	SB R	14.9	B	Airport Connector	WB T	39.0	D
OVERALL		29.4	C	Airport Connector	EB L	20.4	C
Albany Shaker Road & Wolf Road					EB T	14.5	B
Albany Shaker Road	EB TT/R	19.6	B	OVERALL		22.1	C
	EB R	8.2	A	Diamond SB Ramps & Airport Connector			
Albany Shaker Road	WB L	23.9	C	Diamond SB Off-Ramp	SB L	26.0	C
	WB T T	7.0	A		SB R	17.0	B
Wolf Road	NB L	36.5	D	Airport Connector	WB L	10.5	B
	NB R	11.9	B		WB T	24.6	C
OVERALL		16.3	B	Airport Connector	EB T	32.6	C
					EB R	8.0	A
				OVERALL		18.9	B

* Delay provided in seconds per vehicle.

L=Left, T=Through, R=Right, L/T=shared Left/Through, T/R=shared Through/Right

Exhibit F.10.2.1.1-7
VISSIM Analysis Results
Intersection Level of Service
2046 (ETC+30) Diamond Alternative AM

Intersection/Approach		Delay *	LOS	Intersection/Approach		Delay *	LOS
Metro Park Drive/Airport Connector & Wolf Road				Albany Shaker Road & Old Wolf Road			
Airport Connector	EB L	24.9	C	Albany Shaker Road	EB L	25.0	C
	EB T	23.8	C		EB TT	13.0	B
	EB R	6.8	A	Albany Shaker Road	WB TT/R	17.4	B
Metro Park Drive	WB L	24.5	C	Old Wolf Road	SB LL	29.3	C
	WB T/R	25.9	C		SB R	21.0	C
Wolf Road	NB L	33.4	C	OVERALL		20.1	C
	NB TT	14.2	B	Airport Connector & Albany Shaker Road			
	NB R	6.7	A	Albany Shaker Road	EB TT	10.9	B
Wolf Road	SB L	16.3	B		EB RR	3.9	A
	SB TT	22.0	C	Albany Shaker Road	WB L	38.5	D
	SB R	6.8	A		WB TT	6.8	A
OVERALL		18.7	B	Airport Connector	NB LL	32.5	C
Albany Shaker Road & Wolf Road					NB R	6.5	A
Albany Shaker Road	EB TT/R	3.7	A	OVERALL		15.6	B
	EB R	4.8	A	Diamond NB Ramps & Airport Connector			
Albany Shaker Road	WB L	13.1	B	Diamond NB Off-Ramp	NB L	20.7	C
	WB T T	5.3	A		NB R	11.2	B
Wolf Road	NB L	31.0	C	Airport Connector	WB T	26.3	C
	NB R	9.5	A	Airport Connector	EB L	19.3	B
OVERALL		7.8	A		EB T	17.6	B
				OVERALL		18.4	B
				Diamond SB Ramps & Airport Connector			
				Diamond SB Off-Ramp	SB L	20.6	C
					SB R	6.0	A
				Airport Connector	WB L	10.6	B
					WB T	21.7	C
				Airport Connector	EB T	25.6	C
					EB R	1.5	A
				OVERALL		15.7	B

* Delay provided in seconds per vehicle.

L=Left, T=Through, R=Right, L/T=shared Left/Through, T/R=shared Through/Right

Exhibit F.10.2.1.1-8
VISSIM Analysis Results
Intersection Level of Service
2046 (ETC+30) Diamond Alternative PM

Intersection/Approach		Delay *	LOS	Intersection/Approach		Delay *	LOS
Metro Park Drive/Airport Connector & Wolf Road				Albany Shaker Road & Old Wolf Road			
Airport Connector	EB L	36.5	D	Albany Shaker Road	EB L	48.1	D
	EB T	30.9	C		EB TT	1.9	A
	EB R	20.0	C	Albany Shaker Road	WB TT/R	10.7	B
Metro Park Drive	WB L	26.6	C	Old Wolf Road	SB LL	38.8	D
	WB T/R	42.5	D		SB R	29.6	C
Wolf Road	NB L	46.3	D	OVERALL		18.4	B
	NB TT	24.6	C	Airport Connector & Albany Shaker Road			
	NB R	9.5	A	Albany Shaker Road	EB TT	29.7	C
Wolf Road	SB L	22.7	C		EB RR	8.6	A
	SB TT	32.0	C	Albany Shaker Road	WB L	59.4	E
	SB R	15.9	B		WB TT	24.6	C
OVERALL		29.6	C	Airport Connector	NB LL	34.8	C
Albany Shaker Road & Wolf Road					NB R	7.0	A
Albany Shaker Road	EB TT/R	19.4	B	OVERALL		24.8	C
	EB R	8.6	A	Diamond NB Ramps & Airport Connector			
Albany Shaker Road	WB L	23.3	C	Diamond NB Off-Ramp	NB L	22.8	C
	WB T T	7.4	A		NB R	7.5	A
Wolf Road	NB L	35.0	D	Airport Connector	WB T	42.4	D
	NB R	12.2	B	Airport Connector	EB L	23.5	C
OVERALL		16.2	B		EB T	14.7	B
				OVERALL		23.1	C
				Diamond SB Ramps & Airport Connector			
				Diamond SB Off-Ramp	SB L	28.3	C
					SB R	18.3	B
				Airport Connector	WB L	11.5	B
					WB T	25.2	C
				Airport Connector	EB T	33.1	C
					EB R	9.6	A
				OVERALL		20.1	C

* Delay provided in seconds per vehicle.

L=Left, T=Through, R=Right, L/T=shared Left/Through, T/R=shared Through/Right

10.2.1.2 Freeway Level of Service

Freeway analyses for I-87 were conducted in accordance with the Highway Capacity Manual (HCM2000) using HCS+. The analyses were conducted for the freeway segments between Exits 2 and 4, Exits 4 and 5, Exits 5 and 6, and on the segment under the proposed Connector Road and Diamond interchange. Ramp junctions were evaluated at Exits 2, 4 and 5. Weave areas were evaluated at Exit 2. All of these analyses were conducted for Existing, ETC, ETC+10 and ETC+20. The freeway segment under the proposed Connector Road and Diamond interchange was also evaluated for ETC+30.

The results of the AM and PM peak hour Flyover Alternative freeway analyses are summarized in Exhibits F.10.2.1.2-1 and F.10.2.1.2-2.

Exhibit F.10.2.1.2-1 Freeway Level of Service Diamond Alternative AM Peak Hour									
Direction	Segment/Junction	ETC (2016)		ETC+10 (2026)		ETC+20 (2036)		ETC+30 (2046)	
		Density pc/mi/ln	LOS	Density pc/mi/ln	LOS	Density pc/mi/ln	LOS	Density pc/mi/ln	LOS
FREEWAY SEGMENTS									
NB	Exit 2W on to Exit 4 off	21.6	C	22.9	C	23.9	C	-	-
	Exit 4 off to Exit 4 on	16.0	B	16.7	B	16.7	B	17.0	B
	Exit 4 on to Exit 5 off	16.3	B	17.0	B	17.3	B	17.3	B
	Exit 5 on to Exit 6 off	11.8	B	12.5	B	12.5	B	-	-
SB	Exit 6 on to Exit 5 off	29.9	D	30.4	D	30.9	D	-	-
	Exit 5 on to Exit 4 off	35.4	E	37.7	E	40.4	E	40.4	E
	Exit 4 off to Exit 4 on	30.7	D	32.0	D	33.4	D	33.1	D
	Exit 4 on to Exit 2W off	34.2	D	34.6	D	35.0	D	-	-
RAMP JUNCTIONS									
NB	Exit 2W on-ramp	18.1	B	19.2	B	20.1	C	-	-
	Exit 4 off-ramp	20.9	C	22.2	C	23.3	C	-	-
	Exit 4 on-ramp	14.7	B	15.3	B	15.5	B	-	-
	Exit 5 off-ramp	19.2	B	19.8	B	20.1	C	-	-
SB	Exit 5 on-ramp	26.1	C	27.6	C	29.2	D	-	-
	Exit 4 off-ramp	29.8	D	31.0	D	32.1	D	-	-
	Exit 4 on-ramp	26.1	C	27.2	C	28.2	D	-	-
	Exit 2W off-ramp	33.3	D	33.6	D	33.8	D	-	-
WEAVE AREAS									
NB	Exit 2E on-ramp to Exit 2W off-ramp	22.2	C	23.6	C	24.8	C	-	-
SB	Exit 2W on-ramp to Exit 2E off-ramp	29.8	D	30.3	D	31.0	D	-	-

Exhibit F.10.2.1.2-2 Freeway Level of Service Diamond Alternative PM Peak Hour									
Direction	Segment/Junction	ETC (2016)		ETC+10 (2026)		ETC+20 (2036)		ETC+30 (2046)	
		Density pc/mi/ln	LOS	Density pc/mi/ln	LOS	Density pc/mi/ln	LOS	Density pc/mi/ln	LOS
FREEWAY SEGMENTS									
NB	Exit 2W on to Exit 4 off	39.5	E	40.2	E	40.8	E	-	-
	Exit 4 off to Exit 4 on	31.1	D	31.1	D	31.5	D	31.5	D
	Exit 4 on to Exit 5 off	43.0	E	43.7	E	44.6	E	**	F
	Exit 5 on to Exit 6 off	30.1	D	30.9	D	31.7	D	-	-
SB	Exit 6 on to Exit 5 off	17.2	B	17.8	B	18.4	C	-	-
	Exit 5 on to Exit 4 off	23.9	C	24.8	C	25.5	C	25.5	C
	Exit 4 off to Exit 4 on	17.6	B	18.0	B	18.3	C	18.0	B
	Exit 4 on to Exit 2W off	25.2	C	25.8	C	26.5	D	-	-
RAMP JUNCTIONS									
NB	Exit 2W on-ramp	31.1	D	31.2	D	31.4	D	-	-
	Exit 4 off-ramp	32.4	D	32.7	D	32.9	D	-	-
	Exit 4 on-ramp	29.7	D	30.1	D	30.8	D	-	-
	Exit 5 off-ramp	36.4	E	36.6	E	36.9	E	-	-
SB	Exit 5 on-ramp	18.4	B	19.6	B	20.1	C	-	-
	Exit 4 off-ramp	22.6	C	23.5	C	24.2	C	-	-
	Exit 4 on-ramp	21.8	C	22.3	C	22.8	C	-	-
	Exit 2W off-ramp	26.3	C	26.8	C	27.3	C	-	-
WEAVE AREAS									
NB	Exit 2E on-ramp to Exit 2W off-ramp	39.4	E	40.1	E	41.2	E	-	-
SB	Exit 2W on-ramp to Exit 2E off-ramp	23.9	C	24.9	C	25.8	C	-	-

During the AM peak hour, the following locations operate at LOS E under the ETC+20 condition in the southbound direction:

- Freeway Segments
 - Exit 5 on to Exit 4 off

During the PM peak hour, the following locations operate at LOS E under the ETC+20 condition in the northbound direction:

- Freeway Segments
 - Exit 2W on TO Exit 4 off
 - Exit 4 on to Exit 5 off
- Ramp Junctions
 - Exit 5 off
- Weave Areas
 - Exit 2E on to Exit 2W off

The southbound freeway segment between Exit 5 on and Exit 4 off is estimated to degrade from LOS D to LOS E during the AM peak hour when compared to No-Build ETC+20. The operations were approaching the LOS E threshold under the No-Build conditions and higher volume for the Diamond Alternative pushed it over the LOS E threshold (>35 pc/mi/ln). The new ramp configuration and removal of the C-D Road is the primary reason for the increase in traffic volume between Exits 5 and 4.

10.2.2 Flyover Alternative

10.2.2.1 Intersection Level of Service

Summaries of the LOS for the future design years for the Flyover Alternative are presented in Exhibits F.10.2.2.1-1 through F.10.2.2.1-8. As shown in these analyses, there are intersections within the study area, but outside the project area, that continue to have movements that experience LOS E or worse at ETC+20 during the studied peak hours:

- Central Avenue & Wolf Road (PM)
- Sand Creek Road & Wolf Road (PM)
- Exit 5 SB Ramps & Watervliet-Shaker Road (PM)

At the project area intersections, all intersection approaches are estimated to operate at LOS D or better through ETC+20. There is one movement, the westbound left-turn at the Albany-Shaker Road & New Exit 4 Ramps intersection, which operates at LOS E during both peak hours. This is a relatively low volume movement and the LOS E is a result of signal timing priority given to the major through movements on Albany-Shaker Road and the Exit 4 ramps. Observation of other factors such as vehicle queue and volume-to-capacity ratio show that there is reserve capacity for the movement and the delay level is related to the cycle length used to serve the other major movements at the intersection.

The ETC+30 design year was also evaluated for the intersections adjacent to bridge structures that will be replaced as part of the project (I-87 over Albany-Shaker Road). This evaluation was completed to confirm that additional geometry resulting in wider bridge width is not needed to support the ETC+30 design year.

Exhibit F.10.2.2.1-1
VISSIM Analysis Results
Intersection Level of Service
2016 (ETC) Flyover Alternative AM

Signalized Intersections				Signalized Intersections			
Intersection/Approach		Delay *	LOS	Intersection/Approach		Delay *	LOS
Central Avenue & Wolf Road				Albany Shaker Road & Old Wolf Road			
Central Avenue	EB LL	42.1	D	Albany Shaker Road	EB L	18.2	B
	EB TT	19.7	B		EB TT	15.6	B
Central Avenue	WB TTT	38.4	D	Albany Shaker Road	WB TT/R	13.5	B
	WB R	8.5	A	Old Wolf Road	SB LL	29.4	C
Exit 2 NB Off-Ramp	NB TTT	42.5	D		SB R	21.7	C
Wolf Road	SB LL	47.8	D	OVERALL		18.0	B
	SB RR	5.4	A	Exit 5 SB Ramps & Watervliet Shaker Road			
OVERALL		29.2	C	Watervliet Shaker Road	EB L/TT/R	17.1	B
Sand Creek Road & Wolf Road				Watervliet Shaker Road	WB LT	24.5	C
Sand Creek Road	EB L	29.9	C	Exit 5 SB Off-Ramp	SB L	22.7	C
	EB T	25.6	C		SB T/R	24.3	C
	EB R	2.3	A	Sherwood Drive	SB L/T/R	26.4	C
Sand Creek Road	WB L	35.2	D	OVERALL		23.1	C
	WB T	31.8	C	Exit 5 NB Ramps & Watervliet Shaker Road			
	WB R	5.2	A	Watervliet Shaker Road	EB L	20.0	C
Wolf Road	NB L	39.5	D		EB T/R	10.0	A
	NB TT	14.2	B	Watervliet Shaker Road	WB L	9.9	A
	NB R	5.7	A		WB TT/R	10.6	B
Wolf Road	SB L	43.1	D	Holly Lane	NB L/T/R	28.2	C
	SB TT	16.4	B	Exit 5 NB Off-Ramp	SB L	21.4	C
	SB R	6.3	A		SB T/R	9.3	A
OVERALL		19.0	B	OVERALL		12.3	B
Metro Park Drive & Wolf Road				New Exit 4 Ramps & Albany Shaker Road			
Hess Station	EB L/T/R	36.7	D	Albany Shaker Road	EB TT	18.6	B
Metro Park Drive	WB L	45.6	D		EB R	6.0	A
	WB T/R	8.7	A	Albany Shaker Road	WB L	41.4	D
Wolf Road	NB L	4.4	A		WB TT	6.6	A
	NB TT	2.5	A	New Exit 4 Ramps	NB LL	22.7	C
	NB R	4.1	A		NB R	11.0	B
Wolf Road	SB L	3.3	A	OVERALL		15.2	B
	SB TT/R	1.5	A	Unsignalized Intersections			
OVERALL		3.5	A	Intersection/Approach		Delay *	LOS
Albany Shaker Road & Wolf Road				Exit 4 NB Off-Ramp & Wolf Road			
Albany Shaker Road	EB LL	51.1	D	Exit 4 NB Off-Ramp	EB R	14.8	B
	EB TT/R	7.0	A				
	EB R	5.9	A				
Albany Shaker Road	WB L	20.0	B				
	WB T T	10.8	B				
	WB R	5.0	A				
Wolf Road	NB L	28.0	C				
	NB L/TT	26.7	C				
	NB R	2.1	A				
OVERALL		12.9	B				

Exhibit F.10.2.2.1-2
VISSIM Analysis Results
Intersection Level of Service
2016 (ETC) Flyover Alternative PM

Signalized Intersections				Signalized Intersections			
Intersection/Approach		Delay *	LOS	Intersection/Approach		Delay *	LOS
Central Avenue & Wolf Road				Albany Shaker Road & Old Wolf Road			
Central Avenue	EB LL	58.0	E	Albany Shaker Road	EB L	20.8	C
	EB TT	19.8	B		EB TT	17.7	B
Central Avenue	WB TTT	54.4	D	Albany Shaker Road	WB TT/R	9.2	A
	WB R	29.2	C		Old Wolf Road	SB LL	31.7
Exit 2 NB Off-Ramp	NB TTT	54.8	D	SB R		17.8	B
Wolf Road	SB LL	62.8	E	OVERALL		18.9	B
	SB RR	30.1	C	Exit 5 SB Ramps & Watervliet Shaker Road			
OVERALL		43.4	D	Watervliet Shaker Road	EB L/TT/R	42.6	D
Sand Creek Road & Wolf Road				Watervliet Shaker Road	WB LT	23.9	C
Sand Creek Road	EB L	128.3	F	Exit 5 SB Off-Ramp	SB L	36.2	D
	EB T	107.7	F		SB T/R	6.2	A
	EB R	61.3	E	Sherwood Drive	SB L/T/R	45.6	D
Sand Creek Road	WB L	154.1	F	OVERALL		33.0	C
	WB T	169.3	F	Exit 5 NB Ramps & Watervliet Shaker Road			
	WB R	86.0	F	Watervliet Shaker Road	EB L	31.4	C
Wolf Road	NB L	67.3	E		EB T/R	12.5	B
	NB TT	34.4	C	Watervliet Shaker Road	WB L	18.9	B
	NB R	14.3	B		WB TT/R	21.0	C
Wolf Road	SB L	66.2	E	Holly Lane	NB L/T/R	32.2	C
	SB TT	38.0	D	Exit 5 NB Off-Ramp	SB L	34.1	C
	SB R	22.2	C		SB T/R	10.2	B
OVERALL		71.1	E	OVERALL		23.2	C
Metro Park Drive & Wolf Road				New Exit 4 Ramps & Albany Shaker Road			
Hess Station	EB L/T/R	36.3	D	Albany Shaker Road	EB TT	26.8	C
Metro Park Drive	WB L	45.1	D		EB R	9.5	A
	WB T/R	22.0	C	Albany Shaker Road	WB L	64.3	E
Wolf Road	NB L	7.3	A		WB TT	10.9	B
	NB TT	6.4	A	New Exit 4 Ramps	NB LL	22.8	C
	NB R	5.5	A		NB R	8.9	A
Wolf Road	SB L	8.1	A	OVERALL		18.5	B
	SB TT/R	4.0	A	Unsignalized Intersections			
OVERALL		8.4	A	Intersection/Approach		Delay *	LOS
Albany Shaker Road & Wolf Road				Exit 4 NB Off-Ramp & Wolf Road			
Albany Shaker Road	EB LL	51.3	D	Exit 4 NB Off-Ramp	EB R	5.7	A
	EB TT/R	10.0	B				
	EB R	5.5	A				
Albany Shaker Road	WB L	25.0	C				
	WB T T	19.5	B				
	WB R	15.4	B				
Wolf Road	NB L	23.4	C				
	NB L/TT	26.5	C				
	NB R	3.6	A				
OVERALL		19.5	B				

* Delay provided in seconds per vehicle.

L=Left, T=Through, R=Right, L/T=shared Left/Through, T/R=shared Through/Right

Exhibit F.10.2.2.1-3
VISSIM Analysis Results
Intersection Level of Service
2026 (ETC+10) Flyover Alternative AM

Signalized Intersections				Signalized Intersections			
Intersection/Approach		Delay *	LOS	Intersection/Approach		Delay *	LOS
Central Avenue & Wolf Road				Albany Shaker Road & Old Wolf Road			
Central Avenue	EB LL	44.6	D	Albany Shaker Road	EB L	18.3	B
	EB TT	21.1	C		EB TT	15.5	B
Central Avenue	WB TTT	40.2	D	Albany Shaker Road	WB TT/R	13.7	B
	WB R	9.2	A	Old Wolf Road	SB LL	28.6	C
Exit 2 NB Off-Ramp	NB TTT	43.7	D		SB R	21.9	C
Wolf Road	SB LL	50.0	D	OVERALL		17.8	B
	SB RR	6.5	A	Exit 5 SB Ramps & Watervliet Shaker Road			
OVERALL		31.2	C	Watervliet Shaker Road	EB L/TT/R	17.7	B
Sand Creek Road & Wolf Road				Watervliet Shaker Road	WB LT	21.6	C
Sand Creek Road	EB L	33.7	C	Exit 5 SB Off-Ramp	SB L	24.6	C
	EB T	27.9	C		SB T/R	18.3	B
	EB R	2.5	A	Sherwood Drive	SB L/T/R	28.2	C
Sand Creek Road	WB L	35.6	D	OVERALL		21.1	C
	WB T	32.5	C	Exit 5 NB Ramps & Watervliet Shaker Road			
	WB R	5.5	A	Watervliet Shaker Road	EB L	23.2	C
Wolf Road	NB L	43.4	D	Watervliet Shaker Road	EB T/R	10.4	B
	NB TT	14.5	B		WB L	11.7	B
	NB R	7.0	A	Watervliet Shaker Road	WB TT/R	12.8	B
Wolf Road	SB L	44.8	D		NB L/T/R	32.1	C
	SB TT	18.3	B	Exit 5 NB Off-Ramp	SB L	24.1	C
	SB R	7.0	A	Exit 5 NB Off-Ramp	SB T/R	10.1	B
OVERALL		20.3	C				
Metro Park Drive & Wolf Road				OVERALL		14.2	B
Hess Station	EB L/T/R	37.8	D	New Exit 4 Ramps & Albany Shaker Road			
Metro Park Drive	WB L	51.4	D	Albany Shaker Road	EB TT	23.1	C
	WB T/R	8.6	A	Albany Shaker Road	EB R	11.8	B
Wolf Road	NB L	3.0	A		WB L	50.0	D
	NB TT	2.3	A	New Exit 4 Ramps	WB TT	7.4	A
	NB R	4.2	A		NB LL	20.6	C
Wolf Road	SB L	3.1	A	New Exit 4 Ramps	NB R	11.8	B
	SB TT/R	1.6	A	OVERALL		17.0	B
OVERALL		3.5	A	Unsignalized Intersections			
Albany Shaker Road & Wolf Road				Intersection/Approach		Delay *	LOS
Albany Shaker Road	EB LL	48.4	D	Exit 4 NB Off-Ramp & Wolf Road			
	EB TT/R	6.9	A	Exit 4 NB Off-Ramp	EB R	20.3	C
	EB R	7.0	A				
Albany Shaker Road	WB L	22.6	C				
	WB T T	12.2	B				
	WB R	5.2	A				
Wolf Road	NB L	27.9	C				
	NB L/TT	27.2	C				
	NB R	2.3	A				
OVERALL		13.2	B				

* Delay provided in seconds per vehicle.

L=Left, T=Through, R=Right, L/T=shared Left/Through, T/R=shared Through/Right

Exhibit F.10.2.2.1-4
VISSIM Analysis Results
Intersection Level of Service
2026 (ETC+10) Flyover Alternative PM

Signalized Intersections				Signalized Intersections			
Intersection/Approach		Delay *	LOS	Intersection/Approach		Delay *	LOS
Central Avenue & Wolf Road				Albany Shaker Road & Old Wolf Road			
Central Avenue	EB LL	57.7	E	Albany Shaker Road	EB L	22.4	C
	EB TT	19.8	B		EB TT	17.6	B
Central Avenue	WB TTT	56.4	E	Albany Shaker Road	WB TT/R	10.8	B
	WB R	31.5	C	Old Wolf Road	SB LL	35.5	D
Exit 2 NB Off-Ramp	NB TTT	55.3	E		SB R	19.9	B
Wolf Road	SB LL	65.1	E	OVERALL		20.1	C
	SB RR	33.1	C	Exit 5 SB Ramps & Watervliet Shaker Road			
OVERALL		44.7	D	Watervliet Shaker Road	EB L/TT/R	50.5	D
Sand Creek Road & Wolf Road				Watervliet Shaker Road	WB LT	27.3	C
Sand Creek Road	EB L	137.4	F	Exit 5 SB Off-Ramp	SB L	38.1	D
	EB T	121.1	F		SB T/R	7.2	A
		EB R	72.0	E	Sherwood Drive	SB L/T/R	44.4
Sand Creek Road	WB L	170.5	F	OVERALL		37.8	D
	WB T	186.6	F	Exit 5 NB Ramps & Watervliet Shaker Road			
	WB R	102.9	F	Watervliet Shaker Road	EB L	33.7	C
Wolf Road	NB L	66.7	E		EB T/R	13.9	B
	NB TT	36.3	D	Watervliet Shaker Road	WB L	18.2	B
	NB R	14.6	B		WB TT/R	23.1	C
Wolf Road	SB L	73.9	E	Holly Lane	NB L/T/R	50.8	D
	SB TT	42.4	D	Exit 5 NB Off-Ramp	SB L	35.7	D
	SB R	28.6	C		SB T/R	12.4	B
OVERALL		77.1	E	OVERALL		25.0	C
Metro Park Drive & Wolf Road				New Exit 4 Ramps & Albany Shaker Road			
Hess Station	EB L/T/R	38.7	D	Albany Shaker Road	EB TT	30.8	C
Metro Park Drive	WB L	46.0	D		EB R	10.1	B
	WB T/R	23.4	C	Albany Shaker Road	WB L	68.3	E
Wolf Road	NB L	10.8	B		WB TT	9.9	A
	NB TT	7.5	A	New Exit 4 Ramps	NB LL	23.8	C
	NB R	5.7	A		NB R	9.7	A
Wolf Road	SB L	8.3	A	OVERALL		19.7	B
	SB TT/R	4.1	A	Unsignalized Intersections			
OVERALL		9.2	A	Intersection/Approach		Delay *	LOS
Albany Shaker Road & Wolf Road				Exit 4 NB Off-Ramp & Wolf Road			
Albany Shaker Road	EB LL	61.8	E	Exit 4 NB Off-Ramp	EB R	6.0	A
	EB TT/R	10.1	B				
	EB R	5.5	A				
Albany Shaker Road	WB L	27.1	C				
	WB T T	21.8	C				
	WB R	20.0	B				
Wolf Road	NB L	24.4	C				
	NB L/TT	29.8	C				
	NB R	3.6	A				
OVERALL		22.2	C				

* Delay provided in seconds per vehicle.

L=Left, T=Through, R=Right, L/T=shared Left/Through, T/R=shared Through/Right

Exhibit F.10.2.2.1-5
VISSIM Analysis Results
Intersection Level of Service
2036 (ETC+20) Flyover Alternative AM

Signalized Intersections				Signalized Intersections			
Intersection/Approach		Delay *	LOS	Intersection/Approach		Delay *	LOS
Central Avenue & Wolf Road				Albany Shaker Road & Old Wolf Road			
Central Avenue	EB LL	46.4	D	Albany Shaker Road	EB L	16.8	B
	EB TT	23.1	C		EB TT	7.4	A
Central Avenue	WB TTT	41.7	D	Albany Shaker Road	WB TT/R	12.8	B
	WB R	9.2	A		Old Wolf Road	SB LL	31.6
Exit 2 NB Off-Ramp	NB TTT	46.2	D	SB R		24.5	C
Wolf Road	SB LL	53.3	D	OVERALL		14.1	B
	SB RR	7.5	A	Exit 5 SB Ramps & Watervliet Shaker Road			
OVERALL		33.6	C	Watervliet Shaker Road	EB L/TT/R	22.6	C
Sand Creek Road & Wolf Road				Watervliet Shaker Road	WB LT	21.7	C
Sand Creek Road	EB L	34.9	C	Exit 5 SB Off-Ramp	SB L	28.3	C
	EB T	29.6	C		SB T/R	17.2	B
		EB R	2.8	A	Sherwood Drive	SB L/T/R	26.5
Sand Creek Road	WB L	35.2	D	OVERALL		22.5	C
	WB T	34.0	C	Exit 5 NB Ramps & Watervliet Shaker Road			
	WB R	5.5	A	Watervliet Shaker Road	EB L	26.1	C
Wolf Road	NB L	45.2	D		EB T/R	10.4	B
	NB TT	16.6	B	Watervliet Shaker Road	WB L	10.9	B
	NB R	6.6	A		WB TT/R	15.8	B
Wolf Road	SB L	47.0	D	Holly Lane	NB L/T/R	32.8	C
	SB TT	19.7	B	Exit 5 NB Off-Ramp	SB L	27.8	C
	SB R	7.4	A		SB T/R	11.5	B
OVERALL		21.8	C	OVERALL		16.7	B
Metro Park Drive & Wolf Road				New Exit 4 Ramps & Albany Shaker Road			
Hess Station	EB L/T/R	40.9	D	Albany Shaker Road	EB TT	27.3	C
Metro Park Drive	WB L	48.7	D		EB R	11.9	B
	WB T/R	9.0	A	Albany Shaker Road	WB L	61.9	E
Wolf Road	NB L	4.7	A		WB TT	11.3	B
	NB TT	2.7	A	New Exit 4 Ramps	NB LL	21.7	C
	NB R	4.5	A		NB R	15.8	B
Wolf Road	SB L	4.0	A	OVERALL		20.0	C
	SB TT/R	1.7	A	Unsignalized Intersections			
OVERALL		3.7	A	Intersection/Approach		Delay *	LOS
Albany Shaker Road & Wolf Road				Exit 4 NB Off-Ramp & Wolf Road			
Albany Shaker Road	EB LL	33.7	C	Exit 4 NB Off-Ramp	EB R	28.2	D
	EB TT/R	9.0	A				
	EB R	7.1	A				
Albany Shaker Road	WB L	23.8	C				
	WB T T	11.4	B				
	WB R	5.2	A				
Wolf Road	NB L	32.3	C				
	NB L/TT	30.7	C				
	NB R	2.4	A				
OVERALL		13.5	B				

* Delay provided in seconds per vehicle.

L=Left, T=Through, R=Right, L/T=shared Left/Through, T/R=shared Through/Right

Exhibit F.10.2.2.1-6
VISSIM Analysis Results
Intersection Level of Service
2036 (ETC+20) Flyover Alternative PM

Signalized Intersections				Signalized Intersections			
Intersection/Approach		Delay *	LOS	Intersection/Approach		Delay *	LOS
Central Avenue & Wolf Road				Albany Shaker Road & Old Wolf Road			
Central Avenue	EB LL	59.0	E	Albany Shaker Road	EB L	23.6	C
	EB TT	21.3	C		EB TT	9.1	A
Central Avenue	WB TTT	58.9	E	Albany Shaker Road	WB TT/R	8.4	A
	WB R	33.3	C	Old Wolf Road	SB LL	52.6	D
Exit 2 NB Off-Ramp	NB TTT	58.3	E		SB R	26.6	C
Wolf Road	SB LL	67.5	E	OVERALL		19.1	B
	SB RR	36.3	D	Exit 5 SB Ramps & Watervliet Shaker Road			
OVERALL		46.9	D	Watervliet Shaker Road	EB L/TT/R	64.2	E
Sand Creek Road & Wolf Road				Watervliet Shaker Road	WB LT	29.3	C
Sand Creek Road	EB L	142.2	F	Exit 5 SB Off-Ramp	SB L	40.2	D
	EB T	130.9	F		SB T/R	8.7	A
		EB R	81.3	F	Sherwood Drive	SB L/T/R	49.1
Sand Creek Road	WB L	189.1	F	OVERALL		43.6	D
	WB T	206.9	F	Exit 5 NB Ramps & Watervliet Shaker Road			
	WB R	118.5	F	Watervliet Shaker Road	EB L	34.7	C
Wolf Road	NB L	70.0	E		EB T/R	12.2	B
	NB TT	37.8	D	Watervliet Shaker Road	WB L	18.3	B
	NB R	15.9	B		WB TT/R	23.6	C
Wolf Road	SB L	81.2	F	Holly Lane	NB L/T/R	45.4	D
	SB TT	50.5	D	Exit 5 NB Off-Ramp	SB L	36.0	D
	SB R	37.1	D		SB T/R	14.2	B
OVERALL		83.1	F	OVERALL		25.0	C
Metro Park Drive & Wolf Road				New Exit 4 Ramps & Albany Shaker Road			
Hess Station	EB L/T/R	37.1	D	Albany Shaker Road	EB TT	36.4	D
Metro Park Drive	WB L	45.1	D		EB R	10.6	B
	WB T/R	19.8	B	Albany Shaker Road	WB L	73.1	E
Wolf Road	NB L	9.2	A		WB TT	13.5	B
	NB TT	7.5	A	New Exit 4 Ramps	NB LL	27.0	C
	NB R	5.8	A		NB R	14.0	B
Wolf Road	SB L	10.0	A	OVERALL		22.7	C
	SB TT/R	4.0	A	Unsignalized Intersections			
OVERALL		9.1	A	Intersection/Approach		Delay *	LOS
Albany Shaker Road & Wolf Road				Exit 4 NB Off-Ramp & Wolf Road			
Albany Shaker Road	EB LL	52.0	D	Exit 4 NB Off-Ramp	EB R	6.0	A
	EB TT/R	12.1	B				
	EB R	6.1	A				
Albany Shaker Road	WB L	25.6	C				
	WB T T	20.7	C				
	WB R	17.6	B				
Wolf Road	NB L	33.9	C				
	NB L/TT	46.0	D				
	NB R	3.7	A				
OVERALL		24.2	C				

* Delay provided in seconds per vehicle.

L=Left, T=Through, R=Right, L/T=shared Left/Through, T/R=shared Through/Right

Exhibit F.10.2.2.1-7
VISSIM Analysis Results
Intersection Level of Service
2046 (ETC+30) Flyover Alternative AM

Signalized Intersections				Signalized Intersections			
Intersection/Approach		Delay *	LOS	Intersection/Approach		Delay *	LOS
Albany Shaker Road & Wolf Road				New Exit 4 Ramps & Albany Shaker Road			
Albany Shaker Road	EB LL	49.2	D	Albany Shaker Road	EB TT	28.0	C
	EB TT/R	9.2	A		EB R	7.4	A
	EB R	8.3	A	Albany Shaker Road	WB L	78.4	E
Albany Shaker Road	WB L	24.9	C		WB TT	9.7	A
	WB T T	11.8	B	New Exit 4 Ramps	NB LL	21.3	C
	WB R	5.5	A		NB R	16.5	B
Wolf Road	NB L	31.4	C	OVERALL		20.2	C
	NB L/TT	30.0	C	Unsignalized Intersections			
	NB R	2.6	A	Intersection/Approach		Delay *	LOS
OVERALL		14.5	B	Exit 4 NB Off-Ramp & Wolf Road			
Albany Shaker Road & Old Wolf Road				Exit 4 NB Off-Ramp	EB R	81.9	F
Albany Shaker Road	EB L	20.2	C				
	EB TT	14.9	B				
Albany Shaker Road	WB TT/R	14.1	B				
Old Wolf Road	SB LL	32.1	C				
	SB R	24.1	C				
OVERALL		18.3	B				

* Delay provided in seconds per vehicle.

L=Left, T=Through, R=Right, L/T=shared Left/Through, T/R=shared Through/Right

Exhibit F.10.2.2.1-8
VISSIM Analysis Results
Intersection Level of Service
2046 (ETC+30) Flyover Alternative PM

Signalized Intersections				Signalized Intersections			
Intersection/Approach		Delay *	LOS	Intersection/Approach		Delay *	LOS
Albany Shaker Road & Wolf Road				New Exit 4 Ramps & Albany Shaker Road			
Albany Shaker Road	EB LL	82.5	F	Albany Shaker Road	EB TT	39.5	D
	EB TT/R	12.6	B		EB R	11.3	B
	EB R	6.8	A	Albany Shaker Road	WB L	78.2	E
Albany Shaker Road	WB L	31.8	C		WB TT	12.5	B
	WB T T	26.0	C	New Exit 4 Ramps	NB LL	32.0	C
	WB R	32.6	C		NB R	24.6	C
Wolf Road	NB L	30.4	C	OVERALL		26.5	C
	NB L/TT	53.1	D	Unsignalized Intersections			
	NB R	3.3	A	Intersection/Approach		Delay *	LOS
OVERALL		31.0	C				
Albany Shaker Road & Old Wolf Road				Exit 4 NB Off-Ramp & Wolf Road			
Albany Shaker Road	EB L	24.8	C	Exit 4 NB Off-Ramp	EB R	7.4	A
	EB TT	12.0	B				
Albany Shaker Road	WB TT/R	7.4	A				
Old Wolf Road	SB LL	48.5	D				
	SB R	26.5	C				
OVERALL		19.2	B				

* Delay provided in seconds per vehicle.

L=Left, T=Through, R=Right, L/T=shared Left/Through, T/R=shared Through/Right

10.2.2.2 Freeway Level of Service

Freeway analyses for I-87 were conducted in accordance with the Highway Capacity Manual (HCM2000) using HCS+. The analyses were conducted for the freeway segments between Exits 2 and 4, Exits 4 and 5, Exits 5 and 6, on the segments on the bridge over Albany-Shaker Road and on the segments under the proposed Flyover ramps. Ramp junctions were evaluated at Exits 2, 4 and 5. Weave areas were evaluated at Exit 2. All of these analyses were conducted for Existing, ETC, ETC+10 and ETC+20. The freeway segments over Albany-Shaker Road under the Flyover ramp were also evaluated for ETC+30.

The results of the AM and PM peak hour Flyover Alternative freeway analyses are summarized in Exhibits F.10.2.2.2-1 and F.10.2.2.2-2.

Exhibit F.10.2.2.2-1 Freeway Level of Service Flyover Alternative AM Peak Hour									
Direction	Segment/Junction	ETC (2016)		ETC+10 (2026)		ETC+20 (2036)		ETC+30 (2046)	
		Density pc/mi/ln	LOS	Density pc/mi/ln	LOS	Density pc/mi/ln	LOS	Density pc/mi/ln	LOS
FREEWAY SEGMENTS									
NB	Exit 2W on to Exit 4 off	21.2	C	21.9	C	22.9	C	-	-
	Exit 4 off to Exit 4 off	16.0	B	15.7	B	16.0	B	16.0	B
	Exit 4 off to Exit 4 on	14.4	B	14.4	B	14.7	B	14.4	B
	Exit 4 on to Exit 5 off	13.2	B	13.5	B	13.7	B	-	-
	Exit 5 on to Exit 6 off	12.5	B	12.8	B	13.0	B	-	-
SB	Exit 6 on to Exit 5 off	29.4	D	29.9	D	30.1	D	-	-
	Exit 5 on to Exit 4 off	35.0	D	37.7	E	40.4	E	40.4	E
	Exit 4 off to Exit 4 on	31.0	D	32.4	D	33.4	D	33.4	D
	Exit 4 on to Exit 2W off	35.4	E	35.8	E	36.2	E	-	-
	RAMP JUNCTIONS								
NB	Exit 2W on-ramp	18.0	B	18.6	B	19.5	B	-	-
	Exit 4 off-ramp to ASR	20.3	C	21.1	C	22.3	C	-	-
	Exit 4 off-ramp to Wolf	17.5	B	17.2	B	17.5	B	-	-
SB	Exit 5 on-ramp	26.1	C	27.8	C	29.5	D	-	-
	Exit 4 off-ramp	26.3	C	27.7	C	28.9	D	-	-
	Exit 4 on-ramp	27.1	C	28.5	D	29.6	D	-	-
	Exit 2W off-ramp	33.6	D	33.8	D	34.1	D	-	-
WEAVE AREAS									
NB	Exit 2E on-ramp to Exit 2W off-ramp	21.8	C	22.7	C	23.9	C	-	-
SB	Exit 2W on-ramp to Exit 2E off-ramp	32.4	D	33.1	D	33.8	D	-	-

Exhibit F.10.2.2.2-2 Freeway Level of Service Flyover Alternative PM Peak Hour									
Direction	Segment/Junction	ETC (2016)		ETC+10 (2026)		ETC+20 (2036)		ETC+30 (2046)	
		Density pc/mi/ln	LOS	Density pc/mi/ln	LOS	Density pc/mi/ln	LOS	Density pc/mi/ln	LOS
FREEWAY SEGMENTS									
NB	Exit 2W on to Exit 4 off	40.8	E	42.2	E	43.0	E	-	-
	Exit 4 off to Exit 4 off	30.8	D	31.1	D	30.8	D	29.7	D
	Exit 4 off to Exit 4 on	30.1	D	30.4	D	30.1	D	29.0	D
	Exit 4 on to Exit 5 off	30.9	D	31.2	D	31.2	D	-	-
	Exit 5 on to Exit 6 off	32.3	D	32.4	D	32.5	D	-	-
SB	Exit 6 on to Exit 5 off	17.2	B	17.9	B	18.6	C	-	-
	Exit 5 on to Exit 4 off	23.9	C	24.8	C	25.5	C	25.5	C
	Exit 4 off to Exit 4 on	19.3	C	19.9	C	19.9	C	19.6	C
	Exit 4 on to Exit 2W off	25.5	C	26.1	D	27.1	D	-	-
RAMP JUNCTIONS									
NB	Exit 2W on-ramp	31.9	D	32.3	D	32.4	D	-	-
	Exit 4 off-ramp to ASR	33.0	D	33.6	D	34.0	D	-	-
	Exit 4 off-ramp to Wolf	29.3	D	29.6	D	29.3	D	-	-
SB	Exit 5 on-ramp	18.5	B	19.3	B	20.1	C	-	-
	Exit 4 off-ramp	18.8	B	19.7	B	20.4	C	-	-
	Exit 4 on-ramp	20.7	C	21.4	C	21.6	C	-	-
	Exit 2W off-ramp	26.3	C	26.8	C	27.6	C	-	-
WEAVE AREAS									
NB	Exit 2E on-ramp to Exit 2W off-ramp	39.6	E	41.1	E	41.8	E	-	-
SB	Exit 2W on-ramp to Exit 2E off-ramp	26.7	C	26.5	C	29.2	D	-	-

During the AM peak hour, the following locations operate at LOS E under the ETC+20 condition in the southbound direction:

- Freeway Segments
 - Exit 5 on to Exit 4 off
 - Exit 4 on to Exit 2W off

During the PM peak hour, the following locations operate at LOS E under the ETC+20 condition in the northbound direction:

- Freeway Segments
 - Exit 2W on to Exit 4 off
- Weave Areas
 - Exit 2E on to Exit 2W off

The operations for some of these locations are a change from a LOS D in the No-Build condition. The southbound freeway segments from Exit 5 to Exit 4 and Exit 4 to Exit 2W were approaching the LOS E threshold under the No-Build conditions and slightly higher volume for the Flyover Alternative pushed them over the LOS E threshold (>35 pc/m/l). The new ramp configuration and removal of the C-D Road is the primary reason for the increase in traffic volume between Exits 5 and 4. The segment from Exit 4 to Exit 2W was exactly at the threshold for No-Build ETC+20 AM and adds only 150 additional vehicles for the Flyover Alternative.

10.3 Travel Time

Travel time on the network roadways was evaluated from the VISSIM models for the future No-Build and Build alternative conditions. The 2036 (ETC+20) travel time comparisons are presented in Exhibits 3.3.1.5 a and 3.3.1.5 b. These routes represent the major routes that measure whether the alternatives meets one of the key needs of the project: access improvements between I-87, Wolf Road and the Albany International Airport.

Exhibit 3.3.1.5 a Travel Time Estimates 2036 (ETC+20) Build Alternatives AM Peak Hour			
Roadway: Segment	No-Build (m:ss)	Diamond (m:ss)	Flyover (m:ss)
Northbound			
I-87: Sand Creek Overpass to Airport	6:05	4:23	3:41
I-87: Sand Creek Overpass to Exit 6 Off-Ramp	3:55	3:55	3:56
Southbound			
I-87: Exit 6 On-Ramp to Airport	7:03	6:10	4:59
I-87: Exit 6 On-Ramp to Wolf Road (Metro Park)	6:53	4:33	5:19
I-87: Exit 6 On-Ramp to Sand Creek Overpass	3:37	3:40	3:35

m:ss = minutes:seconds

Exhibit 3.3.1.5 b Travel Time Estimates 2036 (ETC+20) Build Alternatives PM Peak Hour			
Roadway: Segment	No-Build (m:ss)	Diamond (m:ss)	Flyover (m:ss)
Northbound			
I-87: Sand Creek Overpass to Airport	7:37	4:40	3:52
I-87: Sand Creek Overpass to Exit 6 Off-Ramp	4:36	4:38	4:33
Southbound			
I-87: Exit 6 On-Ramp to Airport	5:57	6:37	5:09
I-87: Exit 6 On-Ramp to Wolf Road (Metro Park)	6:05	4:49	5:23
I-87: Exit 6 On-Ramp to Sand Creek Overpass	3:46	3:43	3:41

m:ss = minutes:seconds

The Diamond Alternative reduces the expected travel time for major routes by 20% when compared to the No-Build Alternative. In the southbound direction during the AM peak hour, the travel time to the airport is reduced from 7:03 to 6:10 (0:53 reduction) and the travel time to Metro Park Road is reduced from 6:53 to 4:33 (2:20 reduction). In the northbound direction during the PM peak hour, the travel time to airport is reduced from 7:37 to 4:40 (2:57 reduction). However, the travel time to the airport in the southbound direction during the PM peak hour is estimated to be greater than the No-Build Alternative. This is a result of the longer distance a vehicle must travel to reach the Exit 4 southbound off-ramp and then to Albany-Shaker Road.

The Flyover Alternative reduces the expected travel time for major routes by 25% when compared to the No-Build Alternative. In the southbound direction during the AM peak hour, the travel time to the airport is reduced from 7:03 to 4:59 (2:07 reduction) and the travel time to Metro Park Road is reduced from 6:53 to 5:19 (1:34 reduction). In the northbound direction during the PM peak hour, the travel time to the airport is reduced from 7:37 to 3:52 (3:45 reduction).

For both alternatives, the northbound and southbound through travel times (between Sand Creek Road Overpass and Exit 6 ramps) on I-87 are approximately the same as No-Build. As a result, it is not anticipated that the Build Alternatives will increase delay for through vehicles on I-87.

Overall, the Flyover Alternative provides the most reductions in travel time when compared to the No-Build condition.

10.4 Network Delay and Distance Traveled

Network-wide measures of effectiveness (MOE's) were gathered from the VISSIM models to compare the Build alternatives. Vehicle hours of delay (VHD) and vehicle miles traveled (VMT) are both presented in Exhibit 3.3.1.7 y.

Exhibit 3.3.1.7 y Network Measures of Effectiveness 2036 (ETC+20) Design Year			
	No-Build	Diamond	Flyover
AM Peak Hour			
Vehicle Hours of Delay	274	219	195
Vehicle Miles Traveled	55,940	56,530	57,480
PM Peak Hour			
Vehicle Hours of Delay	785	402	372
Vehicle Miles Traveled	63,480	70,450	66,140

As shown, the Build alternatives dramatically reduce the VHD during the PM peak hour, with the Flyover Alternative providing slightly better VHD improvements than the Diamond Alternative. For the Diamond Alternative, the VHD decreases by 20% for the AM Peak Hour and 49% for the PM Peak Hour. For the Flyover Alternative, the VHD decreases by 29% for the AM Peak Hour, and 53% for the PM Peak Hour. The VMT increases for both of the Build alternatives compared to the No-Build condition because they both have greater volume demand than the No-Build condition (i.e. more volume is diverted to the improved interchange). So although the distance that some vehicles travel within the network is reduced due to the Build alternative geometry, the increased number of vehicles in turn causes increased VMT.

10.5 Ramp Queues

The ETC+20 design year 95th percentile queues for the I-87 off-ramps at Exits 4, 5, and 6 were determined using Synchro 7. Exhibit 3.3.1.7 z below provides a summary of the ETC+20 design year queues; the No-Build queues are provided for comparison purposes.

Exhibit 3.3.1.7 z 95 th Percentile Queues - ETC+20 Design Year No-Build & Diamond Alternative					
Approach	mvmt	No-Build AM	Diamond AM	No-Build PM	Diamond PM
Exit 4 Ramps					
Exit 4 NB Off-Ramp	L	310*	159	380	266
	R	137	103	123	41
Exit 4 SB Off-Ramp	LR	878	-	551	-
	L	-	257	-	482
	R	-	154	-	471
Exit 5 Ramps					
Exit 5 NB Off-Ramp	L	157	161	418	408
	TR	59	22	0	0
Exit 5 SB Off-Ramp	L	395	767	410	740
	TR	223	494	336	249
Exit 6 Ramps					
Exit 6 NB Off-Ramp	L	350	336	237	190
	R	50	36	50	21
Exit 6 SB Off-Ramp	L	174	147	216	219
	R	494	540	661	593

* All 95th Percentile Queues shown in feet.

As shown, all of the Diamond Alternative queues are estimated to be approximately the same or less than the No-Build queues with the exception of the Exit 5 southbound off-ramp. The Exit 5 southbound left-turn movement for both peak periods and the through/right turn movement during the AM peak hour are estimated to have longer queues than the No-Build Alternative. The longer queues at this off-ramp are a result of the elimination of the C-D Road to Old Wolf Road, and the resulting redistribution of volumes in the area. However, it is estimated that the queues for these movements will not extend back to the I-87 mainline.

It is also noted that existing queue observations show that the Exit 4 SB off-ramp often backs to the I-87 mainline during the AM peak hour. The extent of that queue is not captured in the No-Build Synchro results shown since it is a cumulative result of the southbound queue on Old Wolf Road at Albany-Shaker Road backing to the intersection with the Exit 4 SB off-ramp. Since the C-D Road is eliminated with the Diamond Alternative, this queuing condition is also eliminated.

The ETC+20 design year 95th percentile queues for the I-87 off-ramps at Exits 4, 5, and 6 were determined using Synchro 7. Exhibit 3.3.1.7 aa below provides a summary of the ETC+20 design year queues; the No-Build queues are provided for comparison purposes.

Exhibit 3.3.1.7 aa 95 th Percentile Queues - ETC+20 Design Year No-Build & Flyover Alternative					
Approach	mvmt	No-Build AM	Flyover AM	No-Build PM	Flyover PM
Exit 4 Ramps					
Exit 4 NB Off-Ramp to Wolf Rd	L	310*	-	380	-
	R	137	57	123	21
Exit 4 SB Off-Ramp to Old Wolf Rd	LR	878	-	551	-
Exit 4 Off-Ramp to ASR	L	-	367	-	728
	R	-	534	-	518
Exit 5 Ramps					
Exit 5 NB Off-Ramp	L	157	156	418	493
	TR	59	21	0	0
Exit 5 SB Off-Ramp	L	395	385	410	610
	TR	223	276	336	231
Exit 6 Ramps					
Exit 6 NB Off-Ramp	L	350	380	237	189
	R	50	53	50	14
Exit 6 SB Off-Ramp	L	174	201	216	229
	R	494	554	661	615

* All 95th Percentile Queues shown in feet.

For the Flyover Alternative, all of the Build Alternative queues are estimated to be approximately the same or less than the No-Build queues with the exception of the Exit 4 off-ramp to Albany-Shaker Road and the Exit 5 southbound left-turn movement during the PM peak hour. It is estimated that the Exit 4 off-ramp to Albany-Shaker Road queue will be longer than No-Build due to the combination of the northbound off-ramp left-turn volume and the southbound off-ramp volume at the new intersection. However, the queue is not estimated to extend back to the I-87 mainline. As with the Diamond Alternative, the Exit 5 SB off-ramp queue is estimated to be longer than the No-Build Alternative due to the elimination of the C-D road, and the resulting redistribution of volume. It is not estimated that the southbound queue will extend back to the I-87 mainline in this alternative.

Like the Diamond Alternative, since the C-D Road is eliminated with the Flyover Alternative, the existing queuing condition of the Exit 4 SB off-ramp to the I-87 mainline is eliminated.

11.0 Safety Considerations, Accident History and Analysis

NYSDOT Region 1 conducted an accident history investigation for the project study area. The accident data covered a three year period from January 1, 2007 to December 31, 2009 and covered the project study area on I-87, Wolf Road, Watervliet-Shaker Road, Albany-Shaker Road and Old Wolf Road. They provided an updated set of data that included an additional three months of data and included a signal study that was conducted at the intersection of Albany-Shaker Road & Old Wolf Road/I-87 SB on-ramp. The memos, accident records and collision diagrams are included in Attachment F.

The current High Accident Location (HAL) period is from November 1, 2007 to October 31, 2009. There were no HALs on the section of I-87 studied from RM 2016 (Colonie Town Line) to RM 2042 (just north of the Exit 5 northbound on ramp). Wolf Road (NY 910B) was a Priority Investigation Location (PIL) from RM 1010 (Computer Drive) to RM 1015 (just south of Marcus Boulevard) and from RM 1016 (Marcus Boulevard) to 1019 (Albany-Shaker Road). Watervliet-Shaker Road (NY 155) was a Safety Deficient Location (SDL) from RM 3058 (Sherwood Drive) to RM 3060 (Old Niskayuna Road).

I-87 is a six lane divided Urban Principal Arterial Interstate highway with full control of access. There were 303 total accidents on this segment of I-87 during the study period. The accident rate was 0.87 accidents per million vehicle miles (acc/mvm) which is less than the expected accident rate of 1.10 acc/mvm for similar highways statewide. There was one fatality and no accidents involving pedestrians or bicyclists.

Wolf Road is a four lane divided Urban Principal Arterial highway with free access. There were 52 accidents in the first section studied (RM 1010 to 1015) during the January 1, 2007 to March 31, 2010 study period. The accident rate was 2.41 acc/mvm which is less than the expected accident rate of 3.59 acc/mvm for similar highways statewide. There was one accident involving a pedestrian and no accidents involving bicyclists.

There were 132 accidents in the second section of Wolf Road studied (RM 1016 to 1019) and the accident rate was 9.46 acc/mvm which is greater than the expected accident rate of 3.59 acc/mvm for similar highways statewide. There were no accidents involving pedestrians or bicyclists.

Watervliet-Shaker Road is a four lane undivided Urban Minor Arterials highway with free access. There were 46 accidents on the SDL section (RM 3058 to 3061 (Feiden Lane)) evaluated during the period January 1, 2007 to September 30, 2010. The accident rate of 8.79 acc/mvm is greater than the expected accident rate of 4.27 acc/mvm for similar highways statewide. There were no accidents involving pedestrians or bicyclists.

Albany-Shaker Road (CR 151) carries NY Touring Route 155. There were 55 accidents on the section studied, and the accident rate was 1.98 acc/mvm. This rate cannot be compared to the statewide average as it is not a state route. There were no accidents involving pedestrians or bicyclists.

Old Wolf Road (CR 153) also carries NY Touring Route 155. There were 55 accidents on the section studied, and the accident rate was 5.11 acc/mvm. This rate cannot be compared to the statewide average as it is not a state route. There were no accidents involving pedestrians and one involving a bicyclist.

The majority of accidents on all the roadways reviewed in the study occurred during the peak hours and are congestion related.

A summary crash severity for the project area is provided in Exhibit 2.3.1.8 a and a summary of accident type for the project area intersections is provided in Exhibit 2.3.1.8 b.

Exhibit 2.3.1.8 a Crash Severity Jan 1, 2007 to Dec 31, 2009				
Facility Type	Non-Reportable	Property Damage Only	Personal Injury	Fatality
Non-freeway	0%	62%	38%	0%
Freeway	22%	53%	25%	0%*

* There was one fatality reported during the studied period.

Exhibit 2.3.1.8 b Crash Types: Intersections Jan 1, 2007 to Dec 31, 2009										
Link	Head On	Right Angle	Rear End	Left Turn	Fixed Object	Over take	Side swipe	Ped/ Bike	Backing	Total
Wolf Road & Metro Park Road	1	3	3	2	0	2	0	0	0	11
Wolf Road & I-87 Exit 4 NB off-ramp	0	0	9	0	0	3	0	0	0	12
Wolf Road & Albany-Shaker Road	0	10	42	27	0	6	0	0	0	85
Albany-Shaker Road & Old Wolf Road/I-87 Exit 4 SB on-ramp	0	1	11	5	1	1	2	0	0	21
Old Wolf Road & I-87 Exit 4 SB off-ramp	0	0	33	0	1	0	0	0	0	34
Watervliet-Shaker Road & I-87 Exit 5 NB ramps	0	1	2	4	2	0	0	0	0	9
Watervliet-Shaker Road & I-87 Exit 5 SB ramps	0	2	6	4	0	1	0	1	1	15
Total	1	17	106	42	4	13	2	1	1	187

The accident rates for intersections are expressed as accidents per million entering vehicles (ACC/MEV) and accident rates for roadway links are expressed as accidents per million vehicle miles (ACC/MVM). For intersections on or including State facilities, the statewide average accident rate for similar facilities is provided for comparison purposes. Accident rates for the project area intersections are summarized in Exhibit 2.3.1.8 c.

Exhibit 2.3.1.8 c Intersection Accident Rates		
Intersection	Accident Rate ACC/MEV	Statewide Average ACC/MEV
Wolf Road & Metro Park Road	0.27	0.15
Wolf Road & I-87 Exit 4 NB off-ramp	0.33	0.11
Wolf Road & Albany-Shaker Road	1.54	0.11
Albany-Shaker Road & Old Wolf Road/I-87 Exit 4 SB on-ramp	0.46	0.11
Old Wolf Road & I-87 Exit 4 SB off-ramp	1.77	0.19
Watervliet-Shaker Road & I-87 Exit 5 NB ramps	0.35	0.15
Watervliet-Shaker Road & I-87 Exit 5 SB ramps	0.66	0.15








As summarized in Exhibit 2.3.1.8 c, all of the studied intersections exceed statewide averages for similar facilities. Locations that particularly stand out as greatly exceeding the statewide average are Wolf Road & Albany-Shaker Road and Old Wolf Road & I-87 Exit 4 SB off-ramp. The predominant accident types at Wolf Road & Albany-Shaker Road were rear end and left-turn. At Old Wolf Road & I-87 Exit 4 SB off-ramp, all but one of the reported accidents were rear ends. A high occurrence of rear end accidents typically correlates to traffic congestion where vehicles are in stop-and-go traffic and/or reaching the end of forming queues.

The dismissed Upgrade Alternative did not address many of the crash patterns in the study area since the alternative only included adding additional capacity at the existing intersections and is not estimated to divert traffic to other routes. The existing C-D road between Watervliet-Shaker Road and Old Wolf Road, which also serves the Exit 4 southbound off-ramp and Exit 5 southbound on-ramp, is maintained with the Upgrade Alternative. In addition to the 34 accidents at the intersection with Old Wolf Road & I-87 SB off-ramp, another 14 accidents occurred on the C-D road during the studied period. Traffic routinely backs up on the C-D road to the Exit 4 southbound off-ramp. While it would be anticipated that the number of accidents would be reduced due to less congestion under the alternative, the geometric conditions in this area would remain the same.


The Flyover and Diamond Alternatives both remove the C-D road and the existing Exit 4 and 5 ramp configuration, therefore eliminating those accidents and resulting in an accident cost savings of \$584,000 per year (\$11,680,000 over 20 years). The traffic volumes at the Wolf Road & Albany-Shaker Road intersection are also reduced under these alternatives which will improve operations and safety. The Diamond Alternative removes the Exit 4 northbound on-ramp and reduces the peak hour volumes at this intersection by 42 percent. The Flyover Alternative reduces the peak hour volumes at this intersection by 35 percent.


The Flyover and Diamond Alternatives will also improve safety at the intersections with Albany-Shaker Road & Old Wolf Road/I-87 Exit 4 southbound on-ramp and Wolf Road & I-87 Exit 4 northbound off-ramp. The Flyover Alternative eliminates the I-87 Exit 4 southbound on-ramp at the existing intersection and modifies the I-87 Exit 4 northbound off-ramp to be unsignalized with right-turns onto Wolf Road southbound only. The Diamond Alternative eliminates the I-87 Exit 4 southbound on-ramp and the I-87 Exit 4 northbound off-ramp at their existing intersections. These modifications reduce volume and congestion.

ATTACHMENT A
FIGURES



NOTE: NOT TO SCALE

 III Winners Circle, PO Box 5269 · Albany, NY 12205-0269 Main: (518) 453-4500 • www.ch2m.com/papers.com	2036 NO-BUILD AM PEAK HOUR TRAFFIC VOLUMES		FIGURE F-7
INTERSTATE 87 (I-87) EXIT 3 / 4 ACCESS ACCESS IMPROVEMENTS			DATE: 1/12



NOTE: NOT TO SCALE



III Winners Circle, PO Box 5269 · Albany, NY 12205-0269
Main: (518) 463-4500 · www.chacompanies.com



2009 EXISTING HIGHWAY AM PEAK HOUR TRAFFIC VOLUMES

INTERSTATE 87 (I-87) EXIT 3 / 4
ACCESS IMPROVEMENTS

FIGURE

F-11

DATE: 8/13



NOTE: NOT TO SCALE



III Winners Circle, PO Box 5269 · Albany, NY 12205-0269
Main: (518) 463-4500 · www.chacompanies.com



2009 EXISTING HIGHWAY PM PEAK HOUR TRAFFIC VOLUMES

INTERSTATE 87 (I-87) EXIT 3 / 4
ACCESS IMPROVEMENTS

FIGURE

F-12

DATE: 8/13



NOTE: NOT TO SCALE



III Winners Circle, PO Box 5269 · Albany, NY 12205-0269
Main: (518) 463-4500 · www.chacompanies.com



2016 NO-BUILD HIGHWAY AM PEAK HOUR TRAFFIC VOLUMES

INTERSTATE 87 (I-87) EXIT 3 / 4
ACCESS IMPROVEMENTS

FIGURE

F-13

DATE: 8/13



NOTE: NOT TO SCALE



Ill Winners Circle, PO Box 5269 · Albany, NY 12205-0269
Main: (518) 463-4500 · www.ch2acompanies.com



2016 NO-BUILD HIGHWAY PM PEAK HOUR TRAFFIC VOLUMES

INTERSTATE 87 (I-87) EXIT 3 / 4
ACCESS IMPROVEMENTS

FIGURE

F-14

DATE: 8/13



NOTE: NOT TO SCALE



111 Winners Circle, PO Box 5269 · Albany, NY 12205-0269
Main: (518) 463-4500 · www.ch2acompanies.com



2026 NO-BUILD HIGHWAY AM PEAK HOUR TRAFFIC VOLUMES

INTERSTATE 87 (I-87) EXIT 3 / 4
ACCESS IMPROVEMENTS

FIGURE

F-15

DATE: 8/13



NOTE: NOT TO SCALE



Ill Winners Circle, PO Box 5269 · Albany, NY 12205-0269
Main: (518) 463-4500 · www.ch2acompanies.com


2026 NO-BUILD HIGHWAY PM PEAK HOUR TRAFFIC VOLUMES

INTERSTATE 87 (I-87) EXIT 3 / 4
ACCESS IMPROVEMENTS

FIGURE

F-16

DATE: 8/13



NOTE: NOT TO SCALE



Ill Winners Circle, PO Box 5269 · Albany, NY 12205-0269
Main: (518) 463-4500 · www.ch2acompanies.com


**2036 NO-BUILD HIGHWAY
AM PEAK HOUR TRAFFIC VOLUMES**

**INTERSTATE 87 (I-87) EXIT 3 / 4
ACCESS IMPROVEMENTS**

FIGURE

F-17

DATE: 8/13



NOTE: NOT TO SCALE



Ill Winners Circle, PO Box 5269 · Albany, NY 12205-0269
Main: (518) 463-4500 · www.ch2acompanies.com

2036 NO-BUILD HIGHWAY PM PEAK HOUR TRAFFIC VOLUMES


INTERSTATE 87 (I-87) EXIT 3 / 4
ACCESS IMPROVEMENTS

FIGURE

F-18

DATE: 8/13

Saved: 12/21/2011 10:21:14 AM
 FILE: U:\9456\ACAD\31\ACAD\2008-2009 ANALYSIS\DEIS FIGURES 2012\2046 AM NO-BUILD HIGHWAY VOL.DWG
 User: Kinley, James
 PLOTTED: 1/9/2012 5:07:41 PM



NOTE: NOT TO SCALE



III Winners Circle, PO Box 5269 · Albany, NY 12205-0269
 Maint: (518) 453-4500 · www.chacompanies.com

2046 NO-BUILD HIGHWAY AM PEAK HOUR TRAFFIC VOLUMES


INTERSTATE 87 (I-87) EXIT 3 / 4
ACCESS IMPROVEMENTS

FIGURE

F-19

DATE: 1/12

Saved: 12/21/2011 10:22:31 AM Plotted: 1/9/2012 5:12:59 PM User: Kinley, James
 FILE: U:\9456\ACAD\31\ACAD\2008-2009 ANALYSIS\DEIS FIGURES 2012\2046 PM NO-BUILD HIGHWAY VOL.DWG



NOTE: NOT TO SCALE



III Winners Circle, PO Box 5269 · Albany, NY 12205-0269
 Maint: (518) 453-4500 · www.chacompanies.com


2046 NO-BUILD HIGHWAY PM PEAK HOUR TRAFFIC VOLUMES


INTERSTATE 87 (I-87) EXIT 3 / 4
ACCESS IMPROVEMENTS











FIGURE

F-20


DATE: 1/12







NOTE: NOT TO SCALE



III Winans Circle, PO Box 5269 - Albany, NY 12205-0269
Main: (518) 453-4500 • www.ctscorporates.com


2036 DIAMOND ALTERNATIVE
AM PEAK HOUR TRAFFIC VOLUMES


INTERSTATE 87 (I-87) EXIT 3 / 4 ACCESS
ACCESS IMPROVEMENTS


FIGURE

F-25

DATE: 12/12







NOTE: NOT TO SCALE



III Winners Circle, PO Box 5269 · Albany, NY 12205-0269
Main: (518) 463-4500 · www.chacompanies.com


2016 DIAMOND ALTERNATIVE HIGHWAY AM PEAK HOUR TRAFFIC VOLUMES

INTERSTATE 87 (I-87) EXIT 3 / 4
ACCESS IMPROVEMENTS

FIGURE

F-29

DATE: 8/13



NOTE: NOT TO SCALE



III Winners Circle, PO Box 5269 · Albany, NY 12205-0269
Main: (518) 463-4500 · www.chacompanies.com


2016 DIAMOND ALTERNATIVE HIGHWAY PM PEAK HOUR TRAFFIC VOLUMES

INTERSTATE 87 (I-87) EXIT 3 / 4
ACCESS IMPROVEMENTS

FIGURE

F-30

DATE: 8/13



NOTE: NOT TO SCALE



Ill Winners Circle, PO Box 5269 · Albany, NY 12205-0269
Main: (518) 463-4500 · www.chacompanies.com


2026 DIAMOND ALTERNATIVE HIGHWAY AM PEAK HOUR TRAFFIC VOLUMES

INTERSTATE 87 (I-87) EXIT 3 / 4
ACCESS IMPROVEMENTS

FIGURE

F-31

DATE: 8/13



NOTE: NOT TO SCALE



III Winners Circle, PO Box 5269 · Albany, NY 12205-0269
Main: (518) 463-4500 · www.chacompanies.com


2026 DIAMOND ALTERNATIVE HIGHWAY PM PEAK HOUR TRAFFIC VOLUMES

INTERSTATE 87 (I-87) EXIT 3 / 4
ACCESS IMPROVEMENTS

FIGURE

F-32

DATE: 8/13



NOTE: NOT TO SCALE



III Winners Circle, PO Box 5269 · Albany, NY 12205-0269
Main: (518) 463-4500 · www.chacompanies.com

2036 DIAMOND ALTERNATIVE HIGHWAY AM PEAK HOUR TRAFFIC VOLUMES


INTERSTATE 87 (I-87) EXIT 3 / 4
ACCESS IMPROVEMENTS

FIGURE

F-33

DATE: 8/13

Saved: 12/31/2012 11:06:19 AM Plotted: 8/27/2013 11:27:58 AM User: Gray, Timmalyn
 FILE: U:\9456\ACAD\31\ACAD\2008-2009 ANALYSIS\DEIS FIGURES 2012\2036 PM DIAMOND HIGHWAY VOL.DWG



NOTE: NOT TO SCALE



111 Winners Circle, PO Box 5269 · Albany, NY 12205-0269
 Main: (518) 463-4500 · www.chacompanies.com

2036 DIAMOND ALTERNATIVE HIGHWAY PM PEAK HOUR TRAFFIC VOLUMES


INTERSTATE 87 (I-87) EXIT 3 / 4
 ACCESS IMPROVEMENTS

FIGURE

F-34

DATE: 8/13

Saved: 2/24/2012 9:17:49 AM Plotted: 12/31/2012 9:49:29 AM User: Kinley, James
 FILE: U:\9456\ACAD\31\ACAD\2008-2009 ANALYSIS\DEIS FIGURES 2012\2046 AM DIAMOND HIGHWAY VOL.DWG



NOTE: NOT TO SCALE



III Winners Circle, PO Box 5269 · Albany, NY 12205-0269
 Maint: (518) 453-4500 · www.chacompanies.com

2046 DIAMOND ALTERNATIVE HIGHWAY AM PEAK HOUR TRAFFIC VOLUMES


INTERSTATE 87 (I-87) EXIT 3 / 4
ACCESS IMPROVEMENTS

FIGURE

F-35

DATE: 12/12

Saved: 2/24/2012 9:17:46 AM Plotted: 12/31/2012 9:50:27 AM User: Kinley, James
 FILE: U:\9456\ACAD\31\ACAD\2008-2009 ANALYSIS\DEIS FIGURES 2012\2046 PM DIAMOND HIGHWAY VOL.DWG



NOTE: NOT TO SCALE



III Winners Circle, PO Box 5269 · Albany, NY 12205-0269
 Maint: (518) 453-4500 · www.chacompanies.com




2046 DIAMOND ALTERNATIVE HIGHWAY PM PEAK HOUR TRAFFIC VOLUMES

INTERSTATE 87 (I-87) EXIT 3 / 4
ACCESS IMPROVEMENTS

FIGURE

F-36





DATE: 12/12



GRID NORTH

NOTE: NOT TO SCALE

 III Winners Circle, PO Box 5269 · Albany, NY 12205-0269 Mair: (518) 452-4300 • www.chmcompiles.com	
2016 FLYOVER ALTERNATIVE AM PEAK HOUR TRAFFIC VOLUMES	
INTERSTATE 87 (I-87) EXIT 3 / 4 ACCESS ACCESS IMPROVEMENTS	
FIGURE	F-37
DATE: 12/12	



NOTE: NOT TO SCALE



III Winner's Circle, PO Box 5269 • Albany, NY 12205-0269
Main: (518) 453-4500 • www.chacompanies.com

2046 FLYOVER ALTERNATIVE AM PEAK HOUR TRAFFIC VOLUMES





INTERSTATE 87 (I-87) EXIT 3 / 4 ACCESS

ACCESS IMPROVEMENTS


FIGURE

F-43

DATE: 12/12



NOTE: NOT TO SCALE



III Winners Circle, PO Box 5269 • Albany, NY 12205-0269
Main: (518) 453-4500 • www.chacompanies.com

2046 FLYOVER ALTERNATIVE PM PEAK HOUR TRAFFIC VOLUMES


INTERSTATE 87 (I-87) EXIT 3 / 4 ACCESS

ACCESS IMPROVEMENTS

FIGURE

F-44

DATE: 12/12



NOTE: NOT TO SCALE



Ill Winners Circle, PO Box 5269 · Albany, NY 12205-0269
Main: (518) 463-4500 · www.ch2m.com

2016 FLYOVER ALTERNATIVE HIGHWAY AM PEAK HOUR TRAFFIC VOLUMES


INTERSTATE 87 (I-87) EXIT 3 / 4
ACCESS IMPROVEMENTS

FIGURE

F-45

DATE: 8/13

Saved: 12/31/2012 11:06:52 AM Plotted: 8/27/2013 11:31:07 AM User: Gray, Timmalyn
 FILE: U:\9456\ACAD\31\ACAD\2008-2009 ANALYSIS\DEIS FIGURES 2012\2016 PM FLYOVER HIGHWAY VOL.DWG



NOTE: NOT TO SCALE



111 Winners Circle, PO Box 5269 · Albany, NY 12205-0269
 Main: (518) 463-4500 · www.ch2acompanies.com

2016 FLYOVER ALTERNATIVE HIGHWAY PM PEAK HOUR TRAFFIC VOLUMES


INTERSTATE 87 (I-87) EXIT 3 / 4
 ACCESS IMPROVEMENTS

FIGURE

F-46

DATE: 8/13

Saved: 12/31/2012 11:06:50 AM Plotted: 8/27/2013 11:32:56 AM User: Gray, Timmelyn
 FILE: U:\9456\ACAD\31\ACAD\2008-2009 ANALYSIS\DEIS FIGURES 2012\2026 AM FLYOVER HIGHWAY VOL.DWG



NOTE: NOT TO SCALE



CH2M
 111 Winners Circle, PO Box 5269 · Albany, NY 12205-0269
 Main: (518) 463-4500 · www.ch2m.com

2026 FLYOVER ALTERNATIVE HIGHWAY AM PEAK HOUR TRAFFIC VOLUMES


INTERSTATE 87 (I-87) EXIT 3 / 4
 ACCESS IMPROVEMENTS

FIGURE

F-47

DATE: 8/13

Saved: 12/31/2012 11:06:49 AM Plotted: 8/27/2013 11:34:34 AM User: Gray, Timmelyn
 FILE: U:\9456\ACAD\31\ACAD\2008-2009 ANALYSIS\DEIS FIGURES 2012\2026 PM FLYOVER HIGHWAY VOL.DWG



NOTE: NOT TO SCALE



Ill Winners Circle, PO Box 5269 · Albany, NY 12205-0269
 Main: (518) 463-4500 · www.ch2acompanies.com

2026 FLYOVER ALTERNATIVE HIGHWAY PM PEAK HOUR TRAFFIC VOLUMES


INTERSTATE 87 (I-87) EXIT 3 / 4
ACCESS IMPROVEMENTS

FIGURE

F-48

DATE: 8/13

Saved: 12/31/2012 11:06:47 AM Plotted: 8/27/2013 11:35:48 AM User: Gray, Timmelyn
 FILE: U:\9456\ACAD\31\ACAD\2008-2009 ANALYSIS\DEIS FIGURES 2012\2036 AM FLYOVER HIGHWAY VOL.DWG



NOTE: NOT TO SCALE



111 Winners Circle, PO Box 5269 · Albany, NY 12205-0269
 Main: (518) 463-4500 · www.ch2acompanies.com


2036 FLYOVER ALTERNATIVE HIGHWAY AM PEAK HOUR TRAFFIC VOLUMES

INTERSTATE 87 (I-87) EXIT 3 / 4
 ACCESS IMPROVEMENTS

FIGURE

F-49

DATE: 8/13



NOTE: NOT TO SCALE



Ill Winners Circle, PO Box 5269 · Albany, NY 12205-0269
 Main: (518) 463-4500 · www.ch2m.com

2036 FLYOVER ALTERNATIVE HIGHWAY PM PEAK HOUR TRAFFIC VOLUMES


INTERSTATE 87 (I-87) EXIT 3 / 4
 ACCESS IMPROVEMENTS

FIGURE

F-50

DATE: 8/13

Saved: 2/24/2012 9:18:07 AM Plotted: 12/31/2012 9:21:55 AM User: Kinley, James
 FILE: U:\9456\ACAD\31\ACAD\2008-2009 ANALYSIS\DEIS FIGURES 2012\2046 AM FLYOVER HIGHWAY VOL.DWG



III Winners Circle, PO Box 5269 · Albany, NY 12205-0269
 Maint: (518) 453-4500 · www.chacompanies.com

2046 FLYOVER ALTERNATIVE HIGHWAY AM PEAK HOUR TRAFFIC VOLUMES


INTERSTATE 87 (I-87) EXIT 3 / 4
ACCESS IMPROVEMENTS

FIGURE

F-51

DATE: 12/12

Saved: 2/24/2012 9:18:04 AM Plotted: 12/31/2012 9:23:49 AM User: Kinley, James
 FILE: U:\9456\ACAD\31\ACAD\2008-2009 ANALYSIS\DEIS FIGURES 2012\2046 PM FLYOVER HIGHWAY VOL.DWG



NOTE: NOT TO SCALE



111 Winners Circle, PO Box 5269 · Albany, NY 12205-0269
 Main: (518) 453-4500 · www.ch2m.com

2046 FLYOVER ALTERNATIVE HIGHWAY PM PEAK HOUR TRAFFIC VOLUMES


INTERSTATE 87 (I-87) EXIT 3 / 4
 ACCESS IMPROVEMENTS

FIGURE

F-52

DATE: 12/12

**ATTACHMENT B
TRAFFIC COUNT DATA**



CHRA
 III Winners Circle, P.O. Box 5269
 Albany, NY 12205-0269
 518-453-4500
 www.chacompanies.com

Exit 3/Exit 4
 Old Wolf Road/Albany-Shaker Road
 AM
 7 to 9

File Name : Albany Shaker Road & Old Wolf Road AM
 Site Code : 01270901
 Start Date : 1/27/2009
 Page No : 1


Groups Printed- Passenger Cars - SU Trucks & Buses - MU Trucks

Start Time	Old Wolf Road Southbound						Albany-Shaker Road Westbound						On-Ramp Northbound						Albany-Shaker Road Eastbound					
	Right	Thru	Left	Peds	App. Total		Right	Thru	Left	Peds	App. Total		Right	Thru	Left	Peds	App. Total		Right	Thru	Left	Peds	App. Total	Int. Total
07:00 AM	83	11	138	0	232		21	100	33	2	156		0	0	0	0	0		38	104	16	0	158	546
07:15 AM	80	6	187	0	273		24	151	51	0	226		0	0	0	0	0		46	114	22	0	182	681
07:30 AM	104	7	198	0	309		37	195	64	0	296		0	0	0	0	0		62	133	20	0	215	820
07:45 AM	121	12	219	0	352		24	236	56	0	316		0	0	0	0	0		51	135	28	0	214	882
Total	388	36	742	0	1166		106	682	204	2	994		0	0	0	0	0		197	486	86	0	769	2929
08:00 AM	86	9	194	0	289		23	199	56	0	278		0	0	0	0	0		58	161	24	0	243	810
08:15 AM	101	7	229	0	337		33	200	70	0	303		0	0	0	0	0		61	121	15	0	197	837
08:30 AM	76	11	212	1	300		35	154	60	0	249		0	0	0	0	0		61	157	17	0	235	784
08:45 AM	81	10	272	0	363		25	150	50	0	225		0	0	0	0	0		65	97	14	0	176	764
Total	344	37	907	1	1289		116	703	236	0	1055		0	0	0	0	0		245	536	70	0	851	3195
Grand Total	732	73	1649	1	2455		222	1385	440	2	2049		0	0	0	0	0		442	1022	156	0	1620	6124
Apprch %	29.8	3	67.2	0			10.8	67.6	21.5	0.1			0	0	0	0	0		27.3	63.1	9.6	0		
Total %	12	1.2	26.9	0	40.1		3.6	22.6	7.2	0	33.5		0	0	0	0	0		7.2	16.7	2.5	0	26.5	
Passenger Cars																								
% Passenger Cars	97	89	98.2	100	97.6		91.9	96.7	95.2	100	95.9		0	0	0	0	0		96.6	97	89.7	0	96.2	96.6
SU Trucks & Buses	21	4	24	0	49		11	37	17	0	65		0	0	0	0	0		10	28	16	0	54	168
% SU Trucks & Buses	2.9	5.5	1.5	0	2		5	2.7	3.9	0	3.2		0	0	0	0	0		2.3	2.7	10.3	0	3.3	2.7
MU Trucks	1	4	6	0	11		7	9	4	0	20		0	0	0	0	0		5	3	0	0	8	39
% MU Trucks	0.1	5.5	0.4	0	0.4		3.2	0.6	0.9	0	1		0	0	0	0	0		1.1	0.3	0	0	0.5	0.6

1111 Winners Circle, P.O. Box 5269
Albany, NY 12205-0269
518-453-4500
www.chacompanies.com

Old Wolf Road/Albany-Shaker Road

File Name : Albany Shaker Road & Old Wolf Road AM
Site Code : 01270901
Start Date : 1/27/2009
Page No : 2




CMA
 III Winners Circle, P.O. Box 5269
 Albany, NY 12205-0269
 518-453-4500
 www.chacompanies.com

File Name : Albany Shaker Road & Old Wolf Road AM
 Site Code : 01270901
 Start Date : 1/27/2009
 Page No : 3

Exit 3/Exit 4
 Old Wolf Road/Albany-Shaker Road
 AM
 7 to 9


Start Time	Old Wolf Road Southbound						Albany-Shaker Road Westbound						On-Ramp Northbound						Albany-Shaker Road Eastbound					
	Right	Thru	Left	Peds	App. Total		Right	Thru	Left	Peds	App. Total		Right	Thru	Left	Peds	App. Total		Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour Analysis From 07:00 AM to 08:45 AM - Peak 1 of 1																								
Peak Hour for Entire Intersection Begins at 07:30 AM																								
07:30 AM	104	7	198	0	309		37	195	64	0	316		0	0	0	0	0		62	133	20	0	214	882
07:45 AM	121	12	219	0	352		24	236	56	0	278		0	0	0	0	0		51	135	28	0	243	810
08:00 AM	86	9	194	0	289		23	199	56	0	303		0	0	0	0	0		58	161	24	0	197	837
08:15 AM	101	7	229	0	337		33	200	70	0	1193		0	0	0	0	0		61	121	15	0	869	3349
Total Volume	412	35	840	0	1287		117	830	246	0	944		0	0	0	0	0		232	550	87	0	894	
% App. Total	32	2.7	65.3	0	.914		9.8	69.6	20.6	0	.944		.000	.000	.000	.000	.000		26.7	63.3	10	0	.894	.949
PHF	.851	.729	.917	.000	.914		.791	.879	.879	.000	.944		.000	.000	.000	.000	.000		.935	.854	.777	.000	.894	.949
Passenger Cars	399	32	824	0	1255		108	808	233	0	1149		0	0	0	0	0		225	533	81	0	839	3243
% Passenger Cars	96.8	91.4	98.1	0	97.5		92.3	97.3	94.7	0	96.3		0	0	0	0	0		97.0	96.9	93.1	0	96.5	96.8
SU Trucks & Buses	12	0	13	0	25		6	16	10	0	32		0	0	0	0	0		5	16	6	0	27	84
% SU Trucks & Buses	2.9	0	1.5	0	1.9		5.1	1.9	4.1	0	2.7		0	0	0	0	0		2.2	2.9	6.9	0	3.1	2.5
MU Trucks	1	3	3	0	7		3	6	3	0	12		0	0	0	0	0		2	1	0	0	3	22
% MU Trucks	0.2	8.6	0.4	0	0.5		2.6	0.7	1.2	0	1.0		0	0	0	0	0		0.9	0.2	0	0	0.3	0.7



CTA

File Name : Albany Shaker Road & Wolf Road AM
Site Code : 01270916
Start Date : 1/27/2009
Page No : 1

Groups Printed- Passenger Cars - SU Trucks & Buses - MU Trucks																					
On-Ramp Southbound					Albany-Shaker Road Westbound					Wolf Road Northbound					Albany-Shaker Road Eastbound						
Start Time	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total					
07:00 AM	0	0	0	1	1	44	89	45	0	178	51	32	107	0	190	115	104	21	0	240	609
07:15 AM	0	0	0	0		37	120	62	0	219	48	35	124	0	207	187	138	27	0	352	778
07:30 AM	0	0	0	0	0	52	149	77	0	278	65	45	175	0	285	155	173	28	2	358	921
07:45 AM	0	0	0	0		49	121	89	1	260	89	49	160	0	298	159	128	31	0	318	876
Total	0	0	0	1	1	182	479	273	1	935	253	161	566	0	980	616	543	107	2	1268	3184
08:00 AM	0	0	0	0	0	50	145	74	0	269	90	39	147	0	276	191	152	22	0	365	910
08:15 AM	0	0	0	0	0	39	140	96	0	275	89	54	132	0	275	197	155	19	0	371	921
08:30 AM	0	0	0	0	0	44	125	67	0	236	66	52	130	0	248	215	124	21	0	360	844
08:45 AM	0	0	0	0	0	38	70	83	0	191	72	33	111	1	217	212	133	23	0	368	776
Total	0	0	0	0	0	171	480	320	0	971	317	178	520	1	1016	815	564	85	0	1464	3451
Grand Total	0	0	0	1	1	353	959	593	1	1906	570	339	1086	1	1996	1431	1107	192	2	2732	6635
Approach %	0	0	0	100		18.5	50.3	31.1	0.1		28.6	17	54.4	0.1		52.4	40.5	7	0.1		
Total %	0	0	0	0	0	5.3	14.5	8.9	0	28.7	8.6	5.1	16.4	0	30.1	21.6	16.7	2.9	0	41.2	
Passenger Cars																					
% Passenger Cars	0	0	0	100	100	98.9	98.2	99	0	98.5	98.8	97.6	97	100	97.6	99.4	98.8	99	100	99.1	98.5
SU Trucks & Buses	0	0	0	0	0	2	15	5	1	23	5	5	17	0	27	9	9	2	0	20	70
% SU Trucks & Buses	0	0	0	0	0	0.6	1.6	0.8	100	1.2	0.9	1.5	1.6	0	1.4	0.6	0.8	1	0	0.7	1.1
MU Trucks	0	0	0	0	0	2	2	1	0	5	2	3	16	0	21	0	4	0	0	4	30
% MU Trucks	0	0	0	0	0	0.6	0.2	0.2	0	0.3	0.4	0.9	1.5	0	1.1	0	0.4	0	0	0.1	0.5



CRA

III Winners Circle, P.O. Box 5269
Albany, NY 12205-0269
518-453-4500
www.chacompanies.com

Exit 3/Exit 4

Albany Shaker Road & Wolf Road

AM

7 to 9


File Name : Albany Shaker Road & Wolf Road AM

Site Code : 01270916

Start Date : 1/27/2009

Page No : 3

	On-Ramp Southbound					Albany-Shaker Road Westbound					Wolf Road Northbound					Albany-Shaker Road Eastbound					
Start Time	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour Analysis From 07:00 AM to 08:45 AM - Peak 1 of 1																					
Peak Hour for Entire Intersection Begins at 07:30 AM																					
07:30 AM	0	0	0	0	0	52	149			278		45	175			173	28		2		921
07:45 AM	0	0	0	0	0	49	121	89	1	260		49	160	0	298	159	128	31	0	318	876
08:00 AM	0	0	0	0	0	50	145	74	0	269		39	147	0	276	191	152	22	0	365	910
08:15 AM	0	0	0	0	0	39	140	96	0	275		54	132	0	275	197	155	19	0	371	921
Total Volume	0	0	0	0	0	190	555	336	1	1082		333	614	0	1134	702	608	100	2	1412	3628
% App. Total	0	0	0	0	0	17.6	51.3	31.1	0.1			16.5	54.1	0		49.7	43.1	7.1	0.1		
PHF	.000	.000	.000	.000	.000	.913	.931	.875	.250	.973		.866	.877	.000	.951	.891	.879	.806	.250	.951	.985
Passenger Cars	0	0	0	0	0	188	550	334	0	1072		329	597	0	1107	699	602	98	2	1401	3580
% Passenger Cars	0	0	0	0	0	98.9	99.1	99.4	0	99.1		98.8	97.2	0	97.6	99.6	99.0	98.0	100	99.2	98.7
SU Trucks & Buses	0	0	0	0	0	1	4	2	1	8		3	7	0	13	3	6	2	0	11	32
% SU Trucks & Buses	0	0	0	0	0	0.5	0.7	0.6	100	0.7		0.9	1.1	0	1.1	0.4	1.0	2.0	0	0.8	0.9
MU Trucks	0	0	0	0	0	1	1	0	0	2		1	10	0	14	0	0	0	0	0	16
% MU Trucks	0	0	0	0	0	0.5	0.2	0	0	0.2		0.3	1.6	0	1.2	0	0	0	0	0	0.4



CH/A
 III Winners Circle, P.O. Box 5269
 Albany, NY 12205-0269
 518-453-4500
 www.chacompanies.com

Exit 3/Exit 4
 Exit 4 NB Off-Ramp
 AM
 7-9

File Name : Exit 4 NB Off-Ramp
 Site Code : 00000000
 Start Date : 1/27/2009
 Page No : 1


Groups Printed- Passenger Cars - SU Trucks & Buses - MU Trucks

Group 1 Limited - Passenger Cars - SU Trucks & Buses - MU Trucks																								
Start Time	Southbound						Westbound						Northbound						Exit 4 Off-Ramp Eastbound					
	Right	Thru	Left	Other	App. Total		Right	Thru	Left	Other	App. Total		Right	Thru	Left	Other	App. Total		Right	Thru	Left	Other	App. Total	Int. Total
07:00 AM	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0	0		24	0	71	0	95
07:15 AM	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0	0		28	0	94	0	122
07:30 AM	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0	0		34	0	150	0	184
07:45 AM	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0	0		66	0	194	0	260
Total	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0	0		152	0	509	0	661
08:00 AM	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0	0		58	0	142	0	200
08:15 AM	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0	0		63	0	143	0	206
08:30 AM	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0	0		59	0	124	0	183
08:45 AM	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0	0		56	0	124	1	181
Total	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0	0		236	0	533	1	770
Grand Total	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0	0		388	0	1042	1	1431
Approach %	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0	0		27.1	0	72.8	0.1	100
Total %	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0	0		27.1	0	72.8	0.1	100
Passenger Cars	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0	0		99.2	0	97.5	100	98
% Passenger Cars	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0	0		2	0	19	0	21
SU Trucks & Buses	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0	0		0.5	0	1.8	0	1.5
% SU Trucks & Buses	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0	0		1	0	7	0	8
MU Trucks	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0	0		0.3	0	0.7	0	0.6
% MU Trucks	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0	0		0.3	0	0.7	0	0.6

CHA
 III Winners Circle, P.O. Box 5269
 Albany, NY 12205-0269
 518-453-4500
 www.chacompanies.com

Exit 3/Exit 4
 Exit 4 NB Off-Ramp
 AM
 7-9

File Name : Exit 4 NB Off-Ramp
 Site Code : 00000000
 Start Date : 1/27/2009
 Page No : 2



CHA
 III Winners Circle, P.O. Box 5269
 Albany, NY 12205-0269
 518-453-4500
 www.chacompanies.com

Exit 3/Exit 4
 Exit 4 NB Off-Ramp
 AM
 7-9


File Name : Exit 4 NB Off-Ramp
 Site Code : 00000000
 Start Date : 1/27/2009
 Page No : 3

Start Time	Southbound					Westbound					Northbound					Exit 4 Off-Ramp Eastbound				
	Right	Thru	Left	Other	App. Total	Right	Thru	Left	Other	App. Total	Right	Thru	Left	Other	App. Total	Right	Thru	Left	Other	App. Total
Peak Hour Analysis From 07:00 AM to 08:45 AM - Peak 1 of 1																				
Peak Hour for Entire Intersection Begins at 07:30 AM																				
07:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	34	0	150	0	184
07:45 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	66	0	194	0	260
08:00 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	58	0	142	0	200
08:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	63	0	143	0	206
Total Volume	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	221	0	629	0	850
% App. Total	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	26	0	74	0	850
PHF	.000	.000	.000	.000	.000	.000	.000	.000	.000	.000	.000	.000	.000	.000	.000	.837	.000	.811	.000	.817
Passenger Cars	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	220	0	613	0	833
% Passenger Cars	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	99.5	0	97.5	0	98.0
SU Trucks & Buses	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	12	0	12
% SU Trucks & Buses	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1.9	0	1.4
MU Trucks	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	4	0	5
% MU Trucks	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.5	0	0.6	0	0.6

CHIA
 III Winners Circle, P.O. Box 5269
 Albany, NY 12205-0269
 518-453-4500
 www.chacompanies.com

Exit 3/Exit 4
 Sand Creek & Wolf Road
 AM
 7 to 9

File Name : Sand Creek & Wolf Road TOTAL AM
 Site Code : 12345678
 Start Date : 1/27/2009
 Page No : 4



CHA
 III Winners Circle, P.O. Box 5269
 Albany, NY 12205-0269
 518-453-4500
 www.chacompanies.com

Exit 3/Exit 4
 Sand Creek & Wolf Road
 AM
 7 to 9

File Name : Sand Creek & Wolf Road TOTAL AM
 Site Code : 12345678
 Start Date : 1/27/2009
 Page No : 1


Groups Printed- Passenger Cars - SU Trucks & Buses - MU Trucks

Start Time	Wolf Road Southbound						Sand Creek Westbound						Wolf Road Northbound						Sand Creek Eastbound					
	Right	Thru	Left	Peds	App. Total		Right	Thru	Left	Peds	App. Total		Right	Thru	Left	Peds	App. Total		Right	Thru	Left	Peds	App. Total	Int. Total
07:00 AM	14	66	18	1	99		20	23	11	1	55		4	44	21	0	69		35	53	24	0	112	335
07:15 AM	13	94	23	0	130		35	36	26	3	100		15	85	40	2	142		41	34	32	0	107	479
07:30 AM	25	103	31	0	159		45	27	25	0	97		18	87	52	0	157		48	69	32	0	149	562
07:45 AM	24	99	16	0	139		48	70	31	2	151		4	133	57	4	198		41	47	38	0	126	614
Total	76	362	88	1	527		148	156	93	6	403		41	349	170	6	566		165	203	126	0	494	1990
08:00 AM	22	93	27	0	142		49	45	25	0	119		14	118	44	0	176		50	49	38	0	137	574
08:15 AM	30	95	16	0	141		41	37	19	1	98		9	136	51	0	196		21	62	53	0	136	571
08:30 AM	26	90	14	0	130		29	39	19	0	87		11	123	42	0	176		36	60	38	0	134	527
08:45 AM	28	91	14	1	134		30	42	15	1	88		9	135	37	2	183		40	43	44	0	127	532
Total	106	369	71	1	547		149	163	78	2	392		43	512	174	2	731		147	214	173	0	534	2204
Grand Total	182	731	159	2	1074		297	319	171	8	795		84	861	344	8	1297		312	417	299	0	1028	4194
Apprch %	16.9	68.1	14.8	0.2			37.4	40.1	21.5	1			6.5	66.4	26.5	0.6			30.4	40.6	29.1	0		
Total %	4.3	17.4	3.8	0	25.6		7.1	7.6	4.1	0.2	19		2	20.5	8.2	0.2	30.9		7.4	9.9	7.1	0	24.5	
Passenger Cars	97.8	96.3	96.9	100	96.6		98	91.5	87.7	100	93.2		88.1	95.5	96.2	100	95.2		97.8	91.8	97	0	95.1	95.2
% Passenger Cars	4	27	5	0	36		3	26	21	0	50		9	35	10	0	54		7	33	7	0	47	187
SU Trucks & Buses	2.2	3.7	3.1	0	3.4		1	8.2	12.3	0	6.3		10.7	4.1	2.9	0	4.2		2.2	7.9	2.3	0	4.6	4.5
% SU Trucks & Buses	0	0	0	0	0		3	1	0	0	4		1	4	3	0	8		0	1	2	0	3	15
MU Trucks	0	0	0	0	0		1	0.3	0	0	0.5		1.2	0.5	0.9	0	0.6		0	0.2	0.7	0	0.3	0.4
% MU Trucks	0	0	0	0	0		1	0.3	0	0	0.5		1.2	0.5	0.9	0	0.6		0	0.2	0.7	0	0.3	0.4

1111 Winners Circle, P.O. Box 5269
Albany, NY 12205-0269
518-453-4500
www.chacompanies.com

Exit 3/Exit 4
Sand Creek & Wolf Road
AM
7 to 9

File Name : Sand Creek & Wolf Road TOTAL AM
Site Code : 12345678
Start Date : 1/27/2009
Page No : 2



CHA
 III Winners Circle, P.O. Box 5269
 Albany, NY 12205-0269
 518-453-4500
www.chacompanies.com

Exit 3/Exit 4
 Sand Creek & Wolf Road
 AM
 7 to 9


File Name : Sand Creek & Wolf Road TOTAL AM
 Site Code : 12345678
 Start Date : 1/27/2009
 Page No : 3

	Wolf Road Southbound					Sand Creek Westbound					Wolf Road Northbound					Sand Creek Eastbound					
Start Time	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour Analysis From 07:00 AM to 08:45 AM - Peak 1 of 1																					
Peak Hour for Entire Intersection Begins at 07:30 AM																					
07:30 AM	25	103	31		159						18						69			149	
07:45 AM	24	99	16	0	139	48	70	31	2	151	4	133	57	4	198	41	47	38	0	126	614
08:00 AM	22	93	27	0	142	49	45	25	0	119	14	118	44	0	176	50	49	38	0	137	574
08:15 AM	30	95	16	0	141	41	37	19	1	98	9	136	51	0	196	21	62	53	0	136	571
Total Volume	101	390	90	0	581	183	179	100	3	465	45	474	204	4	727	160	227	161	0	548	2321
% App. Total	17.4	67.1	15.5	0		39.4	38.5	21.5	0.6		6.2	65.2	28.1	0.6		29.2	41.4	29.4	0		
PHF	.842	.947	.726	.000	.914	.934	.639	.806	.375	.770	.625	.871	.895	.250	.918	.800	.822	.759	.000	.919	.945
Passenger Cars	99	376	86	0	561	179	164	89	3	435	41	453	195	4	693	155	215	153	0	523	2212
% Passenger Cars	98.0	96.4	95.6	0	96.6	97.8	91.6	89.0	100	93.5	91.1	95.6	95.6	100	95.3	96.9	94.7	95.0	0	95.4	95.3
SU Trucks & Buses	2	14	4	0	20	3	15	11	0	29	4	18	6	0	28	5	11	6	0	22	99
% SU Trucks & Buses	2.0	3.6	4.4	0	3.4	1.6	8.4	11.0	0	6.2	8.9	3.8	2.9	0	3.9	3.1	4.8	3.7	0	4.0	4.3
MU Trucks	0	0	0	0	0	1	0	0	0	1	0	3	3	0	6	0	1	2	0	3	10
% MU Trucks	0	0	0	0	0	0.5	0	0	0	0.2	0	0.6	1.5	0	0.8	0	0.4	1.2	0	0.5	0.4

CMA
 III Winners Circle, P.O. Box 5269
 Albany, NY 12205-0269
 518-453-4500
www.chacompanies.com

File Name : Watervliet Shaker Road & Exit 5 SB Ramp AM
 Site Code : 11111111
 Start Date : 1/27/2009
 Page No : 4

Exit 3/Exit 4
 Watervliet Shaker Road & Exit 5 SB Ramp
 AM
 7 to 9



CHIA
 III Winners Circle, P.O. Box 5269
 Albany, NY 12205-0269
 518-453-4500
 www.chacompanies.com

Exit 3/Exit 4
 Watervliet Shaker Road & Exit 5 SB Ramp
 AM
 7 to 9

File Name : Watervliet Shaker Road & Exit 5 SB Ramp AM
 Site Code : 11111111
 Start Date : 1/27/2009
 Page No : 1

Groups Printed- Passenger Cars - SU Trucks & Buses - MU Trucks

Start Time	Off-Ramp Southbound						Route 155 Westbound						On-Ramp Northbound						Route 155 Eastbound					
	Right	Thru	Left	Peds	App. Total		Right	Thru	Left	Peds	App. Total		Right	Thru	Left	Peds	App. Total		Right	Thru	Left	Peds	App. Total	Int. Total
07:00 AM	30	6	68	0	104		0	91	60	0	151		0	0	0	0	0		5	16	0	0	21	276
07:15 AM	33	6	79	0	118		0	143	108	0	251		0	0	0	0	0		11	31	1	0	43	412
07:30 AM	51	6	91	0	148		0	132	102	0	234		0	0	0	0	0		7	39	0	0	46	428
07:45 AM	58	4	81	0	143		0	192	136	0	328		0	0	0	0	0		5	36	0	0	41	512
Total	172	22	319	0	513		0	558	406	0	964		0	0	0	0	0		28	122	1	0	151	1628
08:00 AM	56	12	89	0	157		0	151	112	0	263		0	0	0	0	0		14	47	0	0	61	481
08:15 AM	57	9	86	0	152		1	143	119	0	263		0	0	0	0	0		13	30	0	0	43	458
08:30 AM	50	8	86	0	144		1	109	100	0	210		0	0	0	0	0		6	43	0	0	49	403
08:45 AM	36	4	70	0	110		1	117	76	0	194		0	0	0	0	0		9	45	0	0	54	358
Total	199	33	331	0	563		3	520	407	0	930		0	0	0	0	0		42	165	0	0	207	1700
Grand Total	371	55	650	0	1076		3	1078	813	0	1894		0	0	0	0	0		70	287	1	0	358	3328
Approch %	34.5	5.1	60.4	0			0.2	56.9	42.9	0			0	0	0	0	0		19.6	80.2	0.3	0		
Total %	11.1	1.7	19.5	0	32.3		0.1	32.4	24.4	0	56.9		0	0	0	0	0		2.1	8.6	0	0	10.8	
Passenger Cars																								
% Passenger Cars	99.2	100	98	0	98.5		66.7	97.6	98	0	97.7		0	0	0	0	0		85.7	93.4	100	0	91.9	97.4
SU Trucks & Buses	3	0	12	0	15		1	15	16	0	32		0	0	0	0	0		6	16	0	0	22	69
% SU Trucks & Buses	0.8	0	1.8	0	1.4		33.3	1.4	2	0	1.7		0	0	0	0	0		8.6	5.6	0	0	6.1	2.1
MU Trucks	0	0	1	0	1		0	11	0	0	11		0	0	0	0	0		4	3	0	0	7	19
% MU Trucks	0	0	0.2	0	0.1		0	1	0	0	0.6		0	0	0	0	0		5.7	1	0	0	2	0.6

CHA

III Winners Circle, P.O. Box 5269
Albany, NY 12205-0269
518-453-4500
www.chacompanies.com


Exit 3/Exit 4

Watervliet Shaker Road & Exit 5 SB Ramp

AM

7 to 9

File Name : Watervliet Shaker Road & Exit 5 SB Ramp AM
Site Code : 11111111
Start Date : 1/27/2009
Page No : 2



CH&A
 111 Winners Circle, P.O. Box 5269
 Albany, NY 12205-0269
 518-453-4500
www.chacompanies.com

Exit 3/Exit 4
 Watervliet Shaker Road & Exit 5 SB Ramp
 AM
 7 to 9


File Name : Watervliet Shaker Road & Exit 5 SB Ramp AM
 Site Code : 11111111
 Start Date : 1/27/2009
 Page No : 3

	Off-Ramp Southbound					Route 155 Westbound					On-Ramp Northbound					Route 155 Eastbound					
Start Time	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour Analysis From 07:00 AM to 08:45 AM - Peak 1 of 1																					
Peak Hour for Entire Intersection Begins at 07:30 AM																					
07:30 AM	51	6	91																		
07:45 AM	58	4	81	0	143	0	192	136	0	328	0	0	0	0	0	0	5	36	0	0	41
08:00 AM	56	12	89	0	157	0	151	112	0	263	0	0	0	0	0	0	14	47	0	0	61
08:15 AM	57	9	86	0	152	1	143	119	0	263	0	0	0	0	0	0	13	30	0	0	43
Total Volume	222	31	347	0	600	1	618	469	0	1088	0	0	0	0	0	0	39	152	0	0	191
% App. Total	37	5.2	57.8	0		0.1	56.8	43.1	0		0	0	0	0	0	0	20.4	79.6	0	0	
PHF	.957	.646	.953	.000	.955	.250	.805	.862	.000	.829	.000	.000	.000	.000	.000	.696	.809	.000	.000	.783	.917
Passenger Cars	220	31	337	0	588	1	599	458	0	1058	0	0	0	0	0	0	34	139	0	0	173
% Passenger Cars	99.1	100	97.1	0	98.0	100	96.9	97.7	0	97.2	0	0	0	0	0	0	87.2	91.4	0	0	90.6
SU Trucks & Buses	2	0	9	0	11	0	13	11	0	24	0	0	0	0	0	0	3	10	0	0	13
% SU Trucks & Buses	0.9	0	2.6	0	1.8	0	2.1	2.3	0	2.2	0	0	0	0	0	0	7.7	6.6	0	0	6.8
MU Trucks	0	0	1	0	1	0	6	0	0	6	0	0	0	0	0	0	2	3	0	0	5
% MU Trucks	0	0	0.3	0	0.2	0	1.0	0	0	0.6	0	0	0	0	0	0	5.1	2.0	0	0	2.6

CMA
 III Winners Circle, P.O. Box 5269
 Albany, NY 12205-0269
 518-453-4500
 www.chacompanies.com

Exit 3/Exit 4
 Old Wolf Road & Albany Shaker Road
 PM
 4 to 6

File Name : Albany Shaker Road & Old Wolf Road PM
 Site Code : 12345678
 Start Date : 1/27/2009
 Page No : 4



CHA


File Name : Albany Shaker Road & Old Wolf Road PM
Site Code : 12345678
Start Date : 1/27/2009
Page No : 1

Albany-Shaker Road Westbound												On-Ramp Northbound												Albany-Shaker Road Eastbound											
Old Wolf Road Southbound						Albany-Shaker Road Westbound						On-Ramp Northbound						Albany-Shaker Road Eastbound																	
Start Time	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int.	Total													
04:00 PM	76	31	160	0	267	30	155	92	0	277	0	0	0	0	0	115	143	23	1	282		826													
04:15 PM	65	16	154	0	235	32	167	64	0	263	0	0	0	0	0	88	156	27	1	272		770													
04:30 PM	82	30	141	0	253	35	152	76	0	263	0	0	0	0	0	130	171	29	0	330		846													
04:45 PM	66	23	152	0	241	28	158	70	0	256	0	0	0	0	0	114	179	27	0	320		817													
Total	289	100	607	0	996	125	632	302	0	1059	0	0	0	0	0	447	649	106	2	1204		3259													
05:00 PM	70	41	166	0	277	26	137	96	0	259	0	0	0	0	0	141	163	28	0	332		868													
05:15 PM	74	26	161	0	261	42	136	71	0	249	0	0	0	0	0	145	197	44	0	386		896													
05:30 PM	69	8	133	0	210	50	167	71	0	288	0	0	0	0	0	128	148	23	0	299		797													
05:45 PM	66	19	156	0	241	42	174	57	0	273	0	0	0	0	0	91	150	21	0	262		776													
Total	279	94	616	0	989	160	614	295	0	1069	0	0	0	0	0	505	658	116	0	1219		3337													
Grand Total	568	194	1223	0	1985	285	1246	597	0	2128	0	0	0	0	0	952	1307	222	2	2483		6596													
Approch % Total %	28.6 8.6	9.8 2.9	61.6 18.5	0 0	58.6 30.1	13.4 4.3	58.6 18.9	28.1 9.1	0 0	32.3	0 0	0 0	0 0	0 0	0 0	38.3 14.4	52.6 19.8	8.9 3.4	0.1 0	37.6															
Passenger Cars % Passenger Cars	96.5 19	94.3 4	98.6 11	0 0	97.6 34	95.1 7	98.4 17	98.8 5	0 0	98.1 29	0 0	0 0	0 0	0 0	0 0	99.4 5	98.9 13	89.6 21	100 0	98.3 39		98													
SU Trucks & Buses % SU Trucks & Buses	3.3 1	2.1 7	0.9 6	0 0	1.7 14	2.5 7	1.4 3	0.8 2	0 0	1.4 12	0 0	0 0	0 0	0 0	0 0	0.5 1	0.5 1	9.5 2	0 0	1.6 4		1.5													
MU Trucks % MU Trucks	0.2 0.2	3.6 3.6	0.5 0.5	0 0	0.7 0.7	2.5 2.5	0.2 0.2	0.3 0.3	0 0	0.6 0.6	0 0	0 0	0 0	0 0	0 0	0.1 0.1	0.1 0.1	0.9 0.9	0 0	0.2 0.2		0.5													

CH&A
 III Winners Circle, P.O. Box 5269
 Albany, NY 12205-0269
 518-453-4500
 www.chacompanies.com

Exit 3/Exit 4
 Old Wolf Road & Albany Shaker Road
 PM
 4 to 6

File Name : Albany Shaker Road & Old Wolf Road PM
 Site Code : 12345678
 Start Date : 1/27/2009
 Page No : 2



CH&A
 III Winners Circle, P.O. Box 5269
 Albany, NY 12205-0269
 518-453-4500
 www.chacompanies.com


Exit 3/Exit 4
 Old Wolf Road & Albany Shaker Road
 PM
 4 to 6

File Name : Albany Shaker Road & Old Wolf Road PM
 Site Code : 12345678
 Start Date : 1/27/2009
 Page No : 3

Start Time	Old Wolf Road Southbound						Albany-Shaker Road Westbound						On-Ramp Northbound						Albany-Shaker Road Eastbound					
	Right	Thru	Left	Peds	App. Total		Right	Thru	Left	Peds	App. Total		Right	Thru	Left	Peds	App. Total		Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour Analysis From 04:00 PM to 05:45 PM - Peak 1 of 1																								
Peak Hour for Entire Intersection Begins at 04:30 PM																								
04:30 PM	82	30	141				35	152	76										130	171	29			
04:45 PM	66	23	152	0	241		28	158	70	0	256	263	0	0	0	0	0	0	114	179	27	0	320	817
05:00 PM	70	41	166	0	277		26	137	96	0	259	0	0	0	0	0	0	0	141	163	28	0	332	868
05:15 PM	74	26	161	0	261		42	136	71	0	249	0	0	0	0	0	0	0	145	197	44	0	386	896
Total Volume	292	120	620	0	1032		131	583	313	0	1027	0	0	0	0	0	0	0	530	710	128	0	1368	3427
% App. Total	28.3	11.6	60.1	0			12.8	56.8	30.5	0			0	0	0	0	0	0	38.7	51.9	9.4	0		
PHF	.890	.732	.934	.000	.931		.780	.922	.815	.000	.976	.000	.000	.000	.000	.000	.000	.000	.914	.901	.727	.000	.886	.956
Passenger Cars	285	112	610	0	1007		124	570	312	0	1006	0	0	0	0	0	0	0	527	701	118	0	1346	3359
% Passenger Cars	97.6	93.3	98.4	0	97.6		94.7	97.8	99.7	0	98.0	0	0	0	0	0	0	0	99.4	98.7	92.2	0	98.4	98.0
SU Trucks & Buses	7	1	7	0	15		3	10	1	0	14	0	0	0	0	0	0	0	3	9	9	0	21	50
% SU Trucks & Buses	2.4	0.8	1.1	0	1.5		2.3	1.7	0.3	0	1.4	0	0	0	0	0	0	0	0.6	1.3	7.0	0	1.5	1.5
MU Trucks	0	7	3	0	10		4	3	0	0	7	0	0	0	0	0	0	0	0	0	1	0	1	18
% MU Trucks	0	5.8	0.5	0	1.0		3.1	0.5	0	0	0.7	0	0	0	0	0	0	0	0	0	0.8	0	0.1	0.5

File Name : Albany Shaker Road & Wolf Road PM
 Site Code : 01270982
 Start Date : 1/27/2009
 Page No : 4

Exit 3/Exit 4
 Albany Shaker Road & Wolf Road
 PM
 4 to 6



CHA
 III Winners Circle, P.O. Box 5269
 Albany, NY 12205-0269
 518-453-4500
www.chacompanies.com

Exit 3/Exit 4
 Albany Shaker Road & Wolf Road
 PM
 4 to 6

File Name : Albany Shaker Road & Wolf Road PM
 Site Code : 01270982
 Start Date : 1/27/2009
 Page No : 1


Groups Printed- Passenger Cars - SU Trucks & Buses - MU Trucks

Start Time	On-Ramp Southbound						Albany-Shaker Road Westbound						Wolf Road Northbound						Albany-Shaker Road Eastbound					
	Right	Thru	Left	Peds	App. Total		Right	Thru	Left	Peds	App. Total		Right	Thru	Left	Peds	App. Total		Right	Thru	Left	Peds	App. Total	Int. Total
04:00 PM	0	0	0	0	0		72	130	73	0	275		154	176	143	0	473		98	115	86	0	299	1047
04:15 PM	0	0	0	0	0		67	111	83	0	261		141	151	154	0	446		119	136	69	0	324	1031
04:30 PM	0	0	0	0	0		61	133	63	1	258		149	187	139	0	475		109	130	70	0	309	1042
04:45 PM	0	0	0	0	0		87	117	84	0	288		168	172	129	0	469		111	158	64	0	333	1090
Total	0	0	0	0	0		287	491	303	1	1082		612	686	565	0	1863		437	539	289	0	1265	4210
05:00 PM	0	0	0	0	0		53	126	97	0	276		144	160	125	0	429		121	117	101	0	339	1044
05:15 PM	0	0	0	0	0		98	124	78	0	300		159	185	124	0	468		132	156	93	0	381	1149
05:30 PM	0	0	0	0	0		73	142	78	0	293		154	178	119	0	451		118	119	64	0	301	1045
05:45 PM	0	0	0	0	0		70	127	90	0	287		164	126	114	0	404		113	117	74	0	304	995
Total	0	0	0	0	0		294	519	343	0	1156		621	649	482	0	1752		484	509	332	0	1325	4233
Grand Total	0	0	0	0	0		581	1010	646	1	2238		1233	1335	1047	0	3615		921	1048	621	0	2590	8443
Approch %	0	0	0	0	0		26	45.1	28.9	0			34.1	36.9	29	0			35.6	40.5	24	0		
Total %	0	0	0	0	0		6.9	12	7.7	0	26.5		14.6	15.8	12.4	0	42.8		10.9	12.4	7.4	0	30.7	
Passenger Cars	0	0	0	0	0		99.7	99.3	99.5	100	99.5		99.8	99.6	98.8	0	99.4		99.3	99.5	99.8	0	99.5	99.5
% Passenger Cars	0	0	0	0	0		2	5	3	0	10		1	5	7	0	13		6	3	1	0	10	33
SU Trucks & Buses	0	0	0	0	0		0.3	0.5	0.5	0	0.4		0.1	0.4	0.7	0	0.4		0.7	0.3	0.2	0	0.4	0.4
% SU Trucks & Buses	0	0	0	0	0		0	2	0	0	2		2	1	6	0	9		0	2	0	0	2	13
MU Trucks	0	0	0	0	0		0	0.2	0	0	0.1		0.2	0.1	0.6	0	0.2		0	0.2	0	0	0.1	0.2
% MU Trucks	0	0	0	0	0		0	0	0	0	0.1		0.2	0.1	0.6	0	0.2		0	0.2	0	0	0.1	0.2

111 Winners Circle, P.O. Box 5269
 Albany, NY 12205-0269
 518-453-4500
 www.chacompanies.com

Exit 3/Exit 4
 Albany Shaker Road & Wolf Road
 PM
 4 to 6

File Name : Albany Shaker Road & Wolf Road PM
 Site Code : 01270982
 Start Date : 1/27/2009
 Page No : 2



CH&A
 III Winners Circle, P.O. Box 5269
 Albany, NY 12205-0269
 518-453-4500
 www.chacompanies.com

Exit 3/Exit 4
 Albany Shaker Road & Wolf Road
 PM
 4 to 6


File Name : Albany Shaker Road & Wolf Road PM
 Site Code : 01270982
 Start Date : 1/27/2009
 Page No : 3

Start Time	On-Ramp Southbound						Albany-Shaker Road Westbound						Wolf Road Northbound						Albany-Shaker Road Eastbound					
	Right	Thru	Left	Peds	App. Total		Right	Thru	Left	Peds	App. Total		Right	Thru	Left	Peds	App. Total		Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour Analysis From 04:00 PM to 05:45 PM - Peak 1 of 1																								
Peak Hour for Entire Intersection Begins at 04:45 PM																								
04:45 PM	0	0	0	0	0		87	117	84	0	288		168	172	129	0	469		111	158	64	0	339	1044
05:00 PM	0	0	0	0	0		53	126	97	0	276		144	160	125	0	429		121	117	101	0	381	1149
05:15 PM	0	0	0	0	0		98	124	78	0	300		159	185	124	0	468		132	156	93	0	301	1045
05:30 PM	0	0	0	0	0		73	142	78	0	293		154	178	119	0	451		118	119	64	0	1354	4328
Total Volume	0	0	0	0	0		311	509	337	0	1157		625	695	497	0	1817		482	550	322	0	1354	4328
% App. Total	0	0	0	0	0		26.9	44	29.1	0	0		34.4	38.2	27.4	0	0		35.6	40.6	23.8	0	0	0
PHF	.000	.000	.000	.000	.000		.793	.896	.869	.000	.964		.930	.939	.963	.000	.969		.913	.870	.797	.000	.888	.942
Passenger Cars	0	0	0	0	0		309	507	335	0	1151		624	693	490	0	1807		478	547	321	0	1346	4304
% Passenger Cars	0	0	0	0	0		99.4	99.6	99.4	0	99.5		99.8	99.7	98.6	0	99.4		99.2	99.5	99.7	0	99.4	99.4
SU Trucks & Buses	0	0	0	0	0		2	1	2	0	5		0	2	3	0	5		4	2	1	0	7	17
% SU Trucks & Buses	0	0	0	0	0		0.6	0.2	0.6	0	0.4		0	0.3	0.6	0	0.3		0.8	0.4	0.3	0	0.5	0.4
MU Trucks	0	0	0	0	0		0	1	0	0	1		1	0	4	0	5		0	1	0	0	1	7
% MU Trucks	0	0	0	0	0		0	0.2	0	0	0.1		0.2	0	0.8	0	0.3		0	0.2	0	0	0.1	0.2

CH2A
 III Winners Circle, P.O. Box 5269
 Albany, NY 12205-0269
 518-453-4500
 www.chacompanies.com

Exit 3/Exit 4
 Exit 4 NB Off-Ramp
 PM
 4-6

File Name : Exit 4 NB Off-Ramp PM
 Site Code : 00000000
 Start Date : 1/27/2009
 Page No : 4



CHIA

File Name : Exit 4 NB Off-Ramp PM
Site Code : 00000000
Start Date : 1/27/2009
Page No : 1


Groups Printed- Passenger Cars - SU Trucks & Buses - MU Trucks

Groups Printed- Passenger Cars - SU Trucks & Buses - MU Trucks																						
Southbound						Westbound						Northbound						Exit 4 NB Off-Ramp Eastbound				
Start Time	Right	Thru	Left	Other	App. Total	Right	Thru	Left	Other	App. Total	Right	Thru	Left	Other	App. Total	Int. Total						
04:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	111	0	132	132						
04:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	127	0	170	170						
04:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	90	0	123	123						
04:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	134	0	180	180						
Total	0	0	0	0	0	0	0	0	0	0	0	0	462	0	605	605						
05:00 PM	0	0	0	0	0	0	0	0	0	0	0	0	106	0	149	149						
05:15 PM	0	0	0	0	0	0	0	0	0	0	0	0	88	0	134	134						
05:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	94	0	130	130						
05:45 PM	0	0	0	0	0	0	0	0	0	0	0	0	132	0	178	178						
Total	0	0	0	0	0	0	0	0	0	0	0	0	420	0	591	591						
Grand Total	0	0	0	0	0	0	0	0	0	0	0	0	882	0	1196	1196						
Approch %	0	0	0	0	0	0	0	0	0	0	0	0	73.7	0								
Total %	0	0	0	0	0	0	0	0	0	0	0	0	73.7	0	100							
Passenger Cars																						
% Passenger Cars	0	0	0	0	0	0	0	0	0	0	0	0	98.1	0	98.3	98.3						
SU Trucks & Buses	0	0	0	0	0	0	0	0	0	0	0	0	7	0	10	10						
% SU Trucks & Buses	0	0	0	0	0	0	0	0	0	0	0	0	0.8	0	0.8	0.8						
MU Trucks	0	0	0	0	0	0	0	0	0	0	0	0	10	0	10	10						
% MU Trucks	0	0	0	0	0	0	0	0	0	0	0	0	1.1	0	0.8	0.8						

CHIA
 III Winners Circle, P.O. Box 5269
 Albany, NY 12205-0269
 518-453-4500
 www.chacompanies.com

Exit 3/Exit 4
 Exit 4 NB Off-Ramp
 PM
 4-6

File Name : Exit 4 NB Off-Ramp PM
 Site Code : 00000000
 Start Date : 1/27/2009
 Page No : 2



СПА

Exit 3/Exit 4


Exit 3/Exit 4

	Southbound						Westbound						Northbound						Exit 4 NB Off-Ramp Eastbound					
Start Time	Right	Thru	Left	Other	App. Total		Right	Thru	Left	Other	App. Total		Right	Thru	Left	Other	App. Total		Right	Thru	Left	Other	App. Total	Int. Total
Peak Hour Analysis From 04:00 PM to 05:45 PM - Peak 1 of 1																								
Peak Hour for Entire Intersection Begins at 04:15 PM																								
04:15 PM	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0		43	0	127	0	170	170
04:30 PM	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0		33	0	90	0	123	123
04:45 PM	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0		46	134	0	0	180	180
05:00 PM	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0		43	0	106	0	149	149
Total Volume	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0		165	0	457	0	622	622
% App. Total	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0		26.5	0	73.5	0	622	622
PHF	.000	.000	.000	.000	.000		.000	.000	.000	.000	.000		.000	.000	.000	.000	.000		.897	.000	.853	.000	.864	.864
Passenger Cars	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0		164	0	449	0	613	613
% Passenger Cars	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0		99.4	0	98.2	0	98.6	98.6
SU Trucks & Buses	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0		1	0	2	0	3	3
% SU Trucks & Buses	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0		0.6	0	0.4	0	0.5	0.5
MU Trucks	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0		0	0	6	0	6	6
% MU Trucks	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0		0	0	1.3	0	1.0	1.0

CHRA
 III Winners Circle, P.O. Box 5269
 Albany, NY 12205-0269
 518-453-4500
 www.chacompanies.com

File Name : Watervliet Shaker Road & Exit 5 SB Ramp PM
 Site Code : 111111111
 Start Date : 1/27/2009
 Page No : 4

Exit 3/Exit 4
 Watervliet Shaker Road & Exit 5 SB
 PM
 4 to 6



CHA
 III Winners Circle, P.O. Box 5269
 Albany, NY 12205-0269
 518-453-4500
 www.chacompanies.com

Exit 3/Exit 4
 Watervliet Shaker Road & Exit 5 SB
 PM
 4 to 6

File Name : Watervliet Shaker Road & Exit 5 SB Ramp PM
 Site Code : 11111111
 Start Date : 1/27/2009
 Page No : 1


Groups Printed- Passenger Cars - SU Trucks & Buses - MU Trucks

Start Time	Exit 5 SB Ramp Southbound						Route 155 Westbound						On-Ramp Northbound						Route 155 Eastbound					
	Right	Thru	Left	Peds	App. Total		Right	Thru	Left	Peds	App. Total		Right	Thru	Left	Peds	App. Total		Right	Thru	Left	Peds	App. Total	Int. Total
04:00 PM	19	2	74	0	95		1	57	85	0	143		0	0	0	0	0		51	116	1	0	168	406
04:15 PM	9	5	70	0	84		5	69	76	0	150		0	0	0	0	0		39	105	3	0	147	381
04:30 PM	17	1	53	0	71		2	55	103	0	160		0	0	0	0	0		42	135	2	0	179	410
04:45 PM	12	4	68	0	84		1	69	76	0	146		0	0	0	0	0		46	112	0	0	158	388
Total	57	12	265	0	334		9	250	340	0	599		0	0	0	0	0		178	468	6	0	652	1585
05:00 PM	12	1	58	0	71		1	55	82	0	138		0	0	0	0	0		75	178	4	0	257	466
05:15 PM	10	4	69	0	83		2	56	74	0	132		0	0	0	0	0		33	116	4	1	154	369
05:30 PM	7	12	84	0	103		2	59	69	0	130		0	0	0	0	0		23	92	1	0	116	349
05:45 PM	9	4	64	0	77		1	37	67	0	105		0	0	0	0	0		18	54	1	0	73	255
Total	38	21	275	0	334		6	207	292	0	505		0	0	0	0	0		149	440	10	1	600	1439
Grand Total	95	33	540	0	668		15	457	632	0	1104		0	0	0	0	0		327	908	16	1	1252	3024
Approch %	14.2	4.9	80.8	0			1.4	41.4	57.2	0			0	0	0	0	0		26.1	72.5	1.3	0.1		
Total %	3.1	1.1	17.9	0	22.1		0.5	15.1	20.9	0	36.5		0	0	0	0	0		10.8	30	0.5	0	41.4	
Passenger Cars	93.7	100	98.3	0	97.8		100	92.6	99.2	0	96.5		0	0	0	0	0		99.1	99	100	100	99	97.8
SU Trucks & Buses	1	0	9	0	10		0	19	5	0	24		0	0	0	0	0		1	7	0	0	8	42
% SU Trucks & Buses	1.1	0	1.7	0	1.5		0	4.2	0.8	0	2.2		0	0	0	0	0		0.3	0.8	0	0	0.6	1.4
MU Trucks	5	0	0	0	5		0	15	0	0	15		0	0	0	0	0		2	2	0	0	4	24
% MU Trucks	5.3	0	0	0	0.7		0	3.3	0	0	1.4		0	0	0	0	0		0.6	0.2	0	0	0.3	0.8

CHRA
 III Winners Circle, P.O. Box 5269
 Albany, NY 12205-0269
 518-453-4500
 www.chacompanies.com

File Name : Watervliet Shaker Road & Exit 5 SB Ramp PM
 Site Code : 11111111
 Start Date : 1/27/2009
 Page No : 2

Exit 3/Exit 4
 Watervliet Shaker Road & Exit 5 SB
 PM
 4 to 6



CHIA
 III Winners Circle, P.O. Box 5269
 Albany, NY 12205-0269
 518-453-4500
 www.chacompanies.com

Exit 3/Exit 4
 Watervliet Shaker Road & Exit 5 SB
 PM
 4 to 6


File Name : Watervliet Shaker Road & Exit 5 SB Ramp PM
 Site Code : 11111111
 Start Date : 1/27/2009
 Page No : 3

	Exit 5 SB Ramp Southbound					Route 155 Westbound					On-Ramp Northbound					Route 155 Eastbound					
Start Time	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour Analysis From 04:00 PM to 05:45 PM - Peak 1 of 1																					
Peak Hour for Entire Intersection Begins at 04:15 PM																					
04:15 PM	9	5	70		84	5	69	76								39	106	3			
04:30 PM	17	1	53	0	71	2	55	103	0	160	0	0	0	0	0	42	135	2	0	179	410
04:45 PM	12	4	68	0	84	1	69	76	0	146	0	0	0	0	0	46	112	0	0	158	388
05:00 PM	12	1	58	0	71	1	55	82	0	138	0	0	0	0	0	75	178	4	0	257	466
Total Volume	50	11	249	0	310	9	248	337	0	594	0	0	0	0	0	202	530	9	0	741	1645
% App. Total	16.1	3.5	80.3	0		1.5	41.8	56.7	0		0	0	0	0	0	27.3	71.5	1.2	0		
PHF	.735	.550	.889	.000	.923	.450	.899	.818	.000	.928	.000	.000	.000	.000	.000	.673	.744	.563	.000	.721	.883
Passenger Cars	46	11	242	0	299	9	234	333	0	576	0	0	0	0	0	199	524	9	0	732	1607
% Passenger Cars	92.0	100	97.2	0	96.5	100	94.4	98.8	0	97.0	0	0	0	0	0	98.5	98.9	100	0	98.8	97.7
SU Trucks & Buses	0	0	7	0	7	0	8	4	0	12	0	0	0	0	0	1	4	0	0	5	24
% SU Trucks & Buses	0	0	2.8	0	2.3	0	3.2	1.2	0	2.0	0	0	0	0	0	0.5	0.8	0	0	0.7	1.5
MU Trucks	4	0	0	0	4	0	6	0	0	6	0	0	0	0	0	2	2	0	0	4	14
% MU Trucks	8.0	0	0	0	1.3	0	2.4	0	0	1.0	0	0	0	0	0	1.0	0.4	0	0	0.5	0.9

CH&A
 III Winners Circle, P.O. Box 5269
 Albany, NY 12205-0269
 518-453-4500
 www.chacompanies.com

Exit 3/ Exit 4
 Sand Creek & Wolf Road
 PM
 4 to 6

File Name : Sand Creek & Wolf Road TOTAL PM
 Site Code : 87654321
 Start Date : 1/27/2009
 Page No : 4



CHIA
 III Winners Circle, P.O. Box 5269
 Albany, NY 12205-0269
 518-453-4500
 www.chacompanies.com

Exit 3/ Exit 4
 Sand Creek & Wolf Road
 PM
 4 to 6

File Name : Sand Creek & Wolf Road TOTAL PM
 Site Code : 87654321
 Start Date : 1/27/2009
 Page No : 1


Groups Printed- Passenger Cars - SU Trucks & Buses - MU Trucks

Wolf Road Southbound												Sand Creek Westbound						Wolf Road Northbound						Sand Creek Eastbound					
Start Time	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total								
04:00 PM	38	188	62	5	293	49	67	23	0	139	19	155	52	0	226	33	60	43	1	137	795								
04:15 PM	30	158	43	1	232	45	62	19	0	126	20	155	71	2	248	35	78	48	1	162	768								
04:30 PM	36	197	44	0	277	54	78	13	0	145	15	197	81	5	298	48	84	52	0	184	904								
04:45 PM	33	149	56	1	239	51	77	22	0	150	14	181	68	3	266	41	72	50	0	163	818								
Total	137	692	205	7	1041	199	284	77	0	560	68	688	272	10	1038	157	294	193	2	646	3285								
05:00 PM	41	241	57	3	342	49	85	21	0	155	15	175	65	1	256	40	63	53	0	156	909								
05:15 PM	47	190	53	0	290	50	84	24	0	158	23	197	55	1	276	41	114	49	1	205	929								
05:30 PM	27	218	42	0	287	72	77	15	0	164	26	215	72	3	316	42	80	55	0	177	944								
05:45 PM	30	166	40	0	236	51	65	27	0	143	21	182	66	1	270	41	94	49	0	184	833								
Total	145	815	192	3	1155	222	311	87	0	620	85	769	258	6	1118	164	351	206	1	722	3615								
Grand Total	282	1507	397	10	2196	421	595	164	0	1180	153	1457	530	16	2156	321	645	399	3	1368	6900								
Apprch %	12.8	68.6	18.1	0.5		35.7	50.4	13.9	0		7.1	67.6	24.6	0.7		23.5	47.1	29.2	0.2										
Total %	4.1	21.8	5.8	0.1	31.8	6.1	8.6	2.4	0	17.1	2.2	21.1	7.7	0.2	31.2	4.7	9.3	5.8	0	19.8									
Passenger Cars	98.2	98.7	99.7	100	98.8	99	98.8	90.9	0	97.8	93.5	98.8	99.2	100	98.6	99.4	99.5	99.7	100	99.6	98.7								
% Passenger Cars																													
SU Trucks & Buses	4	17	1	0	22	3	7	15	0	25	9	12	4	0	25	2	3	1	0	6	78								
% SU Trucks & Buses	1.4	1.1	0.3	0	1	0.7	1.2	9.1	0	2.1	5.9	0.8	0.8	0	1.2	0.6	0.5	0.3	0	0.4	1.1								
MU Trucks	1	3	0	0	4	1	0	0	0	1	1	5	0	0	6	0	0	0	0	0	11								
% MU Trucks	0.4	0.2	0	0	0.2	0.2	0	0	0	0.1	0.7	0.3	0	0	0.3	0	0	0	0	0	0.2								

CnA
 III Winners Circle, P.O. Box 5269
 Albany, NY 12205-0269
 518-453-4500
 www.chacompanies.com

Exit 3/Exit 4
 Sand Creek & Wolf Road
 PM
 4 to 6

File Name : Sand Creek & Wolf Road TOTAL PM
 Site Code : 87654321
 Start Date : 1/27/2009
 Page No : 2



CHA
 III Winners Circle, P.O. Box 5269
 Albany, NY 12205-0269
 518-453-4500
www.chacompanies.com

Exit 3/ Exit 4
 Sand Creek & Wolf Road
 PM
 4 to 6

File Name : Sand Creek & Wolf Road TOTAL PM
 Site Code : 87654321
 Start Date : 1/27/2009
 Page No : 3


	Wolf Road Southbound					Sand Creek Westbound					Wolf Road Northbound					Sand Creek Eastbound					
Start Time	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
Peak Hour Analysis From 04:00 PM to 05:45 PM - Peak 1 of 1																					
Peak Hour for Entire Intersection Begins at 05:00 PM																					
05:00 PM	41	241	57	3	342		85														
05:15 PM	47	190	53	0	290	50	84	24	0	158	23	197	55	1	276	41	114	49	1	205	929
05:30 PM	27	218	42	0	287	72	77	15	0	164	26	215	72	3	316	42	80	55	0	177	944
05:45 PM	30	166	40	0	236	51	65	27	0	143	21	182	66	1	270	41	94	49	0	184	833
Total Volume	145	815	192	3	1155	222	311	87	0	620	85	769	258	6	1118	164	351	206	1	722	3615
% App. Total	12.6	70.6	16.6	0.3		35.8	50.2	14	0		7.6	68.8	23.1	0.5		22.7	48.6	28.5	0.1		
PHF	.771	.845	.842	.250	.844	.771	.915	.806	.000	.945	.817	.894	.896	.500	.884	.976	.770	.936	.250	.880	.957
Passenger Cars	142	803	191	3	1139	220	310	79	0	609	80	759	257	6	1102	164	348	206	1	719	3569
% Passenger Cars	97.9	98.5	99.5	100	98.6	99.1	99.7	90.8	0	98.2	94.1	98.7	99.6	100	98.6	100	99.1	100	100	99.6	98.7
SU Trucks & Buses	3	10	1	0	14	2	1	8	0	11	4	7	1	0	12	0	3	0	0	3	40
% SU Trucks & Buses	2.1	1.2	0.5	0	1.2	0.9	0.3	9.2	0	1.8	4.7	0.9	0.4	0	1.1	0	0.9	0	0	0.4	1.1
MU Trucks	0	2	0	0	2	0	0	0	0	0	1	3	0	0	4	0	0	0	0	0	6
% MU Trucks	0	0.2	0	0	0.2	0	0	0	0	0	1.2	0.4	0	0	0.4	0	0	0	0	0	0.2



Exit 3 Airport Connector
Wolf Rd & Central Ave
AM
7 to 9

Manual Turning Movement Count
Clough, Harbour & Associates LLP
111 Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

File Name : Wolf - Central AM
Site Code : 62906009
Start Date : 6/29/2006
Page No : 4





Manual Turning Movement Count
Clough, Harbours & Associates LLP
111 Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Airport Connector
Wolf Rd & Central Ave
AM
7 to 9

File Name : Wolf - Central AM
Site Code : 62906009
Start Date : 6/29/2006
Page No : 3


	Wolf Road Southbound					Central Avenue Westbound					I-87 Exit 2 EB Off Ramp Northbound					Central Avenue Eastbound					
Start Time	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Int. Total
Peak Hour Analysis From 07:00 to 08:45 - Peak 1 of 1																					
Peak Hour for Entire Intersection Begins at 07:45																					
07:45	49																				
08:00	41	0	70	0	111	0	165	48	0	213	1	216	40	0	257	89	246	0	0	335	954
08:15	47	0	88	0	135	0	167	70	0	237	0	215	32	0	247	79	229	0	0	308	916
08:30	45	1	77	2	125	0	151	60	0	211	0	188	38	0	226	88	200	0	0	288	927
Total Volume	182	1	304	2	489	0	656	241	0	897	1	835	150	0	986	327	948	0	0	1275	3647
% App. Total	37.2	0.2	62.2	0.4		0	73.1	26.9	0		0.1	84.7	15.2	0		25.6	74.4	0	0		
PHF	.929	.250	.864	.250	.906	.000	.948	.861	.000	.946	.250	.966	.938	.000	.959	.919	.868	.000	.000	.927	.956
Passenger Vehicles	174	1	296	2	473	0	602	229	0	831	1	828	141	0	970	322	923	0	0	1245	3519
% Passenger Vehicles	95.6	100	97.4	100	96.7	0	91.8	95.0	0	92.6	100	99.2	94.0	0	98.4	98.5	97.4	0	0	97.6	96.5
SU Trucks & Buses	8	0	7	0	15	0	42	12	0	54	0	4	3	0	7	4	24	0	0	28	104
% SU Trucks & Buses	4.4	0	2.3	0	3.1	0	6.4	5.0	0	6.0	0	0.5	2.0	0	0.7	1.2	2.5	0	0	2.2	2.9
MU Trucks	0	0	1	0	1	0	12	0	0	12	0	3	6	0	9	1	1	0	0	2	24
% MU Trucks	0	0	0.3	0	0.2	0	1.8	0	0	1.3	0	0.4	4.0	0	0.9	0.3	0.1	0	0	0.2	0.7




Exit 3 Airport Connector
Wolf Rd & Central Ave
AM
7 to 9

Manual Turning Movement Count
Clough, Harbour & Associates LLP
111 Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

File Name : Wolf - Central AM
Site Code : 62906009
Start Date : 6/29/2006
Page No : 2



Groups Printed- Passenger Vehicles - SU Trucks & Buses - MU Trucks																					
Central Avenue Westbound										Northbound					Central Avenue Eastbound						
Start Time	Wolf Road Southbound					Central Avenue Westbound					Northbound					Central Avenue Eastbound					Int. Total
	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	
Factor	1.0	1.0	1.0	1.0		1.0	1.0	1.0	1.0		1.0	1.0	1.0	1.0		1.0	1.0	1.0	1.0		
07:00	27	0	52	1	80	0	92	35	0	127	0	141	27	0	168	59	211	0	0	270	645
07:15	37	0	54	0	91	0	117	39	0	156	0	137	25	0	162	56	200	0	0	256	665
07:30	27	0	67	0	94	0	136	46	0	182	0	160	40	0	200	74	274	0	0	348	824
07:45	49	0	69	0	118	0	173	63	0	236	0	216	40	0	256	71	273	0	0	344	954
Total	140	0	242	1	383	0	518	183	0	701	0	654	132	0	786	260	958	0	0	1218	3088
08:00	41	0	70	0	111	0	165	48	0	213	1	216	40	0	257	89	246	0	0	335	916
08:15	47	0	88	0	135	0	167	70	0	237	0	215	32	0	247	79	229	0	0	308	927
08:30	45	1	77	2	125	0	151	60	0	211	0	188	38	0	226	88	200	0	0	288	850
08:45	55	0	94	0	149	0	154	58	0	212	0	178	43	0	221	86	244	0	0	330	912
Total	188	1	329	2	520	0	637	236	0	873	1	797	153	0	951	342	919	0	0	1261	3605
Grand Total	328	1	571	3	903	0	1155	419	0	1574	1	1451	285	0	1737	602	1877	0	0	2479	6693
Approach %	36.3	0.1	63.2	0.3		0	73.4	26.6	0		0.1	83.5	16.4	0		24.3	75.7	0	0		
Total %	4.9	0	8.5	0	13.5	0	17.3	6.3	0	23.5	0	21.7	4.3	0	26	9	28	0	0	37	
Passenger Vehicles																					
% Passenger Vehicles	94.2	100	97.4	100	96.2	0	92.8	94.5	0	93.3	100	99	93	0	98	98.2	97.3	0	0	97.5	96.5
SU Trucks & Buses	18	0	13	0	31	0	63	23	0	86	0	12	7	0	19	10	40	0	0	50	186
% SU Trucks & Buses	5.5	0	2.3	0	3.4	0	5.5	5.5	0	5.5	0	0.8	2.5	0	1.1	1.7	2.1	0	0	2	2.8
MU Trucks	1	0	2	0	3	0	20	0	0	20	0	3	13	0	16	1	11	0	0	12	51
% MU Trucks	0.3	0	0.4	0	0.3	0	1.7	0	0	1.3	0	0.2	4.6	0	0.9	0.2	0.6	0	0	0.5	0.8





Manual Turning Movement Count
Clough, Harbours & Associates LLP
111 Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Airport Connector
Wolf Rd & Sand Creek Rd
AM
7 to 9


File Name : Wolf - Sand Creek AM
Site Code : 62806005
Start Date : 6/28/2006
Page No : 3

	Wolf Road Southbound					Sand Creek Road Westbound					Wolf Road Northbound					Sand Creek Road Eastbound					
Start Time	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Int. Total
Peak Hour Analysis From 07:00 to 08:45 - Peak 1 of 1																					
Peak Hour for Entire Intersection Begins at 08:00																					
08:00	19	118				25										45		37		151	636
08:15	20	96	23	0	139	18	45	37	0	100	56	156	10	0	222	43	55	34	0	132	593
08:30	33	113	31	1	178	24	42	41	1	108	41	156	15	1	213	34	69	25	3	131	630
08:45	33	100	27	0	160	22	56	45	0	123	58	124	9	0	191	41	64	17	2	124	598
Total Volume	105	427	102	1	635	89	189	163	1	442	201	591	49	1	842	163	255	113	7	538	2457
% App. Total	16.5	67.2	16.1	0.2		20.1	42.8	36.9	0.2		23.9	70.2	5.8	0.1		30.3	47.4	21	1.3		
PHF	.795	.905	.823	.250		.890	.844	.906	.250		.866	.947	.817	.250		.906	.924	.764	.583	.891	.966
Passenger Vehicles	104	411	98	1	614	84	188	161	1	434	194	581	46	1	822	160	251	110	7	528	2398
% Passenger Vehicles	99.0	96.3	96.1	100	96.7	94.4	99.5	98.8	100	98.2	96.5	98.3	93.9	100	97.6	98.2	98.4	97.3	100	98.1	97.6
SU Trucks & Buses	0	15	4	0	19	5	1	2	0	8	7	8	3	0	18	3	4	3	0	10	55
% SU Trucks & Buses	0	3.5	3.9	0	3.0	5.6	0.5	1.2	0	1.8	3.5	1.4	6.1	0	2.1	1.8	1.6	2.7	0	1.9	2.2
MU Trucks	1	1	0	0	2	0	0	0	0	0	0	2	0	0	2	0	0	0	0	0	4
% MU Trucks	1.0	0.2	0	0	0.3	0	0	0	0	0	0	0.3	0	0	0.2	0	0	0	0	0	0.2

Manual Turning Movement Count
Clough, Harbour & Associates LLP
 111 Winners Circle, P.O. Box 5269
 Albany, NY 12205
www.cloughharbour.com

File Name : Wolf - Sand Creek AM
 Site Code : 62806005
 Start Date : 6/28/2006
 Page No : 2

Exit 3 Airport Connector
 Wolf Rd & Sand Creek Rd
 AM
 7 to 9





Manual Turning Movement Count
Clough, Harbour & Associates LLP
111 Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Airport Connector
Wolf Rd & Sand Creek Rd
AM
7 to 9

File Name : Wolf - Sand Creek AM
Site Code : 62806005
Start Date : 6/28/2006
Page No : 1

Groups Printed- Passenger Vehicles - SU Trucks & Buses - MU Trucks


Groups Printed- Passenger Vehicles - SU Trucks & Buses - MU Trucks																																		
Sand Creek Road Westbound												Wolf Road Northbound												Sand Creek Road Eastbound										
Wolf Road Southbound																																		
Start Time	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Int. Total								
07:00	11	71	11	0	93	14	18	26	2	60	19	80	17	0	116	21	27	25	1	74	343													
07:15	12	93	11	0	116	12	20	22	0	54	20	97	6	0	123	26	15	23	0	64	357													
07:30	17	112	26	0	155	7	29	28	0	64	34	109	6	0	149	29	35	26	3	93	461													
07:45	21	105	21	0	147	25	47	28	1	101	48	121	9	0	178	46	41	39	3	129	555													
Total	61	381	69	0	511	58	114	104	3	279	121	407	38	0	566	122	118	113	7	360	1716													
08:00	19	118	21	0	158	25	46	40	0	111	46	155	15	0	216	45	67	37	2	151	636													
08:15	20	96	23	0	139	18	45	37	0	100	56	156	10	0	222	43	55	34	0	132	593													
08:30	33	113	31	1	178	24	42	41	1	108	41	156	15	1	213	34	69	25	3	131	630													
08:45	33	100	27	0	160	22	56	45	0	123	58	124	9	0	191	41	64	17	2	124	598													
Total	105	427	102	1	635	89	189	163	1	442	201	591	49	1	842	163	255	113	7	538	2457													
Grand Total	166	808	171	1	1146	147	303	267	4	721	322	998	87	1	1408	285	373	226	14	898	4173													
Approch %	14.5	70.5	14.9	0.1		20.4	42	37	0.6		22.9	70.9	6.2	0.1		31.7	41.5	25.2	1.6															
Total %	4	19.4	4.1	0	27.5	3.5	7.3	6.4	0.1	17.3	7.7	23.9	2.1	0	33.7	6.8	8.9	5.4	0.3	21.5														
Passenger Vehicles	98.8	97	96.5	100	97.2	92.5	98.7	98.9	100	97.5	97.5	98.4	92	100	97.8	98.6	98.7	97.3	100	98.3	97.7													
% Passenger Vehicles																																		
SU Trucks & Buses	1	23	6	0	30	11	4	3	0	18	8	13	7	0	28	4	5	6	0	15	91													
% SU Trucks & Buses	0.6	2.8	3.5	0	2.6	7.5	1.3	1.1	0	2.5	2.5	1.3	8	0	2	1.4	1.3	2.7	0	1.7	2.2													
MU Trucks	1	1	0	0	2	0	0	0	0	0	0	3	0	0	3	0	0	0	0	0	5													
% MU Trucks	0.6	0.1	0	0	0.2	0	0	0	0	0	0	0.3	0	0	0.2	0	0	0	0	0	0.1													



Exit 3 Airport Connector
Wolf Rd & Metro Park Rd
AM
7 to 9

Manual Turning Movement Count
Clough, Harbour & Associates LLP
111 Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

File Name : Wolf - Metro Park AM
Site Code : 62806003
Start Date : 6/28/2006
Page No : 4





Manual Turning Movement Count
Clough, Harbour & Associates LLP
111 Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Airport Connector
Wolf Rd & Metro Park Rd
AM
7 to 9

File Name : Wolf - Metro Park AM
Site Code : 62806003
Start Date : 6/28/2006
Page No : 3


	Wolf Road Southbound					Metro Park Road Westbound					Wolf Road Northbound					Hess Access Eastbound						
Start Time	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Int. Total	
Peak Hour Analysis From 07:00 to 08:45 - Peak 1 of 1																						
Peak Hour for Entire Intersection Begins at 07:45																						
07:45	43	204	10	0	257	10					19					6	1	3		10		
08:00	56	211	11	0	278	6	1	6	0		13	2	126	21	0	149	3	1	1	0	5	445
08:15	60	208	12	0	280	5	1	11	0		17	0	127	24	0	151	6	1	3	0	10	458
08:30	49	233	9	0	291	8	0	10	1		19	0	130	18	1	149	5	1	0	0	6	465
Total Volume	208	856	42	0	1106	29	2	36	1		68	2	506	84	1	593	20	4	7	0	31	1798
% App. Total	18.8	77.4	3.8	0		42.6	2.9	52.9	1.5			0.3	85.3	14.2	0.2		64.5	12.9	22.6	0		
PHF	.867	.918	.875	.000	.950	.725	.500	.818	.250	.895	.250	.973	.875	.250	.250	.982	.833	1.000	.583	.000	.775	.967
Passenger Vehicles	205	835	40	0	1080	26	2	34	1		63	2	492	82	1	577	19	4	7	0	30	1750
% Passenger Vehicles	98.6	97.5	95.2	0	97.6	89.7	100	94.4	100	92.6		100	97.2	97.6	100	97.3	95.0	100	100	0	96.8	97.3
SU Trucks & Buses	3	20	2	0	25	2	0	2	0		4	0	13	1	0	14	1	0	0	0	1	44
% SU Trucks & Buses	1.4	2.3	4.8	0	2.3	6.9	0	5.6	0	5.9		0	2.6	1.2	0	2.4	5.0	0	0	0	3.2	2.4
MU Trucks	0	1	0	0	1	1	0	0	0		1	0	1	1	0	2	0	0	0	0	0	4
% MU Trucks	0	0.1	0	0	0.1	3.4	0	0	0	1.5		0	0.2	1.2	0	0.3	0	0	0	0	0	0.2



Exit 3 Airport Connector
Wolf Rd & Metro Park Rd
AM
7 to 9

Manual Turning Movement Count
Clough, Harbour & Associates LLP
111 Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

File Name : Wolf - Metro Park AM
Site Code : 62806003
Start Date : 6/28/2006
Page No : 2






III Winners Circle, P.O. Box 5269

www.cloughharbour.com

File Name : Wolf - Metro Park AM
Site Code : 62806003
Start Date : 6/28/2006
Page No : 1

Groups Printed- Passenger Vehicles - SU Trucks & Buses - MU Trucks																							
Wolf Road Southbound						Metro Park Road Westbound						Wolf Road Northbound						Hess Access Eastbound					
Start Time	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Int. Total		
07:00	24	124	10	1	159	1	1	5	0	7	0	67	6	0	73	6	2	2	0	10	249		
07:15	27	161	12	0	200	4	0	4	1	9	2	88	7	0	97	1	0	3	0	4	310		
07:30	36	204	5	0	245	4	0	7	0	11	0	113	15	0	128	2	1	0	2	5	389		
07:45	43	204	10	0	257	10	0	9	0	19	0	123	21	0	144	6	1	3	0	10	430		
Total	130	693	37	1	861	19	1	25	1	46	2	391	49	0	442	15	4	8	2	29	1378		
08:00	56	211	11	0	278	6	1	6	0	13	2	126	21	0	149	3	1	1	0	5	445		
08:15	60	208	12	0	280	5	1	11	0	17	0	127	24	0	151	6	1	3	0	10	458		
08:30	49	233	9	0	291	8	0	10	1	19	0	130	18	1	149	5	1	0	0	6	465		
08:45	38	198	9	0	245	10	1	11	0	22	3	119	22	0	144	2	2	5	1	10	421		
Total	203	850	41	0	1094	29	3	38	1	71	5	502	85	1	593	16	5	9	1	31	1789		
Grand Total	333	1543	78	1	1955	48	4	63	2	117	7	893	134	1	1035	31	9	17	3	60	3167		
Apprch %	17	78.9	4	0.1		41	3.4	53.8	1.7		0.7	86.3	12.9	0.1		51.7	15	28.3	5				
Total %	10.5	48.7	2.5	0	61.7	1.5	0.1	2	0.1	3.7	0.2	28.2	4.2	0	32.7	1	0.3	0.5	0.1	1.9			
Passenger Vehicles																							
% Passenger Vehicles	98.5	97.7	96.2	100	97.7	89.6	100	90.5	100	90.6	100	96.6	97.8	100	96.8	96.8	88.9	94.1	100	95	97.1		
SU Trucks & Buses	5	33	2	0	40	4	0	5	0	9	0	27	2	0	29	1	1	1	0	3	81		
% SU Trucks & Buses	1.5	2.1	2.6	0	2	8.3	0	7.9	0	7.7	0	3	1.5	0	2.8	3.2	11.1	5.9	0	5	2.6		
MU Trucks	0	3	1	0	4	1	0	1	0	2	0	3	1	0	4	0	0	0	0	0	10		
% MU Trucks	0	0.2	1.3	0	0.2	2.1	0	1.6	0	1.7	0	0.3	0.7	0	0.4	0	0	0	0	0	0.3		





Manual Turning Movement Count
Clough, Harbour & Associates LLP
III Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Airport Connector
Wolf & I-87 NB Off-Ramp
AM
7 to 9

File Name : Wolf - Exit 4 NB Off-Ramp AM
Site Code : 71106001
Start Date : 7/11/2006
Page No : 3


Start Time	Wolf Road Southbound					Wolf Road Northbound					I-87 NB Off-Ramp Eastbound				
	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total
Peak Hour Analysis From 07:00 to 08:45 - Peak 1 of 1															
Peak Hour for Entire Intersection Begins at 07:45															
07:45	0	319	0	5	324	0	0	0	0	0	168	0	0	0	172
08:00	0	294	0	0	294	0	0	0	0	0	144	0	0	0	144
08:15	0	285	0	0	285	0	0	0	0	0	153	0	0	0	153
08:30	0	275	0	2	277	0	0	0	0	0	148	0	0	0	148
Total Volume	0	1173	0	7	1180	0	0	0	0	0	613	0	4	0	617
% App. Total	0	99.4	0	0.6	100.0	0	0	0	0	0	99.4	0	0.6	0	100.0
PHF	.000	.919	.000	.350	.910	.000	.000	.000	.000	.000	.912	.250	.000	.888	.951
Passenger Vehicles	0	1153	0	7	1160	0	0	0	0	0	594	0	4	0	598
% Passenger Vehicles	0	98.3	0	100	98.3	0	0	0	0	0	96.9	0	100	0	96.9
SU Trucks & Buses	0	10	0	0	10	0	0	0	0	0	12	0	0	0	12
% SU Trucks & Buses	0	0.9	0	0	0.8	0	0	0	0	0	1.9	0	0	0	1.9
MU Trucks	0	10	0	0	10	0	0	0	0	0	7	0	0	0	7
% MU Trucks	0	0.9	0	0	0.8	0	0	0	0	0	1.1	0	0	0	1.1



Exit 3 Airport Connector
Wolf & I-87 NB Off-Ramp
AM
7 to 9

Manual Turning Movement Count
Clough, Harbour & Associates LLP
111 Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

File Name : Wolf - Exit 4 NB Off-Ramp AM
Site Code : 71106001
Start Date : 7/11/2006
Page No : 2






Manual Turning Movement Count
Clough, Harbour & Associates LLP
III Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Airport Connector
Wolf & I-87 NB Off-Ramp
AM
7 to 9

File Name : Wolf - Exit 4 NB Off-Ramp AM
Site Code : 71106001
Start Date : 7/11/2006
Page No : 1

Groups Printed- Passenger Vehicles - SU Trucks & Buses - MU Trucks

Start Time	Wolf Road Southbound						Wolf Road Northbound						I-87 NB Off-Ramp Eastbound					
	Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total	Int. Total
07:00	0	189	0	0	189		0	0	0	0	0		0	85	0	0	85	409
07:15	0	251	0	0	251		0	0	0	0	0		0	109	0	0	109	528
07:30	0	254	0	0	254		0	0	0	0	0		0	105	0	0	105	551
07:45	0	319	0	5	324		0	0	0	0	4		0	168	0	4	172	715
Total	0	1013	0	5	1018		0	0	0	0	4		0	467	0	4	471	2203
08:00	0	294	0	0	294		0	0	0	0	0		0	144	0	0	144	644
08:15	0	285	0	0	285		0	0	0	0	0		0	153	0	0	153	651
08:30	0	275	0	2	277		0	0	0	0	0		0	148	0	0	148	620
08:45	0	271	0	0	271		0	0	0	0	1		0	160	0	1	161	634
Total	0	1125	0	2	1127		0	0	0	0	1		0	605	0	1	606	2549
Grand Total	0	2138	0	7	2145		0	0	0	0	5		0	1072	0	5	1077	4752
Approch %	0	99.7	0	0.3			0	0	0	0	0.5		0	99.5	0	0.5		
Total %	0	45	0	0.1	45.1		0	0	0	0	0.1		0	22.6	0	0.1	22.7	32.2
Passenger Vehicles	0	97.8	0	100	97.9		0	0	0	0	0		0	96.5	0	100	96.6	97.5
% Passenger Vehicles	0	23	0	0	23		0	0	0	0	0		0	25	0	0	25	61
SU Trucks & Buses	0	1.1	0	0	1.1		0	0	0	0	0		0	2.3	0	0	2.3	1.3
% SU Trucks & Buses	0	23	0	0	23		0	0	0	0	0		0	12	0	0	12	58
MU Trucks	0	1.1	0	0	1.1		0	0	0	0	0		0	1.1	0	0	1.1	1.2
% MU Trucks	0	1.1	0	0	1.1		0	0	0	0	0		0	1.1	0	0	1.1	1.2





Manual Turning Movement Count
Clough, Harbour & Associates LLP
111 Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Airport Connector
Wolf Rd & Albany Shaker
AM
7 to 9

File Name : Albany Shaker - Wolf AM
Site Code : 07116005
Start Date : 7/11/2006
Page No : 3


	I-87 NB On-Ramp Southbound					Albany Shaker Road Westbound					Wolf Road Northbound					Albany Shaker Road Eastbound					
Start Time	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Int. Total
Peak Hour Analysis From 07:00 to 08:45 - Peak 1 of 1																					
Peak Hour for Entire Intersection Begins at 07:45																					
07:45	0	0	0	0	0	95	176			323	163	48	82	1	294	20	150	213	0	382	980
08:00	0	0	0	0	0	77	134	50	0	261	154	54	85	0	293	28	141	182	0	351	937
08:15	0	0	0	0	0	105	136	53	0	294	154	54	85	0	293	28	141	182	0	351	938
08:30	0	0	0	0	0	79	137	37	0	253	141	61	63	0	265	43	131	196	1	371	889
Total Volume	0	0	0	0	0	356	583	192	0	1131	609	217	314	1	1141	116	552	803	1	1472	3744
% App. Total	0	0	0	0	0	31.5	51.5	17	0		53.4	19	27.5	0.1		7.9	37.5	54.6	0.1		
PHF	.000	.000	.000	.000	.000	.848	.828	.906	.000	.875	.934	.889	.924	.250	.970	.674	.920	.942	.250	.963	.955
Passenger Vehicles	0	0	0	0	0	352	570	190	0	1112	597	212	310	1	1120	110	541	783	1	1435	3667
% Passenger Vehicles	0	0	0	0	0	98.9	97.8	99.0	0	98.3	98.0	97.7	98.7	100	98.2	94.8	98.0	97.5	100	97.5	97.9
SU Trucks & Buses	0	0	0	0	0	3	10	2	0	15	10	4	3	0	17	6	8	18	0	32	64
% SU Trucks & Buses	0	0	0	0	0	0.8	1.7	1.0	0	1.3	1.6	1.8	1.0	0	1.5	5.2	1.4	2.2	0	2.2	1.7
MU Trucks	0	0	0	0	0	1	3	0	0	4	2	1	1	0	4	0	3	2	0	5	13
% MU Trucks	0	0	0	0	0	0.3	0.5	0	0	0.4	0.3	0.5	0.3	0	0.4	0	0.5	0.2	0	0.3	0.3



Exit 3 Airport Connector
Wolf Rd & Albany Shaker
AM
7 to 9

Manual Turning Movement Count
Clough, Harbour & Associates LLP
III Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

File Name : Albany Shaker - Wolf AM
Site Code : 07116005
Start Date : 7/11/2006
Page No : 2






Manual Turning Movement Count
Clough, Harbour & Associates LLP
III Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Airport Connector
Wolf Rd & Albany Shaker
AM
7 to 9

File Name : Albany Shaker - Wolf AM
Site Code : 07116005
Start Date : 7/11/2006
Page No : 1

Groups Printed- Passenger Vehicles - SU Trucks & Buses - MU Trucks

Start Time	I-87 NB On-Ramp Southbound						Albany Shaker Road Westbound						Wolf Road Northbound						Albany Shaker Road Eastbound					
	Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total	Int. Total
07:00	0	0	0	0	0		43	74	31	0	148		119	30	38	0	187		36	100	147	0	283	618
07:15	0	0	0	0	0		49	103	46	0	198		153	34	45	0	232		22	111	206	0	339	769
07:30	0	0	0	0	0		51	133	64	1	249		150	26	52	1	229		28	137	201	0	366	844
07:45	0	0	0	0	0		95	176	52	0	323		151	54	84	0	289		25	130	213	0	368	980
Total	0	0	0	0	0		238	486	193	1	918		573	144	219	1	937		111	478	767	0	1356	3211
08:00	0	0	0	0	0		77	134	50	0	261		163	48	82	1	294		20	150	212	0	382	937
08:15	0	0	0	0	0		105	136	53	0	294		154	54	85	0	293		28	141	182	0	351	938
08:30	0	0	0	0	0		79	137	37	0	253		141	61	63	0	265		43	131	196	1	371	889
08:45	0	0	0	0	0		68	120	55	0	243		179	69	84	1	333		36	114	214	0	364	940
Total	0	0	0	0	0		329	527	195	0	1051		637	232	314	2	1185		127	536	804	1	1488	3704
Grand Total	0	0	0	0	0		567	1013	388	1	1969		1210	376	533	3	2122		238	1014	1571	1	2824	6915
Approch %	0	0	0	0	0		28.8	51.4	19.7	0.1			57	17.7	25.1	0.1			8.4	35.9	55.6	0		
Total %	0	0	0	0	0		8.2	14.6	5.6	0	28.5		17.5	5.4	7.7	0	30.7		3.4	14.7	22.7	0	40.8	
Passenger Vehicles	0	0	0	0	0		98.4	98.1	97.4	100	98.1		97.6	98.4	97.2	100	97.6		96.6	97.7	97.4	100	97.5	97.7
% Passenger Vehicles	0	0	0	0	0		7	15	8	0	30		17	5	12	0	34		7	20	34	0	61	125
SU Trucks & Buses	0	0	0	0	0		1.2	1.5	2.1	0	1.5		1.4	1.3	2.3	0	1.6		2.9	2	2.2	0	2.2	1.8
% SU Trucks & Buses	0	0	0	0	0		2	4	2	0	8		12	1	3	0	16		1	3	7	0	11	35
MU Trucks	0	0	0	0	0		0.4	0.4	0.5	0	0.4		1	0.3	0.6	0	0.8		0.4	0.3	0.4	0	0.4	0.5
% MU Trucks	0	0	0	0	0		0.4	0.4	0.5	0	0.4		1	0.3	0.6	0	0.8		0.4	0.3	0.4	0	0.4	0.5





Manual Turning Movement Count
Clough, Harbour & Associates LLP
111 Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Airport Connector
Albany Shaker & Old Wolf Rd
AM
7 to 9

File Name : Albany Shaker - Old Wolf AM
Site Code : 71106003
Start Date : 7/11/2006
Page No : 3


Old Wolf Road Southbound					Albany Shaker Road Westbound					I-87 SB On-Ramp Northbound					Albany Shaker Road Eastbound						
Start Time	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Int. Total
Peak Hour Analysis From 07:00 to 08:45 - Peak 1 of 1																					
Peak Hour for Entire Intersection Begins at 07:45																					
07:45	219	10	98	16		75	235			329						37	175			271	
08:00	252	10	160	0	422	63	220	33	0	316	0	0	1	3	4	22	131	56	0	209	951
08:15	217	11	122	0	350	70	210	31	0	311	0	0	0	0	0	23	143	84	0	250	911
08:30	208	30	112	1	351	51	188	54	0	293	0	0	0	1	1	25	163	56	0	244	889
Total Volume	896	61	492	17	1466	259	853	137	0	1249	0	0	1	4	5	107	612	255	0	974	3694
% App. Total	61.1	4.2	33.6	1.2		20.7	68.3	11	0		0	0	20	80		11	62.8	26.2	0		
PHF	.889	.508	.769	.266	.868	.863	.907	.634	.000	.949	.000	.000	.250	.333	.313	.723	.874	.759	.000	.899	.971
Passenger Vehicles	879	52	477	17	1425	252	838	129	0	1219	0	0	1	4	5	102	598	245	0	945	3594
% Passenger Vehicles	98.1	85.2	97.0	100	97.2	97.3	98.2	94.2	0	97.6	0	0	100	100	100	95.3	97.7	96.1	0	97.0	97.3
SU Trucks & Buses	17	8	15	0	40	6	15	8	0	29	0	0	0	0	0	5	14	9	0	28	97
% SU Trucks & Buses	1.9	13.1	3.0	0	2.7	2.3	1.8	5.8	0	2.3	0	0	0	0	0	4.7	2.3	3.5	0	2.9	2.6
MU Trucks	0	1	0	0	1	1	0	0	0	1	0	0	0	0	0	0	0	1	0	1	3
% MU Trucks	0	1.6	0	0	0.1	0.4	0	0	0	0.1	0	0	0	0	0	0	0	0.4	0	0.1	0.1



Exit 3 Airport Connector
Albany Shaker & Old Wolf Rd
AM
7 to 9

Manual Turning Movement Count
Clough, Harbour & Associates LLP
111 Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

File Name : Albany Shaker - Old Wolf AM
Site Code : 71106003
Start Date : 7/11/2006
Page No : 2





Manual Turning Movement Count
Clough, Harbour & Associates LLP
111 Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Airport Connector
Albany Shaker & Old Wolf Rd
AM
7 to 9

File Name : Albany Shaker - Old Wolf AM
Site Code : 71106003
Start Date : 7/11/2006
Page No : 1

Groups Printed- Passenger Vehicles - SU Trucks & Buses - MU Trucks


Start Time	Old Wolf Road Southbound						Albany Shaker Road Westbound						I-87 SB On-Ramp Northbound						Albany Shaker Road Eastbound					
	Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total	Int. Total
07:00	196	6	96	0	298		43	176	39	0	258		0	0	0	0	3		25	94	30	0	149	708
07:15	179	5	82	0	266		42	148	32	0	222		0	0	0	0	0		24	119	60	0	203	691
07:30	256	12	111	0	379		39	181	34	0	254		0	0	0	0	0		18	115	41	0	174	807
07:45	219	10	98	16	343		75	235	19	0	329		0	0	0	0	0		37	175	59	0	271	943
Total	850	33	387	16	1286		199	740	124	0	1063		0	0	0	0	3		104	503	190	0	797	3149
08:00	252	10	160	0	422		63	220	33	0	316		0	0	1	3	4		22	131	56	0	209	951
08:15	217	11	122	0	350		70	210	31	0	311		0	0	0	0	0		23	143	84	0	250	911
08:30	208	30	112	1	351		51	188	54	0	293		0	0	0	1	1		25	163	56	0	244	889
08:45	228	21	87	1	337		65	194	38	0	297		0	0	0	0	0		23	148	83	0	254	888
Total	905	72	481	2	1460		249	812	156	0	1217		0	0	1	4	5		93	585	279	0	957	3639
Grand Total	1755	105	868	18	2746		448	1552	280	0	2280		0	0	1	7	8		197	1088	469	0	1754	6788
Approch %	63.9	3.8	31.6	0.7			19.6	68.1	12.3	0			0	0	12.5	87.5			11.2	62	26.7	0		
Total %	25.9	1.5	12.8	0.3	40.5		6.6	22.9	4.1	0	33.6		0	0	0	0.1	0.1		2.9	16	6.9	0	25.8	
Passenger Vehicles	98.2	86.7	96.7	100	97.3		95.8	98	94.3	0	97.1		0	0	100	100	100		93.9	97.6	96.6	0	96.9	97.1
% Passenger Vehicles																								
SU Trucks & Buses	31	13	29	0	73		17	31	16	0	64		0	0	0	0	0		12	26	15	0	53	190
% SU Trucks & Buses	1.8	12.4	3.3	0	2.7		3.8	2	5.7	0	2.8		0	0	0	0	0		6.1	2.4	3.2	0	3	2.8
MU Trucks	0	1	0	0	1		2	0	0	0	2		0	0	0	0	0		0	0	1	0	1	4
% MU Trucks	0	1	0	0	0		0.4	0	0	0	0.1		0	0	0	0	0		0	0	0.2	0	0.1	0.1



Manual Turning Movement Count
Clough, Harbour & Associates LLP
111 Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Airport Connector
Old Wolf Rd & I-87 SB Exit 4 Off-Ramp
AM
7 to 9

File Name : Old Wolf - Exit 4 SB AM
Site Code : 62906007
Start Date : 6/29/2006
Page No : 4






Manual Turning Movement Count
Clough, Harbour & Associates LLP
111 Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Airport Connector
Old Wolf Rd & I-87 SB Exit 4 Off-Ramp
AM
7 to 9

File Name : Old Wolf - Exit 4 SB AM
Site Code : 62906007
Start Date : 6/29/2006
Page No : 3

	Old Wolf Road Southbound					I-87 SB Exit 4 Off-Ramp Westbound					Old Wolf Road Northbound					Terminal Drive Eastbound					
Start Time	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Int. Total
Peak Hour Analysis From 07:00 to 08:45 - Peak 1 of 1																					
Peak Hour for Entire Intersection Begins at 07:30																					
07:30	0	47	0	0	47	249	1	6	0	286	1	58	0	0	58	0	0	4	0	4	407
07:45	0	59	0	0	59	279	1	6	0	286	0	58	0	0	52	1	0	0	1	2	406
08:00	0	69	1	0	70	277	0	5	0	282	0	52	0	0	52	0	0	2	0	2	393
08:15	0	52	0	0	52	281	0	6	0	287	0	52	0	0	52	0	0	2	0	2	1564
Total Volume	0	227	1	0	228	1086	2	23	0	1111	1	212	1	0	214	1	0	9	1	11	
% App. Total	0	99.6	0.4	0		97.7	0.2	2.1	0		0.5	99.1	0.5	0		9.1	0	81.8	9.1		
PHF	.000	.822	.250	.000	.814	.966	.500	.958	.000	.968	.250	.914	.250	.000	.922	.250	.000	.563	.250	.688	.961
Passenger Vehicles	0	209	1	0	210	1078	2	23	0	1103	1	202	1	0	204	1	0	3	1	5	1522
% Passenger Vehicles	0	92.1	100	0	92.1	99.3	100	100	0	99.3	100	95.3	100	0	95.3	100	0	33.3	100	45.5	97.3
SU Trucks & Buses	0	16	0	0	16	7	0	0	0	7	0	7	0	0	7	0	0	6	0	6	36
% SU Trucks & Buses	0	7.0	0	0	7.0	0.6	0	0	0	0.6	0	3.3	0	0	3.3	0	0	66.7	0	54.5	2.3
MU Trucks	0	2	0	0	2	1	0	0	0	1	0	3	0	0	3	0	0	0	0	0	6
% MU Trucks	0	0.9	0	0	0.9	0.1	0	0	0	0.1	0	1.4	0	0	1.4	0	0	0	0	0	0.4





Manual Turning Movement Count

Clough, Harbour & Associates LLP

111 Winners Circle, P.O. Box 5269

Albany, NY 12205

www.cloughharbour.com

Exit 3 Airport Connector

Old Wolf Rd & I-87 SB Exit 4 Off-Ramp

AM

7 to 9

File Name : Old Wolf - Exit 4 SB AM


Site Code : 62906007

Start Date : 6/29/2006

Page No : 1

Groups Printed- Passenger Vehicles - SU Trucks & Buses - MU Trucks

Start Time	Old Wolf Road Southbound						I-87 SB Exit 4 Off-Ramp Westbound						Old Wolf Road Northbound						Terminal Drive Eastbound					
	Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total	Int. Total
07:00	0	36	0	0	36		201	1	7	0	209		2	63	0	0	65		0	0	0	0	0	310
07:15	0	27	0	0	27		254	0	4	0	258		0	47	0	0	47		0	0	0	0	0	332
07:30	0	47	0	0	47		249	1	6	0	256		1	50	1	0	52		0	0	3	0	3	358
07:45	0	59	0	0	59		279	1	6	0	286		0	58	0	0	58		0	0	4	0	4	407
Total	0	169	0	0	169		983	3	23	0	1009		3	218	1	0	222		0	0	7	0	7	1407
08:00	0	69	1	0	70		277	0	5	0	282		0	52	0	0	52		1	0	0	1	2	406
08:15	0	52	0	0	52		281	0	6	0	287		0	52	0	0	52		0	0	2	0	2	393
08:30	1	56	1	0	58		232	0	5	0	237		2	55	0	0	57		0	0	0	0	0	352
08:45	1	54	0	0	55		263	0	3	0	266		0	50	0	0	50		0	0	0	0	0	371
Total	2	231	2	0	235		1053	0	19	0	1072		2	209	0	0	211		1	0	2	1	4	1522
Grand Total	2	400	2	0	404		2036	3	42	0	2081		5	427	1	0	433		1	0	9	1	11	2929
Apprch %	0.5	99	0.5	0			97.8	0.1	2	0			1.2	98.6	0.2	0			9.1	0	81.8	9.1		
Total %	0.1	13.7	0.1	0	13.8		69.5	0.1	1.4	0	71		0.2	14.6	0	0	14.8		0	0	0.3	0	0.4	
Passenger Vehicles																								
% Passenger Vehicles	100	91	50	0	90.8		99	66.7	100	0	98.9		40	94.8	100	0	94.2		100	0	33.3	100	45.5	96.9
SU Trucks & Buses	0	29	0	0	29		17	0	0	0	17		3	12	0	0	15		0	0	6	0	6	67
% SU Trucks & Buses	0	7.2	0	0	7.2		0.8	0	0	0	0.8		60	2.8	0	0	3.5		0	0	66.7	0	54.5	2.3
MU Trucks	0	7	1	0	8		4	1	0	0	5		0	10	0	0	10		0	0	0	0	0	23
% MU Trucks	0	1.8	50	0	2		0.2	33.3	0	0	0.2		0	2.3	0	0	2.3		0	0	0	0	0	0.8





Manual Turning Movement Count
Clough, Harbour & Associates LLP
111 Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Airport Connector
Albany Shaker - Alb Int Terminal
AM
7 to 9

File Name : Albany Shaker - Alb Int Term Access AM
Site Code : 71106009
Start Date : 7/11/2006
Page No : 3

Start Time	Albany International Airport Exit Drive Southbound						Albany Shaker Road Westbound						Albany Shaker Road Eastbound					
	Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total	Int. Total
07:45	14	0	10	0	24		0	285	1	0	285		0	0	0	0	225	540
08:00	15	0	4	0	19		0	243	0	0	243		0	0	0	0	226	529
08:15	19	0	5	0	24		0	213	0	0	213		0	0	0	0	252	493
08:30	20	0	7	0	27		0	1009	1	0	1010		0	0	0	0	950	492
Total Volume	68	0	26	0	94		0	99.9	0.1	0	1010		0	0	0	0	950	2054
% App. Total	72.3	0	27.7	0			0	.885	.250	.000	.886		0	.000	.000	.000	.942	.951
PHF	.850	.000	.650	.000	.870		0	.992	1	0	.993		0	.000	.000	0	.932	2016
Passenger Vehicles	67	0	24	0	91		0	98.3	100	0	98.3		0	0	0	0	98.1	98.1
% Passenger Vehicles	98.5	0	92.3	0	96.8		0	14	0	0	14		0	0	0	0	10	25
SU Trucks & Buses	0	0	1	0	1		0	1.4	0	0	1.4		0	0	0	0	1.1	1.2
% SU Trucks & Buses	0	0	3.8	0	1.1		0	3	0	0	3		0	0	0	0	.8	.13
MU Trucks	1	0	1	0	2		0	0.3	0	0	0.3		0	0	0	0	0.8	0.6
% MU Trucks	1.5	0	3.8	0	2.1		0	0.3	0	0	0.3		0	0	0	0	0.8	0.6

Albany International Airport Exit Drive

Out	In	Total
166	164	330
6	9	15
1	2	3
173	175	348

Right	Left	Peds
44	120	0
7	2	0
1	1	0
52	123	0

Out	In	Total
1812	1732	3544
8	13	21
24	22	46
1780	1697	3477

Peds	Thru	Left
0	1562	170
0	12	1
0	16	6
1534	163	163

North
7/11/2006 07:00
7/11/2006 08:45
Passenger Vehicles
SU Trucks & Buses
MU Trucks

Out	In	Total
1654	1739	3393
18	17	35
13	7	20
1685	1763	3448

Right	Thru	Peds
3	1736	0
0	17	0
0	7	0
3	1760	0



Manual Turning Movement Count

Clough, Harbour & Associates LLP

III Winners Circle, P.O. Box 5269

Albany, NY 12205
www.cloughharbour.com

Exit 3 Airport Connector
Albany Shaker - Alb Int Terminal
AM
7 to 9

File Name : Albany Shaker - Alb Int Term Access AM
Site Code : 71106009
Start Date : 7/11/2006
Page No : 1

Groups Printed- Passenger Vehicles - SU Trucks & Buses - MU Trucks


Start Time	Albany International Airport Exit Drive Southbound						Albany Shaker Road Westbound						Albany Shaker Road Eastbound					
	Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total	Int. Total
07:00	23	0	8	0	31		0	148	0	0	148		0	0	0	0	0	337
07:15	10	0	11	0	21		0	165	1	0	166		0	0	0	0	0	389
07:30	11	0	4	0	15		0	231	0	0	231		0	0	0	0	0	432
07:45	14	0	10	0	24		0	268	1	0	269		0	0	0	0	0	540
Total	58	0	33	0	91		0	812	2	0	814		0	0	0	0	0	1698
08:00	15	0	4	0	19		0	285	0	0	285		0	0	0	0	0	529
08:15	19	0	5	0	24		0	243	0	0	243		0	0	0	0	0	493
08:30	20	0	7	0	27		0	213	0	0	213		0	0	0	0	0	492
08:45	11	0	3	0	14		0	207	1	0	208		0	0	0	0	0	458
Total	65	0	19	0	84		0	948	1	0	949		0	0	0	0	0	1972
Grand Total	123	0	52	0	175		0	1760	3	0	1763		0	0	0	0	0	3670
Approach %	70.3	0	29.7	0	4.8		0	99.8	0.2	0	48		0	0	0	0	0	
Total %	3.4	0	1.4	0			0	48	0.1	0			0	0	0	0	0	47.2
Passenger Vehicles	97.6	0	84.6	0	93.7		0	98.6	100	0	98.6		0	0	0	0	0	98
% Passenger Vehicles	2	0	7	0	9		0	17	0	0	17		0	0	0	0	0	48
SU Trucks & Buses	1.6	0	13.5	0	5.1		0	1	0	0	1		0	0	0	0	0	22
% SU Trucks & Buses	1	0	1	0	2		0	7	0	0	7		0	0	0	0	0	1.3
MU Trucks	0.8	0	1.9	0	1.1		0	0.4	0	0	0.4		0	0	0	0	0	13
% MU Trucks													0.6	0.8	0	0	0	0.6



Manual Turning Movement Count
Clough, Harbour & Associates LLP
111 Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Airport Connector
Albany Shaker & Watervliet Shaker
AM
7 to 9

File Name : Albany Shaker - Watervliet Shaker AM
Site Code : 62806001
Start Date : 6/28/2006
Page No : 4





Manual Turning Movement Count
Clough, Harbour & Associates LLP
111 Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Airport Connector
Albany Shaker & Watervliet Shaker
AM
7 to 9

File Name : Albany Shaker - Watervliet Shaker AM
Site Code : 62806001
Start Date : 6/28/2006
Page No : 3


	Albany Shaker Road Southbound					Albany International Airport Drive Westbound					Albany Shaker Road Northbound					Watervliet Shaker Road Eastbound					
Start Time	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Int. Total
Peak Hour Analysis From 07:00 to 08:45 - Peak 1 of 1																					
Peak Hour for Entire Intersection Begins at 07:45																					
07:45	8	123						6								52		75		127	558
08:00	6	110	48	0	164	35	3	25	0	63	69	146	1	0	216	46	0	68	0	114	557
08:15	6	117	43	0	166	21	1	22	0	44	69	111	3	0	183	52	1	67	0	120	513
08:30	13	118	62	0	193	31	5	17	0	53	53	109	3	0	165	46	0	71	0	117	528
Total Volume	33	468	205	0	706	110	15	74	0	199	257	507	9	0	773	196	1	281	0	478	2156
% App. Total	4.7	66.3	29	0		55.3	7.5	37.2	0		33.2	65.6	1.2	0		41	0.2	58.8	0		
PHF	.635	.951	.827	.000	.915	.786	.625	.740	.000	.790	.931	.868	.750	.000	.895	.942	.250	.937	.000	.941	.966
Passenger Vehicles	33	462	204	0	699	110	14	72	0	196	250	500	9	0	759	193	1	280	0	474	2128
% Passenger Vehicles	100	98.7	99.5	0	99.0	100	93.3	97.3	0	98.5	97.3	98.6	100	0	98.2	98.5	100	99.6	0	99.2	98.7
SU Trucks & Buses	0	4	1	0	5	0	0	1	0	1	7	6	0	0	13	2	0	1	0	3	22
% SU Trucks & Buses	0	0.9	0.5	0	0.7	0	0	1.4	0	0.5	2.7	1.2	0	0	1.7	1.0	0	0.4	0	0.6	1.0
MU Trucks	0	2	0	0	2	0	1	1	0	2	0	1	0	0	1	1	0	0	0	1	6
% MU Trucks	0	0.4	0	0	0.3	0	6.7	1.4	0	1.0	0	0.2	0	0	0.1	0.5	0	0	0	0.2	0.3



Manual Turning Movement Count
Clough, Harbour & Associates LLP
111 Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Airport Connector
Albany Shaker & Watervliet Shaker
AM
7 to 9

File Name : Albany Shaker - Watervliet Shaker AM
Site Code : 62806001
Start Date : 6/28/2006
Page No : 2






Manual Turning Movement Count
Clough, Harbour & Associates LLP
111 Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Airport Connector
Albany Shaker & Watervliet Shaker
AM
7 to 9

File Name : Albany Shaker - Watervliet Shaker AM
Site Code : 62806001
Start Date : 6/28/2006
Page No : 1

Groups Printed- Passenger Vehicles - SU Trucks & Buses - MU Trucks														
Albany Shaker Road Southbound					Albany International Airport Drive Westbound					Albany Shaker Road Northbound				
Start Time	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds
Factor	1.0	1.0	1.0	1.0		1.0	1.0	1.0	1.0		1.0	1.0	1.0	1.0
07:00	9	84	18	0	111	36	1	21	0	58	48	71	2	0
07:15	12	99	34	0	145	38	2	28	0	68	54	91	0	0
07:30	10	101	30	0	141	31	2	10	0	43	71	91	0	0
07:45	8	123	52	0	183	23	6	10	0	39	66	141	2	0
Total	39	407	134	0	580	128	11	69	0	208	239	394	4	0
08:00	6	110	48	0	164	35	3	25	0	63	69	146	1	0
08:15	6	117	43	0	166	21	1	22	0	44	69	111	3	0
08:30	13	118	62	0	193	31	5	17	0	53	53	109	3	0
08:45	11	105	45	0	161	26	4	17	0	47	63	111	1	0
Total	36	450	198	0	684	113	13	81	0	207	254	477	8	0
Grand Total	75	857	332	0	1264	241	24	150	0	415	493	871	12	0
Approch %	5.9	67.8	26.3	0		58.1	5.8	36.1	0		35.8	63.3	0.9	0
Total %	1.9	21.6	8.4	0	31.9	6.1	0.6	3.8	0	10.5	12.4	22	0.3	0
Passenger Vehicles														
% Passenger Vehicles	100	98	97.6	0	98	99.6	95.8	96.7	0	98.3	98.4	98.2	100	0
SU Trucks & Buses	0	12	7	0	19	1	0	4	0	5	8	11	0	0
% SU Trucks & Buses	0	1.4	2.1	0	1.5	0.4	0	2.7	0	1.2	1.6	1.3	0	0
MU Trucks	0	5	1	0	6	0	1	1	0	2	0	5	0	0
% MU Trucks	0	0.6	0.3	0	0.5	0	4.2	0.7	0	0.5	0	0.6	0	0
Eastbound														
Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total
1.0	1.0	1.0	1.0		1.0	1.0	1.0	1.0		1.0	1.0	1.0	1.0	
29	0	60	0	89	121	0	60	0	181	29	0	60	0	89
44	0	66	0	110	145	0	66	0	211	44	0	66	0	110
44	0	81	0	125	162	0	81	0	243	44	0	81	0	125
52	0	75	0	127	209	0	75	0	284	52	0	75	0	127
169	0	282	0	451	637	0	282	0	919	169	0	282	0	451
46	0	68	0	114	216	0	68	0	284	46	0	68	0	114
52	1	67	0	120	183	0	67	0	250	52	1	67	0	120
46	0	71	0	117	165	0	71	0	236	46	0	71	0	117
59	1	49	0	109	175	0	49	0	224	59	1	49	0	109
203	2	255	0	460	739	0	255	0	1004	203	2	255	0	460
372	2	537	0	911	1376	0	537	0	1513	372	2	537	0	911
40.8	0.2	58.9	0			40.8	0.2	58.9	0		40.8	0.2	58.9	0
9.4	0.1	13.5	0	23	34.7	9.4	0.1	13.5	0	23	9.4	0.1	13.5	0
Grand Total														
% Passenger Vehicles	98.4	100	99.4	0	98.3	98.9	100	99.4	0	98.2	98.9	100	99.4	0
SU Trucks & Buses	0	3	0	6	19	3	0	3	0	19	3	0	3	0
% SU Trucks & Buses	0	0.3	0	0.7	1.4	0.8	0	0.6	0	1.4	0.8	0	0.6	0
MU Trucks	1	0	0	1	5	1	0	0	0	5	1	0	0	0
% MU Trucks	0.1	0	0	0.1	0.4	0.3	0	0	0	0.4	0.3	0	0	0.1





Manual Turning Movement Count
Clough, Harbour & Associates LLP

111 Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Aripot Connector
Wolf Rd & Central Ave
PM
4 to 6

File Name : Wolf - Central PM
Site Code : 62906010
Start Date : 6/29/2006
Page No : 3


	Wolf Road Southbound					Central Avenue Westbound					I-87 Exit 2 EB Off Ramp Northbound					Central Avenue Eastbound					
Start Time	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Int. Total
Peak Hour Analysis From 16:00 to 17:45 - Peak 1 of 1																					
Peak Hour for Entire Intersection Begins at 16:45																					
16:45	108	0	247	0	355	0	342	107	0	449	0	163	59	0	216	104	223	0	0	327	
17:00	92	0	263	0	355	0	354	91	0	445	2	160	54	0	213	96	212	0	0	308	1324
17:15	114	0	300	0	414	0	332	108	0	440	0	160	53	0	213	91	219	0	0	310	1377
17:30	87	0	210	0	297	0	336	117	0	453	0	171	53	0	224	102	210	0	0	312	1286
Total Volume	401	0	1020	0	1421	0	1364	423	0	1787	2	654	219	0	875	393	864	0	0	1257	5340
% App. Total	28.2	0	71.8	0		0	76.3	23.7	0		0.2	74.7	25	0		31.3	68.7	0	0		
PHF	.879	.000	.850	.000	.858	.000	.963	.904	.000	.986	.250	.956	.928	.000	.977	.945	.969	.000	.000	.961	.969
Passenger Vehicles	392	0	1016	0	1408	0	1342	416	0	1758	2	650	213	0	865	393	835	0	0	1228	5259
% Passenger Vehicles	97.8	0	99.6	0	99.1	0	98.4	98.3	0	98.4	100	99.4	97.3	0	98.9	100	96.6	0	0	97.7	98.5
SU Trucks & Buses	9	0	3	0	12	0	11	7	0	18	0	2	2	0	4	0	16	0	0	16	50
% SU Trucks & Buses	2.2	0	0.3	0	0.8	0	0.8	1.7	0	1.0	0	0.3	0.9	0	0.5	0	1.9	0	0	1.3	0.9
MU Trucks	0	0	1	0	1	0	11	0	0	11	0	2	4	0	6	0	13	0	0	13	31
% MU Trucks	0	0	0.1	0	0.1	0	0.8	0	0	0.6	0	0.3	1.8	0	0.7	0	1.5	0	0	1.0	0.6



Exit 3 Aripport Connector
Wolf Rd & Central Ave
PM
4 to 6

Manual Turning Movement Count
Clough, Harbour & Associates LLP
111 Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

File Name : Wolf - Central PM
Site Code : 62906010
Start Date : 6/29/2006
Page No : 2





Manual Turning Movement Count Clough, Harbour & Associates LLP


111 Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Aripport Connector
Wolf Rd & Central Ave
PM
4 to 6

File Name : Wolf - Central PM
Site Code : 62906010
Start Date : 6/29/2006
Page No : 1

Groups Printed- Passenger Vehicles - SU Trucks & Buses - MU Trucks

Groups Printed- Passenger Vehicles - SU Trucks & Buses - MU Trucks																														
Wolf Road Southbound													Central Avenue Westbound						I-87 Exit 2 EB Off Ramp Northbound						Central Avenue Eastbound					
Start Time	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Int. Total				
Factor	1.0	1.0	1.0	1.0		1.0	1.0	1.0	1.0		1.0	1.0	1.0	1.0		1.0	1.0	1.0	1.0		1.0	1.0	1.0	1.0						
16:00	111	0	217	0	328	0	354	83	0	437	1	130	49	0	180	90	218	0	0	308						1253				
16:15	117	0	280	0	397	0	349	81	0	430	1	127	56	0	184	90	270	0	0	360						1371				
16:30	95	0	240	0	335	0	339	91	0	430	2	150	53	0	205	88	225	0	0	313						1283				
16:45	108	0	247	0	355	0	342	107	0	449	0	163	59	0	222	104	223	0	0	327						1353				
Total	431	0	984	0	1415	0	1384	362	0	1746	4	570	217	0	791	372	936	0	0	1308						5260				
17:00	92	0	263	0	355	0	354	91	0	445	2	160	54	0	216	96	212	0	0	308						1324				
17:15	114	0	300	0	414	0	332	108	0	440	0	160	53	0	213	91	219	0	0	310						1377				
17:30	87	0	210	0	297	0	336	117	0	453	0	171	53	0	224	102	210	0	0	312						1286				
17:45	94	0	210	0	304	0	290	94	0	384	0	151	73	0	224	99	214	0	0	313						1225				
Total	387	0	983	0	1370	0	1312	410	0	1722	2	642	233	0	877	388	855	0	0	1243						5212				
Grand Total	818	0	1967	0	2785	0	2696	772	0	3468	6	1212	450	0	1668	760	1791	0	0	2551						10472				
Approch %	29.4	0	70.6	0		0	77.7	22.3	0		0.4	72.7	27	0		29.8	70.2	0	0											
Total %	7.8	0	18.8	0	26.6	0	25.7	7.4	0	33.1	0.1	11.6	4.3	0	15.9	7.3	17.1	0	0	24.4										
Passenger Vehicles	97.8	0	99.4	0	98.9	0	98.3	97.8	0	98.2	100	99.2	96.4	0	98.4	99.7	97	0	0	97.8						98.3				
% Passenger Vehicles	18	0	10	0	28	0	22	17	0	39	0	7	6	0	13	2	29	0	0	31						111				
SU Trucks & Buses	2.2	0	0.5	0	1	0	0.8	2.2	0	1.1	0	0.6	1.3	0	0.8	0.3	1.6	0	0	1.2						1.1				
% SU Trucks & Buses	0	0	2	0	2	0	24	0	0	24	0	3	10	0	13	0	24	0	0	24						63				
MU Trucks	0	0	0.1	0	0.1	0	0.9	0	0	0.7	0	0.2	2.2	0	0.8	0	1.3	0	0	0.9						0.6				
% MU Trucks	0	0	0.1	0	0.1	0	0.9	0	0	0.7	0	0.2	2.2	0	0.8	0	1.3	0	0	0.9						0.6				





Manual Turning Movement Count
Clough, Harbour & Associates LLP
111 Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Airport Connector
Wolf Rd & Sand Creek Rd
PM
4 to 6

File Name : Wolf - Sand Creek PM
Site Code : 62806006
Start Date : 6/28/2006
Page No : 3


Wolf Road Southbound					Sand Creek Road Westbound					Wolf Road Northbound					Sand Creek Road Eastbound						
Start Time	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Int. Total
Peak Hour Analysis From 16:00 to 17:45 - Peak 1 of 1																					
Peak Hour for Entire Intersection Begins at 16:45																					
16:45	68	195	44	0	307	22	92	45	1	160	68	194	22	2	291	73	93	41	4	211	997
17:00	67	209	48	4	328	25	93	44	5	167	73	201	17	0	354	61	92	61	4	218	1078
17:15	77	212	58	2	349	18	102	34	3	157	77	251	26	0	301	67	134	33	3	237	1037
17:30	71	182	34	0	287	26	130	54	2	212	75	210	16	0	301	67	134	33	3	237	1037
Total Volume	283	798	184	6	1271	91	417	177	11	696	293	856	81	2	1232	273	404	182	12	871	4070
% App. Total	22.3	62.8	14.5	0.5		13.1	59.9	25.4	1.6		23.8	69.5	6.6	0.2		31.3	46.4	20.9	1.4		
PHF	.919	.941	.793	.375	.910	.875	.802	.819	.550	.821	.951	.853	.779	.250	.870	.935	.754	.746	.750	.919	.944
Passenger Vehicles	282	790	184	6	1262	82	417	176	11	686	292	846	79	2	1219	273	403	182	12	870	4037
% Passenger Vehicles	99.6	99.0	100	100	99.3	90.1	100	99.4	100	98.6	99.7	98.8	97.5	100	98.9	100	99.8	100	100	99.9	99.2
SU Trucks & Buses	1	7	0	0	8	8	0	1	0	9	1	9	2	0	12	0	1	0	0	1	30
% SU Trucks & Buses	0.4	0.9	0	0	0.6	8.8	0	0.6	0	1.3	0.3	1.1	2.5	0	1.0	0	0.2	0	0	0.1	0.7
MU Trucks	0	1	0	0	1	1	0	0	0	1	0	1	0	0	1	0	0	0	0	0	3
% MU Trucks	0	0.1	0	0	0.1	1.1	0	0	0	0.1	0	0.1	0	0	0.1	0	0	0	0	0	0.1



Exit 3 Airport Connector
Wolf Rd & Sand Creek Rd
PM
4 to 6

Manual Turning Movement Count
Clough, Harbour & Associates LLP
111 Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

File Name : Wolf - Sand Creek PM
Site Code : 62806006
Start Date : 6/28/2006
Page No : 2





Manual Turning Movement Count
Clough, Harbour & Associates LLP
III Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Airport Connector
Wolf Rd & Sand Creek Rd
PM
4 to 6

File Name : Wolf - Sand Creek PM
Site Code : 62806006
Start Date : 6/28/2006
Page No : 1

Groups Printed- Passenger Vehicles - SU Trucks & Buses - MU Trucks


Start Time	Wolf Road Southbound						Sand Creek Road Westbound						Wolf Road Northbound						Sand Creek Road Eastbound					
	Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total	Int. Total
16:00	61	195	39	1	296		29	65	40	7	141		60	227	16	1	304		60	77	31	2	170	911
16:15	56	152	43	1	252		21	83	50	3	157		66	177	19	1	263		68	81	48	2	199	871
16:30	67	170	40	3	280		16	89	44	5	154		71	179	21	0	271		51	79	54	1	185	890
16:45	68	195	44	0	307		22	92	45	1	160		68	194	22	2	286		72	85	47	1	205	958
Total	252	712	166	5	1135		88	329	179	16	612		265	777	78	4	1124		251	322	180	6	759	3630
17:00	67	209	48	4	328		25	93	44	5	167		73	201	17	0	291		73	93	41	4	211	997
17:15	77	212	58	2	349		18	102	34	3	157		77	251	26	0	354		61	92	61	4	218	1078
17:30	71	182	34	0	287		26	130	54	2	212		75	210	16	0	301		67	134	33	3	237	1037
17:45	67	159	36	1	263		16	119	58	3	196		65	172	20	2	259		58	115	55	2	230	948
Total	282	762	176	7	1227		85	444	190	13	732		290	834	79	2	1205		259	434	190	13	896	4060
Grand Total	534	1474	342	12	2362		173	773	369	29	1344		555	1611	157	6	2329		510	756	370	19	1655	7690
Approch %	22.6	62.4	14.5	0.5			12.9	57.5	27.5	2.2			23.8	69.2	6.7	0.3			30.8	45.7	22.4	1.1		
Total %	6.9	19.2	4.4	0.2	30.7		2.2	10.1	4.8	0.4	17.5		7.2	20.9	2	0.1	30.3		6.6	9.8	4.8	0.2	21.5	
Passenger Vehicles																								
% Passenger Vehicles	99.6	99.1	99.4	100	99.2		91.3	99.9	99.7	100	98.7		99.8	99	95.5	100	99		99.6	99.7	100	100	99.8	99.2
SU Trucks & Buses	2	12	2	0	16		14	1	1	0	16		1	14	6	0	21		2	2	0	0	4	57
% SU Trucks & Buses	0.4	0.8	0.6	0	0.7		8.1	0.1	0.3	0	1.2		0.2	0.9	3.8	0	0.9		0.4	0.3	0	0	0.2	0.7
MU Trucks	0	2	0	0	2		1	0	0	0	1		0	2	1	0	3		0	0	0	0	0	6
% MU Trucks	0	0.1	0	0	0.1		0.6	0	0	0	0.1		0	0.1	0.6	0	0.1		0	0	0	0	0	0.1




Exit 3 Airport Connector
Wolf Rd & Metro Park Rd
PM
4 to 6

Manual Turning Movement Count
Clough, Harbour & Associates LLP
111 Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com


File Name : Wolf - Metro Park PM
Site Code : 62806004
Start Date : 6/28/2006
Page No : 4





File Name : Wolf - Metro Park PM
Site Code : 62806004
Start Date : 6/28/2006
Page No : 3

	Wolf Road Southbound						Metro Park Road Westbound						Wolf Road Northbound						Hess Access Eastbound					
Start Time	Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total	Int. Total
Peak Hour Analysis From 16:00 to 17:45 - Peak 1 of 1																								
Peak Hour for Entire Intersection Begins at 16:45																								
16:45	25	220	13	0	258		34	1	59	1														
17:00	31	223	10	0	264		35	1	69	0	105		4	372	32	1	409		11	2	2	0	15	793
17:15	25	212	14	1	252		35	4	51	0	90		2	325	34	0	361		17	3	0	5	25	728
17:30	40	231	12	0	283		22	3	44	0	69		1	305	31	0	337		16	0	3	1	20	709
Total Volume	121	886	49	1	1057		126	9	223	1	359		9	1300	120	1	1430		57	6	7	7	77	2923
% App. Total	11.4	83.8	4.6	0.1			35.1	2.5	62.1	0.3			.563	.909	8.4	0.1			74	7.8	9.1	9.1		
PHF	.756	.959	.875	.250	.934		.900	.563	.808	.250	.855		.563	.874	.882	.250	.874		.838	.500	.583	.350	.770	.922
Passenger Vehicles	121	875	49	1	1046		126	9	222	1	358		9	1288	119	1	1417		57	6	7	7	77	2898
% Passenger Vehicles	100	98.8	100	100	99.0		100	100	99.6	100	99.7		100	99.1	99.2	100	99.1		100	100	100	100	100	99.1
SU Trucks & Buses	0	10	0	0	10		0	0	1	0	1		0	12	1	0	13		0	0	0	0	0	24
% SU Trucks & Buses	0	1.1	0	0	0.9		0	0	0.4	0	0.3		0	0.9	0.8	0	0.9		0	0	0	0	0	0.8
MU Trucks	0	1	0	0	1		0	0	0	0	0		0	0	0	0	0		0	0	0	0	0	1
% MU Trucks	0	0.1	0	0	0.1		0	0	0	0	0		0	0	0	0	0		0	0	0	0	0	0.0





Manual Turning Movement Count
Clough, Harbour & Associates LLP
III Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Airport Connector
Wolf Rd & Metro Park Rd
PM
4 to 6

File Name : Wolf - Metro Park PM
Site Code : 62806004
Start Date : 6/28/2006
Page No : 1

Groups Printed- Passenger Vehicles - SU Trucks & Buses - MU Trucks


Start Time	Wolf Road Southbound						Metro Park Road Westbound						Wolf Road Northbound						Hess Access Eastbound					
	Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total	Int. Total
Factor	1.0	1.0	1.0	1.0			1.0	1.0	1.0	1.0			1.0	1.0	1.0	1.0			1.0	1.0	1.0	1.0		
16:00	15	193	10	0	218		35	6	47	2	90		5	277	19	0	301		9	1	4	2	16	625
16:15	13	218	9	0	240		13	2	31	0	46		2	305	21	1	329		16	0	4	2	22	637
16:30	21	197	10	0	228		37	2	52	2	93		2	320	24	0	346		10	1	3	2	16	683
16:45	25	220	13	0	258		34	1	59	1	95		2	298	23	0	323		13	1	2	1	17	693
Total	74	828	42	0	944		119	11	189	5	324		11	1200	87	1	1299		48	3	13	7	71	2638
17:00	31	223	10	0	264		35	1	69	0	105		4	372	32	1	409		11	2	2	0	15	793
17:15	25	212	14	1	252		35	4	51	0	90		2	325	34	0	361		17	3	0	5	25	728
17:30	40	231	12	0	283		22	3	44	0	69		1	305	31	0	337		16	0	3	1	20	709
17:45	27	196	13	0	236		17	1	42	5	65		3	279	34	0	316		10	0	2	3	15	632
Total	123	862	49	1	1035		109	9	206	5	329		10	1281	131	1	1423		54	5	7	9	75	2862
Grand Total	197	1690	91	1	1979		228	20	395	10	653		21	2481	218	2	2722		102	8	20	16	146	5500
Approch %	10	85.4	4.6	0.1			34.9	3.1	60.5	1.5			0.8	91.1	8	0.1			69.9	5.5	13.7	11		
Total %	3.6	30.7	1.7	0	36		4.1	0.4	7.2	0.2	11.9		0.4	45.1	4	0	49.5		1.9	0.1	0.4	0.3	2.7	
Passenger Vehicles	100	98.8	98.9	100	98.9		100	100	99.2	100	99.5		100	99.1	99.1	100	99.1		99	100	95	100	98.6	99.1
% Passenger Vehicles																								
SU Trucks & Buses	0	20	1	0	21		0	0	3	0	3		0	21	1	0	22		1	0	1	0	2	48
% SU Trucks & Buses	0	1.2	1.1	0	1.1		0	0	0.8	0	0.5		0	0.8	0.5	0	0.8		1	0	5	0	1.4	0.9
MU Trucks	0	1	0	0	1		0	0	0	0	0		0	1	1	0	2		0	0	0	0	0	3
% MU Trucks	0	0.1	0	0	0.1		0	0	0	0	0		0	0	0.5	0	0.1		0	0	0	0	0	0.1



Exit 3 Airport Connector
Wolf & I-87 NB Off-Ramp
PM
4 to 6

Manual Turning Movement Count
Clough, Harbour & Associates LLP
111 Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

File Name : Wolf - Exit 4 NB Off-Ramp PM
Site Code : 71106002
Start Date : 7/11/2006
Page No : 4





Manual Turning Movement Count
Clough, Harbour & Associates LLP
III Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Airport Connector
Wolf & I-87 NB Off-Ramp
PM
4 to 6

File Name : Wolf - Exit 4 NB Off-Ramp PM
Site Code : 71106002
Start Date : 7/11/2006
Page No : 3


Start Time	Wolf Road Southbound					Wolf Road Northbound					I-87 NB Off-Ramp Eastbound				
	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total
Peak Hour Analysis From 16:00 to 17:45 - Peak 1 of 1															
Peak Hour for Entire Intersection Begins at 16:30															
16:30	0	191	0	1		0	0	0	0	0	0	371	0	8	379
16:45	0	260	0	0	260	0	0	0	0	0	0	449	1	2	452
17:00	0	200	0	0	200	0	0	0	0	0	0	365	0	1	366
17:15	0	218	0	1	219	0	0	0	0	0	0	1531	1	12	1544
Total Volume	0	869	0	2	871	0	0	0	0	0	0	99.2	0.1	0.8	854
% App. Total	0	99.8	0	0.2		0	0	0	0	0	0	852	250	375	854
PHF	.000	.836	.000	.500	.838	.000	.000	.000	.000	.000	.000	.000	.000	.787	.907
Passenger Vehicles	0	861	0	2	863	0	0	0	0	0	0	1524	1	12	1537
% Passenger Vehicles	0	99.1	0	100	99.1	0	0	0	0	0	0	99.5	100	100	99.5
SU Trucks & Buses	0	7	0	0	7	0	0	0	0	0	0	6	0	0	6
% SU Trucks & Buses	0	0.8	0	0	0.8	0	0	0	0	0	0	0.4	0	0	0.4
MU Trucks	0	1	0	0	1	0	0	0	0	0	0	1	0	0	1
% MU Trucks	0	0.1	0	0	0.1	0	0	0	0	0	0	0.1	0	0	0.1



Exit 3 Airport Connector
Wolf & I-87 NB Off-Ramp
PM
4 to 6

Manual Turning Movement Count
Clough, Harbour & Associates LLP
III Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

File Name : Wolf - Exit 4 NB Off-Ramp PM
Site Code : 71106002
Start Date : 7/11/2006
Page No : 2






Manual Turning Movement Count
Clough, Harbour & Associates LLP
III Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Airport Connector
Wolf & I-87 NB Off-Ramp
PM
4 to 6

File Name : Wolf - Exit 4 NB Off-Ramp PM
Site Code : 71106002
Start Date : 7/11/2006
Page No : 1

Groups Printed- Passenger Vehicles - SU Trucks & Buses - MU Trucks

Start Time	Wolf Road Southbound						Wolf Road Northbound						I-87 NB Off-Ramp Eastbound					
	Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total	
16:00	0	207	0	0	207		0	0	0	0	0		0	368	0	0	368	
16:15	0	199	0	1	200		0	0	0	0	0		0	344	0	0	344	
16:30	0	191	0	1	192		0	0	0	0	0		0	346	0	1	347	
16:45	0	260	0	0	260		0	0	0	0	0		0	371	0	8	379	
Total	0	857	0	2	859		0	0	0	0	0		0	1429	0	9	1438	
17:00	0	200	0	0	200		0	0	0	0	0		0	449	1	2	452	
17:15	0	218	0	1	219		0	0	0	0	0		0	365	0	1	366	
17:30	0	208	0	0	208		0	0	0	0	0		0	308	0	0	308	
17:45	0	212	0	2	214		0	0	0	0	0		0	318	0	0	318	
Total	0	838	0	3	841		0	0	0	0	0		0	1440	1	3	1444	
Grand Total	0	1695	0	5	1700		0	0	0	0	0		0	2869	1	12	2882	
Apprch %	0	99.7	0	0.3			0	0	0	0	0		0	99.5	0	0.4	80.2	
Total %	0	29.3	0	0.1	29.4		0	0	0	0	0		0	49.6	0	0.2	49.9	
Passenger Vehicles	0	98.9	0	100	98.9		0	0	0	0	0		0	99.3	100	100	99.3	
% Passenger Vehicles	0	17	0	0	17		0	0	0	0	0		0	14	0	0	14	
SU Trucks & Buses	0	1	0	0	1		0	0	0	0	0		0	0.5	0	0	0.5	
% SU Trucks & Buses	0	1	0	0	1		0	0	0	0	0		0	5	0	0	5	
MU Trucks	0	0.1	0	0	0.1		0	0	0	0	0		0	0.2	0	0	0.2	
% MU Trucks	0	0.1	0	0	0.1		0	0	0	0	0		0	0.2	0	0	0.2	





Manual Turning Movement Count
Clough, Harbour & Associates LLP
III Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Airport Connector
Wolf Rd & Albany Shaker
PM
4 to 6

File Name : Albany Shaker - Wolf PM
Site Code : 71106006
Start Date : 7/11/2006
Page No : 3


I-87 NB On-Ramp Southbound										Albany Shaker Road Westbound				Wolf Road Northbound				Albany Shaker Road Eastbound			
Start Time	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Int. Total
Peak Hour Analysis From 16:00 to 17:45 - Peak 1 of 1																					
Peak Hour for Entire Intersection Begins at 16:45																					
16:45	0	0	0	0	0	83	144	77	0	304	170	203	183	0	547	72	169	155	0	416	1233
17:00	0	0	0	0	0	63	146	63	0	272	176	188	175	0	456	95	143	124	0	339	1158
17:15	0	0	0	0	0	80	138	84	0	302	145	136	175	0	456	95	114	155	2	366	1124
17:30	0	0	0	0	0	84	175	67	0	326	167	134	144	4	449	84	133	130	0	347	1122
Total Volume	0	0	0	0	0	310	603	291	0	1204	658	661	642	4	1965	343	559	564	2	1468	4637
% App. Total	0	0	0	0	0	25.7	50.1	24.2	0	92.3	93.5	81.4	87.7	0.2	89.8	23.4	38.1	38.4	0.1	88.2	940
PHF	.000	.000	.000	.000	.000	.923	.861	.866	.000	.923	.935	.814	.877	.250	.898	.903	.827	.910	.250	.882	4604
Passenger Vehicles	0	0	0	0	0	309	602	291	0	1202	649	658	641	4	1952	343	552	553	2	1450	99.3
% Passenger Vehicles	0	0	0	0	0	99.7	99.8	100	0	99.8	98.6	99.5	99.8	100	99.3	100	98.7	98.0	100	98.8	99.3
SU Trucks & Buses	0	0	0	0	0	1	1	0	0	2	4	2	1	0	7	0	6	10	0	16	25
% SU Trucks & Buses	0	0	0	0	0	0.3	0.2	0	0	0.2	0.6	0.3	0.2	0	0.4	0	1.1	1.8	0	1.1	0.5
MU Trucks	0	0	0	0	0	0	0	0	0	0	5	1	0	0	6	0	1	1	0	2	8
% MU Trucks	0	0	0	0	0	0	0	0	0	0	0.8	0.2	0	0	0.3	0	0.2	0.2	0	0.1	0.2



Exit 3 Airport Connector
Wolf Rd & Albany Shaker
PM
4 to 6

Manual Turning Movement Count
Clough, Harbour & Associates LLP
111 Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

File Name : Albany Shaker - Wolf PM
Site Code : 71106006
Start Date : 7/11/2006
Page No : 2





Manual Turning Movement Count

Clough, Harbour & Associates LLP

III Winners Circle, P.O. Box 5269

Albany, NY 12205

www.cloughharbour.com

Exit 3 Airport Connector
Wolf Rd & Albany Shaker
PM

4 to 6

File Name : Albany Shaker - Wolf PM

Site Code : 71106006

Start Date : 7/11/2006

Page No : 1

Groups Printed- Passenger Vehicles - SU Trucks & Buses - MU Trucks


Start Time	I-87 NB On-Ramp Southbound						Albany Shaker Road Westbound						Wolf Road Northbound						Albany Shaker Road Eastbound					
	Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total	Int. Total
16:00	0	0	0	0	0		60	122	69	0	251		158	160	146	0	464		99	125	128	0	352	1067
16:15	0	0	0	0	0		71	157	69	0	297		180	157	131	16	484		116	121	114	0	351	1132
16:30	0	0	0	0	0		79	151	71	0	301		149	167	131	0	447		95	127	120	0	342	1090
16:45	0	0	0	0	0		83	144	77	0	304		170	203	140	0	513		92	169	155	0	416	1233
Total	0	0	0	0	0		293	574	286	0	1153		657	687	548	16	1908		402	542	517	0	1461	4522
17:00	0	0	0	0	0		63	146	63	0	272		176	188	183	0	547		72	143	124	0	339	1158
17:15	0	0	0	0	0		80	138	84	0	302		145	136	175	0	456		95	114	155	2	366	1124
17:30	0	0	0	0	0		84	175	67	0	326		167	134	144	4	449		84	133	130	0	347	1122
17:45	0	0	0	0	0		72	108	60	0	240		141	173	156	0	470		76	117	121	0	314	1024
Total	0	0	0	0	0		299	567	274	0	1140		629	631	658	4	1922		327	507	530	2	1366	4428
Grand Total	0	0	0	0	0		592	1141	560	0	2293		1286	1318	1206	20	3830		729	1049	1047	2	2827	8950
Apprch %	0	0	0	0	0		25.8	49.8	24.4	0	25.6		33.6	34.4	31.5	0.5	42.8		25.8	37.1	37	0.1	31.6	
Total %	0	0	0	0	0		6.6	12.7	6.3	0	25.6		14.4	14.7	13.5	0.2	42.8		8.1	11.7	11.7	0	31.6	
Passenger Vehicles	0	0	0	0	0		99.7	99.6	100	0	99.7		98.6	99.6	99.8	100	99.3		99.5	98.7	98.3	100	98.7	99.2
% Passenger Vehicles	0	0	0	0	0		2	3	0	0	5		9	4	1	0	14		4	10	17	0	31	50
SU Trucks & Buses	0	0	0	0	0		0.3	0.3	0	0	0.2		0.7	0.3	0.1	0	0.4		0.5	1	1.6	0	1.1	0.6
% SU Trucks & Buses	0	0	0	0	0		0	2	0	0	2		9	1	2	0	12		0	4	1	0	5	19
MU Trucks	0	0	0	0	0		0	0.2	0	0	0.1		0.7	0.1	0.2	0	0.3		0	0.4	0.1	0	0.2	0.2
% MU Trucks	0	0	0	0	0		0	0.2	0	0	0.1		0.7	0.1	0.2	0	0.3		0	0.4	0.1	0	0.2	0.2




Manual Turning Movement Count
Clough, Harbour & Associates LLP
III Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Airport Connector
Albany Shaker & Old Wolf Rd
PM
4 to 6

File Name : Albany Shaker - Old Wolf PM
Site Code : 71106004
Start Date : 7/11/2006
Page No : 4





File Name : Albany Shaker - Old Wolf PM
Site Code : 71106004
Start Date : 7/11/2006
Page No : 3


	Old Wolf Road Southbound						Albany Shaker Road Westbound						I-87 SB On-Ramp Northbound						Albany Shaker Road Eastbound					
Start Time	Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Int. Total		
Peak Hour Analysis From 16:00 to 17:45 - Peak 1 of 1																								
Peak Hour for Entire Intersection Begins at 16:30																								
16:30	134	29	85	0	248		87	185	17	0	289		0	0	0	3		48	219	160	2	429	1038	
16:45	183	18	85	1	287		87	209	25	0	321		0	0	0	1		23	201	158	0	382	1003	
17:00	165	51	113	0	329		100	177	15	0	292		0	0	0	0		64	224	164	0	452	1051	
17:15	164	27	92	0	283		94	197	25	0	316		0	0	0	0		170	864	640	3	1677	4046	
Total Volume	646	125	375	1	1147		368	768	82	0	1218		0	0	0	4		10.1	51.5	38.2	0.2			
% App. Total	56.3	10.9	32.7	0.1			30.2	63.1	6.7	0		.000	.000	.000	.333	.333		.664	.964	.976	.375	.928	.962	
PHF	.883	.613	.830	.250	.872		.920	.919	.820	.000	.949		.000	.000	.000	.333		.664	.964	.976	.375	.928	.962	
Passenger Vehicles	641	121	374	1	1137		365	762	78	0	1205		0	0	0	4		166	857	638	3	1664	4010	
% Passenger Vehicles	99.2	96.8	99.7	100	99.1		99.2	99.2	95.1	0	98.9		0	0	0	100		97.6	99.2	99.7	100	99.2	99.1	
SU Trucks & Buses	5	4	1	0	10		2	5	4	0	11		0	0	0	0		4	7	2	0	13	34	
% SU Trucks & Buses	0.8	3.2	0.3	0	0.9		0.5	0.7	4.9	0	0.9		0	0	0	0		2.4	0.8	0.3	0	0.8	0.8	
MU Trucks	0	0	0	0	0		0	1	1	0	2		0	0	0	0		0	0	0	0	0	2	
% MU Trucks	0	0	0	0	0		0.3	0.1	0	0	0.2		0	0	0	0		0	0	0	0	0	0.0	



Exit 3 Airport Connector
Albany Shaker & Old Wolf Rd
PM
4 to 6

Manual Turning Movement Count
Clough, Harbour & Associates LLP
III Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

File Name : Albany Shaker - Old Wolf PM
Site Code : 71106004
Start Date : 7/11/2006
Page No : 2






Manual Turning Movement Count
Clough, Harbour & Associates LLP
III Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Airport Connector
Albany Shaker & Old Wolf Rd
PM
4 to 6

File Name : Albany Shaker - Old Wolf PM
Site Code : 71106004
Start Date : 7/11/2006
Page No : 1

Groups Printed- Passenger Vehicles - SU Trucks & Buses - MU Trucks

Start Time	Old Wolf Road Southbound						Albany Shaker Road Westbound						I-87 SB On-Ramp Northbound						Albany Shaker Road Eastbound					
	Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total	Int. Total
16:00	148	18	85	0	251		74	191	38	0	303		0	0	0	0	0		27	202	126	0	355	909
16:15	137	38	92	0	267		90	242	27	0	359		0	0	0	4	4		28	216	157	0	401	1031
16:30	134	29	85	0	248		87	185	17	0	289		0	0	0	3	3		35	220	158	1	414	954
16:45	183	18	85	1	287		87	209	25	0	321		0	0	0	1	1		48	219	160	2	429	1038
Total	602	103	347	1	1053		338	827	107	0	1272		0	0	0	8	8		138	857	601	3	1599	3932
17:00	165	51	113	0	329		100	177	15	0	292		0	0	0	0	0		23	201	158	0	382	1003
17:15	164	27	92	0	283		94	197	25	0	316		0	0	0	0	0		64	224	164	0	452	1051
17:30	155	14	70	0	239		88	212	40	0	340		0	0	0	1	1		23	202	119	0	344	924
17:45	139	15	55	1	210		79	173	27	0	279		0	0	0	2	2		27	174	126	0	327	818
Total	623	107	330	1	1061		361	759	107	0	1227		0	0	0	3	3		137	801	567	0	1505	3796
Grand Total	1225	210	677	2	2114		699	1586	214	0	2499		0	0	0	11	11		275	1658	1168	3	3104	7728
Apprch %	57.9	9.9	32	0.1			28	63.5	8.6	0			0	0	0	100			8.9	53.4	37.6	0.1		
Total %	15.9	2.7	8.8	0	27.4		9	20.5	2.8	0	32.3		0	0	0	0.1	0.1		3.6	21.5	15.1	0	40.2	
Passenger Vehicles																								
% Passenger Vehicles	99.2	95.7	99	100	98.8		99.6	99.2	94.9	0	98.9		0	0	0	100	100		96.7	99.1	99.6	100	99.1	98.9
SU Trucks & Buses	10	9	7	0	26		2	12	11	0	25		0	0	0	0	0		9	15	5	0	29	80
% SU Trucks & Buses	0.8	4.3	1	0	1.2		0.3	0.8	5.1	0	1		0	0	0	0	0		3.3	0.9	0.4	0	0.9	1
MU Trucks	0	0	0	0	0		1	1	0	0	2		0	0	0	0	0		0	0	0	0	0	2
% MU Trucks	0	0	0	0	0		0.1	0.1	0	0	0.1		0	0	0	0	0		0	0	0	0	0	0






Manual Turning Movement Count
Clough, Harbour & Associates LLP
111 Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Airport Connector
Old Wolf Rd & I-87 SB Exit 4 Off-Ramp
PM
4 to 6

File Name : Old Wolf - Exit 4 SB PM
Site Code : 62906008
Start Date : 6/29/2006
Page No : 3

	Old Wolf Road Southbound					I-87 SB Exit 4 Off-Ramp Westbound					Old Wolf Road Northbound					Terminal Drive Eastbound					
Start Time	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Int. Total
Peak Hour Analysis From 16:00 to 17:45 - Peak 1 of 1																					
Peak Hour for Entire Intersection Begins at 16:45																					
16:45	0	96	0	0	96	180	0	4	1							1	0	1	0	2	368
17:00	0	115	0	0	115	166	1	3	0	170	0	67	0	0	67	1	0	1	0	2	354
17:15	0	91	0	0	91	174	0	7	1	182	0	93	0	0	93	0	0	2	0	2	368
17:30	0	56	0	0	56	201	0	3	0	204	0	85	0	0	85	1	0	1	0	2	347
Total Volume	0	358	0	0	358	721	1	17	2	741	0	330	0	0	330	2	0	5	1	8	1437
% App. Total	0	100	0	0		97.3	0.1	2.3	0.3		0	100	0	0		25	0	62.5	12.5		
PHF	.000	.778	.000	.000	.778	.897	.250	.607	.500	.908	.000	.887	.000	.000	.887	.500	.000	.625	.250	1.000	.976
Passenger Vehicles	0	349	0	0	349	715	1	17	2	735	0	322	0	0	322	2	0	5	1	8	1414
% Passenger Vehicles	0	97.5	0	0	97.5	99.2	100	100	100	99.2	0	97.6	0	0	97.6	100	0	100	100	100	98.4
SU Trucks & Buses	0	6	0	0	6	5	0	0	0	5	0	6	0	0	6	0	0	0	0	0	17
% SU Trucks & Buses	0	1.7	0	0	1.7	0.7	0	0	0	0.7	0	1.8	0	0	1.8	0	0	0	0	0	1.2
MU Trucks	0	3	0	0	3	1	0	0	0	1	0	2	0	0	2	0	0	0	0	0	6
% MU Trucks	0	0.8	0	0	0.8	0.1	0	0	0	0.1	0	0.6	0	0	0.6	0	0	0	0	0	0.4





Manual Turning Movement Count
Clough, Harbour & Associates LLP
111 Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Airport Connector
Old Wolf Rd & I-87 SB Exit 4 Off-Ramp
PM
4 to 6

File Name : Old Wolf - Exit 4 SB PM
Site Code : 62906008
Start Date : 6/29/2006
Page No : 1


Groups Printed: Passenger Vehicles - SU Trucks & Buses - MU Trucks																	
Old Wolf Road Southbound						Old Wolf Road Northbound						Terminal Drive Eastbound					
Start Time	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Int. Total	
16:00	0	91	0	0	91	181	0	9	0	190	0	44	0	0	44	1	326
16:15	0	71	0	0	71	158	0	6	0	164	0	63	0	0	63	1	300
16:30	0	92	0	0	92	165	0	3	0	168	0	54	0	0	54	0	315
16:45	0	96	0	0	96	180	0	4	1	185	0	85	0	0	85	0	368
Total	0	350	0	0	350	684	0	22	1	707	0	246	0	0	246	3	1309
17:00	0	115	0	0	115	166	1	3	0	170	0	67	0	0	67	1	354
17:15	0	91	0	0	91	174	0	7	1	182	0	93	0	0	93	0	368
17:30	0	56	0	0	56	201	0	3	0	204	0	85	0	0	85	1	347
17:45	0	46	0	0	46	199	0	2	0	201	0	71	0	0	71	0	319
Total	0	308	0	0	308	740	1	15	1	757	0	316	0	0	316	2	1388
Grand Total	0	658	0	0	658	1424	1	37	2	1464	0	562	0	0	562	5	2697
Approch %	0	100	0	0	100	97.3	0.1	2.5	0.1	97.3	0	100	0	0	100	38.5	23.1
Total %	0	24.4	0	0	24.4	52.8	0	1.4	0.1	54.3	0	20.8	0	0	20.8	0.2	0.1
Passenger Vehicles																	
% Passenger Vehicles	0	97.3	0	0	97.3	99.2	100	97.3	100	99.1	0	96.6	0	0	96.6	100	98.1
SU Trucks & Buses	0	11	0	0	11	10	0	1	0	11	0	15	0	0	15	0	37
% SU Trucks & Buses	0	1.7	0	0	1.7	0.7	0	2.7	0	0.8	0	2.7	0	0	2.7	0	1.4
MU Trucks	0	7	0	0	7	2	0	0	0	2	0	4	0	0	4	0	13
% MU Trucks	0	1.1	0	0	1.1	0.1	0	0	0	0.1	0	0.7	0	0	0.7	0	0.5



Manual Turning Movement Count
Clough, Harbour & Associates LLP
III Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

File Name : Albany Shaker - Alb Int Term Access PM
Site Code : 71106010
Start Date : 7/11/2006
Page No : 4

Exit 3 Airport Connector
Albany Shaker & Alb Int Terminal
PM
4 to 6



File Name : Albany Shaker - Alb Int Term Access PM

Site Code : 71106010

Start Date : 7/11/2006

Page No : 3

Exit 3 Airport Connector

Albany Shaker & Alb Int Terminal

PM

4 to 6


Albany International Airport Exit Drive Southbound					Albany Shaker Road Westbound					Albany Shaker Road Eastbound						
Start Time	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Int. Total
Peak Hour Analysis From 16:00 to 17:45 - Peak 1 of 1																
Peak Hour for Entire Intersection Begins at 16:30																
16:30	68	20			88											738
16:45	34	0	12	0	46	0	191	0	0	191	0	0	0	0	0	611
17:00	52	0	19	0	71	1	217	0	0	218	0	0	0	0	0	668
17:15	54	0	6	0	60	0	193	0	0	193	0	0	0	0	0	613
Total Volume	208	0	57	0	265	1	787	0	0	788	0	0	0	0	0	2630
% App. Total	78.5	0	21.5	0		0.1	99.9	0	0		0	0	0	0	0	
PHF	.765	.000	.713	.000	.753	.250	.907	.000	.000	.904	.000	.000	.000	.000	.850	.891
Passenger Vehicles	208	0	57	0	265	1	783	0	0	784	0	0	0	0	0	2616
% Passenger Vehicles	100	0	100	0	100	100	99.5	0	0	99.5	0	0	0	0	0	99.5
SU Trucks & Buses	0	0	0	0	0	0	1	0	0	1	0	0	0	0	0	9
% SU Trucks & Buses	0	0	0	0	0	0	0.1	0	0	0.1	0	0	0	0	0	0.3
MU Trucks	0	0	0	0	0	0	3	0	0	3	0	0	0	0	0	5
% MU Trucks	0	0	0	0	0	0	0.4	0	0	0.4	0	0	0	0	0	0.2



Manual Turning Movement Count
Clough, Harbour & Associates LLP
111 Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Airport Connector
Albany Shaker & Alb Int Terminal
PM
4 to 6

File Name : Albany Shaker - Alb Int Term Access PM
Site Code : 71106010
Start Date : 7/11/2006
Page No : 2






Manual Turning Movement Count
Clough, Harbour & Associates LLP
III Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Airport Connector
Albany Shaker & Alb Int Terminal
PM
4 to 6

File Name : Albany Shaker - Alb Int Term Access PM
Site Code : 71106010
Start Date : 7/11/2006
Page No : 1

Groups Printed- Passenger Vehicles - SU Trucks & Buses - MU Trucks

Start Time	Albany International Airport Exit Drive Southbound						Albany Shaker Road Westbound						Albany Shaker Road Eastbound					
	Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total	
16:00	48	0	8	0	56		0	178	1	0	179		0	0	0	0	0	
16:15	55	0	15	0	70		1	203	0	0	204		0	0	0	0	0	
16:30	68	0	20	0	88		0	186	0	0	186		0	0	0	0	0	
16:45	34	0	12	0	46		0	191	0	0	191		0	0	0	0	0	
Total	205	0	55	0	260		1	758	1	0	760		0	0	0	0	0	
17:00	52	0	19	0	71		1	217	0	0	218		0	0	0	0	0	
17:15	54	0	6	0	60		0	193	0	0	193		0	0	0	0	0	
17:30	41	0	13	0	54		0	176	0	0	176		0	0	0	0	0	
17:45	48	0	15	0	63		0	143	0	0	143		0	0	0	0	0	
Total	195	0	53	0	248		1	729	0	0	730		0	0	0	0	0	
Grand Total	400	0	108	0	508		2	1487	1	0	1490		0	0	0	0	0	
Approch %	78.7	0	21.3	0			0.1	99.8	0.1	0			0	0	0	0		
Total %	8.3	0	2.2	0	10.5		0	30.8	0	0	30.9		0	0	0	0		
Passenger Vehicles	99.5	0	99.1	0	99.4		100	99.3	100	0	99.3		0	0	0	0		
% Passenger Vehicles																		
SU Trucks & Buses	2	0	1	0	3		0	5	0	0	5		0	0	0	0		
% SU Trucks & Buses	0.5	0	0.9	0	0.6		0	0.3	0	0	0.3		0	0	0	0		
MU Trucks	0	0	0	0	0		0	6	0	0	6		0	0	0	0		
% MU Trucks	0	0	0	0	0		0	0.4	0	0	0.4		0	0	0	0		



Manual Turning Movement Count

Clough, Harbour & Associates LLP
 111 Winners Circle, P.O. Box 5269
 Albany, NY 12205
 www.cloughharbour.com

File Name : Albany Shaker - Watervliet Shaker PM
 Site Code : 62806002
 Start Date : 6/28/2006
 Page No : 3



Exit 3 Airport Connector
 Albany Shaker & Watervliet Shaker
 PM
 4 to 6


Start Time	Albany Shaker Road Southbound						Albany International Airport Drive Westbound						Albany Shaker Road Northbound						Watervliet Shaker Road Eastbound					
	Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total		Left	Thru	Right	Peds	App. Total	Int. Total
	16:00 to 17:45 - Peak 1 of 1																							
Peak Hour Analysis From 16:00 to 17:45 - Peak 1 of 1	54	72	32	0	100		89	111	2	0	202		61	2	78	0	139		61	2	78	0	139	670
Peak Hour for Entire Intersection Begins at 16:30	72	72	26	0	85		70	118	5	0	193		56	0	109	0	166		56	0	109	0	166	721
16:30	16	165	57	0	229		102	123	1	0	226		60	0	93	0	153		60	0	93	0	153	712
16:45	17	168	44	0	277		361	449	11	0	821		221	0	370	0	594		221	0	370	0	594	2770
17:00	11	200	66	0	243		44	54.7	1.3	0	908		37.2	0.5	62.3	0.00	895		37.2	0.5	62.3	0.00	895	2757
17:15	10	190	43	0	987		239	17	112	0	368		906	3	367	0	99.5		906	3	367	0	99.5	11
17:30	54	723	21.3	0	891		64.9	4.6	30.4	0	920		221	100	99.2	0	0.5		221	100	99.2	0	0.5	2
17:45	5.5	73.3	21.3	0	985		830	607	875	0	367		99.1	0	0.8	0	0		99.1	0	0.8	0	0	0.1
Total Volume	794	904	795	0	99.8		99.7	99.2	4	0	0		0	0	0	0	0		0	0	0	0	0	0
% App. Total	54	721	210	0	99.8		1	0.6	0.9	0	0		1	0	0	0	0		1	0	0	0	0	0
PHF	54	99.7	100	0	0		0	0.3	0	0	0		0	0.3	0	0	0		0	0	0	0	0	0
Passenger Vehicles	100	1	0	0	0		0	0	0	0	0		0	0	0	0	0		0	0	0	0	0	0
% Passenger Vehicles	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0		0	0	0	0	0	0
SU Trucks & Buses	0	0.1	0	0	0		0	0	0	0	0		0	0	0	0	0		0	0	0	0	0	0
% SU Trucks & Buses	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0		0	0	0	0	0	0
MU Trucks	0	0.1	0	0	0		0	0	0	0	0		0	0	0	0	0		0	0	0	0	0	0
% MU Trucks	0	0	0	0	0		0	0	0	0	0		0	0	0	0	0		0	0	0	0	0	0



Manual Turning Movement Count
Clough, Harbour & Associates LLP
III Winners Circle, P.O. Box 5269
Albany, NY 12205
www.cloughharbour.com

Exit 3 Airport Connector
Albany Shaker & Watervliet Shaker
PM
4 to 6

File Name : Albany Shaker - Watervliet Shaker PM
Site Code : 62806002
Start Date : 6/28/2006
Page No : 2





Manual Turning Movement Count

Clough, Harbour & Associates LLP

III Winners Circle, P.O. Box 5269

Albany, NY 12205

Albany, NY 12203
www.cloughharbour.com

Exit 3 Airport Connector
Albany Shaker & Watervliet Shaker
PM

File Name : Albany Shaker - Watervliet Shaker PM

Site Code : 62806002

Start Date : 6/28/2006

Page No : 1

4 to 6

Groups Printed- Passenger Vehicles - SU Trucks & Buses - MU Trucks																							
Albany Shaker Road Southbound						Albany International Airport Drive Westbound						Albany Shaker Road Northbound						Watervliet Shaker Road Eastbound					
Start Time	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Int. Total		
Factor	1.0	1.0	1.0	1.0		1.0	1.0	1.0	1.0		1.0	1.0	1.0	1.0		1.0	1.0	1.0	1.0				
16:00	18	140	42	0	200	85	6	41	0	132	62	87	2	0	151	39	1	86	0	126	609		
16:15	25	138	53	0	216	50	6	25	0	81	83	87	1	0	171	29	0	94	0	123	591		
16:30	16	165	57	0	238	54	7	32	0	93	100	97	3	0	200	44	2	90	0	136	667		
16:45	17	168	44	0	229	72	2	26	0	100	89	111	2	0	202	61	0	78	0	139	670		
Total	76	611	196	0	883	261	21	124	0	406	334	382	8	0	724	173	3	348	0	524	2537		
17:00	11	200	66	0	277	56	3	26	0	85	70	118	5	0	193	56	1	109	0	166	721		
17:15	10	190	43	0	243	57	5	28	0	90	102	123	1	0	226	60	0	93	0	153	712		
17:30	13	140	44	0	197	63	5	24	0	92	96	96	0	0	192	49	1	83	0	133	614		
17:45	10	100	50	0	160	51	4	22	0	77	85	96	4	0	185	32	0	87	0	119	541		
Total	44	630	203	0	877	227	17	100	0	344	353	433	10	0	796	197	2	372	0	571	2588		
Grand Total	120	1241	399	0	1760	488	38	224	0	750	687	815	18	0	1520	370	5	720	0	1095	5125		
Approach %	6.8	70.5	22.7	0		65.1	5.1	29.9	0		45.2	53.6	1.2	0		33.8	0.5	65.8	0				
Total %	2.3	24.2	7.8	0	34.3	9.5	0.7	4.4	0	14.6	13.4	15.9	0.4	0	29.7	7.2	0.1	14	0	21.4			
Passenger Vehicles	100	99.4	99.2	0	99.4	99.2	100	100	0	99.5	98.3	99.3	100	0	98.8	99.2	100	99.3	0	99.3	99.2		
% Passenger Vehicles																							
SU Trucks & Buses	0	5	1	0	6	4	0	0	0	4	5	4	0	0	9	1	0	5	0	6	25		
% SU Trucks & Buses	0	0.4	0.3	0	0.3	0.8	0	0	0	0.5	0.7	0.5	0	0	0.6	0.3	0	0.7	0	0.5	0.5		
MU Trucks	0	2	2	0	4		0	0	0	0	7	2	0	0	9	2	0	0	0	2	15		
% MU Trucks	0	0.2	0.5	0	0.2	0	0	0	0	0	1	0.2	0	0	0.6	0.5	0	0	0	0.2	0.3		

ATTACHMENT C
MICROSIMULATION CALIBRATION GUIDELINES

Calibration Criteria

Criteria and Measures	Calibration Acceptance Targets
Hourly Flows, Model Versus Observed	
Individual Link Flows	
Within 15%, for 700 veh/h < Flow < 2700 veh/h	>85% of cases
Within 100 veh/h, for Flow < 700 veh/h	>85% of cases
Within 400 veh/h, for Flow > 2700 veh/h	>85% of cases
Sum of All Link Flows	Within 5% of sum of all link counts
GEH Statistic < 5 for Individual Link Flows	>85% of cases
GEH Statistic for Sum of All Link Flows	GEH < 4 for sum of all link counts
Travel Times, Model Versus Observed	
Journey Times, Network	
Within 15% (or 1 min, if higher)	>85% of cases
Visual Audits	
Individual Link Speeds	
Visually Acceptable Speed-Flow Relationship	To analyst's satisfaction
Bottlenecks	
Visually Acceptable Queuing	To analyst's satisfaction

Source: Traffic Analysis Toolbox Volume III: Guidelines for Applying Traffic Microsimulation Modeling Software, Publication No. FHWA-HRT-04-040, Federal Highway Administration, July 2004.

ATTACHMENT D
LEVEL OF SERVICE CRITERIA

From the Highway Capacity Manual 2000 published by the Transportation Research Board:

Signalized Intersections

TABLE A	
HCS SIGNALIZED LOS STANDARDS	
LOS	Control Delay per Vehicle (s/veh)
A	10 or less
B	10 – 20
C	20 - 35
D	35 – 55
E	55 - 80
F	greater than 80

* s/veh = seconds per vehicle

LOS A describes operations with low control delay, up to 10 s/veh. This LOS occurs when progression is extremely favorable and most vehicles arrive during the green phase. Most vehicles do not stop at all. Short cycle lengths may tend to contribute to low delay values.

LOS B describes operations with control delay greater than 10 and up to 20 s/veh. This level generally occurs with good progression, short cycle lengths, or both. More vehicles stop than with LOS A, causing higher levels of delay.

LOS C describes operations with control delay greater than 20 and up to 35 s/veh. These higher delays may result from only fair progression, longer cycle lengths, or both. Individual cycle failures may begin to appear at this level. Cycle failure occurs when a green phase does not serve queued vehicles, and overflows occur. The number of vehicles stopping is significant at this level, though many still pass through the intersection without stopping.

LOS D describes operations with control delay greater than 35 and up to 55 s/veh. At LOS D, the influence of congestion becomes more noticeable. Longer delays may result from some combination of unfavorable progression, long cycle lengths, or high volume-to-capacity (v/c) ratios. Many vehicles stop, and the proportion of vehicles not stopping declines. Individual cycle failures are noticeable.

LOS E describes operations with control delay greater than 55 and up to 80 s/veh. These high delay values generally indicate poor progression, long cycle lengths, and high v/c ratios. Individual cycle failures are frequent.

LOS F describes operations with delay in excess of 80.0 s/veh. This level, considered unacceptable to most drivers, often occurs with over-saturation, that is, when arrival flow rates exceed the capacity of lane groups. It may also occur at high v/c ratios with many individual cycle failures. Poor progression and long cycle lengths may also contribute significantly to high delay levels. Often, vehicles do not pass through the intersection in one signal cycle.

Unsignalized Intersection Delay

The level of service criteria for an unsignalized intersection differs from that of a signalized intersection because of the expectation that signalized intersections encounter more traffic and therefore greater delays. The thresholds for the levels of service of unsignalized intersections are as follows:

TABLE B HCS UNSIGNALIZED LOS STANDARDS	
LOS	Control Delay per Vehicle (s/veh)
A	10 or less
B	10 – 15
C	15 - 25
D	25 – 35
E	35 - 50
F	greater than 50

* s/veh = seconds per vehicle

Levels-of-service A, B, and C are considered acceptable, LOS D is generally considered marginally acceptable during peak periods and LOS E and F are considered unacceptable.

Freeways

A basic freeway segment can be characterized by three performance measures: density in terms of passenger cars per mile per lane, speed in terms of mean passenger-car speed and volume-to capacity (v/c) ratio. The measure used to provide an estimate of the LOS is density and are as follows:

TABLE C HCS FREEWAY LOS STANDARDS	
LOS	Density (pc/mi/ln)
A	0 – 11
B	11 – 18
C	18 – 26
D	26 – 35
E	35 - 45
F	> 45

Ramps and Ramp Junctions

TABLE D HCS MERGE AND DIVERGE AREA LOS STANDARDS	
LOS	Density (pc/mi/ln)
A	10 or less
B	10 – 20
C	20 - 28
D	28 – 35
E	Greater than 35
F	Demand exceeds capacity

LOS in merge (and diverge) influence areas is determined by density for all cases of stable operation, represented by LOS A through E. LOS F exists when the total flow departing from the merge area exceeds the capacity of the downstream freeway segment.

LOS A represents unrestricted operations. Density is low enough to permit smooth merging and diverging, with virtually no turbulence in the traffic stream.

LOS B, merging and diverging maneuvers become noticeable to through drivers, and minimal turbulence occurs. Merging drivers must adjust speeds to accomplish smooth transitions from the acceleration lane to the freeway.

LOS C, speed within the influence area begins to decline as turbulence levels become noticeable. Both ramp and freeway vehicles begin to adjust their speeds to accomplish smooth transitions.

LOS D, turbulence levels in the influence area become intrusive, and virtually all vehicles slow to accommodate merging and diverging. Some ramp queues may form at heavily used on-ramps, but freeway operations remains stable.

LOS E represents conditions approaching capacity.

Weaving Segments


A single LOS is used to characterize total flow in the weaving segment, although it is recognized that in some situations (particularly in cases of constrained operations) nonweaving vehicles may achieve higher-quality operations than weaving vehicles.

TABLE E HCS WEAVE LOS STANDARDS	
LOS	Density (pc/mi/ln)
A	10 or less
B	10 – 20
C	20 - 28
D	28 – 35
E	35 – 43
F	Greater than 43

ATTACHMENT E
LEVEL OF SERVICE WORKSHEETS

EXISTING

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst **SEB**
 Agency or Company **CHA**
 Date Performed **9/08/2011**
 Analysis Time Period **AM**

Site Information

Highway/Direction of Travel **Northbound I-87**
 From/To **Exit 2 to Exit 4**
 Jurisdiction **NYSDOT**
 Analysis Year **2009 - Existing**

Project Description **Exit 4**

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V **3000** veh/h
 AADT **veh/day**
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D **veh/h**
 Driver type adjustment **1.00**
 Peak-Hour Factor, PHF **0.92**
 %Trucks and Buses, P_T **2**
 %RVs, P_R **0**
 General Terrain: **Level**
 Grade % Length **mi**
 Up/Down %

Calculate Flow Adjustments

f_p **1.00**
 E_T **1.5**
 E_R **1.2**
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ **0.990**

Speed Inputs

Lane Width **12.0** ft
 Rt-Shoulder Lat. Clearance **6.0** ft
 Interchange Density **0.50** l/mi
 Number of Lanes, N **3**
 FFS (measured) **56.0** mi/h
 Base free-flow Speed, BFFS **mi/h**

Calc Speed Adj and FFS

f_{LW} **mi/h**
 f_{LC} **mi/h**
 f_{ID} **mi/h**
 f_N **mi/h**
 FFS **56.0** **mi/h**

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ **1098** pc/h/ln
 S **56.0** mi/h
 $D = v_p / S$ **19.6** pc/mi/ln
 LOS **C**

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ **pc/h**
 S **mi/h**
 $D = v_p / S$ **pc/mi/ln**
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 to Exit 2*
 Jurisdiction *NYS DOT*
 Analysis Year *2009 - Existing*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5150* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.92*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1 + P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1885* pc/h/ln
 S *55.7* mi/h
 $D = v_p / S$ *33.8* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst: SEB
 Agency or Company: CHA
 Date Performed: 9/08/2011
 Analysis Time Period: AM

Site Information

Highway/Direction of Travel: Northbound I-87
 From/To: Exit 4 off to Exit 4 on
 Jurisdiction: NYSDOT
 Analysis Year: 2009 - Existing

Project Description: Exit 4

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V	2200	veh/h	Peak-Hour Factor, PHF	0.92
AADT		veh/day	%Trucks and Buses, P_T	2
Peak-Hr Prop. of AADT, K			%RVs, P_R	0
Peak-Hr Direction Prop, D			General Terrain:	Level
DDHV = AADT x K x D		veh/h	Grade %	mi
Driver type adjustment	1.00		Up/Down %	

Calculate Flow Adjustments

f_p	1.00	E_R	1.2
E_T	1.5	$f_{HV} = 1/[1+P_T(E_T-1) + P_R(E_R-1)]$	0.990

Speed Inputs

Lane Width	12.0	ft
Rt-Shoulder Lat. Clearance	6.0	ft
Interchange Density	0.50	l/mi
Number of Lanes, N	3	
FFS (measured)	56.0	mi/h
Base free-flow Speed, BFFS		mi/h

Calc Speed Adj and FFS

f_{LW}	mi/h
f_{LC}	mi/h
f_{ID}	mi/h
f_N	mi/h
FFS	56.0 mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$	805	pc/h/ln
S	56.0	mi/h
$D = v_p / S$	14.4	pc/mi/ln
LOS	B	

Design (N)

Design (N)

Design LOS	
$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$	pc/h
f_p	
S	mi/h
$D = v_p / S$	pc/mi/ln
Required Number of Lanes, N	


Glossary

N - Number of lanes	S - Speed
V - Hourly volume	D - Density
v_p - Flow rate	FFS - Free-flow speed
LOS - Level of service	BFFS - Base free-flow speed
DDHV - Directional design hour volume	

Factor Location

E_R - Exhibits 23-8, 23-10	f_{LW} - Exhibit 23-4
E_T - Exhibits 23-8, 23-10, 23-11	f_{LC} - Exhibit 23-5
f_p - Page 23-12	f_N - Exhibit 23-6
LOS, S, FFS, v_p - Exhibits 23-2, 23-3	f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst **SEB**
 Agency or Company **CHA**
 Date Performed **12/08/2011**
 Analysis Time Period **AM**

Site Information

Highway/Direction of Travel **Southbound I-87**
 From/To **Exit 5 on to Exit 4 on**
 Jurisdiction **NYSDOT**
 Analysis Year **2009 - Existing**

Project Description **Exit 4**

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V	4600	veh/h	Peak-Hour Factor, PHF	0.92
AADT		veh/day	%Trucks and Buses, P_T	2
Peak-Hr Prop. of AADT, K			%RVs, P_R	0
Peak-Hr Direction Prop, D			General Terrain:	Level
DDHV = AADT x K x D		veh/h	Grade %	Length mi
Driver type adjustment	1.00		Up/Down %	

Calculate Flow Adjustments

f_p	1.00	E_R	1.2
E_T	1.5	$f_{HV} = 1/[1 + P_T(E_T - 1) + P_R(E_R - 1)]$	0.990

Speed Inputs

Lane Width	12.0	ft
Rt-Shoulder Lat. Clearance	6.0	ft
Interchange Density	0.50	l/mi
Number of Lanes, N	3	
FFS (measured)	56.0	mi/h
Base free-flow Speed, BFFS		mi/h

Calc Speed Adj and FFS

f_{LW}	mi/h
f_{LC}	mi/h
f_{ID}	mi/h
f_N	mi/h
FFS	56.0 mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$	1683	pc/h/ln
S	56.0	mi/h
$D = v_p / S$	30.1	pc/mi/ln
LOS	D	

Design (N)

Design (N)

Design LOS	
$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$	pc/h
S	mi/h
$D = v_p / S$	pc/mi/ln
Required Number of Lanes, N	


Glossary

N - Number of lanes	S - Speed
V - Hourly volume	D - Density
v_p - Flow rate	FFS - Free-flow speed
LOS - Level of service	BFFS - Base free-flow speed
DDHV - Directional design hour volume	

Factor Location

E_R - Exhibits 23-8, 23-10	f_{LW} - Exhibit 23-4
E_T - Exhibits 23-8, 23-10, 23-11	f_{LC} - Exhibit 23-5
f_p - Page 23-12	f_N - Exhibit 23-6
LOS, S, FFS, v_p - Exhibits 23-2, 23-3	f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst **SEB**
 Agency or Company **CHA**
 Date Performed **9/08/2011**
 Analysis Time Period **AM**

Site Information

Highway/Direction of Travel **Northbound I-87**
 From/To **Exit 4 to Exit 5**
 Jurisdiction **NYS DOT**
 Analysis Year **2009 - Existing**

Project Description **Exit 4**

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V **2700** veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D
 Driver type adjustment **1.00** veh/h
 Peak-Hour Factor, PHF **0.92**
 %Trucks and Buses, P_T **2**
 %RVs, P_R **0**
 General Terrain: **Level**
 Grade % Length **mi**
 Up/Down %

Calculate Flow Adjustments

f_p **1.00**
 E_T **1.5**
 E_R **1.2**
 $f_{HV} = 1/[1 + P_T(E_T - 1) + P_R(E_R - 1)]$ **0.990**

Speed Inputs

Lane Width **12.0** ft
 Rt-Shoulder Lat. Clearance **6.0** ft
 Interchange Density **0.50** l/mi
 Number of Lanes, N **3**
 FFS (measured) **56.0** mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS **56.0** mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ **988** pc/h/ln
 S **56.0** mi/h
 $D = v_p / S$ **17.6** pc/mi/ln
 LOS **B**

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *9/08/2011*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 5 to Exit 4*
 Jurisdiction *NYS DOT*
 Analysis Year *2009 - Existing*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *4400* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D
 Driver type adjustment *1.00*

Peak-Hour Factor, PHF *0.92*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1 + P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1610* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *28.8* pc/mi/ln
 LOS *D*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume


S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3

f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst: SEB
 Agency or Company: CHA
 Date Performed: 9/08/2011
 Analysis Time Period: AM

Site Information

Highway/Direction of Travel: Northbound I-87
 From/To: Exit 5 to Exit 6
 Jurisdiction: NYSDOT
 Analysis Year: 2009 - Existing

Project Description: Exit 4

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V: 2500 veh/h
 AADT: veh/day
 Peak-Hr Prop. of AADT, K: 0.92
 Peak-Hr Direction Prop, D: 2
 DDHV = AADT x K x D: veh/h
 Driver type adjustment: 1.00
 Peak-Hour Factor, PHF: 0.92
 %Trucks and Buses, P_T : 2
 %RVs, P_R : 0
 General Terrain: Level
 Grade % Length: mi
 Up/Down %

Calculate Flow Adjustments

f_p : 1.00
 E_T : 1.5
 E_R : 1.2
 $f_{HV} = 1/[1 + P_T(E_T - 1) + P_R(E_R - 1)]$: 0.990

Speed Inputs

Lane Width: 12.0 ft
 Rt-Shoulder Lat. Clearance: 6.0 ft
 Interchange Density: 0.50 l/mi
 Number of Lanes, N: 4
 FFS (measured): 56.0 mi/h
 Base free-flow Speed, BFFS: mi/h

Calc Speed Adj and FFS

f_{LW} : mi/h
 f_{LC} : mi/h
 f_{ID} : mi/h
 f_N : mi/h
 FFS: 56.0 mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$: 686 pc/h/ln
 S: 56.0 mi/h
 D = v_p / S : 12.3 pc/mi/ln
 LOS: B

Design (N)

Design (N)

Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$: pc/h
 f_p : mi/h
 S: mi/h
 D = v_p / S : pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *9/08/2011*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 6 to Exit 5*
 Jurisdiction *NYS DOT*
 Analysis Year *2009 - Existing*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *6100* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *4*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1674* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *29.9* pc/mi/ln
 LOS *D*

Design (N)

Design (N)

Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 $S = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 2W On-Ramp			
Date Performed		9/08/2011		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2009 Existing			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1100$ ft $V_u = 690$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2650	0.92	Level	2	0	0.990	1.00	2909	
Ramp	340	0.92	Level	2	0	0.990	1.00	373	
UpStream	690	0.92	Level	2	0	0.990	1.00	757	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 769.55$ (Equation 25-2 or 25-3) $P_{FM} = 0.601$ using Equation (Exhibit 25-5) $V_{12} = 1749$ pc/h V_3 or $V_{av34} = 1160$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	3282	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	2122	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 16.5$ (pc/mi/ln) LOS = B (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.286$ (Exhibit 25-19) $S_R = 52.0$ mph (Exhibit 25-19) $S_0 = 53.6$ mph (Exhibit 25-19) $S = 52.6$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

Generated: 12/16/2011 8:32 AM

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 4 NB On-Ramp			
Date Performed		9/08/2011		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2009 Existing			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{down} =$ 3500 ft $V_D =$ 440 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2200	0.92	Level	2	0	0.990	1.00	2415	
Ramp	550	0.92	Level	2	0	0.990	1.00	604	
UpStream									
DownStream	440	0.96	Level	2	0	0.990	1.00	463	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 2248.66$ (Equation 25-2 or 25-3) $P_{FM} = 0.603$ using Equation (Exhibit 25-5) $V_{12} = 1456$ pc/h V_3 or $V_{av34} = 959$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	3019	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	2060	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 15.6$ (pc/mi/ln) LOS = B (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.280$ (Exhibit 25-19) $S_R = 52.1$ mph (Exhibit 25-19) $S_0 = 54.3$ mph (Exhibit 25-19) $S = 52.8$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 5 NB Off			
Date Performed		9/08/2011		Jurisdiction		NYS DOT			
Analysis Time Period		AM		Analysis Year		2009 Existing			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ 3500 ft $V_u =$ 550 veh/h			Terrain: Level $S_{FF} =$ 56.0 mph $S_{FR} =$ 35.0 mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2700	0.92	Level	2	0	0.990	1.00	2964	
Ramp	440	0.96	Level	2	0	0.990	1.00	463	
UpStream	550	0.92	Level	2	0	0.990	1.00	604	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ using Equation (Exhibit 25-5) $P_{FM} =$ pc/h $V_{12} =$ pc/h (Equation 25-4 or 25-5) V_3 or V_{av34} pc/h Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ 5808.59 (Equation 25-8 or 25-9) $P_{FD} =$ 0.706 using Equation (Exhibit 25-12) $V_{12} =$ 2228 pc/h V_3 or V_{av34} 736 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	2964	Exhibit 25-14	6780	No
					$V_{FO} = V_F - V_R$	2501	Exhibit 25-14	6780	No
					V_R	463	Exhibit 25-3	2000	No
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	2228	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 21.2 (pc/mi/ln) $LOS =$ C (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.470 (Exhibit 25-19) $S_R =$ 49.4 mph (Exhibit 25-19) $S_0 =$ 61.4 mph (Exhibit 25-19) $S =$ 51.9 mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB			Freeway/Dir of Travel		Southbound		
Agency or Company		CHA			Junction		Exit 2W Off		
Date Performed		9/08/2011			Jurisdiction		NYS DOT		
Analysis Time Period		AM			Analysis Year		2009 Existing		
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h		Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)					Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1300 ft $V_D =$ 310 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	5150	0.92	Level	2	0	0.990	1.00	5654	
Ramp	890	0.92	Level	2	0	0.990	1.00	977	
UpStream									
DownStream	310	0.92	Level	2	0	0.990	1.00	340	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.574 using Equation (Exhibit 25-12) $V_{12} =$ 3660 pc/h V_3 or V_{av34} 1994 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	5654	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	4677	Exhibit 25-14	6780	No	
				V_R	977	Exhibit 25-3	2100	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	3660	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 33.0 (pc/mi/ln) $LOS =$ D (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.451 (Exhibit 25-19) $S_R =$ 49.7 mph (Exhibit 25-19) $S_0 =$ 57.6 mph (Exhibit 25-19) $S =$ 52.2 mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 4 SB Off			
Date Performed		9/08/2011		Jurisdiction		NYS DOT			
Analysis Time Period		AM		Analysis Year		2009 Existing			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 3100 ft $V_D =$ 490 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	5500	0.92	Level	2	0	0.990	1.00	6038	
Ramp	1070	0.92	Level	2	0	0.990	1.00	1175	
UpStream									
DownStream	490	0.93	Level	3	0	0.985	1.00	535	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.555 using Equation (Exhibit 25-12) $V_{12} =$ 3874 pc/h V_3 or V_{av34} 2164 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	6038	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	4863	Exhibit 25-14	6780	No	
				V_R	1175	Exhibit 25-3	2100	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	3874	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 33.3 (pc/mi/ln) $LOS =$ D (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.469 (Exhibit 25-19) $S_R =$ 49.4 mph (Exhibit 25-19) $S_0 =$ 56.9 mph (Exhibit 25-19) $S =$ 51.9 mph (Exhibit 25-15)				


RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 4 SB On-Ramp			
Date Performed		9/08/2011		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2009 Existing			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{up} = 2035$ ft $V_u = 490$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4600	0.92	Level	2	0	0.990	1.00	5050	
Ramp	540	0.93	Level	5	0	0.976	1.00	595	
UpStream	490	0.93	Level	3	0	0.985	1.00	535	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} = 0.603$ using Equation (Exhibit 25-5) $V_{12} = 3044$ pc/h V_3 or $V_{av34} = 2006$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	5645	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	3639	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 27.9$ (pc/mi/ln) LOS = C (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.397$ (Exhibit 25-19) $S_R = 50.4$ mph (Exhibit 25-19) $S_0 = 50.6$ mph (Exhibit 25-19) $S = 50.5$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 5 SB On-Ramp			
Date Performed		9/08/2011		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2009 Existing			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 2035 ft $V_D =$ 540 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4400	0.92	Level	2	0	0.990	1.00	4830	
Ramp	490	0.93	Level	3	0	0.985	1.00	535	
UpStream									
DownStream	540	0.93	Level	5	0	0.976	1.00	595	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} = 0.603$ using Equation (Exhibit 25-5) $V_{12} = 2911$ pc/h V_3 or $V_{av34} = 1919$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	5365	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	3446	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 26.5$ (pc/mi/ln) LOS = C (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.371$ (Exhibit 25-19) $S_R = 50.8$ mph (Exhibit 25-19) $S_0 = 50.9$ mph (Exhibit 25-19) $S = 50.8$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 9/08/2011 Analysis Time Period AM					Freeway/Dir of Travel I-87 Northbound Weaving Seg Location Exit 2E on to 2W off Jurisdiction NYSDOT Analysis Year 2009 Existing				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 815 Terrain Level					Weaving type A Volume ratio, VR 0.31 Weaving ratio, R 0.32				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	2320	0.92	2	0	1.5	1.2	0.990	1.00	2546
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	690	0.92	2	0	1.5	1.2	0.990	1.00	757
V_{w2}	330	0.92	2	0	1.5	1.2	0.990	1.00	362
V_w				1119	V_{nw}				2546
V									3665
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (i = nw)		
a (Exhibit 24-6)					0.35		0.0020		
b (Exhibit 24-6)					2.20		4.00		
c (Exhibit 24-6)					0.97		1.30		
d (Exhibit 24-6)					0.80		0.75		
Weaving intensity factor, W_i					2.20		0.27		
Weaving and non-weaving speeds, S_i (mi/h)					29.36		51.22		
Number of lanes required for unconstrained operation, N_w					1.46				
Maximum number of lanes, N_w (max)					1.40				
<input type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input checked="" type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					41.74				
Weaving segment density, D (pc/mi/ln)					21.95				
Level of service, LOS					C				
Capacity of base condition, c_b (pc/h)					6158				
Capacity as a 15-minute flow rate, c (veh/h)					6097				
Capacity as a full-hour volume, c_h (veh/h)					5609				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 9/08/2011 Analysis Time Period AM					Freeway/Dir of Travel I-87 Southbound Weaving Seg Location Exit 2W on to 2E off Jurisdiction NYSDOT Analysis Year 2009 Existing				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 810 Terrain Level					Weaving type A Volume ratio, VR 0.19 Weaving ratio, R 0.35				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	3680	0.92	2	0	1.5	1.2	0.990	1.00	4039
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	570	0.92	2	0	1.5	1.2	0.990	1.00	625
V_{w2}	310	0.92	2	0	1.5	1.2	0.990	1.00	340
V_w				965	V_{nw}				4039
V									5004
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (i = nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	1.05		0.50						
Weaving and non-weaving speeds, S_i (mi/h)	37.41		45.75						
Number of lanes required for unconstrained operation, N_w					1.13				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					43.86				
Weaving segment density, D (pc/mi/ln)					28.52				
Level of service, LOS					D				
Capacity of base condition, c_b (pc/h)					6776				
Capacity as a 15-minute flow rate, c (veh/h)					6709				
Capacity as a full-hour volume, c_h (veh/h)					6172				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *9/08/2011*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 2 to Exit 4*
 Jurisdiction *NYS DOT*
 Analysis Year *2009 - Existing*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V	5100	veh/h	Peak-Hour Factor, PHF	0.86
AADT		veh/day	% Trucks and Buses, P_T	2
Peak-Hr Prop. of AADT, K			% RVs, P_R	0
Peak-Hr Direction Prop, D			General Terrain:	Level
DDHV = AADT x K x D		veh/h	Grade %	Length mi
Driver type adjustment	1.00		Up/Down %	

Calculate Flow Adjustments

f_p	1.00	E_R	1.2
E_T	1.5	$f_{HV} = 1/[1 + P_T(E_T - 1) + P_R(E_R - 1)]$	0.990

Speed Inputs

Lane Width	12.0	ft
Rt-Shoulder Lat. Clearance	6.0	ft
Interchange Density	0.50	l/mi
Number of Lanes, N	3	
FFS (measured)	56.0	mi/h
Base free-flow Speed, BFFS		mi/h

Calc Speed Adj and FFS

f_{LW}		mi/h
f_{LC}		mi/h
f_{ID}		mi/h
f_N		mi/h
FFS	56.0	mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$	1997	pc/h/ln
S	55.0	mi/h
$D = v_p / S$	36.3	pc/mi/ln
LOS	E	

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$		pc/h
S		mi/h
$D = v_p / S$		pc/mi/ln
Required Number of Lanes, N		


Glossary

N - Number of lanes	S - Speed
V - Hourly volume	D - Density
v_p - Flow rate	FFS - Free-flow speed
LOS - Level of service	BFFS - Base free-flow speed
DDHV - Directional design hour volume	

Factor Location

E_R - Exhibits 23-8, 23-10	f_{LW} - Exhibit 23-4
E_T - Exhibits 23-8, 23-10, 23-11	f_{LC} - Exhibit 23-5
f_p - Page 23-12	f_N - Exhibit 23-6
LOS, S, FFS, v_p - Exhibits 23-2, 23-3	f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *9/08/2011*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 to Exit 2*
 Jurisdiction *NYS DOT*
 Analysis Year *2009 - Existing*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *3750* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.92*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1 + P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1372* pc/h/ln
 S *56.0* mi/h
 D = v_p / S *24.5* pc/mi/ln
 LOS *C*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 D = v_p / S pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst **SEB**
 Agency or Company **CHA**
 Date Performed **9/09/2011**
 Analysis Time Period **PM**

Site Information

Highway/Direction of Travel **Northbound I-87**
 From/To **Exit 4 off to Exit 4 on**
 Jurisdiction **NYS DOT**
 Analysis Year **2009 - Existing**

Project Description **Exit 4**

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V **4500** veh/h
 AADT **veh/day**
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D **veh/h**
 Driver type adjustment **1.00**
 Peak-Hour Factor, PHF **0.86**
 % Trucks and Buses, P_T **2**
 % RVs, P_R **0**
 General Terrain: **Level**
 Grade % Length **mi**
 Up/Down %

Calculate Flow Adjustments

f_p **1.00**
 E_T **1.5**
 E_R **1.2**
 $f_{HV} = 1/[1 + P_T(E_T - 1) + P_R(E_R - 1)]$ **0.990**

Speed Inputs

Lane Width **12.0** ft
 Rt-Shoulder Lat. Clearance **6.0** ft
 Interchange Density **0.50** l/mi
 Number of Lanes, N **3**
 FFS (measured) **56.0** mi/h
 Base free-flow Speed, BFFS **mi/h**

Calc Speed Adj and FFS

f_{LW} **mi/h**
 f_{LC} **mi/h**
 f_{ID} **mi/h**
 f_N **mi/h**
 FFS **56.0** mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ **1762** pc/h/ln
 S **56.0** mi/h
 $D = v_p / S$ **31.5** pc/mi/ln
 LOS **D**

Design (N)

Design (N)

Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ **pc/h**
 f_p **pc/h**
 S **mi/h**
 $D = v_p / S$ **pc/mi/ln**
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst **SEB**
 Agency or Company **CHA**
 Date Performed **12/09/2011**
 Analysis Time Period **PM**

Site Information

Highway/Direction of Travel **Southbound I-87**
 From/To **Exit 5 on to Exit 4 on**
 Jurisdiction **NYSDOT**
 Analysis Year **2009 - Existing**

Project Description **Exit 4**

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V	2700	veh/h	Peak-Hour Factor, PHF	0.92
AADT		veh/day	%Trucks and Buses, P_T	2
Peak-Hr Prop. of AADT, K			%RVs, P_R	0
Peak-Hr Direction Prop, D			General Terrain:	Level
DDHV = AADT x K x D		veh/h	Grade %	Length mi
Driver type adjustment	1.00		Up/Down %	

Calculate Flow Adjustments

f_p	1.00	E_R	1.2
E_T	1.5	$f_{HV} = 1/[1+P_T(E_T-1) + P_R(E_R-1)]$	0.990

Speed Inputs

Lane Width	12.0	ft
Rt-Shoulder Lat. Clearance	6.0	ft
Interchange Density	0.50	l/mi
Number of Lanes, N	3	
FFS (measured)	56.0	mi/h
Base free-flow Speed, BFFS		mi/h

Calc Speed Adj and FFS

f_{LW}	mi/h
f_{LC}	mi/h
f_{ID}	mi/h
f_N	mi/h
FFS	56.0 mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$	988	pc/h/ln
S	56.0	mi/h
$D = v_p / S$	17.6	pc/mi/ln
LOS	B	

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$	pc/h
f_p	
S	mi/h
$D = v_p / S$	pc/mi/ln
Required Number of Lanes, N	


Glossary

N - Number of lanes	S - Speed
V - Hourly volume	D - Density
v_p - Flow rate	FFS - Free-flow speed
LOS - Level of service	BFFS - Base free-flow speed
DDHV - Directional design hour volume	

Factor Location

E_R - Exhibits 23-8, 23-10	f_{LW} - Exhibit 23-4
E_T - Exhibits 23-8, 23-10, 23-11	f_{LC} - Exhibit 23-5
f_p - Page 23-12	f_N - Exhibit 23-6
LOS, S, FFS, v_p - Exhibits 23-2, 23-3	f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst **SEB**
 Agency or Company **CHA**
 Date Performed **9/08/2011**
 Analysis Time Period **PM**

Site Information

Highway/Direction of Travel **Northbound I-87**
 From/To **Exit 4 to Exit 5**
 Jurisdiction **NYS DOT**
 Analysis Year **2009 - Existing**

Project Description **Exit 4**

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V	5800	veh/h	Peak-Hour Factor, PHF	0.86
AADT		veh/day	% Trucks and Buses, P_T	2
Peak-Hr Prop. of AADT, K			% RVs, P_R	0
Peak-Hr Direction Prop, D			General Terrain:	Level
DDHV = AADT x K x D		veh/h	Grade %	Length mi
Driver type adjustment	1.00		Up/Down %	

Calculate Flow Adjustments

f_p	1.00	E_R	1.2
E_T	1.5	$f_{HV} = 1/[1 + P_T(E_T - 1) + P_R(E_R - 1)]$	0.990

Speed Inputs

Lane Width	12.0	ft
Rt-Shoulder Lat. Clearance	6.0	ft
Interchange Density	0.50	l/mi
Number of Lanes, N	3	
FFS (measured)	56.0	mi/h
Base free-flow Speed, BFFS		mi/h

Calc Speed Adj and FFS

f_{LW}	mi/h
f_{LC}	mi/h
f_{ID}	mi/h
f_N	mi/h
FFS	56.0 mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or DDHV}) / (PHF \times N \times f_{HV} \times f_p)$ **2271** pc/h/ln
 S mi/h
 $D = v_p / S$ pc/mi/ln
LOS F

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or DDHV}) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *9/08/2011*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 5 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2009 - Existing*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2500* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.92*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *915* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *16.3* pc/mi/ln
 LOS *B*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst **SEB**
 Agency or Company **CHA**
 Date Performed **9/08/2011**
 Analysis Time Period **PM**

Site Information

Highway/Direction of Travel **Northbound I-87**
 From/To **Exit 5 to Exit 6**
 Jurisdiction **NYS DOT**
 Analysis Year **2009 - Existing**

Project Description **Exit 4**

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V	6000	veh/h	Peak-Hour Factor, PHF	0.86
AADT		veh/day	% Trucks and Buses, P_T	2
Peak-Hr Prop. of AADT, K			% RVs, P_R	0
Peak-Hr Direction Prop, D			General Terrain:	Level
DDHV = AADT x K x D		veh/h	Grade % Length	mi
Driver type adjustment	1.00		Up/Down %	

Calculate Flow Adjustments

f_p	1.00	E_R	1.2
E_T	1.5	$f_{HV} = 1/[1 + P_T(E_T - 1) + P_R(E_R - 1)]$	0.990

Speed Inputs

Lane Width	12.0	ft
Rt-Shoulder Lat. Clearance	6.0	ft
Interchange Density	0.50	l/mi
Number of Lanes, N	4	
FFS (measured)	56.0	mi/h
Base free-flow Speed, BFFS		mi/h

Calc Speed Adj and FFS

f_{LW}		mi/h
f_{LC}		mi/h
f_{ID}		mi/h
f_N		mi/h
FFS	56.0	mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$	1762	pc/h/ln
S	56.0	mi/h
$D = v_p / S$	31.5	pc/mi/ln
LOS	D	

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$		pc/h
f_p		
S		mi/h
$D = v_p / S$		pc/mi/ln
Required Number of Lanes, N		


Glossary

N - Number of lanes	S - Speed
V - Hourly volume	D - Density
v_p - Flow rate	FFS - Free-flow speed
LOS - Level of service	BFFS - Base free-flow speed
DDHV - Directional design hour volume	

Factor Location

E_R - Exhibits 23-8, 23-10	f_{LW} - Exhibit 23-4
E_T - Exhibits 23-8, 23-10, 23-11	f_{LC} - Exhibit 23-5
f_p - Page 23-12	f_N - Exhibit 23-6
LOS, S, FFS, v_p - Exhibits 23-2, 23-3	f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *9/08/2011*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 6 to Exit 5*
 Jurisdiction *NYS DOT*
 Analysis Year *2009 - Existing*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *3300* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D
 Driver type adjustment *1.00*

Peak-Hour Factor, PHF *0.92*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T-1)+P_R(E_R-1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *4*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *906* pc/h/ln
 S *56.0* mi/h
 D = v_p / S *16.2* pc/mi/ln
 LOS *B*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p pc/h
 S mi/h
 D = v_p / S pc/mi/ln

Required Number of Lanes, N

Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume

S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3

f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 2W On-Ramp			
Date Performed		9/08/2011		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2009 Existing			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1100$ ft $V_u = 910$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4400	0.86	Level	2	0	0.990	1.00	5167	
Ramp	700	0.92	Level	2	0	0.990	1.00	768	
UpStream	910	0.92	Level	2	0	0.990	1.00	999	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 1337.29$ (Equation 25-2 or 25-3) $P_{FM} = 0.586$ using Equation (Exhibit 25-5) $V_{12} = 3029$ pc/h V_3 or $V_{av34} = 2138$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	5935	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	3797	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 29.4$ (pc/mi/ln) LOS = D (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.427$ (Exhibit 25-19) $S_R = 50.0$ mph (Exhibit 25-19) $S_0 = 50.1$ mph (Exhibit 25-19) $S = 50.1$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 4 NB Off			
Date Performed		9/08/2011		Jurisdiction		NYS DOT			
Analysis Time Period		PM		Analysis Year		2009 Existing			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 2660 ft $V_D =$ 1330 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	5100	0.86	Level	2	0	0.990	1.00	5990	
Ramp	600	0.86	Level	2	0	0.990	1.00	705	
UpStream									
DownStream	1330	0.88	Level	1	0	0.995	1.00	1519	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.578 using Equation (Exhibit 25-12) $V_{12} =$ 3759 pc/h V_3 or V_{av34} 2231 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	5990	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	5285	Exhibit 25-14	6780	No	
				V_R	705	Exhibit 25-3	2100	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	3759	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 33.4 (pc/mi/ln) $LOS =$ D (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.426 (Exhibit 25-19) $S_R =$ 50.0 mph (Exhibit 25-19) $S_0 =$ 56.6 mph (Exhibit 25-19) $S =$ 52.3 mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 4 NB On-Ramp			
Date Performed		9/08/2011		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2009 Existing			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_I)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{down} =$ 3500 ft $V_D =$ 440 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4500	0.86	Level	2	0	0.990	1.00	5285	
Ramp	1330	0.88	Level	1	0	0.995	1.00	1519	
UpStream									
DownStream	440	0.92	Level	3	0	0.985	1.00	485	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 2355.51$ (Equation 25-2 or 25-3) $P_{FM} = 0.603$ using Equation (Exhibit 25-5) $V_{12} = 3185$ pc/h V_3 or $V_{av34} = 2100$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	6804	Exhibit 25-7		Yes	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	4704	Exhibit 25-7	4600:All	Yes	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 35.8$ (pc/mi/ln) LOS = F (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.680$ (Exhibit 25-19) $S_R = 46.5$ mph (Exhibit 25-19) $S_0 = 50.2$ mph (Exhibit 25-19) $S = 47.6$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 5 NB Off			
Date Performed		9/08/2011		Jurisdiction		NYS DOT			
Analysis Time Period		PM		Analysis Year		2009 Existing			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off L _{up} = 3500 ft V _u = 1330 veh/h			Terrain: Level <div style="display: flex; justify-content: space-around;"> S_{FF} = 56.0 mph S_{FR} = 35.0 mph </div> Sketch (show lanes, L _A , L _D , V _R , V _P)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off L _{down} = ft V _D = veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f _{HV}	f _p	v = V/PHF x f _{HV} x f _p	
Freeway	5800	0.86	Level	2	0	0.990	1.00	6812	
Ramp	440	0.92	Level	3	0	0.985	1.00	485	
UpStream	1330	0.88	Level	1	0	0.995	1.00	1519	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v₁₂					Estimation of v₁₂				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) L _{EQ} = P _{FM} = using Equation (Exhibit 25-5) V ₁₂ = pc/h V ₃ or V _{av34} pc/h (Equation 25-4 or 25-5) Is V ₃ or V _{av34} > 2,700 pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V ₃ or V _{av34} > 1.5 * V ₁₂ /2 <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, V _{12a} = pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ L _{EQ} = 7960.55 (Equation 25-8 or 25-9) P _{FD} = 0.713 using Equation (Exhibit 25-12) V ₁₂ = 4999 pc/h V ₃ or V _{av34} 1813 pc/h (Equation 25-15 or 25-16) Is V ₃ or V _{av34} > 2,700 pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V ₃ or V _{av34} > 1.5 * V ₁₂ /2 <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, V _{12a} = pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V _{FO}		Exhibit 25-7			V _F	6812	Exhibit 25-14	6780	Yes
					V _{FO} = V _F - V _R	6327	Exhibit 25-14	6780	No
					V _R	485	Exhibit 25-3	2000	No
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V _{R12}		Exhibit 25-7			V ₁₂	4999	Exhibit 25-14	4400:All	Yes
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ D _R = (pc/mi/ln) LOS = (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ D _R = 45.0 (pc/mi/ln) LOS = F (Exhibit 25-4)				
Speed Determination					Speed Determination				
M _S = (Exhibit 25-19) S _R = mph (Exhibit 25-19) S ₀ = mph (Exhibit 25-19) S = mph (Exhibit 25-14)					D _S = 0.472 (Exhibit 25-19) S _R = 49.4 mph (Exhibit 25-19) S ₀ = 58.3 mph (Exhibit 25-19) S = 51.5 mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET											
General Information					Site Information						
Analyst		SEB		Freeway/Dir of Travel		Southbound					
Agency or Company		CHA		Junction		Exit 2W Off					
Date Performed		9/08/2011		Jurisdiction		NYS DOT					
Analysis Time Period		PM		Analysis Year		2009 Existing					
Project Description Exit 4											
Inputs											
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1300 ft $V_D =$ 890 veh/h				
Conversion to pc/h Under Base Conditions											
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$			
Freeway	3750	0.92	Level	2	0	0.990	1.00	4117			
Ramp	430	0.92	Level	2	0	0.990	1.00	472			
UpStream											
DownStream	890	0.92	Level	2	0	0.990	1.00	977			
Merge Areas					Diverge Areas						
Estimation of v_{12}					Estimation of v_{12}						
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ $P_{FD} = 0.635$ using Equation (Exhibit 25-12) $V_{12} = 2788$ pc/h V_3 or V_{av34} 1329 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)						
Capacity Checks					Capacity Checks						
		Actual	Capacity		LOS F?			Actual	Capacity	LOS F?	
V_{FO}		Exhibit 25-7				V_F		4117	Exhibit 25-14	6780	No
						$V_{FO} = V_F - V_R$		3645	Exhibit 25-14	6780	No
						V_R		472	Exhibit 25-3	2100	No
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area						
		Actual	Max Desirable		Violation?			Actual	Max Desirable		Violation?
V_{R12}			Exhibit 25-7			V_{12}		2788	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)						
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 25.5$ (pc/mi/ln) $LOS = C$ (Exhibit 25-4)						
Speed Determination					Speed Determination						
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.405$ (Exhibit 25-19) $S_R = 50.3$ mph (Exhibit 25-19) $S_0 = 60.1$ mph (Exhibit 25-19) $S = 53.1$ mph (Exhibit 25-15)						

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 4 SB Off			
Date Performed		9/08/2011		Jurisdiction		NYS DOT			
Analysis Time Period		PM		Analysis Year		2009 Existing			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 3100 ft $V_D =$ 490 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2900	0.92	Level	2	0	0.990	1.00	3184	
Ramp	730	0.92	Level	2	0	0.990	1.00	801	
UpStream									
DownStream	490	0.87	Level	1	0	0.995	1.00	566	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.644 using Equation (Exhibit 25-12) $V_{12} =$ 2335 pc/h V_3 or V_{av34} 849 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	3184	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	2383	Exhibit 25-14	6780	No	
				V_R	801	Exhibit 25-3	2100	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	2335	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 20.1 (pc/mi/ln) $LOS =$ C (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.435 (Exhibit 25-19) $S_R =$ 49.9 mph (Exhibit 25-19) $S_0 =$ 61.4 mph (Exhibit 25-19) $S =$ 52.5 mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 4 SB On-Ramp			
Date Performed		9/08/2011		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2009 Existing			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{up} = 2035$ ft $V_u = 490$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2700	0.92	Level	2	0	0.990	1.00	2964	
Ramp	1030	0.93	Level	4	0	0.980	1.00	1130	
UpStream	490	0.87	Level	1	0	0.995	1.00	566	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} = 0.603$ using Equation (Exhibit 25-5) $V_{12} = 1786$ pc/h V_3 or $V_{av34} = 1178$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	4094	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	2916	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 22.1$ (pc/mi/ln) LOS = C (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.321$ (Exhibit 25-19) $S_R = 51.5$ mph (Exhibit 25-19) $S_0 = 53.6$ mph (Exhibit 25-19) $S = 52.1$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				


RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 5 SB On-Ramp			
Date Performed		9/08/2011		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2009 Existing			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 2035 ft $V_D =$ 1030 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2500	0.92	Level	2	0	0.990	1.00	2745	
Ramp	490	0.87	Level	1	0	0.995	1.00	566	
UpStream									
DownStream	1030	0.93	Level	4	0	0.980	1.00	1130	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} = 0.603$ using Equation (Exhibit 25-5) $V_{12} = 1654$ pc/h V_3 or $V_{av34} = 1091$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	3311	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	2220	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 16.9$ (pc/mi/ln) LOS = B (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.285$ (Exhibit 25-19) $S_R = 52.0$ mph (Exhibit 25-19) $S_0 = 53.9$ mph (Exhibit 25-19) $S = 52.6$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 9/08/2011 Analysis Time Period PM					Freeway/Dir of Travel I-87 Northbound Weaving Seg Location Exit 2E on to 2W off Jurisdiction NYSDOT Analysis Year 2009 Existing				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 815 Terrain Level					Weaving type A Volume ratio, VR 0.25 Weaving ratio, R 0.34				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	3930	0.86	2	0	1.5	1.2	0.990	1.00	4615
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	910	0.92	2	0	1.5	1.2	0.990	1.00	999
V_{w2}	470	0.92	2	0	1.5	1.2	0.990	1.00	515
V_w				1514	V_{nw}				4615
V									6129
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	1.41		0.77						
Weaving and non-weaving speeds, S_i (mi/h)	34.12		41.02						
Number of lanes required for unconstrained operation, N_w					1.36				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					39.07				
Weaving segment density, D (pc/mi/ln)					39.22				
Level of service, LOS					E				
Capacity of base condition, c_b (pc/h)					6482				
Capacity as a 15-minute flow rate, c (veh/h)					6418				
Capacity as a full-hour volume, c_h (veh/h)					5620				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst Agency/Company Date Performed Analysis Time Period					SEB CHA 6/22/2011 PM				
Freeway/Dir of Travel Weaving Seg Location Jurisdiction Analysis Year					I-87 Southbound Exit 2W on to 2E off NYSDOT 2009 Existing				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h)					56				
Weaving number of lanes, N					4				
Weaving seg length, L (ft)					810				
Terrain					Level				
Weaving type					A				
Volume ratio, VR					0.31				
Weaving ratio, R					0.31				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	2900	0.92	2	0	1.5	1.2	0.990	1.00	3183
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	890	0.92	2	0	1.5	1.2	0.990	1.00	977
V_{w2}	400	0.92	2	0	1.5	1.2	0.990	1.00	439
V_w				1416	V_{nw}				3183
V									4599
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (i = nw)		
a (Exhibit 24-6)					0.35		0.0020		
b (Exhibit 24-6)					2.20		4.00		
c (Exhibit 24-6)					0.97		1.30		
d (Exhibit 24-6)					0.80		0.75		
Weaving intensity factor, W_i					2.77		0.37		
Weaving and non-weaving speeds, S_i (mi/h)					27.20		48.65		
Number of lanes required for unconstrained operation, N_w					1.51				
Maximum number of lanes, N_w (max)					1.40				
<input type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input checked="" type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					39.15				
Weaving segment density, D (pc/mi/ln)					29.37				
Level of service, LOS					D				
Capacity of base condition, c_b (pc/h)					6136				
Capacity as a 15-minute flow rate, c (veh/h)					6075				
Capacity as a full-hour volume, c_h (veh/h)					5589				
Notes									
<p>a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions".</p> <p>b. Capacity constrained by basic freeway capacity.</p> <p>c. Capacity occurs under constrained operating conditions.</p> <p>d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases.</p> <p>e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases.</p> <p>f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C).</p> <p>g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases.</p> <p>h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases.</p> <p>i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.</p>									

NO-BUILD

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *6/22/2011*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 2 to Exit 4*
 Jurisdiction *NYS DOT*
 Analysis Year *2016 No-Build*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *3000* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D
 Driver type adjustment *1.00* veh/h
 Peak-Hour Factor, PHF *0.92*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS *mi/h*

Calc Speed Adj and FFS

f_{LW} *mi/h*
 f_{LC} *mi/h*
 f_{ID} *mi/h*
 f_N *mi/h*
 FFS *56.0* *mi/h*

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1098* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *19.6* pc/mi/ln
 LOS *C*

Design (N)

Design (N)

Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *pc/h*
 f_p *mi/h*
 S *mi/h*
 $D = v_p / S$ *pc/mi/ln*
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst **SEB**
 Agency or Company **CHA**
 Date Performed **6/22/2011**
 Analysis Time Period **AM**

Site Information

Highway/Direction of Travel **Southbound I-87**
 From/To **Exit 4 to Exit 2**
 Jurisdiction **NYSDOT**
 Analysis Year **2016 No-Build**

Project Description **Exit 4**

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V **5200** veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment **1.00**

Peak-Hour Factor, PHF **0.92**
 %Trucks and Buses, P_T **2**
 %RVs, P_R **0**
 General Terrain: **Level**
 Grade % Length **mi**
 Up/Down %

Calculate Flow Adjustments

f_p **1.00**
 E_T **1.5**
 E_R **1.2**
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ **0.990**

Speed Inputs

Lane Width **12.0** ft
 Rt-Shoulder Lat. Clearance **6.0** ft
 Interchange Density **0.50** l/mi
 Number of Lanes, N **3**
 FFS (measured) **56.0** mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS **56.0** mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ **1903** pc/h/ln
 S **55.7** mi/h
 $D = v_p / S$ **34.2** pc/mi/ln
 LOS **D**

Design (N)

Design (N)

Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume


S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3

f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst: SEB
 Agency or Company: CHA
 Date Performed: 9/09/2011
 Analysis Time Period: AM

Site Information

Highway/Direction of Travel: Northbound I-87
 From/To: Exit 4 off to Exit 4 on
 Jurisdiction: NYSDOT
 Analysis Year: 2016 No-Build

Project Description: Exit 4

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V: 2250 veh/h
 AADT: veh/day
 Peak-Hr Prop. of AADT, K:
 Peak-Hr Direction Prop. D:
 DDHV = AADT x K x D: veh/h
 Driver type adjustment: 1.00
 Peak-Hour Factor, PHF: 0.92
 %Trucks and Buses, P_T : 2
 %RVs, P_R : 0
 General Terrain: Level
 Grade % Length: mi
 Up/Down %:

Calculate Flow Adjustments

f_p : 1.00
 E_T : 1.5
 E_R : 1.2
 $f_{HV} = 1/[1 + P_T(E_T - 1) + P_R(E_R - 1)]$: 0.990

Speed Inputs

Lane Width: 12.0 ft
 Rt-Shoulder Lat. Clearance: 6.0 ft
 Interchange Density: 0.50 l/mi
 Number of Lanes, N: 3
 FFS (measured): 56.0 mi/h
 Base free-flow Speed, BFFS: mi/h

Calc Speed Adj and FFS

f_{LW} : mi/h
 f_{LC} : mi/h
 f_{ID} : mi/h
 f_N : mi/h
 FFS: 56.0 mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$: 823 pc/h/ln
 S: 56.0 mi/h
 D = v_p / S : 14.7 pc/mi/ln
 LOS: B

Design (N)

Design (N)

Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$: pc/h
 f_p :
 S: mi/h
 D = v_p / S : pc/mi/ln
 Required Number of Lanes, N:


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst **SEB**
 Agency or Company **CHA**
 Date Performed **12/09/2011**
 Analysis Time Period **AM**

Site Information

Highway/Direction of Travel **Southbound I-87**
 From/To **Exit 5 on to Exit 4 on**
 Jurisdiction **NYSDOT**
 Analysis Year **2016 No-Build**

Project Description **Exit 4**

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V **4650** veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D
 Driver type adjustment **1.00**

Peak-Hour Factor, PHF **0.92**
 %Trucks and Buses, P_T **2**
 %RVs, P_R **0**
 General Terrain: **Level**
 Grade % Length **mi**
 Up/Down %

Calculate Flow Adjustments

f_p **1.00**
 E_T **1.5**
 E_R **1.2**
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ **0.990**

Speed Inputs

Lane Width **12.0** ft
 Rt-Shoulder Lat. Clearance **6.0** ft
 Interchange Density **0.50** l/mi
 Number of Lanes, N **3**
 FFS (measured) **56.0** mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS **56.0** mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ **1702** pc/h/ln
 S **56.0** mi/h
 $D = v_p / S$ **30.4** pc/mi/ln
 LOS **D**

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume


S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3

f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst **SEB**
 Agency or Company **CHA**
 Date Performed **6/22/2011**
 Analysis Time Period **AM**

Site Information

Highway/Direction of Travel **Northbound I-87**
 From/To **Exit 4 to Exit 5**
 Jurisdiction **NYS DOT**
 Analysis Year **2016 No-Build**

Project Description **Exit 4**

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V **2750** veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D
 Driver type adjustment **1.00** veh/h
 Peak-Hour Factor, PHF **0.92**
 %Trucks and Buses, P_T **2**
 %RVs, P_R **0**
 General Terrain: **Level**
 Grade % Length **mi**
 Up/Down %

Calculate Flow Adjustments

f_p **1.00**
 E_T **1.5**
 E_R **1.2**
 $f_{HV} = 1/[1+P_T(E_T-1)+P_R(E_R-1)]$ **0.990**

Speed Inputs

Lane Width **12.0** ft
 Rt-Shoulder Lat. Clearance **6.0** ft
 Interchange Density **0.50** l/mi
 Number of Lanes, N **3**
 FFS (measured) **56.0** mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS **56.0** mi/h

LOS and Performance Measures

Operational (LOS)
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ **1006** pc/h/ln
 S **56.0** mi/h
 $D = v_p / S$ **18.0** pc/mi/ln
 LOS **B**

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *6/22/2011*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 5 to Exit 4*
 Jurisdiction *NYS DOT*
 Analysis Year *2016 No-Build*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *4400* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D
 Driver type adjustment *1.00* veh/h
 Peak-Hour Factor, PHF *0.92*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1 + P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1610* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *28.8* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *6/22/2011*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 5 to Exit 6*
 Jurisdiction *NYS DOT*
 Analysis Year *2016 No-Build*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2500* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.92*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T-1)+P_R(E_R-1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *4*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *686* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *12.3* pc/mi/ln
 LOS *B*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *6/22/2011*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 6 to Exit 5*
 Jurisdiction *NYS DOT*
 Analysis Year *2016 No-Build*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *6100* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.92*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T-1) + P_R(E_R-1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *4*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1674* pc/h/ln
 S *56.0* mi/h
 D = v_p / S *29.9* pc/mi/ln
 LOS *D*

Design (N)

Design (N)

Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p pc/h
 S mi/h
 D = v_p / S pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 2W On-Ramp			
Date Performed		9/08/2011		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2016 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1100$ ft $V_u = 620$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2650	0.92	Level	2	0	0.990	1.00	2909	
Ramp	350	0.92	Level	2	0	0.990	1.00	384	
UpStream	620	0.92	Level	2	0	0.990	1.00	681	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 771.90$ (Equation 25-2 or 25-3) $P_{FM} = 0.601$ using Equation (Exhibit 25-5) $V_{12} = 1749$ pc/h V_3 or $V_{av34} = 1160$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	3293	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	2133	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 16.6$ (pc/mi/ln) LOS = B (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.286$ (Exhibit 25-19) $S_R = 52.0$ mph (Exhibit 25-19) $S_0 = 53.6$ mph (Exhibit 25-19) $S = 52.6$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 4 NB Off			
Date Performed		9/08/2011		Jurisdiction		NYS DOT			
Analysis Time Period		AM		Analysis Year		2016 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 2660 ft $V_D =$ 670 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	3000	0.92	Level	2	0	0.990	1.00	3293	
Ramp	740	0.82	Level	2	0	0.990	1.00	911	
UpStream									
DownStream	670	0.92	Level	2	0	0.990	1.00	736	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ $P_{FD} = 0.636$ using Equation (Exhibit 25-12) $V_{12} = 2425$ pc/h V_3 or V_{av34} 868 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	3293	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	2382	Exhibit 25-14	6780	No	
				V_R	911	Exhibit 25-3	2100	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	2425	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 22.0$ (pc/mi/ln) $LOS = C$ (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.445$ (Exhibit 25-19) $S_R = 49.8$ mph (Exhibit 25-19) $S_0 = 61.4$ mph (Exhibit 25-19) $S = 52.4$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 4 NB On-Ramp			
Date Performed		9/08/2011		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2016 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{down} =$ 3500 ft $V_D =$ 460 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2250	0.92	Level	2	0	0.990	1.00	2470	
Ramp	670	0.92	Level	2	0	0.990	1.00	736	
UpStream									
DownStream	460	0.96	Level	2	0	0.990	1.00	484	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 2350.66$ (Equation 25-2 or 25-3) $P_{FM} = 0.603$ using Equation (Exhibit 25-5) $V_{12} = 1489$ pc/h V_3 or $V_{av34} = 981$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	3206	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	2225	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 16.8$ (pc/mi/ln) LOS = B (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.285$ (Exhibit 25-19) $S_R = 52.0$ mph (Exhibit 25-19) $S_0 = 54.3$ mph (Exhibit 25-19) $S = 52.7$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 5 NB Off			
Date Performed		9/08/2011		Jurisdiction		NYS DOT			
Analysis Time Period		AM		Analysis Year		2016 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ 3500 ft $V_u =$ 670 veh/h			Terrain: Level $S_{FF} =$ 56.0 mph $S_{FR} =$ 35.0 mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2750	0.92	Level	2	0	0.990	1.00	3019	
Ramp	460	0.96	Level	2	0	0.990	1.00	484	
UpStream	670	0.92	Level	2	0	0.990	1.00	736	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ 7100.61 (Equation 25-8 or 25-9) $P_{FD} =$ 0.726 using Equation (Exhibit 25-12) $V_{12} =$ 2325 pc/h V_3 or V_{av34} 694 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	3019	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	2535	Exhibit 25-14	6780	No	
				V_R	484	Exhibit 25-3	2000	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	2325	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 22.0 (pc/mi/ln) $LOS =$ C (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.472 (Exhibit 25-19) $S_R =$ 49.4 mph (Exhibit 25-19) $S_0 =$ 61.4 mph (Exhibit 25-19) $S =$ 51.7 mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound			
Agency or Company		CHA		Junction		Exit 2W Off			
Date Performed		9/08/2011		Jurisdiction		NYS DOT			
Analysis Time Period		AM		Analysis Year		2016 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1300 ft $V_D =$ 370 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	5200	0.92	Level	2	0	0.990	1.00	5709	
Ramp	780	0.92	Level	2	0	0.990	1.00	856	
UpStream									
DownStream	370	0.92	Level	2	0	0.990	1.00	406	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.578 using Equation (Exhibit 25-12) $V_{12} =$ 3661 pc/h V_3 or V_{av34} 2048 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	5709	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	4853	Exhibit 25-14	6780	No	
				V_R	856	Exhibit 25-3	2100	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	3661	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 33.0 (pc/mi/ln) $LOS =$ D (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.440 (Exhibit 25-19) $S_R =$ 49.8 mph (Exhibit 25-19) $S_0 =$ 57.3 mph (Exhibit 25-19) $S =$ 52.3 mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 4 SB Off			
Date Performed		9/08/2011		Jurisdiction		NYS DOT			
Analysis Time Period		AM		Analysis Year		2016 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 3100 ft $V_D =$ 370 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	5400	0.92	Level	2	0	0.990	1.00	5928	
Ramp	1020	0.92	Level	2	0	0.990	1.00	1120	
UpStream									
DownStream	370	0.93	Level	3	0	0.985	1.00	404	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.560 using Equation (Exhibit 25-12) $V_{12} =$ 3814 pc/h V_3 or V_{av34} 2114 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	5928	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	4808	Exhibit 25-14	6780	No	
				V_R	1120	Exhibit 25-3	2100	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	3814	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 32.8 (pc/mi/ln) $LOS =$ D (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.464 (Exhibit 25-19) $S_R =$ 49.5 mph (Exhibit 25-19) $S_0 =$ 57.1 mph (Exhibit 25-19) $S =$ 52.0 mph (Exhibit 25-15)				


RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 4 SB On-Ramp			
Date Performed		9/08/2011		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2016 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{up} = 2035$ ft $V_u = 370$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4650	0.92	Level	2	0	0.990	1.00	5105	
Ramp	530	0.93	Level	5	0	0.976	1.00	584	
UpStream	370	0.93	Level	3	0	0.985	1.00	404	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} = 0.603$ using Equation (Exhibit 25-5) $V_{12} = 3077$ pc/h V_3 or $V_{av34} = 2028$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	5689	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	3661	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 28.1$ (pc/mi/ln) LOS = D (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.401$ (Exhibit 25-19) $S_R = 50.4$ mph (Exhibit 25-19) $S_0 = 50.5$ mph (Exhibit 25-19) $S = 50.4$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 5 SB On-Ramp			
Date Performed		9/08/2011		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2016 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 2035 ft $V_D =$ 530 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4400	0.92	Level	2	0	0.990	1.00	4830	
Ramp	370	0.93	Level	3	0	0.985	1.00	404	
UpStream									
DownStream	530	0.93	Level	5	0	0.976	1.00	584	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} = 0.603$ using Equation (Exhibit 25-5) $V_{12} = 2911$ pc/h V_3 or $V_{av34} = 1919$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	5234	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	3315	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 25.5$ (pc/mi/ln) LOS = C (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.356$ (Exhibit 25-19) $S_R = 51.0$ mph (Exhibit 25-19) $S_0 = 50.9$ mph (Exhibit 25-19) $S = 51.0$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 9/08/2011 Analysis Time Period AM					Freeway/Dir of Travel I-87 Northbound Weaving Seg Location Exit 2E on to 2W off Jurisdiction NYSDOT Analysis Year 2016 No-Build				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 815 Terrain Level					Weaving type A Volume ratio, VR 0.29 Weaving ratio, R 0.30				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	2360	0.92	2	0	1.5	1.2	0.990	1.00	2590
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	670	0.92	2	0	1.5	1.2	0.990	1.00	735
V_{w2}	290	0.92	2	0	1.5	1.2	0.990	1.00	318
V_w				1053	V_{nw}				2590
V									3643
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (i = nw)		
a (Exhibit 24-6)					0.35		0.0020		
b (Exhibit 24-6)					2.20		4.00		
c (Exhibit 24-6)					0.97		1.30		
d (Exhibit 24-6)					0.80		0.75		
Weaving intensity factor, W_i					2.13		0.25		
Weaving and non-weaving speeds, S_i (mi/h)					29.70		51.66		
Number of lanes required for unconstrained operation, N_w 1.40									
Maximum number of lanes, N_w (max) 1.40									
<input type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input checked="" type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					42.56				
Weaving segment density, D (pc/mi/ln)					21.40				
Level of service, LOS					C				
Capacity of base condition, c_b (pc/h)					6249				
Capacity as a 15-minute flow rate, c (veh/h)					6187				
Capacity as a full-hour volume, c_h (veh/h)					5692				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CGA Date Performed 9/08/2011 Analysis Time Period AM					Freeway/Dir of Travel I-87 Southbound Weaving Seg Location Exit 2W on to 2E off Jurisdiction NYSDOT Analysis Year 2016 No-Build				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 810 Terrain Level					Weaving type A Volume ratio, VR 0.22 Weaving ratio, R 0.35				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	3700	0.92	2	0	1.5	1.2	0.990	1.00	4061
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	700	0.92	2	0	1.5	1.2	0.990	1.00	768
V_{w2}	370	0.92	2	0	1.5	1.2	0.990	1.00	406
V_w				1174	V_{nw}				4061
V									5235
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	1.16		0.58						
Weaving and non-weaving speeds, S_i (mi/h)	36.26		44.05						
Number of lanes required for unconstrained operation, N_w					1.25				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					42.02				
Weaving segment density, D (pc/mi/ln)					31.14				
Level of service, LOS					D				
Capacity of base condition, c_b (pc/h)					6601				
Capacity as a 15-minute flow rate, c (veh/h)					6536				
Capacity as a full-hour volume, c_h (veh/h)					6013				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst **SEB**
 Agency or Company **CHA**
 Date Performed **6/22/2011**
 Analysis Time Period **AM**

Site Information

Highway/Direction of Travel **Northbound I-87**
 From/To **Exit 2 to Exit 4**
 Jurisdiction **NYSDOT**
 Analysis Year **2026 No-Build**

Project Description **Exit 4**

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V **3000** veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment **1.00**
 Peak-Hour Factor, PHF **0.92**
 %Trucks and Buses, P_T **2**
 %RVs, P_R **0**
 General Terrain: **Level**
 Grade % Length **mi**
 Up/Down %

Calculate Flow Adjustments

f_p **1.00**
 E_T **1.5**
 E_R **1.2**
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ **0.990**

Speed Inputs

Lane Width **12.0** ft
 Rt-Shoulder Lat. Clearance **6.0** ft
 Interchange Density **0.50** l/mi
 Number of Lanes, N **3**
 FFS (measured) **56.0** mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS **56.0** mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ **1098** pc/h/ln
 S **56.0** mi/h
 $D = v_p / S$ **19.6** pc/mi/ln
 LOS **C**

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *6/22/2011*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 to Exit 2*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 No-Build*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5250* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1921* pc/h/ln
 S *55.6* mi/h
 $D = v_p / S$ *34.6* pc/mi/ln
 LOS *D*

Design (N)

Design (N)

Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst **SEB**
 Agency or Company **CHA**
 Date Performed **9/09/2011**
 Analysis Time Period **AM**

Site Information

Highway/Direction of Travel **Northbound I-87**
 From/To **Exit 4 off to Exit 4 on**
 Jurisdiction **NYSDOT**
 Analysis Year **2026 No-Build**

Project Description **Exit 4**

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V **2250** veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment **1.00**

Peak-Hour Factor, PHF **0.92**
 %Trucks and Buses, P_T **2**
 %RVs, P_R **0**
 General Terrain: **Level**
 Grade % Length **mi**
 Up/Down %

Calculate Flow Adjustments

f_p **1.00**
 E_T **1.5**
 E_R **1.2**
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ **0.990**

Speed Inputs

Lane Width **12.0** ft
 Rt-Shoulder Lat. Clearance **6.0** ft
 Interchange Density **0.50** l/mi
 Number of Lanes, N **3**
 FFS (measured) **56.0** mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS **56.0** mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ **823** pc/h/ln
 S **56.0** mi/h
 $D = v_p / S$ **14.7** pc/mi/ln
 LOS **B**

Design (N)

Design (N)

Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume


S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3

f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *12/09/2011*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 5 on to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 No-Build*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *4750* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1738* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *31.0* pc/mi/ln
 LOS *D*

Design (N)

Design (N)

Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *6/22/2011*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 to Exit 5*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 No-Build*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2750* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T-1)+P_R(E_R-1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1006* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *18.0* pc/mi/ln
 LOS *B*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst **SEB**
 Agency or Company **CHA**
 Date Performed **6/22/2011**
 Analysis Time Period **AM**

Site Information

Highway/Direction of Travel **Southbound I-87**
 From/To **Exit 5 to Exit 4**
 Jurisdiction **NYSDOT**
 Analysis Year **2026 No-Build**

Project Description **Exit 4**

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V **4450** veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment **1.00**
 Peak-Hour Factor, PHF **0.92**
 %Trucks and Buses, P_T **2**
 %RVs, P_R **0**
 General Terrain: **Level**
 Grade % Length **mi**
 Up/Down %

Calculate Flow Adjustments

f_p **1.00**
 E_T **1.5**
 E_R **1.2**
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ **0.990**

Speed Inputs

Lane Width **12.0** ft
 Rt-Shoulder Lat. Clearance **6.0** ft
 Interchange Density **0.50** l/mi
 Number of Lanes, N **3**
 FFS (measured) **56.0** mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS **56.0** mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ **1628** pc/h/ln
 S **56.0** mi/h
 $D = v_p / S$ **29.1** pc/mi/ln
 LOS **D**

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *6/22/2011*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 5 to Exit 6*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 No-Build*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2550* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *4*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *700* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *12.5* pc/mi/ln
 LOS *B*

Design (N)

Design (N)

Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst **SEB**
 Agency or Company **CHA**
 Date Performed **6/22/2011**
 Analysis Time Period **AM**

Site Information

Highway/Direction of Travel **Southbound I-87**
 From/To **Exit 6 to Exit 5**
 Jurisdiction **NYSDOT**
 Analysis Year **2026 No-Build**

Project Description **Exit 4**

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V **6050** veh/h Peak-Hour Factor, PHF **0.92**
 AADT veh/day %Trucks and Buses, P_T **2**
 Peak-Hr Prop. of AADT, K %RVs, P_R **0**
 Peak-Hr Direction Prop, D General Terrain: **Level**
 DDHV = AADT x K x D veh/h Grade % Length **mi**
 Driver type adjustment **1.00** Up/Down %

Calculate Flow Adjustments

f_p **1.00** E_R **1.2**
 E_T **1.5** $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ **0.990**

Speed Inputs

Lane Width **12.0** ft
 Rt-Shoulder Lat. Clearance **6.0** ft
 Interchange Density **0.50** l/mi
 Number of Lanes, N **4**
 FFS (measured) **56.0** mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS **56.0** mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ **1660** pc/h/ln
 S **56.0** mi/h
 $D = v_p / S$ **29.6** pc/mi/ln
 LOS **D**

Design (N)

Design (N)

Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB			Freeway/Dir of Travel		Northbound I-87		
Agency or Company		CHA			Junction		Exit 2W On-Ramp		
Date Performed		9/08/2011			Jurisdiction		NYSDOT		
Analysis Time Period		AM			Analysis Year		2026 No-Build		
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1100$ ft $V_u = 680$ veh/h		Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)					Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2650	0.92	Level	2	0	0.990	1.00	2909	
Ramp	360	0.92	Level	2	0	0.990	1.00	395	
UpStream	680	0.92	Level	2	0	0.990	1.00	747	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 774.26$ (Equation 25-2 or 25-3) $P_{FM} = 0.601$ using Equation (Exhibit 25-5) $V_{12} = 1749$ pc/h V_3 or $V_{av34} = 1160$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	3304	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	2144	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 16.7$ (pc/mi/ln) LOS = B (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.286$ (Exhibit 25-19) $S_R = 52.0$ mph (Exhibit 25-19) $S_0 = 53.6$ mph (Exhibit 25-19) $S = 52.6$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

Generated: 12/16/2011 8:47 AM

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 4 NB On-Ramp			
Date Performed		9/08/2011		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2026 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{down} =$ 3500 ft $V_D =$ 470 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2250	0.92	Level	2	0	0.990	1.00	2470	
Ramp	650	0.92	Level	2	0	0.990	1.00	714	
UpStream									
DownStream	470	0.96	Level	2	0	0.990	1.00	494	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 2399.22$ (Equation 25-2 or 25-3) $P_{FM} = 0.603$ using Equation (Exhibit 25-5) $V_{12} = 1489$ pc/h V_3 or $V_{av34} = 981$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	3184	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	2203	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 16.7$ (pc/mi/ln) LOS = B (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.284$ (Exhibit 25-19) $S_R = 52.0$ mph (Exhibit 25-19) $S_0 = 54.3$ mph (Exhibit 25-19) $S = 52.7$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 5 NB Off			
Date Performed		9/08/2011		Jurisdiction		NYS DOT			
Analysis Time Period		AM		Analysis Year		2026 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{up} = 3500$ ft $V_u = 650$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 35.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_P)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2750	0.92	Level	2	0	0.990	1.00	3019	
Ramp	470	0.96	Level	2	0	0.990	1.00	494	
UpStream	650	0.92	Level	2	0	0.990	1.00	714	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} = 6939.25$ (Equation 25-8 or 25-9) $P_{FD} = 0.722$ using Equation (Exhibit 25-12) $V_{12} = 2318$ pc/h V_3 or $V_{av34} = 701$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	3019	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	2525	Exhibit 25-14	6780	No	
				V_R	494	Exhibit 25-3	2000	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	2318	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 21.9$ (pc/mi/ln) $LOS = C$ (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.472$ (Exhibit 25-19) $S_R = 49.4$ mph (Exhibit 25-19) $S_0 = 61.4$ mph (Exhibit 25-19) $S = 51.7$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound			
Agency or Company		CHA		Junction		Exit 2W Off			
Date Performed		9/08/2011		Jurisdiction		NYS DOT			
Analysis Time Period		AM		Analysis Year		2026 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1300 ft $V_D =$ 360 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	5250	0.92	Level	2	0	0.990	1.00	5764	
Ramp	770	0.92	Level	2	0	0.990	1.00	845	
UpStream									
DownStream	360	0.92	Level	2	0	0.990	1.00	395	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.577 using Equation (Exhibit 25-12) $V_{12} =$ 3683 pc/h V_3 or V_{av34} 2081 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	5764	Exhibit 25-14	6780	No
					$V_{FO} = V_F - V_R$	4919	Exhibit 25-14	6780	No
					V_R	845	Exhibit 25-3	2100	No
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	3683	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 33.2 (pc/mi/ln) $LOS =$ D (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.439 (Exhibit 25-19) $S_R =$ 49.9 mph (Exhibit 25-19) $S_0 =$ 57.2 mph (Exhibit 25-19) $S =$ 52.3 mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 4 SB Off			
Date Performed		9/08/2011		Jurisdiction		NYS DOT			
Analysis Time Period		AM		Analysis Year		2026 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 3100 ft $V_D =$ 370 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	5400	0.92	Level	2	0	0.990	1.00	5928	
Ramp	1010	0.92	Level	2	0	0.990	1.00	1109	
UpStream									
DownStream	370	0.93	Level	3	0	0.985	1.00	404	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.561 using Equation (Exhibit 25-12) $V_{12} =$ 3811 pc/h V_3 or V_{av34} 2117 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	5928	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	4819	Exhibit 25-14	6780	No	
				V_R	1109	Exhibit 25-3	2100	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	3811	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 32.8 (pc/mi/ln) $LOS =$ D (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.463 (Exhibit 25-19) $S_R =$ 49.5 mph (Exhibit 25-19) $S_0 =$ 57.1 mph (Exhibit 25-19) $S =$ 52.0 mph (Exhibit 25-15)				


RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB			Freeway/Dir of Travel		Southbound I-87		
Agency or Company		CHA			Junction		Exit 4 SB On-Ramp		
Date Performed		9/08/2011			Jurisdiction		NYSDOT		
Analysis Time Period		AM			Analysis Year		2026 No-Build		
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{up} = 2035$ ft $V_u = 370$ veh/h		Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)					Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4750	0.92	Level	2	0	0.990	1.00	5215	
Ramp	510	0.93	Level	5	0	0.976	1.00	562	
UpStream	370	0.93	Level	3	0	0.985	1.00	404	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} = 0.603$ using Equation (Exhibit 25-5) $V_{12} = 3143$ pc/h V_3 or $V_{av34} = 2072$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	5777	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	3705	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 28.5$ (pc/mi/ln) LOS = D (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.408$ (Exhibit 25-19) $S_R = 50.3$ mph (Exhibit 25-19) $S_0 = 50.3$ mph (Exhibit 25-19) $S = 50.3$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 5 SB On-Ramp			
Date Performed		9/08/2011		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2026 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 2035 ft $V_D =$ 510 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4450	0.92	Level	2	0	0.990	1.00	4885	
Ramp	370	0.93	Level	3	0	0.985	1.00	404	
UpStream									
DownStream	510	0.93	Level	5	0	0.976	1.00	562	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} = 0.603$ using Equation (Exhibit 25-5) $V_{12} = 2944$ pc/h V_3 or $V_{av34} = 1941$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	5289	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	3348	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 25.8$ (pc/mi/ln) LOS = C (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.360$ (Exhibit 25-19) $S_R = 51.0$ mph (Exhibit 25-19) $S_0 = 50.8$ mph (Exhibit 25-19) $S = 50.9$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 9/08/2011 Analysis Time Period AM					Freeway/Dir of Travel I-87 Northbound Weaving Seg Location Exit 2E on to 2W off Jurisdiction NYSDOT Analysis Year 2026 No-Build				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 815 Terrain Level					Weaving type A Volume ratio, VR 0.29 Weaving ratio, R 0.31				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	2350	0.92	2	0	1.5	1.2	0.990	1.00	2579
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	680	0.92	2	0	1.5	1.2	0.990	1.00	746
V_{w2}	300	0.92	2	0	1.5	1.2	0.990	1.00	329
V_w				1075	V_{nw}				2579
V									3654
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (i = nw)		
a (Exhibit 24-6)					0.35		0.0020		
b (Exhibit 24-6)					2.20		4.00		
c (Exhibit 24-6)					0.97		1.30		
d (Exhibit 24-6)					0.80		0.75		
Weaving intensity factor, W_i					2.15		0.26		
Weaving and non-weaving speeds, S_i (mi/h)					29.58		51.51		
Number of lanes required for unconstrained operation, N_w 1.42									
Maximum number of lanes, N_w (max) 1.40									
<input type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input checked="" type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					42.29				
Weaving segment density, D (pc/mi/ln)					21.60				
Level of service, LOS					C				
Capacity of base condition, c_b (pc/h)					6221				
Capacity as a 15-minute flow rate, c (veh/h)					6159				
Capacity as a full-hour volume, c_h (veh/h)					5666				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 9/08/2011 Analysis Time Period AM					Freeway/Dir of Travel I-87 Southbound Weaving Seg Location Exit 2W on to 2E off Jurisdiction NYSDOT Analysis Year 2026 No-Build				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 810 Terrain Level					Weaving type A Volume ratio, VR 0.23 Weaving ratio, R 0.32				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	3750	0.92	2	0	1.5	1.2	0.990	1.00	4116
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	750	0.92	2	0	1.5	1.2	0.990	1.00	823
V_{w2}	360	0.92	2	0	1.5	1.2	0.990	1.00	395
V_w				1218	V_{nw}				4116
V									5334
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (i = nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	1.19		0.61						
Weaving and non-weaving speeds, S_i (mi/h)	35.97		43.64						
Number of lanes required for unconstrained operation, N_w					1.27				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					41.61				
Weaving segment density, D (pc/mi/ln)					32.04				
Level of service, LOS					D				
Capacity of base condition, c_b (pc/h)					6578				
Capacity as a 15-minute flow rate, c (veh/h)					6513				
Capacity as a full-hour volume, c_h (veh/h)					5992				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *6/22/2011*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 2 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 No-Build*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *3000* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or DDHV}) / (PHF \times N \times f_{HV} \times f_p)$ *1098* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *19.6* pc/mi/ln
 LOS *C*

Design (N)

Design (N)

Design LOS
 $v_p = (V \text{ or DDHV}) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume.

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *6/22/2011*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 to Exit 2*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 No-Build*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5300* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1939* pc/h/ln
 S *55.4* mi/h
 $D = v_p / S$ *35.0* pc/mi/ln
 LOS *D*

Design (N)

Design (N)

Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *9/09/2011*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYS DOT*
 Analysis Year *2036 No-Build*

Project Description *Exit 4*

☒ Oper. (LOS)

☐ Des. (N)

☐ Planning Data

Flow Inputs

Volume, V *2200* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day % Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K % RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1 + P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *805* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *14.4* pc/mi/ln
 LOS *B*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst **SEB**
 Agency or Company **CHA**
 Date Performed **12/09/2011**
 Analysis Time Period **AM**

Site Information

Highway/Direction of Travel **Southbound I-87**
 From/To **Exit 5 on to Exit 4 on**
 Jurisdiction **NYSDOT**
 Analysis Year **2036 No-Build**

Project Description **Exit 4**

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V **4800** veh/h Peak-Hour Factor, PHF **0.92**
 AADT veh/day %Trucks and Buses, P_T **2**
 Peak-Hr Prop. of AADT, K %RVs, P_R **0**
 Peak-Hr Direction Prop, D General Terrain: **Level**
 DDHV = AADT x K x D veh/h Grade % Length **mi**
 Driver type adjustment **1.00** Up/Down %

Calculate Flow Adjustments

f_p **1.00** E_R **1.2**
 E_T **1.5** $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ **0.990**

Speed Inputs

Lane Width **12.0** ft
 Rt-Shoulder Lat. Clearance **6.0** ft
 Interchange Density **0.50** l/mi
 Number of Lanes, N **3**
 FFS (measured) **56.0** mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS **56.0** mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ **1757** pc/h/ln
 S **56.0** mi/h
 $D = v_p / S$ **31.4** pc/mi/ln
 LOS **D**

Design (N)

Design (N)

Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *6/22/2011*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 to Exit 5*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 No-Build*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2800* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.92*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1 + P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1025* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *18.3* pc/mi/ln
 LOS *C*

Design (N)

Design (N)

Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst **SEB**
 Agency or Company **CHA**
 Date Performed **6/22/2011**
 Analysis Time Period **AM**

Site Information

Highway/Direction of Travel **Southbound I-87**
 From/To **Exit 5 to Exit 4**
 Jurisdiction **NYS DOT**
 Analysis Year **2036 No-Build**

Project Description **Exit 4**

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V **4550** veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment **1.00**
 Peak-Hour Factor, PHF **0.92**
 %Trucks and Buses, P_T **2**
 %RVs, P_R **0**
 General Terrain: **Level**
 Grade % Length **mi**
 Up/Down %

Calculate Flow Adjustments

f_p **1.00**
 E_T **1.5**
 E_R **1.2**
 $f_{HV} = 1/[1 + P_T(E_T - 1) + P_R(E_R - 1)]$ **0.990**

Speed Inputs

Lane Width **12.0** ft
 Rt-Shoulder Lat. Clearance **6.0** ft
 Interchange Density **0.50** l/mi
 Number of Lanes, N **3**
 FFS (measured) **56.0** mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS **56.0** mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ **1665** pc/h/ln
 S **56.0** mi/h
 $D = v_p / S$ **29.7** pc/mi/ln
 LOS **D**

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *6/22/2011*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 5 to Exit 6*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 No-Build*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2600* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *4*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *714* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *12.8* pc/mi/ln
 LOS *B*

Design (N)

Design (N)

Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *6/22/2011*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 6 to Exit 5*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 No-Build*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *6050* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *4*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1660* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *29.6* pc/mi/ln
 LOS *D*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB			Freeway/Dir of Travel		Northbound I-87		
Agency or Company		CHA			Junction		Exit 2W On-Ramp		
Date Performed		9/08/2011			Jurisdiction		NYSDOT		
Analysis Time Period		AM			Analysis Year		2036 No-Build		
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1100$ ft $V_u = 700$ veh/h		Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)					Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2600	0.92	Level	2	0	0.990	1.00	2854	
Ramp	380	0.92	Level	2	0	0.990	1.00	417	
UpStream	700	0.92	Level	2	0	0.990	1.00	768	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 767.19$ (Equation 25-2 or 25-3) $P_{FM} = 0.601$ using Equation (Exhibit 25-5) $V_{12} = 1716$ pc/h V_3 or $V_{av34} = 1138$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	3271	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	2133	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 16.6$ (pc/mi/ln) LOS = B (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.286$ (Exhibit 25-19) $S_R = 52.0$ mph (Exhibit 25-19) $S_0 = 53.7$ mph (Exhibit 25-19) $S = 52.6$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 4 NB Off			
Date Performed		9/08/2011		Jurisdiction		NYS DOT			
Analysis Time Period		AM		Analysis Year		2036 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 2660 ft $V_D =$ 640 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	3000	0.92	Level	2	0	0.990	1.00	3293	
Ramp	800	0.82	Level	2	0	0.990	1.00	985	
UpStream									
DownStream	640	0.92	Level	2	0	0.990	1.00	703	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.632 using Equation (Exhibit 25-12) $V_{12} =$ 2444 pc/h V_3 or V_{av34} 849 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	3293	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	2308	Exhibit 25-14	6780	No	
				V_R	985	Exhibit 25-3	2100	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	2444	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 22.1 (pc/mi/ln) $LOS =$ C (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.452 (Exhibit 25-19) $S_R =$ 49.7 mph (Exhibit 25-19) $S_0 =$ 61.4 mph (Exhibit 25-19) $S =$ 52.3 mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 4 NB On-Ramp			
Date Performed		9/08/2011		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2036 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{down} =$ 3500 ft $V_D =$ 480 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2200	0.92	Level	2	0	0.990	1.00	2415	
Ramp	640	0.92	Level	2	0	0.990	1.00	703	
UpStream									
DownStream	480	0.96	Level	2	0	0.990	1.00	505	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 2452.65$ (Equation 25-2 or 25-3) $P_{FM} = 0.603$ using Equation (Exhibit 25-5) $V_{12} = 1456$ pc/h V_3 or $V_{av34} = 959$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	3118	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	2159	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 16.3$ (pc/mi/ln) LOS = B (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.283$ (Exhibit 25-19) $S_R = 52.0$ mph (Exhibit 25-19) $S_0 = 54.3$ mph (Exhibit 25-19) $S = 52.7$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 5 NB Off			
Date Performed		9/08/2011		Jurisdiction		NYS DOT			
Analysis Time Period		AM		Analysis Year		2036 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{up} = 3500$ ft $V_u = 640$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 35.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2800	0.92	Level	2	0	0.990	1.00	3074	
Ramp	480	0.96	Level	2	0	0.990	1.00	505	
UpStream	640	0.92	Level	2	0	0.990	1.00	703	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} = 6803.97$ (Equation 25-8 or 25-9) $P_{FD} = 0.718$ using Equation (Exhibit 25-12) $V_{12} = 2351$ pc/h V_3 or $V_{av34} = 723$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	3074	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	2569	Exhibit 25-14	6780	No	
				V_R	505	Exhibit 25-3	2000	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	2351	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 22.2$ (pc/mi/ln) $LOS = C$ (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.473$ (Exhibit 25-19) $S_R = 49.4$ mph (Exhibit 25-19) $S_0 = 61.4$ mph (Exhibit 25-19) $S = 51.8$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB			Freeway/Dir of Travel		Southbound		
Agency or Company		CHA			Junction		Exit 2W Off		
Date Performed		9/08/2011			Jurisdiction		NYS DOT		
Analysis Time Period		AM			Analysis Year		2036 No-Build		
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h		Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)					Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1300 ft $V_D =$ 360 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	5300	0.92	Level	2	0	0.990	1.00	5818	
Ramp	760	0.92	Level	2	0	0.990	1.00	834	
UpStream									
DownStream	360	0.92	Level	2	0	0.990	1.00	395	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.576 using Equation (Exhibit 25-12) $V_{12} =$ 3706 pc/h V_3 or V_{av34} 2112 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	5818	Exhibit 25-14	6780	No
					$V_{FO} = V_F - V_R$	4984	Exhibit 25-14	6780	No
					V_R	834	Exhibit 25-3	2100	No
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	3706	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 33.4 (pc/mi/ln) $LOS =$ D (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.438 (Exhibit 25-19) $S_R =$ 49.9 mph (Exhibit 25-19) $S_0 =$ 57.1 mph (Exhibit 25-19) $S =$ 52.3 mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET											
General Information					Site Information						
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87					
Agency or Company		CHA		Junction		Exit 4 SB Off					
Date Performed		9/08/2011		Jurisdiction		NYSDOT					
Analysis Time Period		AM		Analysis Year		2036 No-Build					
Project Description Exit 4											
Inputs											
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 3100 ft $V_D =$ 400 veh/h				
Conversion to pc/h Under Base Conditions											
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$			
Freeway	5400	0.92	Level	2	0	0.990	1.00	5928			
Ramp	1020	0.92	Level	2	0	0.990	1.00	1120			
UpStream											
DownStream	400	0.93	Level	3	0	0.985	1.00	437			
Merge Areas					Diverge Areas						
Estimation of v_{12}					Estimation of v_{12}						
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ $P_{FD} = 0.560$ using Equation (Exhibit 25-12) $V_{12} = 3814$ pc/h V_3 or V_{av34} 2114 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)						
Capacity Checks					Capacity Checks						
		Actual	Capacity		LOS F?						
V_{FO}							V_F	5928	Exhibit 25-14	6780	No
			Exhibit 25-7				$V_{FO} = V_F - V_R$	4808	Exhibit 25-14	6780	No
							V_R	1120	Exhibit 25-3	2100	No
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area						
		Actual	Max Desirable		Violation?						
V_{R12}			Exhibit 25-7				V_{12}	3814	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)						
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 32.8$ (pc/mi/ln) $LOS = D$ (Exhibit 25-4)						
Speed Determination					Speed Determination						
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.464$ (Exhibit 25-19) $S_R = 49.5$ mph (Exhibit 25-19) $S_0 = 57.1$ mph (Exhibit 25-19) $S = 52.0$ mph (Exhibit 25-15)						


RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 4 SB On-Ramp			
Date Performed		9/08/2011		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2036 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{up} = 2035$ ft $V_u = 400$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4800	0.92	Level	2	0	0.990	1.00	5270	
Ramp	490	0.93	Level	5	0	0.976	1.00	540	
UpStream	400	0.93	Level	3	0	0.985	1.00	437	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} = 0.603$ using Equation (Exhibit 25-5) $V_{12} = 3176$ pc/h V_3 or $V_{av34} = 2094$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	5810	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	3716	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 28.6$ (pc/mi/ln) LOS = D (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.409$ (Exhibit 25-19) $S_R = 50.3$ mph (Exhibit 25-19) $S_0 = 50.3$ mph (Exhibit 25-19) $S = 50.3$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 5 SB On-Ramp			
Date Performed		9/08/2011		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2036 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 2035 ft $V_D =$ 490 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4550	0.92	Level	2	0	0.990	1.00	4995	
Ramp	400	0.93	Level	3	0	0.985	1.00	437	
UpStream									
DownStream	490	0.93	Level	5	0	0.976	1.00	540	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} = 0.603$ using Equation (Exhibit 25-5) $V_{12} = 3010$ pc/h V_3 or $V_{av34} = 1985$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	5432	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	3447	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 26.5$ (pc/mi/ln) LOS = C (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.371$ (Exhibit 25-19) $S_R = 50.8$ mph (Exhibit 25-19) $S_0 = 50.7$ mph (Exhibit 25-19) $S = 50.7$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 9/08/2011 Analysis Time Period AM					Freeway/Dir of Travel I-87 Northbound Weaving Seg Location Exit 2E on to 2W off Jurisdiction NYSDOT Analysis Year 2036 No-Build				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 815 Terrain Level					Weaving type A Volume ratio, VR 0.31 Weaving ratio, R 0.31				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	2290	0.92	2	0	1.5	1.2	0.990	1.00	2514
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	700	0.92	2	0	1.5	1.2	0.990	1.00	768
V_{w2}	310	0.92	2	0	1.5	1.2	0.990	1.00	340
V_w				1108	V_{nw}				2514
V									3622
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)					0.35		0.0020		
b (Exhibit 24-6)					2.20		4.00		
c (Exhibit 24-6)					0.97		1.30		
d (Exhibit 24-6)					0.80		0.75		
Weaving intensity factor, W_i					2.18		0.27		
Weaving and non-weaving speeds, S_i (mi/h)					29.47		51.33		
Number of lanes required for unconstrained operation, N_w					1.46				
Maximum number of lanes, N_w (max)					1.40				
<input type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input checked="" type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					41.83				
Weaving segment density, D (pc/mi/ln)					21.64				
Level of service, LOS					C				
Capacity of base condition, c_b (pc/h)					6154				
Capacity as a 15-minute flow rate, c (veh/h)					6093				
Capacity as a full-hour volume, c_h (veh/h)					5606				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 9/08/2011 Analysis Time Period AM					Freeway/Dir of Travel I-87 Southbound Weaving Seg Location Exit 2W on to 2E off Jurisdiction NYSDOT Analysis Year 2036 No-Build				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 810 Terrain Level					Weaving type A Volume ratio, VR 0.24 Weaving ratio, R 0.31				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	3740	0.92	2	0	1.5	1.2	0.990	1.00	4105
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	810	0.92	2	0	1.5	1.2	0.990	1.00	889
V_{w2}	360	0.92	2	0	1.5	1.2	0.990	1.00	395
V_w				1284	V_{nw}				4105
V									5389
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	1.23		0.63						
Weaving and non-weaving speeds, S_i (mi/h)	35.65		43.15						
Number of lanes required for unconstrained operation, N_w					1.31				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					41.09				
Weaving segment density, D (pc/mi/ln)					32.79				
Level of service, LOS					D				
Capacity of base condition, c_b (pc/h)					6524				
Capacity as a 15-minute flow rate, c (veh/h)					6459				
Capacity as a full-hour volume, c_h (veh/h)					5942				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *12/13/2011*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2046 No-Build*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2100* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *768* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *13.7* pc/mi/ln
 LOS *B*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *12/13/2011*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 5 on to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2046 No-Build*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *4800* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1757* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *31.4* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *6/22/2011*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 2 to Exit 4*
 Jurisdiction *NYS DOT*
 Analysis Year *2016 No-Build*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5100* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.86*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T-1)+P_R(E_R-1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1997* pc/h/ln
 S *55.0* mi/h
 D = v_p / S *36.3* pc/mi/ln
 LOS *E*

Design (N)

Design (N)

Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p pc/h
 S mi/h
 D = v_p / S pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *6/22/2011*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 to Exit 2*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 No-Build*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *3850* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1409* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *25.2* pc/mi/ln
 LOS *C*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 $S = v_p / D$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst **SEB**
 Agency or Company **CHA**
 Date Performed **9/09/2011**
 Analysis Time Period **PM**

Site Information

Highway/Direction of Travel **Northbound I-87**
 From/To **Exit 4 off to Exit 4 on**
 Jurisdiction **NYS DOT**
 Analysis Year **2016 No-Build**

Project Description **Exit 4**

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V **4500** veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D
 Driver type adjustment **1.00** veh/h
 Peak-Hour Factor, PHF **0.86**
 %Trucks and Buses, P_T **2**
 %RVs, P_R **0**
 General Terrain: **Level**
 Grade % Length **mi**
 Up/Down %

Calculate Flow Adjustments

f_p **1.00**
 E_T **1.5**
 E_R **1.2**
 $f_{HV} = 1/[1 + P_T(E_T - 1) + P_R(E_R - 1)]$ **0.990**

Speed Inputs

Lane Width **12.0** ft
 Rt-Shoulder Lat. Clearance **6.0** ft
 Interchange Density **0.50** l/mi
 Number of Lanes, N **3**
 FFS (measured) **56.0** mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS **56.0** mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ **1762** pc/h/ln
 S **56.0** mi/h
 $D = v_p / S$ **31.5** pc/mi/ln
 LOS **D**

Design (N)

Design (N)

Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst: **SEB**
 Agency or Company: **CHA**
 Date Performed: **12/09/2011**
 Analysis Time Period: **PM**

Site Information

Highway/Direction of Travel: **Southbound I-87**
 From/To: **Exit 5 on to Exit 4 on**
 Jurisdiction: **NYSDOT**
 Analysis Year: **2016 No-Build**

Project Description: **Exit 4**

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V	2800	veh/h	Peak-Hour Factor, PHF	0.92
AADT		veh/day	%Trucks and Buses, P_T	2
Peak-Hr Prop. of AADT, K			%RVs, P_R	0
Peak-Hr Direction Prop, D			General Terrain:	Level
DDHV = AADT x K x D		veh/h	Grade %	Length mi
Driver type adjustment	1.00		Up/Down %	

Calculate Flow Adjustments

f_p	1.00	E_R	1.2
E_T	1.5	$f_{HV} = 1/[1 + P_T(E_T - 1) + P_R(E_R - 1)]$	0.990

Speed Inputs

Lane Width	12.0	ft
Rt-Shoulder Lat. Clearance	6.0	ft
Interchange Density	0.50	l/mi
Number of Lanes, N	3	
FFS (measured)	56.0	mi/h
Base free-flow Speed, BFFS		mi/h

Calc Speed Adj and FFS

f_{LW}	mi/h
f_{LC}	mi/h
f_{ID}	mi/h
f_N	mi/h
FFS	56.0 mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$	1025	pc/h/ln
S	56.0	mi/h
$D = v_p / S$	18.3	pc/mi/ln
LOS	C	

Design (N)

Design (N)

Design LOS	
$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$	pc/h
f_p	
S	mi/h
$D = v_p / S$	pc/mi/ln
Required Number of Lanes, N	


Glossary

N - Number of lanes	S - Speed
V - Hourly volume	D - Density
v_p - Flow rate	FFS - Free-flow speed
LOS - Level of service	BFFS - Base free-flow speed
DDHV - Directional design hour volume	

Factor Location

E_R - Exhibits 23-8, 23-10	f_{LW} - Exhibit 23-4
E_T - Exhibits 23-8, 23-10, 23-11	f_{LC} - Exhibit 23-5
f_p - Page 23-12	f_N - Exhibit 23-6
LOS, S, FFS, v_p - Exhibits 23-2, 23-3	f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst: SEB
 Agency or Company: CHA
 Date Performed: 6/22/2011
 Analysis Time Period: PM

Site Information

Highway/Direction of Travel: Northbound I-87
 From/To: Exit 4 to Exit 5
 Jurisdiction: NYSDOT
 Analysis Year: 2016 No-Build

Project Description: Exit 4

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V: 5900 veh/h
 AADT: veh/day
 Peak-Hr Prop. of AADT, K:
 Peak-Hr Direction Prop, D:
 DDHV = AADT x K x D: veh/h
 Driver type adjustment: 1.00
 Peak-Hour Factor, PHF: 0.86
 %Trucks and Buses, P_T : 2
 %RVs, P_R : 0
 General Terrain: Level
 Grade % Length: mi
 Up/Down %

Calculate Flow Adjustments

f_p : 1.00
 E_T : 1.5
 E_R : 1.2
 $f_{HV} = 1/[1 + P_T(E_T - 1) + P_R(E_R - 1)]$: 0.990

Speed Inputs

Lane Width: 12.0 ft
 Rt-Shoulder Lat. Clearance: 6.0 ft
 Interchange Density: 0.50 l/mi
 Number of Lanes, N: 3
 FFS (measured): 56.0 mi/h
 Base free-flow Speed, BFFS: mi/h

Calc Speed Adj and FFS

f_{LW} : mi/h
 f_{LC} : mi/h
 f_{ID} : mi/h
 f_N : mi/h
 FFS: 56.0 mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$: 2310 pc/h/ln
 S : mi/h
 $D = v_p / S$: pc/mi/ln
 LOS: F

Design (N)

Design (N)

Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$: pc/h
 S : mi/h
 $D = v_p / S$: pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *6/22/2011*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 5 to Exit 4*
 Jurisdiction *NYS DOT*
 Analysis Year *2016 No-Build*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2550* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D
 Driver type adjustment *1.00* veh/h
 Peak-Hour Factor, PHF *0.92*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1 + P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *933* pc/h/ln
 S *56.0* mi/h
 D = v_p / S *16.7* pc/mi/ln
 LOS *B*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 D = v_p / S pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst **SEB**
 Agency or Company **CHA**
 Date Performed **6/22/2011**
 Analysis Time Period **PM**

Site Information

Highway/Direction of Travel **Northbound I-87**
 From/To **Exit 5 to Exit 6**
 Jurisdiction **NYS DOT**
 Analysis Year **2016 No-Build**

Project Description **Exit 4**

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V **6100** veh/h
 AADT **6100** veh/day
 Peak-Hr Prop. of AADT, K **0.86**
 Peak-Hr Direction Prop, D **0.86**
 DDHV = AADT x K x D **4500** veh/h
 Driver type adjustment **1.00**
 Peak-Hour Factor, PHF **0.86**
 %Trucks and Buses, P_T **2**
 %RVs, P_R **0**
 General Terrain: **Level**
 Grade % **0** Length **mi**
 Up/Down % **0**

Calculate Flow Adjustments

f_p **1.00**
 E_T **1.5**
 E_R **1.2**
 $f_{HV} = 1/[1 + P_T(E_T - 1) + P_R(E_R - 1)]$ **0.990**

Speed Inputs

Lane Width **12.0** ft
 Rt-Shoulder Lat. Clearance **6.0** ft
 Interchange Density **0.50** l/mi
 Number of Lanes, N **4**
 FFS (measured) **56.0** mi/h
 Base free-flow Speed, BFFS **56.0** mi/h

Calc Speed Adj and FFS

f_{LW} **0.95** mi/h
 f_{LC} **0.95** mi/h
 f_{ID} **0.95** mi/h
 f_N **0.95** mi/h
 FFS **56.0** mi/h

LOS and Performance Measures

Operational (LOS)
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ **1791** pc/h/ln
 S **56.0** mi/h
 $D = v_p / S$ **32.0** pc/mi/ln
 LOS **D**

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ **1791** pc/h
 f_p **0.95**
 S **56.0** mi/h
 $D = v_p / S$ **32.0** pc/mi/ln
 Required Number of Lanes, N **4**


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst **SEB**
 Agency or Company **CHA**
 Date Performed **6/22/2011**
 Analysis Time Period **PM**

Site Information

Highway/Direction of Travel **Southbound I-87**
 From/To **Exit 6 to Exit 5**
 Jurisdiction **NYS DOT**
 Analysis Year **2016 No-Build**

Project Description **Exit 4**

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V **3450** veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D
 Driver type adjustment **1.00** veh/h
 Peak-Hour Factor, PHF **0.92**
 %Trucks and Buses, P_T **2**
 %RVs, P_R **0**
 General Terrain: **Level**
 Grade % Length **mi**
 Up/Down %

Calculate Flow Adjustments

f_p **1.00**
 E_T **1.5**
 E_R **1.2**
 $f_{HV} = 1/[1 + P_T(E_T - 1) + P_R(E_R - 1)]$ **0.990**

Speed Inputs

Lane Width **12.0** ft
 Rt-Shoulder Lat. Clearance **6.0** ft
 Interchange Density **0.50** l/mi
 Number of Lanes, N **4**
 FFS (measured) **56.0** mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS **56.0** mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ **947** pc/h/ln
 S **56.0** mi/h
 $D = v_p / S$ **16.9** pc/mi/ln
 LOS **B**

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 2W On-Ramp			
Date Performed		9/08/2011		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2016 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1100$ ft $V_u = 900$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4400	0.86	Level	2	0	0.990	1.00	5167	
Ramp	730	0.92	Level	2	0	0.990	1.00	801	
UpStream	900	0.92	Level	2	0	0.990	1.00	988	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 1344.35$ (Equation 25-2 or 25-3) $P_{FM} = 0.586$ using Equation (Exhibit 25-5) $V_{12} = 3027$ pc/h V_3 or $V_{av34} = 2140$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	5968	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	3828	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 29.6$ (pc/mi/ln) LOS = D (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.432$ (Exhibit 25-19) $S_R = 49.9$ mph (Exhibit 25-19) $S_0 = 50.1$ mph (Exhibit 25-19) $S = 50.0$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET														
General Information					Site Information									
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87								
Agency or Company		CHA		Junction		Exit 4 NB Off								
Date Performed		9/08/2011		Jurisdiction		NYSDOT								
Analysis Time Period		PM		Analysis Year		2016 No-Build								
Project Description Exit 4														
Inputs														
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 2660 ft $V_D =$ 1430 veh/h							
Conversion to pc/h Under Base Conditions														
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$						
Freeway	5100	0.86	Level	2	0	0.990	1.00	5990						
Ramp	620	0.86	Level	2	0	0.990	1.00	728						
UpStream														
DownStream	1430	0.88	Level	1	0	0.995	1.00	1633						
Merge Areas					Diverge Areas									
Estimation of v_{12}					Estimation of v_{12}									
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.577 using Equation (Exhibit 25-12) $V_{12} =$ 3763 pc/h V_3 or V_{av34} 2227 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)									
Capacity Checks					Capacity Checks									
		Actual	Capacity		LOS F?									
V_{FO}		Exhibit 25-7					V_F	5990	Exhibit 25-14	6780	No			
							$V_{FO} = V_F - V_R$	5262	Exhibit 25-14	6780	No			
							V_R	728	Exhibit 25-3	2100	No			
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area									
		Actual	Max Desirable		Violation?				Actual	Max Desirable		Violation?		
V_{R12}			Exhibit 25-7						V_{12}	3763	Exhibit 25-14		4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)									
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 33.5 (pc/mi/ln) $LOS =$ D (Exhibit 25-4)									
Speed Determination					Speed Determination									
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.429 (Exhibit 25-19) $S_R =$ 50.0 mph (Exhibit 25-19) $S_0 =$ 56.6 mph (Exhibit 25-19) $S =$ 52.3 mph (Exhibit 25-15)									

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 4 NB On-Ramp			
Date Performed		9/08/2011		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2016 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{down} =$ 3500 ft $V_D =$ 440 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4500	0.86	Level	2	0	0.990	1.00	5285	
Ramp	1430	0.88	Level	1	0	0.995	1.00	1633	
UpStream									
DownStream	440	0.92	Level	3	0	0.985	1.00	485	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 2355.51$ (Equation 25-2 or 25-3) $P_{FM} = 0.603$ using Equation (Exhibit 25-5) $V_{12} = 3185$ pc/h V_3 or $V_{av34} = 2100$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	6918	Exhibit 25-7		Yes	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	4818	Exhibit 25-7	4600:All	Yes	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 36.7$ (pc/mi/ln) LOS = F (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.731$ (Exhibit 25-19) $S_R = 45.8$ mph (Exhibit 25-19) $S_0 = 50.2$ mph (Exhibit 25-19) $S = 47.0$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 5 NB Off			
Date Performed		9/08/2011		Jurisdiction		NYS DOT			
Analysis Time Period		PM		Analysis Year		2016 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{up} = 3500$ ft $V_u = 1430$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 35.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_P)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	5900	0.86	Level	2	0	0.990	1.00	6929	
Ramp	440	0.92	Level	3	0	0.985	1.00	485	
UpStream	1430	0.88	Level	1	0	0.995	1.00	1633	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} = 8438.97$ (Equation 25-8 or 25-9) $P_{FD} = 0.729$ using Equation (Exhibit 25-12) $V_{12} = 5180$ pc/h V_3 or $V_{av34} 1749$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	6929	Exhibit 25-14	6780	Yes
				$V_{FO} = V_F - V_R$	6444	Exhibit 25-14	6780	No	
				V_R	485	Exhibit 25-3	2000	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	5180	Exhibit 25-14	4400:All	Yes
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 46.6$ (pc/mi/ln) $LOS = F$ (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.472$ (Exhibit 25-19) $S_R = 49.4$ mph (Exhibit 25-19) $S_0 = 58.5$ mph (Exhibit 25-19) $S = 51.4$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound			
Agency or Company		CHA		Junction		Exit 2W Off			
Date Performed		9/08/2011		Jurisdiction		NYS DOT			
Analysis Time Period		PM		Analysis Year		2016 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1300 ft $V_D =$ 800 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	3850	0.92	Level	2	0	0.990	1.00	4227	
Ramp	500	0.92	Level	2	0	0.990	1.00	549	
UpStream									
DownStream	800	0.92	Level	2	0	0.990	1.00	878	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.629 using Equation (Exhibit 25-12) $V_{12} =$ 2863 pc/h V_3 or V_{av34} 1364 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	4227	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	3678	Exhibit 25-14	6780	No	
				V_R	549	Exhibit 25-3	2100	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	2863	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 26.2 (pc/mi/ln) $LOS =$ C (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.412 (Exhibit 25-19) $S_R =$ 50.2 mph (Exhibit 25-19) $S_0 =$ 60.0 mph (Exhibit 25-19) $S =$ 53.0 mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 4 SB Off			
Date Performed		9/08/2011		Jurisdiction		NYS DOT			
Analysis Time Period		PM		Analysis Year		2016 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 3100 ft $V_D =$ 440 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2800	0.92	Level	2	0	0.990	1.00	3074	
Ramp	640	0.92	Level	2	0	0.990	1.00	703	
UpStream									
DownStream	440	0.87	Level	1	0	0.995	1.00	508	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ using Equation (Exhibit 25-5) $P_{FM} =$ pc/h $V_{12} =$ pc/h (Equation 25-4 or 25-5) V_3 or V_{av34} pc/h Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ using Equation (Exhibit 25-12) $P_{FD} =$ 0.651 $V_{12} =$ 2246 pc/h V_3 or V_{av34} 828 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	3074	Exhibit 25-14	6780	No
					$V_{FO} = V_F - V_R$	2371	Exhibit 25-14	6780	No
					V_R	703	Exhibit 25-3	2100	No
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	2246	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 19.3 (pc/mi/ln) $LOS =$ B (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.426 (Exhibit 25-19) $S_R =$ 50.0 mph (Exhibit 25-19) $S_0 =$ 61.4 mph (Exhibit 25-19) $S =$ 52.7 mph (Exhibit 25-15)				


RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 4 SB On-Ramp			
Date Performed		9/08/2011		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2016 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{up} = 2035$ ft $V_u = 440$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2800	0.92	Level	2	0	0.990	1.00	3074	
Ramp	1050	0.93	Level	4	0	0.980	1.00	1152	
UpStream	440	0.87	Level	1	0	0.995	1.00	508	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} = 0.603$ using Equation (Exhibit 25-5) $V_{12} = 1853$ pc/h V_3 or $V_{av34} = 1221$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	4226	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	3005	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 22.7$ (pc/mi/ln) LOS = C (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.328$ (Exhibit 25-19) $S_R = 51.4$ mph (Exhibit 25-19) $S_0 = 53.4$ mph (Exhibit 25-19) $S = 52.0$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 5 SB On-Ramp			
Date Performed		9/08/2011		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2016 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 2035 ft $V_D =$ 1050 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2550	0.92	Level	2	0	0.990	1.00	2799	
Ramp	440	0.87	Level	1	0	0.995	1.00	508	
UpStream									
DownStream	1050	0.93	Level	4	0	0.980	1.00	1152	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} = 0.603$ using Equation (Exhibit 25-5) $V_{12} = 1687$ pc/h V_3 or $V_{av34} = 1112$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	3307	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	2195	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 16.7$ (pc/mi/ln) LOS = B (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.284$ (Exhibit 25-19) $S_R = 52.0$ mph (Exhibit 25-19) $S_0 = 53.8$ mph (Exhibit 25-19) $S = 52.6$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 9/08/2011 Analysis Time Period PM					Freeway/Dir of Travel I-87 Northbound Weaving Seg Location Exit 2E on to 2W off Jurisdiction NYSDOT Analysis Year 2016 No-Build				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 815 Terrain Level					Weaving type A Volume ratio, VR 0.25 Weaving ratio, R 0.34				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	3930	0.86	2	0	1.5	1.2	0.990	1.00	4615
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	900	0.92	2	0	1.5	1.2	0.990	1.00	988
V_{w2}	470	0.92	2	0	1.5	1.2	0.990	1.00	515
V_w				1503	V_{nw}				4615
V									6118
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	1.40		0.76						
Weaving and non-weaving speeds, S_i (mi/h)	34.17		41.10						
Number of lanes required for unconstrained operation, N_w					1.36				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					39.15				
Weaving segment density, D (pc/mi/ln)					39.07				
Level of service, LOS					E				
Capacity of base condition, c_b (pc/h)					6490				
Capacity as a 15-minute flow rate, c (veh/h)					6426				
Capacity as a full-hour volume, c_h (veh/h)					5626				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 6/22/2011 Analysis Time Period PM					Freeway/Dir of Travel I-87 Southbound Weaving Seg Location Exit 2W on to 2E off Jurisdiction NYSDOT Analysis Year 2016 No-Build				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 810 Terrain Level					Weaving type A Volume ratio, VR 0.26 Weaving ratio, R 0.25				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	3080	0.92	2	0	1.5	1.2	0.990	1.00	3381
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	800	0.92	2	0	1.5	1.2	0.990	1.00	878
V_{w2}	270	0.92	2	0	1.5	1.2	0.990	1.00	296
V_w				1174	V_{nw}				3381
V									4555
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	1.08		0.54						
Weaving and non-weaving speeds, S_i (mi/h)	37.12		44.82						
Number of lanes required for unconstrained operation, N_w					1.34				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					42.55				
Weaving segment density, D (pc/mi/ln)					26.76				
Level of service, LOS					C				
Capacity of base condition, c_b (pc/h)					6416				
Capacity as a 15-minute flow rate, c (veh/h)					6352				
Capacity as a full-hour volume, c_h (veh/h)					5844				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *6/22/2011*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 2 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 No-Build*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5150* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*

Peak-Hour Factor, PHF *0.86*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *2016* pc/h/ln
 S *54.8* mi/h
 $D = v_p / S$ *36.8* pc/mi/ln
 LOS *E*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume


S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3

f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst **SEB**
 Agency or Company **CHA**
 Date Performed **6/22/2011**
 Analysis Time Period **PM**

Site Information

Highway/Direction of Travel **Southbound I-87**
 From/To **Exit 4 to Exit 2**
 Jurisdiction **NYSDOT**
 Analysis Year **2026 No-Build**

Project Description **Exit 4**

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V **3950** veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment **1.00**
 Peak-Hour Factor, PHF **0.92**
 %Trucks and Buses, P_T **2**
 %RVs, P_R **0**
 General Terrain: **Level**
 Grade % Length **mi**
 Up/Down %

Calculate Flow Adjustments

f_p **1.00**
 E_T **1.5**
 E_R **1.2**
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ **0.990**

Speed Inputs

Lane Width **12.0** ft
 Rt-Shoulder Lat. Clearance **6.0** ft
 Interchange Density **0.50** l/mi
 Number of Lanes, N **3**
 FFS (measured) **56.0** mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS **56.0** mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ **1445** pc/h/ln
 S **56.0** mi/h
 $D = v_p / S$ **25.8** pc/mi/ln
 LOS **C**

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *9/09/2011*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 No-Build*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *4500* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.86*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T-1)+P_R(E_R-1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1762* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *31.5* pc/mi/ln
 LOS *D*

Design (N)

Design (N)

Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *12/09/2011*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 5 on to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 No-Build*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V	2850	veh/h	Peak-Hour Factor, PHF	0.92
AADT		veh/day	%Trucks and Buses, P_T	2
Peak-Hr Prop. of AADT, K			%RVs, P_R	0
Peak-Hr Direction Prop, D			General Terrain:	<i>Level</i>
DDHV = AADT x K x D		veh/h	Grade %	<i>mi</i>
Driver type adjustment	1.00		Length	
			Up/Down %	

Calculate Flow Adjustments

f_p	1.00	E_R	1.2
E_T	1.5	$f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$	0.990

Speed Inputs

Lane Width	12.0	ft
Rt-Shoulder Lat. Clearance	6.0	ft
Interchange Density	0.50	l/mi
Number of Lanes, N	3	
FFS (measured)	56.0	mi/h
Base free-flow Speed, BFFS		mi/h

Calc Speed Adj and FFS

f_{LW}	mi/h
f_{LC}	mi/h
f_{ID}	mi/h
f_N	mi/h
FFS	56.0 mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1043* pc/h/ln
 $S = v_p / f_p$ *56.0* mi/h
 $D = v_p / S$ *18.6* pc/mi/ln
 LOS *C*

Design (N)

Design (N)

Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *pc/h*
 $S = v_p / f_p$ *mi/h*
 $D = v_p / S$ *pc/mi/ln*
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst: SEB
 Agency or Company: CHA
 Date Performed: 6/22/2011
 Analysis Time Period: PM

Site Information

Highway/Direction of Travel: Northbound I-87
 From/To: Exit 4 to Exit 5
 Jurisdiction: NYSDOT
 Analysis Year: 2026 No-Build

Project Description: Exit 4

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V: 5950 veh/h
 AADT: veh/day
 Peak-Hr Prop. of AADT, K: 0.86
 Peak-Hr Direction Prop, D: 2
 DDHV = AADT x K x D: 0
 Driver type adjustment: 1.00
 Peak-Hr Factor, PHF: 0.86
 %Trucks and Buses, P_T : 2
 %RVs, P_R : 0
 General Terrain: Level
 Grade % Length: mi
 Up/Down %

Calculate Flow Adjustments

f_p : 1.00
 E_T : 1.5
 E_R : 1.2
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$: 0.990

Speed Inputs

Lane Width: 12.0 ft
 Rt-Shoulder Lat. Clearance: 6.0 ft
 Interchange Density: 0.50 l/mi
 Number of Lanes, N: 3
 FFS (measured): 56.0 mi/h
 Base free-flow Speed, BFFS: mi/h

Calc Speed Adj and FFS

f_{LW} : mi/h
 f_{LC} : mi/h
 f_{ID} : mi/h
 f_N : mi/h
 FFS: 56.0 mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$: 2329 pc/h/ln
 S : mi/h
 $D = v_p / S$: pc/mi/ln
 LOS: F

Design (N)

Design (N)

Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$: pc/h
 f_p : pc/h
 S : mi/h
 $D = v_p / S$: pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *6/22/2011*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 5 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 No-Build*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2600* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T-1)+P_R(E_R-1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *951* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *17.0* pc/mi/ln
 LOS *B*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst: SEB
 Agency or Company: CHA
 Date Performed: 6/22/2011
 Analysis Time Period: PM

Site Information

Highway/Direction of Travel: Northbound I-87
 From/To: Exit 5 to Exit 6
 Jurisdiction: NYSDOT
 Analysis Year: 2026 No-Build

Project Description: Exit 4

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V: 6150 veh/h
 AADT: veh/day
 Peak-Hr Prop. of AADT, K: 0.86
 Peak-Hr Direction Prop, D: 2
 DDHV = AADT x K x D: veh/h
 Driver type adjustment: 1.00
 Peak-Hour Factor, PHF: 0.86
 %Trucks and Buses, P_T : 2
 %RVs, P_R : 0
 General Terrain: Level
 Grade % Length: mi
 Up/Down %

Calculate Flow Adjustments

f_p : 1.00
 E_T : 1.5
 E_R : 1.2
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$: 0.990

Speed Inputs

Lane Width: 12.0 ft
 Rt-Shoulder Lat. Clearance: 6.0 ft
 Interchange Density: 0.50 l/mi
 Number of Lanes, N: 4
 FFS (measured): 56.0 mi/h
 Base free-flow Speed, BFFS: mi/h

Calc Speed Adj and FFS

f_{LW} : mi/h
 f_{LC} : mi/h
 f_{ID} : mi/h
 f_N : mi/h
 FFS: 56.0 mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$: 1806 pc/h/ln
 S : 56.0 mi/h
 $D = v_p / S$: 32.3 pc/mi/ln
 LOS: D

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$: pc/h
 S : mi/h
 $D = v_p / S$: pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *6/22/2011*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 6 to Exit 5*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 No-Build*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *3650* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *4*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1002* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *17.9* pc/mi/ln
 LOS *B*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 2W On-Ramp			
Date Performed		9/08/2011		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2026 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1100$ ft $V_u = 880$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4400	0.86	Level	2	0	0.990	1.00	5167	
Ramp	730	0.92	Level	2	0	0.990	1.00	801	
UpStream	880	0.92	Level	2	0	0.990	1.00	966	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 1344.35$ (Equation 25-2 or 25-3) $P_{FM} = 0.586$ using Equation (Exhibit 25-5) $V_{12} = 3027$ pc/h V_3 or $V_{av34} = 2140$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	5968	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	3828	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 29.6$ (pc/mi/ln) LOS = D (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.432$ (Exhibit 25-19) $S_R = 49.9$ mph (Exhibit 25-19) $S_0 = 50.1$ mph (Exhibit 25-19) $S = 50.0$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET														
General Information					Site Information									
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87								
Agency or Company		CHA		Junction		Exit 4 NB Off								
Date Performed		9/08/2011		Jurisdiction		NYSDOT								
Analysis Time Period		PM		Analysis Year		2026 No-Build								
Project Description Exit 4														
Inputs														
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 2660 ft $V_D =$ 1470 veh/h							
Conversion to pc/h Under Base Conditions														
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$						
Freeway	5150	0.86	Level	2	0	0.990	1.00	6048						
Ramp	630	0.86	Level	2	0	0.990	1.00	740						
UpStream														
DownStream	1470	0.88	Level	1	0	0.995	1.00	1679						
Merge Areas					Diverge Areas									
Estimation of v_{12}					Estimation of v_{12}									
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.575 using Equation (Exhibit 25-12) $V_{12} =$ 3791 pc/h V_3 or V_{av34} 2257 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)									
Capacity Checks					Capacity Checks									
		Actual	Capacity		LOS F?									
V_{FO}							V_F	6048	Exhibit 25-14	6780	No			
			Exhibit 25-7				$V_{FO} = V_F - V_R$	5308	Exhibit 25-14	6780	No			
							V_R	740	Exhibit 25-3	2100	No			
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area									
		Actual	Max Desirable		Violation?				Actual	Max Desirable		Violation?		
V_{R12}			Exhibit 25-7				V_{12}		3791	Exhibit 25-14		4400:All		No
Level of Service Determination (if not F)					Level of Service Determination (if not F)									
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 33.7 (pc/mi/ln) $LOS =$ D (Exhibit 25-4)									
Speed Determination					Speed Determination									
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.430 (Exhibit 25-19) $S_R =$ 50.0 mph (Exhibit 25-19) $S_0 =$ 56.5 mph (Exhibit 25-19) $S =$ 52.2 mph (Exhibit 25-15)									

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 4 NB On-Ramp			
Date Performed		9/08/2011		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2026 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{down} =$ 3500 ft $V_D =$ 450 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4500	0.86	Level	2	0	0.990	1.00	5285	
Ramp	1470	0.88	Level	1	0	0.995	1.00	1679	
UpStream									
DownStream	450	0.92	Level	3	0	0.985	1.00	496	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 2408.94$ (Equation 25-2 or 25-3) $P_{FM} = 0.603$ using Equation (Exhibit 25-5) $V_{12} = 3185$ pc/h V_3 or $V_{av34} = 2100$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	6964	Exhibit 25-7		Yes	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	4864	Exhibit 25-7	4600:All	Yes	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 37.0$ (pc/mi/ln) LOS = F (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.754$ (Exhibit 25-19) $S_R = 45.4$ mph (Exhibit 25-19) $S_0 = 50.2$ mph (Exhibit 25-19) $S = 46.8$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 5 NB Off			
Date Performed		9/08/2011		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2026 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{up} = 3500$ ft $V_u = 1470$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 35.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	5950	0.86	Level	2	0	0.990	1.00	6988	
Ramp	450	0.92	Level	3	0	0.985	1.00	496	
UpStream	1470	0.88	Level	1	0	0.995	1.00	1679	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} = 8653.39$ (Equation 25-8 or 25-9) $P_{FD} = 0.734$ using Equation (Exhibit 25-12) $V_{12} = 5263$ pc/h V_3 or $V_{av34} = 1725$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	6988	Exhibit 25-14	6780	Yes
					$V_{FO} = V_F - V_R$	6492	Exhibit 25-14	6780	No
					V_R	496	Exhibit 25-3	2000	No
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	5263	Exhibit 25-14	4400:All	Yes
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 47.3$ (pc/mi/ln) $LOS = F$ (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.473$ (Exhibit 25-19) $S_R = 49.4$ mph (Exhibit 25-19) $S_0 = 58.6$ mph (Exhibit 25-19) $S = 51.4$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound			
Agency or Company		CHA		Junction		Exit 2W Off			
Date Performed		9/08/2011		Jurisdiction		NYS DOT			
Analysis Time Period		PM		Analysis Year		2026 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1300 ft $V_D =$ 850 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	3950	0.92	Level	2	0	0.990	1.00	4336	
Ramp	570	0.92	Level	2	0	0.990	1.00	626	
UpStream									
DownStream	850	0.92	Level	2	0	0.990	1.00	933	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.623 using Equation (Exhibit 25-12) $V_{12} =$ 2937 pc/h V_3 or V_{av34} 1399 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	4336	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	3710	Exhibit 25-14	6780	No	
				V_R	626	Exhibit 25-3	2100	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	2937	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 26.8 (pc/mi/ln) $LOS =$ C (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.419 (Exhibit 25-19) $S_R =$ 50.1 mph (Exhibit 25-19) $S_0 =$ 59.9 mph (Exhibit 25-19) $S =$ 52.9 mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 4 SB Off			
Date Performed		9/08/2011		Jurisdiction		NYS DOT			
Analysis Time Period		PM		Analysis Year		2026 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 3100 ft $V_D =$ 450 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	3000	0.92	Level	2	0	0.990	1.00	3293	
Ramp	620	0.92	Level	2	0	0.990	1.00	681	
UpStream									
DownStream	450	0.87	Level	1	0	0.995	1.00	520	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.646 using Equation (Exhibit 25-12) $V_{12} =$ 2369 pc/h V_3 or V_{av34} 924 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	3293	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	2612	Exhibit 25-14	6780	No	
				V_R	681	Exhibit 25-3	2100	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	2369	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 20.4 (pc/mi/ln) $LOS =$ C (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.424 (Exhibit 25-19) $S_R =$ 50.1 mph (Exhibit 25-19) $S_0 =$ 61.4 mph (Exhibit 25-19) $S =$ 52.8 mph (Exhibit 25-15)				


RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 4 SB On-Ramp			
Date Performed		9/08/2011		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2026 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{up} = 2035$ ft $V_u = 450$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2850	0.92	Level	2	0	0.990	1.00	3129	
Ramp	1110	0.93	Level	4	0	0.980	1.00	1217	
UpStream	450	0.87	Level	1	0	0.995	1.00	520	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} = 0.603$ using Equation (Exhibit 25-5) $V_{12} = 1886$ pc/h V_3 or $V_{av34} = 1243$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	4346	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	3103	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 23.5$ (pc/mi/ln) LOS = C (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.336$ (Exhibit 25-19) $S_R = 51.3$ mph (Exhibit 25-19) $S_0 = 53.3$ mph (Exhibit 25-19) $S = 51.9$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 5 SB On-Ramp			
Date Performed		9/08/2011		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2026 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 2035 ft $V_D =$ 1110 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2600	0.92	Level	2	0	0.990	1.00	2854	
Ramp	450	0.87	Level	1	0	0.995	1.00	520	
UpStream									
DownStream	1110	0.93	Level	4	0	0.980	1.00	1217	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} = 0.603$ using Equation (Exhibit 25-5) $V_{12} = 1720$ pc/h V_3 or $V_{av34} = 1134$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	3374	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	2240	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 17.1$ (pc/mi/ln) $LOS = B$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.286$ (Exhibit 25-19) $S_R = 52.0$ mph (Exhibit 25-19) $S_0 = 53.7$ mph (Exhibit 25-19) $S = 52.6$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst Agency/Company Date Performed Analysis Time Period					SEB CHA 9/08/2011 PM				
Freeway/Dir of Travel Weaving Seg Location Jurisdiction Analysis Year					I-87 Northbound Exit 2E on to 2W off NYSDOT 2026 No-Build				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h)					56				
Weaving number of lanes, N					4				
Weaving seg length, L (ft)					815				
Terrain					Level				
Weaving type					A				
Volume ratio, VR					0.24				
Weaving ratio, R					0.35				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	3930	0.86	2	0	1.5	1.2	0.990	1.00	4615
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	880	0.92	2	0	1.5	1.2	0.990	1.00	966
V_{w2}	470	0.92	2	0	1.5	1.2	0.990	1.00	515
V_w				1481	V_{nw}				4615
V									6096
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	1.39		0.75						
Weaving and non-weaving speeds, S_i (mi/h)	34.26		41.25						
Number of lanes required for unconstrained operation, N_w					1.35				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					39.30				
Weaving segment density, D (pc/mi/ln)					38.78				
Level of service, LOS					E				
Capacity of base condition, c_b (pc/h)					6505				
Capacity as a 15-minute flow rate, c (veh/h)					6441				
Capacity as a full-hour volume, c_h (veh/h)					5638				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 6/22/2011 Analysis Time Period PM					Freeway/Dir of Travel I-87 Southbound Weaving Seg Location Exit 2W on to 2E off Jurisdiction NYSDOT Analysis Year 2026 No-Build				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 810 Terrain Level					Weaving type A Volume ratio, VR 0.26 Weaving ratio, R 0.23				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	3150	0.92	2	0	1.5	1.2	0.990	1.00	3458
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	850	0.92	2	0	1.5	1.2	0.990	1.00	933
V_{w2}	250	0.92	2	0	1.5	1.2	0.990	1.00	274
V_w				1207	V_{nw}				3458
V									4665
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	1.11		0.56						
Weaving and non-weaving speeds, S_i (mi/h)	36.84		44.46						
Number of lanes required for unconstrained operation, N_w					1.35				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					42.20				
Weaving segment density, D (pc/mi/ln)					27.64				
Level of service, LOS					C				
Capacity of base condition, c_b (pc/h)					6410				
Capacity as a 15-minute flow rate, c (veh/h)					6347				
Capacity as a full-hour volume, c_h (veh/h)					5839				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *6/22/2011*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 2 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 No-Build*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5200* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.86*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1 + P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *2036* pc/h/ln
 S *54.6* mi/h
 $D = v_p / S$ *37.3* pc/mi/ln
 LOS *E*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst: SEB
 Agency or Company: CHA
 Date Performed: 6/22/2011
 Analysis Time Period: PM

Site Information

Highway/Direction of Travel: Southbound I-87
 From/To: Exit 4 to Exit 2
 Jurisdiction: NYSDOT
 Analysis Year: 2036 No-Build

Project Description: Exit 4

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V: 4100 veh/h
 AADT: veh/day
 Peak-Hr Prop. of AADT, K: 0.92
 Peak-Hr Direction Prop, D: %Trucks and Buses, P_T : 2
 DDHV = AADT x K x D: %RVs, P_R : 0
 Driver type adjustment: 1.00
 General Terrain: Level
 Grade % Length: mi
 Up/Down %

Calculate Flow Adjustments

f_p : 1.00
 E_T : 1.5
 E_R : 1.2
 $f_{HV} = 1/[1 + P_T(E_T - 1) + P_R(E_R - 1)]$: 0.990

Speed Inputs

Lane Width: 12.0 ft
 Rt-Shoulder Lat. Clearance: 6.0 ft
 Interchange Density: 0.50 l/mi
 Number of Lanes, N: 3
 FFS (measured): 56.0 mi/h
 Base free-flow Speed, BFFS: mi/h

Calc Speed Adj and FFS

f_{LW} : mi/h
 f_{LC} : mi/h
 f_{ID} : mi/h
 f_N : mi/h
 FFS: 56.0 mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$: 1500 pc/h/ln
 S: 56.0 mi/h
 $D = v_p / S$: 26.8 pc/mi/ln
 LOS: D

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$: pc/h
 f_p :
 S: mi/h
 $D = v_p / S$: pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst **SEB**
 Agency or Company **CHA**
 Date Performed **9/09/2011**
 Analysis Time Period **PM**

Site Information

Highway/Direction of Travel **Northbound I-87**
 From/To **Exit 4 off to Exit 4 on**
 Jurisdiction **NYSDOT**
 Analysis Year **2036 No-Build**

Project Description **Exit 4**

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V **4600** veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment **1.00**
 Peak-Hour Factor, PHF **0.86**
 %Trucks and Buses, P_T **2**
 %RVs, P_R **0**
 General Terrain: **Level**
 Grade % Length **mi**
 Up/Down %

Calculate Flow Adjustments

f_p **1.00**
 E_T **1.5**
 E_R **1.2**
 $f_{HV} = 1/[1 + P_T(E_T - 1) + P_R(E_R - 1)]$ **0.990**

Speed Inputs

Lane Width **12.0** ft
 Rt-Shoulder Lat. Clearance **6.0** ft
 Interchange Density **0.50** l/mi
 Number of Lanes, N **3**
 FFS (measured) **56.0** mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS **56.0** mi/h

LOS and Performance Measures

Operational (LOS)
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ **1801** pc/h/ln
 S **56.0** mi/h
 $D = v_p / S$ **32.2** pc/mi/ln
 LOS **D**

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *12/09/2011*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 5 on to Exit 4 on*
 Jurisdiction *NYS DOT*
 Analysis Year *2036 No-Build*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V	2950	veh/h	Peak-Hour Factor, PHF	0.92
AADT		veh/day	% Trucks and Buses, P_T	2
Peak-Hr Prop. of AADT, K			% RVs, P_R	0
Peak-Hr Direction Prop, D			General Terrain:	<i>Level</i>
DDHV = AADT x K x D		veh/h	Grade %	<i>mi</i>
Driver type adjustment	1.00		Up/Down %	

Calculate Flow Adjustments

f_p	1.00	E_R	1.2
E_T	1.5	$f_{HV} = 1/[1 + P_T(E_T - 1) + P_R(E_R - 1)]$	0.990

Speed Inputs

Lane Width	12.0	ft
Rt-Shoulder Lat. Clearance	6.0	ft
Interchange Density	0.50	l/mi
Number of Lanes, N	3	
FFS (measured)	56.0	mi/h
Base free-flow Speed, BFFS		mi/h

Calc Speed Adj and FFS

f_{LW}	mi/h
f_{LC}	mi/h
f_{ID}	mi/h
f_N	mi/h
FFS	56.0 mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1080* pc/h/ln

S *56.0* mi/h

$D = v_p / S$ *19.3* pc/mi/ln

LOS *C*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h

S mi/h

$D = v_p / S$ pc/mi/ln

Required Number of Lanes, N


Glossary

N - Number of lanes	S - Speed
V - Hourly volume	D - Density
v_p - Flow rate	FFS - Free-flow speed
LOS - Level of service	BFFS - Base free-flow speed
DDHV - Directional design hour volume	

Factor Location

E_R - Exhibits 23-8, 23-10	f_{LW} - Exhibit 23-4
E_T - Exhibits 23-8, 23-10, 23-11	f_{LC} - Exhibit 23-5
f_p - Page 23-12	f_N - Exhibit 23-6
LOS, S, FFS, v_p - Exhibits 23-2, 23-3	f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (M)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst **SEB**
 Agency or Company **CHA**
 Date Performed **6/22/2011**
 Analysis Time Period **PM**

Site Information

Highway/Direction of Travel **Northbound I-87**
 From/To **Exit 4 to Exit 5**
 Jurisdiction **NYS DOT**
 Analysis Year **2036 No-Build**

Project Description **Exit 4**

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V **6050** veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment **1.00**
 Peak-Hour Factor, PHF **0.86**
 %Trucks and Buses, P_T **2**
 %RVs, P_R **0**
 General Terrain: **Level**
 Grade % Length **mi**
 Up/Down %

Calculate Flow Adjustments

f_p **1.00**
 E_T **1.5**
 E_R **1.2**
 $f_{HV} = 1/[1 + P_T(E_T - 1) + P_R(E_R - 1)]$ **0.990**

Speed Inputs

Lane Width **12.0** ft
 Rt-Shoulder Lat. Clearance **6.0** ft
 Interchange Density **0.50** I/mi
 Number of Lanes, N **3**
 FFS (measured) **56.0** mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS **56.0** mi/h

LOS and Performance Measures

Operational (LOS)
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ **2368** pc/h/ln
 S mi/h
 $D = v_p / S$ pc/mi/ln
 LOS **F**

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst **SEB**
 Agency or Company **CHA**
 Date Performed **6/22/2011**
 Analysis Time Period **PM**

Site Information

Highway/Direction of Travel **Southbound I-87**
 From/To **Exit 5 to Exit 4**
 Jurisdiction **NYS DOT**
 Analysis Year **2036 No-Build**

Project Description **Exit 4**

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V **2750** veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment **1.00**
 Peak-Hour Factor, PHF **0.92**
 %Trucks and Buses, P_T **2**
 %RVs, P_R **0**
 General Terrain: **Level**
 Grade % Length **mi**
 Up/Down %

Calculate Flow Adjustments

f_p **1.00** E_R **1.2**
 E_T **1.5** $f_{HV} = 1/[1 + P_T(E_T - 1) + P_R(E_R - 1)]$ **0.990**

Speed Inputs

Lane Width **12.0** ft
 Rt-Shoulder Lat. Clearance **6.0** ft
 Interchange Density **0.50** I/mi
 Number of Lanes, N **3**
 FFS (measured) **56.0** mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS **56.0** mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ **1006** pc/h/ln
 S **56.0** mi/h
 $D = v_p / S$ **18.0** pc/mi/ln
 LOS **B**

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst **SEB**
 Agency or Company **CHA**
 Date Performed **6/22/2011**
 Analysis Time Period **PM**

Site Information

Highway/Direction of Travel **Northbound I-87**
 From/To **Exit 5 to Exit 6**
 Jurisdiction **NYS DOT**
 Analysis Year **2036 No-Build**

Project Description **Exit 4**

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V **6250** veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment **1.00**
 Peak-Hour Factor, PHF **0.86**
 %Trucks and Buses, P_T **2**
 %RVs, P_R **0**
 General Terrain: **Level**
 Grade % Length **mi**
 Up/Down %

Calculate Flow Adjustments

f_p **1.00**
 E_T **1.5**
 E_R **1.2**
 $f_{HV} = 1/[1 + P_T(E_T - 1) + P_R(E_R - 1)]$ **0.990**

Speed Inputs

Lane Width **12.0** ft
 Rt-Shoulder Lat. Clearance **6.0** ft
 Interchange Density **0.50** l/mi
 Number of Lanes, N **4**
 FFS (measured) **56.0** mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS **56.0** mi/h

LOS and Performance Measures

Operational (LOS)
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ **1835** pc/h/ln
 S **55.9** mi/h
 $D = v_p / S$ **32.8** pc/mi/ln
 LOS **D**

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (M)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst **SEB**
 Agency or Company **CHA**
 Date Performed **6/22/2011**
 Analysis Time Period **PM**

Site Information

Highway/Direction of Travel **Southbound I-87**
 From/To **Exit 6 to Exit 5**
 Jurisdiction **NYS DOT**
 Analysis Year **2036 No-Build**

Project Description **Exit 4**

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V **3800** veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment **1.00**
 Peak-Hour Factor, PHF **0.92**
 %Trucks and Buses, P_T **2**
 %RVs, P_R **0**
 General Terrain: **Level**
 Grade % Length **mi**
 Up/Down %

Calculate Flow Adjustments

f_p **1.00**
 E_T **1.5**
 E_R **1.2**
 $f_{HV} = 1/[1 + P_T(E_T - 1) + P_R(E_R - 1)]$ **0.990**

Speed Inputs

Lane Width **12.0** ft
 Rt-Shoulder Lat. Clearance **6.0** ft
 Interchange Density **0.50** l/mi
 Number of Lanes, N **4**
 FFS (measured) **56.0** mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS **56.0** mi/h

LOS and Performance Measures

Operational (LOS)
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ **1043** pc/h/ln
 S **56.0** mi/h
 $D = v_p / S$ **18.6** pc/mi/ln
 LOS **C**

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 2W On-Ramp			
Date Performed		9/08/2011		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2036 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1100$ ft $V_u = 860$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_l)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4450	0.86	Level	2	0	0.990	1.00	5226	
Ramp	740	0.92	Level	2	0	0.990	1.00	812	
UpStream	860	0.92	Level	2	0	0.990	1.00	944	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 1359.33$ (Equation 25-2 or 25-3) $P_{FM} = 0.585$ using Equation (Exhibit 25-5) $V_{12} = 3056$ pc/h V_3 or $V_{av34} = 2170$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	6038	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	3868	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 29.9$ (pc/mi/ln) LOS = D (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.440$ (Exhibit 25-19) $S_R = 49.8$ mph (Exhibit 25-19) $S_0 = 50.0$ mph (Exhibit 25-19) $S = 49.9$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 4 NB Off			
Date Performed		9/08/2011		Jurisdiction		NYS DOT			
Analysis Time Period		PM		Analysis Year		2036 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 2660 ft $V_D =$ 1500 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	5200	0.86	Level	2	0	0.990	1.00	6107	
Ramp	630	0.86	Level	2	0	0.990	1.00	740	
UpStream									
DownStream	1500	0.88	Level	1	0	0.995	1.00	1713	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.573 using Equation (Exhibit 25-12) $V_{12} =$ 3817 pc/h V_3 or V_{av34} 2290 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	6107	Exhibit 25-14	6780	No
					$V_{FO} = V_F - V_R$	5367	Exhibit 25-14	6780	No
					V_R	740	Exhibit 25-3	2100	No
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	3817	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 33.9 (pc/mi/ln) $LOS =$ D (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.430 (Exhibit 25-19) $S_R =$ 50.0 mph (Exhibit 25-19) $S_0 =$ 56.4 mph (Exhibit 25-19) $S =$ 52.2 mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 4 NB On-Ramp			
Date Performed		9/08/2011		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2036 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{down} =$ 3500 ft $V_D =$ 470 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4600	0.86	Level	2	0	0.990	1.00	5402	
Ramp	1500	0.88	Level	1	0	0.995	1.00	1713	
UpStream									
DownStream	470	0.92	Level	3	0	0.985	1.00	519	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 2520.64$ (Equation 25-2 or 25-3) $P_{FM} = 0.603$ using Equation (Exhibit 25-5) $V_{12} = 3256$ pc/h V_3 or $V_{av34} = 2146$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	7115	Exhibit 25-7		Yes	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	4969	Exhibit 25-7	4600:All	Yes	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 37.8$ (pc/mi/ln) LOS = F (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.810$ (Exhibit 25-19) $S_R = 44.7$ mph (Exhibit 25-19) $S_0 = 50.1$ mph (Exhibit 25-19) $S = 46.2$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 5 NB Off			
Date Performed		9/08/2011		Jurisdiction		NYS DOT			
Analysis Time Period		PM		Analysis Year		2036 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{up} = 3500$ ft $V_u = 1500$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 35.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_P)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	6050	0.86	Level	2	0	0.990	1.00	7105	
Ramp	470	0.92	Level	3	0	0.985	1.00	519	
UpStream	1500	0.88	Level	1	0	0.995	1.00	1713	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} = 8785.92$ (Equation 25-8 or 25-9) $P_{FD} = 0.736$ using Equation (Exhibit 25-12) $V_{12} = 5363$ pc/h V_3 or $V_{av34} = 1742$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	7105	Exhibit 25-14	6780	Yes
					$V_{FO} = V_F - V_R$	6586	Exhibit 25-14	6780	No
					V_R	519	Exhibit 25-3	2000	No
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	5363	Exhibit 25-14	4400:All	Yes
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 48.1$ (pc/mi/ln) $LOS = F$ (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.475$ (Exhibit 25-19) $S_R = 49.4$ mph (Exhibit 25-19) $S_0 = 58.5$ mph (Exhibit 25-19) $S = 51.3$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET													
General Information					Site Information								
Analyst		SEB			Freeway/Dir of Travel		Southbound						
Agency or Company		CHA			Junction		Exit 2W Off						
Date Performed		9/08/2011			Jurisdiction		NYS DOT						
Analysis Time Period		PM			Analysis Year		2036 No-Build						
Project Description Exit 4													
Inputs													
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h		Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)					Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1300 ft $V_D =$ 910 veh/h						
Conversion to pc/h Under Base Conditions													
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$					
Freeway	4100	0.92	Level	2	0	0.990	1.00	4501					
Ramp	650	0.92	Level	2	0	0.990	1.00	714					
UpStream													
DownStream	910	0.92	Level	2	0	0.990	1.00	999					
Merge Areas					Diverge Areas								
Estimation of v_{12}					Estimation of v_{12}								
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ $P_{FD} = 0.615$ using Equation (Exhibit 25-12) $V_{12} = 3042$ pc/h V_3 or V_{av34} 1459 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)								
Capacity Checks					Capacity Checks								
		Actual	Capacity		LOS F?								
V_{FO}			Exhibit 25-7				V_F	4501	Exhibit 25-14	6780	No		
							$V_{FO} = V_F - V_R$	3787	Exhibit 25-14	6780	No		
							V_R	714	Exhibit 25-3	2100	No		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area								
		Actual	Max Desirable		Violation?				Actual	Max Desirable		Violation?	
V_{R12}			Exhibit 25-7				V_{12}		3042	Exhibit 25-14	4400:All	No	
Level of Service Determination (if not F)					Level of Service Determination (if not F)								
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 27.7$ (pc/mi/ln) $LOS = C$ (Exhibit 25-4)								
Speed Determination					Speed Determination								
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.427$ (Exhibit 25-19) $S_R = 50.0$ mph (Exhibit 25-19) $S_0 = 59.6$ mph (Exhibit 25-19) $S = 52.8$ mph (Exhibit 25-15)								

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 4 SB Off			
Date Performed		9/08/2011		Jurisdiction		NYS DOT			
Analysis Time Period		PM		Analysis Year		2036 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 3100 ft $V_D =$ 470 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	3100	0.92	Level	2	0	0.990	1.00	3403	
Ramp	600	0.92	Level	2	0	0.990	1.00	659	
UpStream									
DownStream	470	0.87	Level	1	0	0.995	1.00	543	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.645 using Equation (Exhibit 25-12) $V_{12} =$ 2428 pc/h V_3 or V_{av34} 975 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	3403	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	2744	Exhibit 25-14	6780	No	
				V_R	659	Exhibit 25-3	2100	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	2428	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 20.9 (pc/mi/ln) $LOS =$ C (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.422 (Exhibit 25-19) $S_R =$ 50.1 mph (Exhibit 25-19) $S_0 =$ 61.4 mph (Exhibit 25-19) $S =$ 52.9 mph (Exhibit 25-15)				


RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 4 SB On-Ramp			
Date Performed		9/08/2011		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2036 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{up} = 2035$ ft $V_u = 470$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2950	0.92	Level	2	0	0.990	1.00	3239	
Ramp	1170	0.93	Level	4	0	0.980	1.00	1283	
UpStream	470	0.87	Level	1	0	0.995	1.00	543	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} = 0.603$ using Equation (Exhibit 25-5) $V_{12} = 1952$ pc/h V_3 or $V_{av34} = 1287$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	4522	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	3235	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 24.5$ (pc/mi/ln) LOS = C (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.348$ (Exhibit 25-19) $S_R = 51.1$ mph (Exhibit 25-19) $S_0 = 53.2$ mph (Exhibit 25-19) $S = 51.7$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 5 SB On-Ramp			
Date Performed		9/08/2011		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2036 No-Build			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 2035 ft $V_D =$ 1170 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2750	0.92	Level	2	0	0.990	1.00	3019	
Ramp	470	0.87	Level	1	0	0.995	1.00	543	
UpStream									
DownStream	1170	0.93	Level	4	0	0.980	1.00	1283	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} = 0.603$ using Equation (Exhibit 25-5) $V_{12} = 1820$ pc/h V_3 or $V_{av34} = 1199$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	3562	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	2363	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 18.0$ (pc/mi/ln) $LOS = B$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.290$ (Exhibit 25-19) $S_R = 51.9$ mph (Exhibit 25-19) $S_0 = 53.5$ mph (Exhibit 25-19) $S = 52.4$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 9/08/2011 Analysis Time Period PM					Freeway/Dir of Travel I-87 Northbound Weaving Seg Location Exit 2E on to 2W off Jurisdiction NYSDOT Analysis Year 2036 No-Build				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 815 Terrain Level					Weaving type A Volume ratio, VR 0.24 Weaving ratio, R 0.35				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	3980	0.86	2	0	1.5	1.2	0.990	1.00	4674
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	860	0.92	2	0	1.5	1.2	0.990	1.00	944
V_{w2}	470	0.92	2	0	1.5	1.2	0.990	1.00	515
V_w				1459	V_{nw}				4674
V									6133
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	1.38		0.75						
Weaving and non-weaving speeds, S_i (mi/h)	34.30		41.35						
Number of lanes required for unconstrained operation, N_w					1.33				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					39.42				
Weaving segment density, D (pc/mi/ln)					38.90				
Level of service, LOS					E				
Capacity of base condition, c_b (pc/h)					6533				
Capacity as a 15-minute flow rate, c (veh/h)					6468				
Capacity as a full-hour volume, c_h (veh/h)					5660				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 6/22/2011 Analysis Time Period PM					Freeway/Dir of Travel I-87 Southbound Weaving Seg Location Exit 2W on to 2E off Jurisdiction NYSDOT Analysis Year 2036 No-Build				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 810 Terrain Level					Weaving type A Volume ratio, VR 0.26 Weaving ratio, R 0.20				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	3220	0.92	2	0	1.5	1.2	0.990	1.00	3534
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	910	0.92	2	0	1.5	1.2	0.990	1.00	999
V_{w2}	230	0.92	2	0	1.5	1.2	0.990	1.00	252
V_w				1251	V_{nw}				3534
V									4785
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	1.14		0.59						
Weaving and non-weaving speeds, S_i (mi/h)	36.50		44.02						
Number of lanes required for unconstrained operation, N_w					1.36				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					41.77				
Weaving segment density, D (pc/mi/ln)					28.64				
Level of service, LOS					D				
Capacity of base condition, c_b (pc/h)					6395				
Capacity as a 15-minute flow rate, c (veh/h)					6332				
Capacity as a full-hour volume, c_h (veh/h)					5825				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *12/13/2011*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2046 No-Build*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *4550* veh/h Peak-Hour Factor, PHF *0.86*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1781* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *31.8* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *12/13/2011*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 5 on to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2046 No-Build*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *3050* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.92*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1116* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *19.9* pc/mi/ln
 LOS *C*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

DIAMOND

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 2 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *3300* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1208* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *21.6* pc/mi/ln
 LOS *C*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 to Exit 2*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5200* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1903* pc/h/ln
 S *55.7* mi/h
 $D = v_p / S$ *34.2* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2450* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *897* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *16.0* pc/mi/ln
 LOS *B*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *4700* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1720* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *30.7* pc/mi/ln
 LOS *D*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 to Exit 5*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2500* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.92*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *915* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *16.3* pc/mi/ln
 LOS *B*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 5 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5350* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1958* pc/h/ln
 S *55.3* mi/h
 $D = v_p / S$ *35.4* pc/mi/ln
 LOS *E*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary


N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET																										
			<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Application</th> <th>Input</th> <th>Output</th> </tr> </thead> <tbody> <tr> <td>Operational (LOS)</td> <td>FFS, N, v_p</td> <td>LOS, S, D</td> </tr> <tr> <td>Design (N)</td> <td>FFS, LOS, v_p</td> <td>N, S, D</td> </tr> <tr> <td>Design (v_p)</td> <td>FFS, LOS, N</td> <td>v_p, S, D</td> </tr> <tr> <td>Planning (LOS)</td> <td>FFS, N, AADT</td> <td>LOS, S, D</td> </tr> <tr> <td>Planning (N)</td> <td>FFS, LOS, AADT</td> <td>N, S, D</td> </tr> <tr> <td>Planning (v_p)</td> <td>FFS, LOS, N</td> <td>v_p, S, D</td> </tr> </tbody> </table>			Application	Input	Output	Operational (LOS)	FFS, N, v_p	LOS, S, D	Design (N)	FFS, LOS, v_p	N, S, D	Design (v_p)	FFS, LOS, N	v_p , S, D	Planning (LOS)	FFS, N, AADT	LOS, S, D	Planning (N)	FFS, LOS, AADT	N, S, D	Planning (v_p)	FFS, LOS, N	v_p , S, D
Application	Input	Output																								
Operational (LOS)	FFS, N, v_p	LOS, S, D																								
Design (N)	FFS, LOS, v_p	N, S, D																								
Design (v_p)	FFS, LOS, N	v_p , S, D																								
Planning (LOS)	FFS, N, AADT	LOS, S, D																								
Planning (N)	FFS, LOS, AADT	N, S, D																								
Planning (v_p)	FFS, LOS, N	v_p , S, D																								
General Information			Site Information																							
Analyst		CLD		Highway/Direction of Travel																						
Agency or Company		CHA		Northbound I-87																						
Date Performed		07/29/13		From/To																						
Analysis Time Period		AM		Exit 5 to Exit 6																						
				Jurisdiction																						
				NYSDOT																						
Project Description		Exit 4		Analysis Year																						
				2016 Diamond																						
<input checked="" type="checkbox"/> Oper.(LOS)			<input type="checkbox"/> Des.(N)		<input type="checkbox"/> Planning Data																					
Flow Inputs																										
Volume, V		2400		veh/h																						
AADT				veh/day																						
Peak-Hr Prop. of AADT, K				Peak-Hour Factor, PHF																						
Peak-Hr Direction Prop, D				0.92																						
DDHV = AADT x K x D				%Trucks and Buses, P_T																						
Driver type adjustment		1.00		2																						
				%RVs, P_R																						
				0																						
				General Terrain:																						
				Level																						
				Grade % Length																						
				mi																						
				Up/Down %																						
Calculate Flow Adjustments																										
f_p		1.00		E_R																						
E_T		1.5		1.2																						
				$f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$																						
				0.990																						
Speed Inputs			Calc Speed Adj and FFS																							
Lane Width		12.0		ft																						
Rt-Shoulder Lat. Clearance		6.0		ft																						
Interchange Density		0.50		l/mi																						
Number of Lanes, N		4																								
FFS (measured)		56.0		mi/h																						
Base free-flow Speed, BFFS				mi/h																						
				FFS																						
				56.0																						
				mi/h																						
LOS and Performance Measures			Design (N)																							
<u>Operational (LOS)</u>			<u>Design (N)</u>																							
$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$			Design LOS																							
659			$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$																							
pc/h/ln			pc/h																							
S			S																							
56.0			mi/h																							
D = v_p / S			D = v_p / S																							
11.8			pc/mi/ln																							
LOS			Required Number of Lanes, N																							
B																										
Glossary			Factor Location																							
N - Number of lanes			S - Speed																							
V - Hourly volume			D - Density																							
v_p - Flow rate			FFS - Free-flow speed																							
LOS - Level of service			BFFS - Base free-flow speed																							
DDHV - Directional design hour volume																										
			E _R - Exhibits 23-8, 23-10																							
			E _T - Exhibits 23-8, 23-10, 23-11																							
			f _p - Page 23-12																							
			LOS, S, FFS, v_p - Exhibits 23-2, 23-3																							
			f _{LW} - Exhibit 23-4																							
			f _{LC} - Exhibit 23-5																							
			f _N - Exhibit 23-6																							
			f _{ID} - Exhibit 23-7																							

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *CLD*
 Agency or Company *CHA*
 Date Performed *07/29/13*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 6 to Exit 5*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *6100* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *4*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1674* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *29.9* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 2W On-Ramp			
Date Performed		02/15/12		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2016 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1100$ ft $V_u = 660$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2900	0.92	Level	2	0	0.990	1.00	3184	
Ramp	380	0.92	Level	2	0	0.990	1.00	417	
UpStream	660	0.92	Level	2	0	0.990	1.00	725	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 837.81$ (Equation 25-2 or 25-3) $P_{FM} = 0.601$ using Equation (Exhibit 25-5) $V_{12} = 1915$ pc/h V_3 or $V_{av34} = 1269$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	3601	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	2332	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 18.1$ (pc/mi/ln) LOS = B (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.293$ (Exhibit 25-19) $S_R = 51.9$ mph (Exhibit 25-19) $S_0 = 53.2$ mph (Exhibit 25-19) $S = 52.4$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET													
General Information					Site Information								
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87							
Agency or Company		CHA		Junction		Exit 4 NB Off							
Date Performed		02/15/12		Jurisdiction		NYS DOT							
Analysis Time Period		AM		Analysis Year		2016 Diamond							
Project Description Exit 4													
Inputs													
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1850 ft $V_D =$ 560 veh/h						
Conversion to pc/h Under Base Conditions													
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$					
Freeway	3300	0.92	Level	2	0	0.990	1.00	3623					
Ramp	850	0.82	Level	2	0	0.990	1.00	1047					
UpStream													
DownStream	560	0.92	Level	2	0	0.990	1.00	615					
Merge Areas					Diverge Areas								
Estimation of v_{12}					Estimation of v_{12}								
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.621 using Equation (Exhibit 25-12) $V_{12} =$ 2647 pc/h V_3 or V_{av34} 976 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)								
Capacity Checks					Capacity Checks								
		Actual	Capacity		LOS F?								
V_{FO}			Exhibit 25-7				V_F	3623	Exhibit 25-14	6780	No		
							$V_{FO} = V_F - V_R$	2576	Exhibit 25-14	6780	No		
							V_R	1047	Exhibit 25-3	2100	No		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area								
		Actual	Max Desirable		Violation?				Actual	Max Desirable		Violation?	
V_{R12}			Exhibit 25-7				V_{12}		2647	Exhibit 25-14	4400:All	No	
Level of Service Determination (if not F)					Level of Service Determination (if not F)								
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 20.9 (pc/mi/ln) $LOS =$ C (Exhibit 25-4)								
Speed Determination					Speed Determination								
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.457 (Exhibit 25-19) $S_R =$ 49.6 mph (Exhibit 25-19) $S_0 =$ 61.4 mph (Exhibit 25-19) $S =$ 52.3 mph (Exhibit 25-15)								

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 4 NB On-Ramp			
Date Performed		02/15/12		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2016 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1850$ ft $V_u = 850$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2450	0.92	Level	2	0	0.990	1.00	2690	
Ramp	560	0.92	Level	2	0	0.990	1.00	615	
UpStream	850	0.96	Level	2	0	0.990	1.00	894	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 978.71$ (Equation 25-2 or 25-3) $P_{FM} = 0.614$ using Equation (Exhibit 25-5) $V_{12} = 1652$ pc/h V_3 or $V_{av34} = 1038$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	3305	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	2267	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 14.7$ (pc/mi/ln) LOS = B (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.254$ (Exhibit 25-19) $S_R = 52.4$ mph (Exhibit 25-19) $S_0 = 54.1$ mph (Exhibit 25-19) $S = 52.9$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 5 NB Off			
Date Performed		02/15/12		Jurisdiction		NYS DOT			
Analysis Time Period		AM		Analysis Year		2016 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{up} = 7810$ ft $V_u = 560$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 35.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_P)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2500	0.92	Level	2	0	0.990	1.00	2745	
Ramp	490	0.96	Level	2	0	0.990	1.00	516	
UpStream	560	0.92	Level	2	0	0.990	1.00	615	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} = 6479.21$ (Equation 25-8 or 25-9) $P_{FD} = 0.668$ using Equation (Exhibit 25-12) $V_{12} = 2004$ pc/h V_3 or $V_{av34} = 741$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	2745	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	2229	Exhibit 25-14	6780	No	
				V_R	516	Exhibit 25-3	2000	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	2004	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 19.2$ (pc/mi/ln) $LOS = B$ (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.474$ (Exhibit 25-19) $S_R = 49.4$ mph (Exhibit 25-19) $S_0 = 61.4$ mph (Exhibit 25-19) $S = 52.1$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound			
Agency or Company		CHA		Junction		Exit 2W Off			
Date Performed		02/15/12		Jurisdiction		NYS DOT			
Analysis Time Period		AM		Analysis Year		2016 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1300 ft $V_D =$ 340 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	5200	0.92	Level	2	0	0.990	1.00	5709	
Ramp	930	0.92	Level	2	0	0.990	1.00	1021	
UpStream									
DownStream	340	0.92	Level	2	0	0.990	1.00	373	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.570 using Equation (Exhibit 25-12) $V_{12} =$ 3695 pc/h V_3 or V_{av34} 2014 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	5709	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	4688	Exhibit 25-14	6780	No	
				V_R	1021	Exhibit 25-3	2100	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	3695	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 33.3 (pc/mi/ln) $LOS =$ D (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.455 (Exhibit 25-19) $S_R =$ 49.6 mph (Exhibit 25-19) $S_0 =$ 57.5 mph (Exhibit 25-19) $S =$ 52.1 mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET														
General Information					Site Information									
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87								
Agency or Company		CHA		Junction		Exit 4 SB Off								
Date Performed		02/15/12		Jurisdiction		NYS DOT								
Analysis Time Period		AM		Analysis Year		2016 Diamond								
Project Description Exit 4														
Inputs														
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1820 ft $V_D =$ 510 veh/h							
Conversion to pc/h Under Base Conditions														
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$						
Freeway	5350	0.92	Level	2	0	0.990	1.00	5873						
Ramp	630	0.92	Level	2	0	0.990	1.00	692						
UpStream														
DownStream	510	0.93	Level	5	0	0.976	1.00	562						
Merge Areas					Diverge Areas									
Estimation of v_{12}					Estimation of v_{12}									
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ $P_{FD} = 0.581$ using Equation (Exhibit 25-12) $V_{12} = 3704$ pc/h V_3 or V_{av34} 2169 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)									
Capacity Checks					Capacity Checks									
		Actual	Capacity		LOS F?									
V_{FO}		Exhibit 25-7					V_F	5873	Exhibit 25-14	6780	No			
							$V_{FO} = V_F - V_R$	5181	Exhibit 25-14	6780	No			
							V_R	692	Exhibit 25-3	2100	No			
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area									
		Actual	Max Desirable		Violation?				Actual	Max Desirable		Violation?		
V_{R12}			Exhibit 25-7						V_{12}	3704	Exhibit 25-14		4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)									
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 29.8$ (pc/mi/ln) $LOS = D$ (Exhibit 25-4)									
Speed Determination					Speed Determination									
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.425$ (Exhibit 25-19) $S_R = 50.0$ mph (Exhibit 25-19) $S_0 = 56.9$ mph (Exhibit 25-19) $S = 52.4$ mph (Exhibit 25-15)									


RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 4 SB On-Ramp			
Date Performed		02/15/12		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2016 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1820$ ft $V_u = 630$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4700	0.92	Level	2	0	0.990	1.00	5160	
Ramp	510	0.93	Level	5	0	0.976	1.00	562	
UpStream	630	0.92	Level	2	0	0.990	1.00	692	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 1493.73$ (Equation 25-2 or 25-3) $P_{FM} = 0.614$ using Equation (Exhibit 25-5) $V_{12} = 3168$ pc/h V_3 or $V_{av34} = 1992$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	5722	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	3730	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 26.1$ (pc/mi/ln) LOS = C (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.379$ (Exhibit 25-19) $S_R = 50.7$ mph (Exhibit 25-19) $S_0 = 50.6$ mph (Exhibit 25-19) $S = 50.7$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 5 SB On-Ramp			
Date Performed		02/15/12		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2016 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_I)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{down} =$ 6100 ft $V_D =$ 630 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	5100	0.92	Level	2	0	0.990	1.00	5599	
Ramp	250	0.93	Level	3	0	0.985	1.00	273	
UpStream									
DownStream	630	0.92	Level	2	0	0.990	1.00	692	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 2782.47$ (Equation 25-2 or 25-3) $P_{FM} = 0.614$ using Equation (Exhibit 25-5) $V_{12} = 3437$ pc/h V_3 or $V_{av34} = 2162$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	5872	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	3710	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 26.1$ (pc/mi/ln) LOS = C (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.376$ (Exhibit 25-19) $S_R = 50.7$ mph (Exhibit 25-19) $S_0 = 50.0$ mph (Exhibit 25-19) $S = 50.5$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB					Freeway/Dir of Travel I-87 Northbound				
Agency/Company CHA					Weaving Seg Location Exit 2E on to 2W off				
Date Performed 02/15/12					Jurisdiction NYSDOT				
Analysis Time Period AM					Analysis Year 2016 Diamond				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56					Weaving type A				
Weaving number of lanes, N 4					Volume ratio, VR 0.27				
Weaving seg length, L (ft) 815					Weaving ratio, R 0.31				
Terrain Level									
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	2600	0.92	2	0	1.5	1.2	0.990	1.00	2854
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	660	0.92	2	0	1.5	1.2	0.990	1.00	724
V_{w2}	300	0.92	2	0	1.5	1.2	0.990	1.00	329
V_w				1053	V_{nw}				2854
V									3907
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	0.94		0.46						
Weaving and non-weaving speeds, S_i (mi/h)	38.65		46.52						
Number of lanes required for unconstrained operation, N_w					1.36				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					44.10				
Weaving segment density, D (pc/mi/ln)					22.15				
Level of service, LOS					C				
Capacity of base condition, c_b (pc/h)					6357				
Capacity as a 15-minute flow rate, c (veh/h)					6294				
Capacity as a full-hour volume, c_h (veh/h)					5790				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 02/15/12 Analysis Time Period AM					Freeway/Dir of Travel I-87 Southbound Weaving Seg Location Exit 2W on to 2E off Jurisdiction NYSDOT Analysis Year 2016 Diamond				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 810 Terrain Level					Weaving type A Volume ratio, VR 0.23 Weaving ratio, R 0.32				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	3530	0.92	2	0	1.5	1.2	0.990	1.00	3875
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	720	0.92	2	0	1.5	1.2	0.990	1.00	790
V_{w2}	340	0.92	2	0	1.5	1.2	0.990	1.00	373
V_w				1163	V_{nw}				3875
V									5038
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	1.13		0.57						
Weaving and non-weaving speeds, S_i (mi/h)	36.55		44.35						
Number of lanes required for unconstrained operation, N_w					1.27				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					42.27				
Weaving segment density, D (pc/mi/ln)					29.80				
Level of service, LOS					D				
Capacity of base condition, c_b (pc/h)					6565				
Capacity as a 15-minute flow rate, c (veh/h)					6500				
Capacity as a full-hour volume, c_h (veh/h)					5980				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 2 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *3500* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1281* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *22.9* pc/mi/ln
 LOS *C*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 to Exit 2*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5250* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1921* pc/h/ln
 S *55.6* mi/h
 $D = v_p / S$ *34.6* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2550* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *933* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *16.7* pc/mi/ln
 LOS *B*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *4900* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.92*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1793* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *32.0* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 to Exit 5*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2600* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *951* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *17.0* pc/mi/ln
 LOS *B*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 5 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5600* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *2049* pc/h/ln
 S *54.4* mi/h
 $D = v_p / S$ *37.7* pc/mi/ln
 LOS *E*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *CLD*
 Agency or Company *CHA*
 Date Performed *7/30/13*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 5 to Exit 6*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2550* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *4*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *700* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *12.5* pc/mi/ln
 LOS *B*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *CLD*
 Agency or Company *CHA*
 Date Performed *07/30/13*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 6 to Exit 5*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *6200* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *4*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1702* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *30.4* pc/mi/ln
 LOS *D*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 2W On-Ramp			
Date Performed		02/15/12		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2026 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1100$ ft $V_u = 670$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	3100	0.92	Level	2	0	0.990	1.00	3403	
Ramp	390	0.92	Level	2	0	0.990	1.00	428	
UpStream	670	0.92	Level	2	0	0.990	1.00	736	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 887.03$ (Equation 25-2 or 25-3) $P_{FM} = 0.601$ using Equation (Exhibit 25-5) $V_{12} = 2046$ pc/h V_3 or $V_{av34} = 1357$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	3831	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	2474	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 19.2$ (pc/mi/ln) LOS = B (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.299$ (Exhibit 25-19) $S_R = 51.8$ mph (Exhibit 25-19) $S_0 = 52.9$ mph (Exhibit 25-19) $S = 52.2$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET														
General Information					Site Information									
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87								
Agency or Company		CHA		Junction		Exit 4 NB Off								
Date Performed		02/15/12		Jurisdiction		NYS DOT								
Analysis Time Period		AM		Analysis Year		2026 Diamond								
Project Description Exit 4														
Inputs														
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1850 ft $V_D =$ 570 veh/h							
Conversion to pc/h Under Base Conditions														
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$						
Freeway	3500	0.92	Level	2	0	0.990	1.00	3842						
Ramp	950	0.82	Level	2	0	0.990	1.00	1170						
UpStream														
DownStream	570	0.92	Level	2	0	0.990	1.00	626						
Merge Areas					Diverge Areas									
Estimation of v_{12}					Estimation of v_{12}									
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ using Equation (Exhibit 25-5) $P_{FM} =$ pc/h $V_{12} =$ pc/h (Equation 25-4 or 25-5) V_3 or V_{av34} pc/h Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ using Equation (Exhibit 25-12) $P_{FD} =$ 0.610 $V_{12} =$ 2800 pc/h V_3 or V_{av34} 1042 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)									
Capacity Checks					Capacity Checks									
		Actual	Capacity		LOS F?									
V_{FO}		Exhibit 25-7					V_F	3842	Exhibit 25-14	6780	No			
							$V_{FO} = V_F - V_R$	2672	Exhibit 25-14	6780	No			
							V_R	1170	Exhibit 25-3	2100	No			
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area									
		Actual	Max Desirable		Violation?				Actual	Max Desirable		Violation?		
V_{R12}		Exhibit 25-7					V_{12}		2800	Exhibit 25-14		4400:All		No
Level of Service Determination (if not F)					Level of Service Determination (if not F)									
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 22.2 (pc/mi/ln) $LOS =$ C (Exhibit 25-4)									
Speed Determination					Speed Determination									
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.468 (Exhibit 25-19) $S_R =$ 49.4 mph (Exhibit 25-19) $S_0 =$ 61.3 mph (Exhibit 25-19) $S =$ 52.2 mph (Exhibit 25-15)									

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 4 NB On-Ramp			
Date Performed		02/15/12		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2026 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1850$ ft $V_u = 950$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_l)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2550	0.92	Level	2	0	0.990	1.00	2799	
Ramp	570	0.92	Level	2	0	0.990	1.00	626	
UpStream	950	0.96	Level	2	0	0.990	1.00	999	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 1004.39$ (Equation 25-2 or 25-3) $P_{FM} = 0.614$ using Equation (Exhibit 25-5) $V_{12} = 1719$ pc/h V_3 or $V_{av34} = 1080$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	3425	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	2345	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 15.3$ (pc/mi/ln) LOS = B (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.257$ (Exhibit 25-19) $S_R = 52.4$ mph (Exhibit 25-19) $S_0 = 53.9$ mph (Exhibit 25-19) $S = 52.9$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 5 NB Off			
Date Performed		02/15/12		Jurisdiction		NYS DOT			
Analysis Time Period		AM		Analysis Year		2026 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{up} = 7810$ ft $V_u = 570$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 35.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2600	0.92	Level	2	0	0.990	1.00	2854	
Ramp	490	0.96	Level	2	0	0.990	1.00	516	
UpStream	570	0.92	Level	2	0	0.990	1.00	626	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} = 6425.39$ (Equation 25-8 or 25-9) $P_{FD} = 0.665$ using Equation (Exhibit 25-12) $V_{12} = 2071$ pc/h V_3 or $V_{av34} = 783$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	2854	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	2338	Exhibit 25-14	6780	No	
				V_R	516	Exhibit 25-3	2000	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	2071	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 19.8$ (pc/mi/ln) $LOS = B$ (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.474$ (Exhibit 25-19) $S_R = 49.4$ mph (Exhibit 25-19) $S_0 = 61.4$ mph (Exhibit 25-19) $S = 52.2$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound			
Agency or Company		CHA		Junction		Exit 2W Off			
Date Performed		02/15/12		Jurisdiction		NYS DOT			
Analysis Time Period		AM		Analysis Year		2026 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1300 ft $V_D =$ 340 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	5250	0.92	Level	2	0	0.990	1.00	5764	
Ramp	940	0.92	Level	2	0	0.990	1.00	1032	
UpStream									
DownStream	340	0.92	Level	2	0	0.990	1.00	373	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.568 using Equation (Exhibit 25-12) $V_{12} =$ 3722 pc/h V_3 or V_{av34} 2042 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	5764	Exhibit 25-14	6780	No
					$V_{FO} = V_F - V_R$	4732	Exhibit 25-14	6780	No
					V_R	1032	Exhibit 25-3	2100	No
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	3722	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 33.6 (pc/mi/ln) $LOS =$ D (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.456 (Exhibit 25-19) $S_R =$ 49.6 mph (Exhibit 25-19) $S_0 =$ 57.4 mph (Exhibit 25-19) $S =$ 52.1 mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET													
General Information					Site Information								
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87							
Agency or Company		CHA		Junction		Exit 4 SB Off							
Date Performed		02/15/12		Jurisdiction		NYS DOT							
Analysis Time Period		AM		Analysis Year		2026 Diamond							
Project Description Exit 4													
Inputs													
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1820 ft $V_D =$ 510 veh/h						
Conversion to pc/h Under Base Conditions													
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$					
Freeway	5600	0.92	Level	2	0	0.990	1.00	6148					
Ramp	690	0.92	Level	2	0	0.990	1.00	757					
UpStream													
DownStream	510	0.93	Level	5	0	0.976	1.00	562					
Merge Areas					Diverge Areas								
Estimation of v_{12}					Estimation of v_{12}								
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ $P_{FD} = 0.571$ using Equation (Exhibit 25-12) $V_{12} = 3838$ pc/h V_3 or $V_{av34} 2310$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)								
Capacity Checks					Capacity Checks								
		Actual	Capacity		LOS F?								
V_{FO}		Exhibit 25-7					V_F	6148	Exhibit 25-14	6780	No		
							$V_{FO} = V_F - V_R$	5391	Exhibit 25-14	6780	No		
							V_R	757	Exhibit 25-3	2100	No		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area								
		Actual	Max Desirable		Violation?				Actual	Max Desirable		Violation?	
V_{R12}			Exhibit 25-7				V_{12}		3838	Exhibit 25-14	4400:All	No	
Level of Service Determination (if not F)					Level of Service Determination (if not F)								
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 31.0$ (pc/mi/ln) $LOS = D$ (Exhibit 25-4)								
Speed Determination					Speed Determination								
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.431$ (Exhibit 25-19) $S_R = 50.0$ mph (Exhibit 25-19) $S_0 = 56.3$ mph (Exhibit 25-19) $S = 52.2$ mph (Exhibit 25-15)								


RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 4 SB On-Ramp			
Date Performed		02/15/12		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2026 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1820$ ft $V_u = 690$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4900	0.92	Level	2	0	0.990	1.00	5379	
Ramp	510	0.93	Level	5	0	0.976	1.00	562	
UpStream	690	0.92	Level	2	0	0.990	1.00	757	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 1540.59$ (Equation 25-2 or 25-3) $P_{FM} = 0.614$ using Equation (Exhibit 25-5) $V_{12} = 3303$ pc/h V_3 or $V_{av34} = 2076$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	5941	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	3865	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 27.2$ (pc/mi/ln) LOS = C (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.403$ (Exhibit 25-19) $S_R = 50.4$ mph (Exhibit 25-19) $S_0 = 50.3$ mph (Exhibit 25-19) $S = 50.4$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 5 SB On-Ramp			
Date Performed		02/15/12		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2026 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{down} =$ 6100 ft $V_D =$ 690 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	5300	0.92	Level	2	0	0.990	1.00	5818	
Ramp	300	0.93	Level	3	0	0.985	1.00	327	
UpStream									
DownStream	690	0.92	Level	2	0	0.990	1.00	757	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 3043.83$ (Equation 25-2 or 25-3) $P_{FM} = 0.614$ using Equation (Exhibit 25-5) $V_{12} = 3572$ pc/h V_3 or $V_{av34} = 2246$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	6145	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	3899	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 27.6$ (pc/mi/ln) LOS = C (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.409$ (Exhibit 25-19) $S_R = 50.3$ mph (Exhibit 25-19) $S_0 = 49.7$ mph (Exhibit 25-19) $S = 50.1$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 02/15/12 Analysis Time Period AM					Freeway/Dir of Travel I-87 Northbound Weaving Seg Location Exit 2E on to 2W off Jurisdiction NYSDOT Analysis Year 2026 Diamond				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 815 Terrain Level					Weaving type A Volume ratio, VR 0.26 Weaving ratio, R 0.32				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	2790	0.92	2	0	1.5	1.2	0.990	1.00	3062
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	670	0.92	2	0	1.5	1.2	0.990	1.00	735
V_{w2}	310	0.92	2	0	1.5	1.2	0.990	1.00	340
V_w				1075	V_{nw}				3062
V									4137
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	0.98		0.48						
Weaving and non-weaving speeds, S_i (mi/h)	38.21		46.09						
Number of lanes required for unconstrained operation, N_w					1.33				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					43.74				
Weaving segment density, D (pc/mi/ln)					23.64				
Level of service, LOS					C				
Capacity of base condition, c_b (pc/h)					6411				
Capacity as a 15-minute flow rate, c (veh/h)					6348				
Capacity as a full-hour volume, c_h (veh/h)					5840				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 02/15/12 Analysis Time Period AM					Freeway/Dir of Travel I-87 Southbound Weaving Seg Location Exit 2W on to 2E off Jurisdiction NYSDOT Analysis Year 2026 Diamond				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 810 Terrain Level					Weaving type A Volume ratio, VR 0.23 Weaving ratio, R 0.31				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	3550	0.92	2	0	1.5	1.2	0.990	1.00	3897
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	750	0.92	2	0	1.5	1.2	0.990	1.00	823
V_{w2}	340	0.92	2	0	1.5	1.2	0.990	1.00	373
V_w				1196	V_{nw}				3897
V									5093
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	1.16		0.58						
Weaving and non-weaving speeds, S_i (mi/h)	36.35		44.06						
Number of lanes required for unconstrained operation, N_w					1.29				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					41.97				
Weaving segment density, D (pc/mi/ln)					30.34				
Level of service, LOS					D				
Capacity of base condition, c_b (pc/h)					6543				
Capacity as a 15-minute flow rate, c (veh/h)					6478				
Capacity as a full-hour volume, c_h (veh/h)					5960				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 2 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *3650* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1336* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *23.9* pc/mi/ln
 LOS *C*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 to Exit 2*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5300* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1939* pc/h/ln
 S *55.4* mi/h
 $D = v_p / S$ *35.0* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2560* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *937* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *16.7* pc/mi/ln
 LOS *B*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5100* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1866* pc/h/ln
 S *55.8* mi/h
 $D = v_p / S$ *33.4* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 to Exit 5*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2650* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *970* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *17.3* pc/mi/ln
 LOS *B*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 5 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5850* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *2141* pc/h/ln
 S *53.0* mi/h
 $D = v_p / S$ *40.4* pc/mi/ln
 LOS *E*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary


N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET																										
			<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Application</th> <th>Input</th> <th>Output</th> </tr> </thead> <tbody> <tr> <td>Operational (LOS)</td> <td>FFS, N, v_p</td> <td>LOS, S, D</td> </tr> <tr> <td>Design (N)</td> <td>FFS, LOS, v_p</td> <td>N, S, D</td> </tr> <tr> <td>Design (v_p)</td> <td>FFS, LOS, N</td> <td>v_p, S, D</td> </tr> <tr> <td>Planning (LOS)</td> <td>FFS, N, AADT</td> <td>LOS, S, D</td> </tr> <tr> <td>Planning (N)</td> <td>FFS, LOS, AADT</td> <td>N, S, D</td> </tr> <tr> <td>Planning (v_p)</td> <td>FFS, LOS, N</td> <td>v_p, S, D</td> </tr> </tbody> </table>			Application	Input	Output	Operational (LOS)	FFS, N, v_p	LOS, S, D	Design (N)	FFS, LOS, v_p	N, S, D	Design (v_p)	FFS, LOS, N	v_p , S, D	Planning (LOS)	FFS, N, AADT	LOS, S, D	Planning (N)	FFS, LOS, AADT	N, S, D	Planning (v_p)	FFS, LOS, N	v_p , S, D
Application	Input	Output																								
Operational (LOS)	FFS, N, v_p	LOS, S, D																								
Design (N)	FFS, LOS, v_p	N, S, D																								
Design (v_p)	FFS, LOS, N	v_p , S, D																								
Planning (LOS)	FFS, N, AADT	LOS, S, D																								
Planning (N)	FFS, LOS, AADT	N, S, D																								
Planning (v_p)	FFS, LOS, N	v_p , S, D																								
General Information			Site Information																							
Analyst		CLD		Highway/Direction of Travel																						
Agency or Company		CHA		Northbound I-87																						
Date Performed		07/30/13		From/To																						
Analysis Time Period		AM		Exit 5 to Exit 6																						
Project Description		Exit 4		Jurisdiction																						
				NYSDOT																						
				Analysis Year																						
				2036 Diamond																						
<input checked="" type="checkbox"/> Oper.(LOS) <input type="checkbox"/> Des.(N) <input type="checkbox"/> Planning Data																										
Flow Inputs																										
Volume, V		2550		veh/h																						
AADT				veh/day																						
Peak-Hr Prop. of AADT, K				Peak-Hour Factor, PHF																						
Peak-Hr Direction Prop, D				0.92																						
DDHV = AADT x K x D				%Trucks and Buses, P_T																						
Driver type adjustment		1.00		2																						
				%RVs, P_R																						
				0																						
				General Terrain:																						
				Level																						
				Grade % Length																						
				mi																						
				Up/Down %																						
Calculate Flow Adjustments																										
f_p		1.00		E_R																						
E_T		1.5		1.2																						
				$f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$																						
				0.990																						
Speed Inputs			Calc Speed Adj and FFS																							
Lane Width		12.0		ft																						
Rt-Shoulder Lat. Clearance		6.0		ft																						
Interchange Density		0.50		l/mi																						
Number of Lanes, N		4																								
FFS (measured)		56.0		mi/h																						
Base free-flow Speed, BFFS				mi/h																						
				FFS																						
				56.0																						
				mi/h																						
LOS and Performance Measures			Design (N)																							
<u>Operational (LOS)</u>			<u>Design (N)</u>																							
$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$			Design LOS																							
700			$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$																							
pc/h/ln			pc/h																							
S			S																							
56.0			mi/h																							
D = v_p / S			D = v_p / S																							
12.5			pc/mi/ln																							
LOS			Required Number of Lanes, N																							
B																										
Glossary			Factor Location																							
N - Number of lanes			S - Speed																							
V - Hourly volume			D - Density																							
v_p - Flow rate			FFS - Free-flow speed																							
LOS - Level of service			BFFS - Base free-flow speed																							
DDHV - Directional design hour volume																										
			E _R - Exhibits 23-8, 23-10																							
			E _T - Exhibits 23-8, 23-10, 23-11																							
			f _p - Page 23-12																							
			LOS, S, FFS, v_p - Exhibits 23-2, 23-3																							
			f _{LW} - Exhibit 23-4																							
			f _{LC} - Exhibit 23-5																							
			f _N - Exhibit 23-6																							
			f _{ID} - Exhibit 23-7																							

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *CLD*
 Agency or Company *CHA*
 Date Performed *07/30/13*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 6 to Exit 5*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *6300* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *4*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1729* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *30.9* pc/mi/ln
 LOS *D*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 2W On-Ramp			
Date Performed		02/15/12		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2036 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1100$ ft $V_u = 680$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	3250	0.92	Level	2	0	0.990	1.00	3568	
Ramp	400	0.92	Level	2	0	0.990	1.00	439	
UpStream	680	0.92	Level	2	0	0.990	1.00	747	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 924.70$ (Equation 25-2 or 25-3) $P_{FM} = 0.601$ using Equation (Exhibit 25-5) $V_{12} = 2145$ pc/h V_3 or $V_{av34} = 1423$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	4007	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	2584	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 20.1$ (pc/mi/ln) LOS = C (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.305$ (Exhibit 25-19) $S_R = 51.7$ mph (Exhibit 25-19) $S_0 = 52.7$ mph (Exhibit 25-19) $S = 52.1$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 4 NB Off			
Date Performed		02/15/12		Jurisdiction		NYS DOT			
Analysis Time Period		AM		Analysis Year		2036 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1850 ft $V_D =$ 590 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	3650	0.92	Level	2	0	0.990	1.00	4007	
Ramp	1060	0.82	Level	2	0	0.990	1.00	1306	
UpStream									
DownStream	590	0.92	Level	2	0	0.990	1.00	648	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.600 using Equation (Exhibit 25-12) $V_{12} =$ 2926 pc/h V_3 or V_{av34} 1081 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	4007	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	2701	Exhibit 25-14	6780	No	
				V_R	1306	Exhibit 25-3	2100	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	2926	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 23.3 (pc/mi/ln) $LOS =$ C (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.481 (Exhibit 25-19) $S_R =$ 49.3 mph (Exhibit 25-19) $S_0 =$ 61.1 mph (Exhibit 25-19) $S =$ 52.0 mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 4 NB On-Ramp			
Date Performed		02/15/12		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2036 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1850$ ft $V_u = 1060$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2560	0.92	Level	2	0	0.990	1.00	2810	
Ramp	590	0.92	Level	2	0	0.990	1.00	648	
UpStream	1060	0.96	Level	2	0	0.990	1.00	1115	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 1011.45$ (Equation 25-2 or 25-3) $P_{FM} = 0.614$ using Equation (Exhibit 25-5) $V_{12} = 1726$ pc/h V_3 or $V_{av34} = 1084$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	3458	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	2374	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 15.5$ (pc/mi/ln) LOS = B (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.258$ (Exhibit 25-19) $S_R = 52.4$ mph (Exhibit 25-19) $S_0 = 53.9$ mph (Exhibit 25-19) $S = 52.9$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 5 NB Off			
Date Performed		02/15/12		Jurisdiction		NYS DOT			
Analysis Time Period		AM		Analysis Year		2036 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{up} = 7810$ ft $V_u = 590$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 35.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2650	0.92	Level	2	0	0.990	1.00	2909	
Ramp	500	0.96	Level	2	0	0.990	1.00	526	
UpStream	590	0.92	Level	2	0	0.990	1.00	648	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} = 6616.90$ (Equation 25-8 or 25-9) $P_{FD} = 0.663$ using Equation (Exhibit 25-12) $V_{12} = 2106$ pc/h V_3 or $V_{av34} = 803$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	2909	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	2383	Exhibit 25-14	6780	No	
				V_R	526	Exhibit 25-3	2000	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	2106	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 20.1$ (pc/mi/ln) LOS = C (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.475$ (Exhibit 25-19) $S_R = 49.3$ mph (Exhibit 25-19) $S_0 = 61.4$ mph (Exhibit 25-19) $S = 52.2$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound			
Agency or Company		CHA		Junction		Exit 2W Off			
Date Performed		02/15/12		Jurisdiction		NYS DOT			
Analysis Time Period		AM		Analysis Year		2036 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1300 ft $V_D =$ 350 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	5300	0.92	Level	2	0	0.990	1.00	5818	
Ramp	960	0.92	Level	2	0	0.990	1.00	1054	
UpStream									
DownStream	350	0.92	Level	2	0	0.990	1.00	384	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.566 using Equation (Exhibit 25-12) $V_{12} =$ 3751 pc/h V_3 or V_{av34} 2067 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	5818	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	4764	Exhibit 25-14	6780	No	
				V_R	1054	Exhibit 25-3	2100	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	3751	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 33.8 (pc/mi/ln) $LOS =$ D (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.458 (Exhibit 25-19) $S_R =$ 49.6 mph (Exhibit 25-19) $S_0 =$ 57.3 mph (Exhibit 25-19) $S =$ 52.1 mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET													
General Information					Site Information								
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87							
Agency or Company		CHA		Junction		Exit 4 SB Off							
Date Performed		02/15/12		Jurisdiction		NYS DOT							
Analysis Time Period		AM		Analysis Year		2036 Diamond							
Project Description Exit 4													
Inputs													
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1820 ft $V_D =$ 510 veh/h						
Conversion to pc/h Under Base Conditions													
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$					
Freeway	5850	0.92	Level	2	0	0.990	1.00	6422					
Ramp	760	0.92	Level	2	0	0.990	1.00	834					
UpStream													
DownStream	510	0.93	Level	5	0	0.976	1.00	562					
Merge Areas					Diverge Areas								
Estimation of v_{12}					Estimation of v_{12}								
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ $P_{FD} = 0.561$ using Equation (Exhibit 25-12) $V_{12} = 3969$ pc/h V_3 or V_{av34} 2453 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)								
Capacity Checks					Capacity Checks								
		Actual	Capacity		LOS F?								
V_{FO}		Exhibit 25-7					V_F	6422	Exhibit 25-14	6780	No		
							$V_{FO} = V_F - V_R$	5588	Exhibit 25-14	6780	No		
							V_R	834	Exhibit 25-3	2100	No		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area								
		Actual	Max Desirable		Violation?				Actual	Max Desirable		Violation?	
V_{R12}			Exhibit 25-7				V_{12}		3969	Exhibit 25-14	4400:All	No	
Level of Service Determination (if not F)					Level of Service Determination (if not F)								
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 32.1$ (pc/mi/ln) $LOS = D$ (Exhibit 25-4)								
Speed Determination					Speed Determination								
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.438$ (Exhibit 25-19) $S_R = 49.9$ mph (Exhibit 25-19) $S_0 = 55.8$ mph (Exhibit 25-19) $S = 52.0$ mph (Exhibit 25-15)								


RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 4 SB On-Ramp			
Date Performed		02/15/12		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2036 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1820$ ft $V_u = 760$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	5100	0.92	Level	2	0	0.990	1.00	5599	
Ramp	510	0.93	Level	5	0	0.976	1.00	562	
UpStream	760	0.92	Level	2	0	0.990	1.00	834	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 1587.67$ (Equation 25-2 or 25-3) $P_{FM} = 0.614$ using Equation (Exhibit 25-5) $V_{12} = 3438$ pc/h V_3 or $V_{av34} = 2161$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	6161	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	4000	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 28.2$ (pc/mi/ln) LOS = D (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.430$ (Exhibit 25-19) $S_R = 50.0$ mph (Exhibit 25-19) $S_0 = 50.0$ mph (Exhibit 25-19) $S = 50.0$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 5 SB On-Ramp			
Date Performed		02/15/12		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2036 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{down} =$ 6100 ft $V_D =$ 760 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	5500	0.92	Level	2	0	0.990	1.00	6038	
Ramp	370	0.93	Level	3	0	0.985	1.00	404	
UpStream									
DownStream	760	0.92	Level	2	0	0.990	1.00	834	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 3353.44$ (Equation 25-2 or 25-3) $P_{FM} = 0.614$ using Equation (Exhibit 25-5) $V_{12} = 3707$ pc/h V_3 or $V_{av34} = 2331$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	6442	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	4111	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 29.2$ (pc/mi/ln) LOS = D (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.455$ (Exhibit 25-19) $S_R = 49.6$ mph (Exhibit 25-19) $S_0 = 49.3$ mph (Exhibit 25-19) $S = 49.5$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 02/15/12 Analysis Time Period AM					Freeway/Dir of Travel I-87 Northbound Weaving Seg Location Exit 2E on to 2W off Jurisdiction NYSDOT Analysis Year 2036 Diamond				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 815 Terrain Level					Weaving type A Volume ratio, VR 0.25 Weaving ratio, R 0.32				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	2930	0.92	2	0	1.5	1.2	0.990	1.00	3216
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	680	0.92	2	0	1.5	1.2	0.990	1.00	746
V_{w2}	320	0.92	2	0	1.5	1.2	0.990	1.00	351
V_w				1097	V_{nw}				3216
V									4313
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	1.01		0.50						
Weaving and non-weaving speeds, S_i (mi/h)	37.86		45.72						
Number of lanes required for unconstrained operation, N_w					1.32				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					43.42				
Weaving segment density, D (pc/mi/ln)					24.83				
Level of service, LOS					C				
Capacity of base condition, c_b (pc/h)					6442				
Capacity as a 15-minute flow rate, c (veh/h)					6378				
Capacity as a full-hour volume, c_h (veh/h)					5868				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 02/15/12 Analysis Time Period AM					Freeway/Dir of Travel I-87 Southbound Weaving Seg Location Exit 2W on to 2E off Jurisdiction NYSDOT Analysis Year 2036 Diamond				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 810 Terrain Level					Weaving type A Volume ratio, VR 0.24 Weaving ratio, R 0.31				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	3570	0.92	2	0	1.5	1.2	0.990	1.00	3919
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	780	0.92	2	0	1.5	1.2	0.990	1.00	856
V_{w2}	350	0.92	2	0	1.5	1.2	0.990	1.00	384
V_w				1240	V_{nw}				3919
V									5159
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	1.18		0.60						
Weaving and non-weaving speeds, S_i (mi/h)	36.09		43.69						
Number of lanes required for unconstrained operation, N_w					1.31				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					41.59				
Weaving segment density, D (pc/mi/ln)					31.01				
Level of service, LOS					D				
Capacity of base condition, c_b (pc/h)					6512				
Capacity as a 15-minute flow rate, c (veh/h)					6448				
Capacity as a full-hour volume, c_h (veh/h)					5932				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2046 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2600* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *951* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *17.0* pc/mi/ln
 LOS *B*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2046 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5050* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1848* pc/h/ln
 S *55.9* mi/h
 $D = v_p / S$ *33.1* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *12/12/2011*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 to Exit 5*
 Jurisdiction *NYSDOT*
 Analysis Year *2046 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2650* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *970* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *17.3* pc/mi/ln
 LOS *B*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 5 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2046 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5850* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *2141* pc/h/ln
 S *53.0* mi/h
 $D = v_p / S$ *40.4* pc/mi/ln
 LOS *E*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 2 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5400* veh/h Peak-Hour Factor, PHF *0.86*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *2114* pc/h/ln
 S *53.5* mi/h
 $D = v_p / S$ *39.5* pc/mi/ln
 LOS *E*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 to Exit 2*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *3850* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1409* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *25.2* pc/mi/ln
 LOS *C*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *4450* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.86*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1742* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *31.1* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2700* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *988* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *17.6* pc/mi/ln
 LOS *B*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 to Exit 5*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5650* veh/h Peak-Hour Factor, PHF *0.86*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *2212* pc/h/ln
 S *51.5* mi/h
 $D = v_p / S$ *43.0* pc/mi/ln
 LOS *E*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 5 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *3650* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1336* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *23.9* pc/mi/ln
 LOS *C*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *CLD*
 Agency or Company *CHA*
 Date Performed *07/29/13*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 5 to Exit 6*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5750* veh/h Peak-Hour Factor, PHF *0.86*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *4*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1688* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *30.1* pc/mi/ln
 LOS *D*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET																										
			<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Application</th> <th>Input</th> <th>Output</th> </tr> </thead> <tbody> <tr> <td>Operational (LOS)</td> <td>FFS, N, v_p</td> <td>LOS, S, D</td> </tr> <tr> <td>Design (N)</td> <td>FFS, LOS, v_p</td> <td>N, S, D</td> </tr> <tr> <td>Design (v_p)</td> <td>FFS, LOS, N</td> <td>v_p, S, D</td> </tr> <tr> <td>Planning (LOS)</td> <td>FFS, N, AADT</td> <td>LOS, S, D</td> </tr> <tr> <td>Planning (N)</td> <td>FFS, LOS, AADT</td> <td>N, S, D</td> </tr> <tr> <td>Planning (v_p)</td> <td>FFS, LOS, N</td> <td>v_p, S, D</td> </tr> </tbody> </table>			Application	Input	Output	Operational (LOS)	FFS, N, v_p	LOS, S, D	Design (N)	FFS, LOS, v_p	N, S, D	Design (v_p)	FFS, LOS, N	v_p , S, D	Planning (LOS)	FFS, N, AADT	LOS, S, D	Planning (N)	FFS, LOS, AADT	N, S, D	Planning (v_p)	FFS, LOS, N	v_p , S, D
Application	Input	Output																								
Operational (LOS)	FFS, N, v_p	LOS, S, D																								
Design (N)	FFS, LOS, v_p	N, S, D																								
Design (v_p)	FFS, LOS, N	v_p , S, D																								
Planning (LOS)	FFS, N, AADT	LOS, S, D																								
Planning (N)	FFS, LOS, AADT	N, S, D																								
Planning (v_p)	FFS, LOS, N	v_p , S, D																								
General Information			Site Information																							
Analyst		CLD		Highway/Direction of Travel																						
Agency or Company		CHA		Southbound I-87																						
Date Performed		7/29/13		From/To																						
Analysis Time Period		PM		Exit 6 to Exit 5																						
				Jurisdiction																						
				NYSDOT																						
Project Description		Exit 4		Analysis Year																						
				2016 Diamond																						
<input checked="" type="checkbox"/> Oper.(LOS)			<input type="checkbox"/> Des.(N)		<input type="checkbox"/> Planning Data																					
Flow Inputs																										
Volume, V		3500		veh/h																						
AADT				veh/day																						
Peak-Hr Prop. of AADT, K				Peak-Hour Factor, PHF																						
Peak-Hr Direction Prop, D				0.92																						
DDHV = AADT x K x D				%Trucks and Buses, P_T																						
Driver type adjustment		1.00		2																						
				%RVs, P_R																						
				0																						
				General Terrain:																						
				Level																						
				Grade % Length																						
				mi																						
				Up/Down %																						
Calculate Flow Adjustments																										
f_p		1.00		E_R																						
E_T		1.5		1.2																						
				$f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$																						
				0.990																						
Speed Inputs			Calc Speed Adj and FFS																							
Lane Width		12.0		ft																						
Rt-Shoulder Lat. Clearance		6.0		ft																						
Interchange Density		0.50		l/mi																						
Number of Lanes, N		4																								
FFS (measured)		56.0		mi/h																						
Base free-flow Speed, BFFS				mi/h																						
				FFS																						
				56.0																						
				mi/h																						
LOS and Performance Measures			Design (N)																							
<u>Operational (LOS)</u>			<u>Design (N)</u>																							
$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$			Design LOS																							
961			$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$																							
pc/h/ln			pc/h																							
S			S																							
56.0			mi/h																							
$D = v_p / S$			$D = v_p / S$																							
17.2			pc/mi/ln																							
LOS			Required Number of Lanes, N																							
B																										
Glossary			Factor Location																							
N - Number of lanes			S - Speed																							
V - Hourly volume			D - Density																							
v_p - Flow rate			FFS - Free-flow speed																							
LOS - Level of service			BFFS - Base free-flow speed																							
DDHV - Directional design hour volume																										
			E_R - Exhibits 23-8, 23-10																							
			E_T - Exhibits 23-8, 23-10, 23-11																							
			f_p - Page 23-12																							
			LOS, S, FFS, v_p - Exhibits 23-2, 23-3																							
			f_{LW} - Exhibit 23-4																							
			f_{LC} - Exhibit 23-5																							
			f_N - Exhibit 23-6																							
			f_{ID} - Exhibit 23-7																							

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 2W On-Ramp			
Date Performed		02/15/12		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2016 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1100$ ft $V_u = 800$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4650	0.86	Level	2	0	0.990	1.00	5461	
Ramp	770	0.92	Level	2	0	0.990	1.00	845	
UpStream	800	0.92	Level	2	0	0.990	1.00	878	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 1416.68$ (Equation 25-2 or 25-3) $P_{FM} = 0.581$ using Equation (Exhibit 25-5) $V_{12} = 3174$ pc/h V_3 or $V_{av34} = 2287$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	6306	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	4019	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 31.1$ (pc/mi/ln) LOS = D (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.470$ (Exhibit 25-19) $S_R = 49.4$ mph (Exhibit 25-19) $S_0 = 49.6$ mph (Exhibit 25-19) $S = 49.5$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET														
General Information					Site Information									
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87								
Agency or Company		CHA		Junction		Exit 4 NB Off								
Date Performed		02/15/12		Jurisdiction		NYS DOT								
Analysis Time Period		PM		Analysis Year		2016 Diamond								
Project Description Exit 4														
Inputs														
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1850 ft $V_D =$ 880 veh/h							
Conversion to pc/h Under Base Conditions														
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$						
Freeway	5400	0.86	Level	2	0	0.990	1.00	6342						
Ramp	960	0.86	Level	2	0	0.990	1.00	1127						
UpStream														
DownStream	880	0.88	Level	1	0	0.995	1.00	1005						
Merge Areas					Diverge Areas									
Estimation of v_{12}					Estimation of v_{12}									
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.550 using Equation (Exhibit 25-12) $V_{12} =$ 3993 pc/h V_3 or V_{av34} 2349 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)									
Capacity Checks					Capacity Checks									
		Actual	Capacity		LOS F?									
V_{FO}		Exhibit 25-7					V_F	6342	Exhibit 25-14	6780	No			
							$V_{FO} = V_F - V_R$	5215	Exhibit 25-14	6780	No			
							V_R	1127	Exhibit 25-3	2100	No			
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area									
		Actual	Max Desirable		Violation?				Actual	Max Desirable		Violation?		
V_{R12}			Exhibit 25-7						V_{12}	3993	Exhibit 25-14		4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)									
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 32.4 (pc/mi/ln) $LOS =$ D (Exhibit 25-4)									
Speed Determination					Speed Determination									
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.464 (Exhibit 25-19) $S_R =$ 49.5 mph (Exhibit 25-19) $S_0 =$ 56.2 mph (Exhibit 25-19) $S =$ 51.8 mph (Exhibit 25-15)									

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB			Freeway/Dir of Travel		Northbound I-87		
Agency or Company		CHA			Junction		Exit 4 NB On-Ramp		
Date Performed		02/15/12			Jurisdiction		NYSDOT		
Analysis Time Period		PM			Analysis Year		2016 Diamond		
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1850$ ft $V_u = 960$ veh/h		Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)					Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4450	0.86	Level	2	0	0.990	1.00	5226	
Ramp	880	0.88	Level	1	0	0.995	1.00	1005	
UpStream	960	0.92	Level	3	0	0.985	1.00	1059	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 1604.87$ (Equation 25-2 or 25-3) $P_{FM} = 0.614$ using Equation (Exhibit 25-5) $V_{12} = 3210$ pc/h V_3 or $V_{av34} = 2016$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	6231	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	4215	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 29.7$ (pc/mi/ln) LOS = D (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.480$ (Exhibit 25-19) $S_R = 49.3$ mph (Exhibit 25-19) $S_0 = 50.5$ mph (Exhibit 25-19) $S = 49.7$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 5 NB Off			
Date Performed		02/15/12		Jurisdiction		NYS DOT			
Analysis Time Period		PM		Analysis Year		2016 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{up} = 7810$ ft $V_u = 880$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 35.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_P)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	5650	0.86	Level	2	0	0.990	1.00	6635	
Ramp	410	0.92	Level	3	0	0.985	1.00	452	
UpStream	880	0.88	Level	1	0	0.995	1.00	1005	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} = 5310.35$ (Equation 25-8 or 25-9) $P_{FD} = 0.573$ using Equation (Exhibit 25-12) $V_{12} = 3997$ pc/h V_3 or $V_{av34} = 2638$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	6635	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	6183	Exhibit 25-14	6780	No	
				V_R	452	Exhibit 25-3	2000	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	3997	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 36.4$ (pc/mi/ln) $LOS = E$ (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.469$ (Exhibit 25-19) $S_R = 49.4$ mph (Exhibit 25-19) $S_0 = 55.0$ mph (Exhibit 25-19) $S = 51.5$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET														
General Information					Site Information									
Analyst		SEB		Freeway/Dir of Travel		Southbound								
Agency or Company		CHA		Junction		Exit 2W Off								
Date Performed		02/15/12		Jurisdiction		NYS DOT								
Analysis Time Period		PM		Analysis Year		2016 Diamond								
Project Description Exit 4														
Inputs														
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1300 ft $V_D =$ 680 veh/h							
Conversion to pc/h Under Base Conditions														
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$						
Freeway	3850	0.92	Level	2	0	0.990	1.00	4227						
Ramp	540	0.92	Level	2	0	0.990	1.00	593						
UpStream														
DownStream	680	0.92	Level	2	0	0.990	1.00	747						
Merge Areas					Diverge Areas									
Estimation of v_{12}					Estimation of v_{12}									
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ $P_{FD} = 0.627$ using Equation (Exhibit 25-12) $V_{12} = 2872$ pc/h V_3 or V_{av34} 1355 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)									
Capacity Checks					Capacity Checks									
		Actual	Capacity		LOS F?									
V_{FO}		Exhibit 25-7					V_F	4227	Exhibit 25-14	6780	No			
							$V_{FO} = V_F - V_R$	3634	Exhibit 25-14	6780	No			
							V_R	593	Exhibit 25-3	2100	No			
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area									
		Actual	Max Desirable		Violation?				Actual	Max Desirable		Violation?		
V_{R12}			Exhibit 25-7						V_{12}	2872	Exhibit 25-14		4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)									
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 26.3$ (pc/mi/ln) $LOS = C$ (Exhibit 25-4)									
Speed Determination					Speed Determination									
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.416$ (Exhibit 25-19) $S_R = 50.2$ mph (Exhibit 25-19) $S_0 = 60.0$ mph (Exhibit 25-19) $S = 53.0$ mph (Exhibit 25-15)									

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 4 SB Off			
Date Performed		02/15/12		Jurisdiction		NYS DOT			
Analysis Time Period		PM		Analysis Year		2016 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1820 ft $V_D =$ 1280 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	3650	0.92	Level	2	0	0.990	1.00	4007	
Ramp	970	0.92	Level	2	0	0.990	1.00	1065	
UpStream									
DownStream	1280	0.93	Level	4	0	0.980	1.00	1404	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.611 using Equation (Exhibit 25-12) $V_{12} =$ 2862 pc/h V_3 or V_{av34} 1145 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	4007	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	2942	Exhibit 25-14	6780	No	
				V_R	1065	Exhibit 25-3	2100	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	2862	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 22.6 (pc/mi/ln) $LOS =$ C (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.459 (Exhibit 25-19) $S_R =$ 49.6 mph (Exhibit 25-19) $S_0 =$ 60.9 mph (Exhibit 25-19) $S =$ 52.4 mph (Exhibit 25-15)				


RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 4 SB On-Ramp			
Date Performed		02/15/12		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2016 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1820$ ft $V_u = 970$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2700	0.92	Level	2	0	0.990	1.00	2964	
Ramp	1280	0.93	Level	4	0	0.980	1.00	1404	
UpStream	970	0.92	Level	2	0	0.990	1.00	1065	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 1203.97$ (Equation 25-2 or 25-3) $P_{FM} = 0.614$ using Equation (Exhibit 25-5) $V_{12} = 1820$ pc/h V_3 or $V_{av34} = 1144$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	4368	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	3224	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 21.8$ (pc/mi/ln) LOS = C (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.315$ (Exhibit 25-19) $S_R = 51.6$ mph (Exhibit 25-19) $S_0 = 53.7$ mph (Exhibit 25-19) $S = 52.1$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 5 SB On-Ramp			
Date Performed		02/15/12		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2016 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{down} =$ 6100 ft $V_D =$ 970 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	3000	0.92	Level	2	0	0.990	1.00	3293	
Ramp	630	0.87	Level	1	0	0.995	1.00	728	
UpStream									
DownStream	970	0.92	Level	2	0	0.990	1.00	1065	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 4282.27$ (Equation 25-2 or 25-3) $P_{FM} = 0.614$ using Equation (Exhibit 25-5) $V_{12} = 2022$ pc/h V_3 or $V_{av34} = 1271$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	4021	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	2750	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 18.4$ (pc/mi/ln) LOS = B (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.278$ (Exhibit 25-19) $S_R = 52.1$ mph (Exhibit 25-19) $S_0 = 53.2$ mph (Exhibit 25-19) $S = 52.5$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 02/15/12 Analysis Time Period PM					Freeway/Dir of Travel I-87 Northbound Weaving Seg Location Exit 2E on to 2W off Jurisdiction NYSDOT Analysis Year 2016 Diamond				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 815 Terrain Level					Weaving type A Volume ratio, VR 0.21 Weaving ratio, R 0.35				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	4220	0.86	2	0	1.5	1.2	0.990	1.00	4956
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	800	0.92	2	0	1.5	1.2	0.990	1.00	878
V_{w2}	430	0.92	2	0	1.5	1.2	0.990	1.00	472
V_w				1350	V_{nw}				4956
V									6306
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	1.36		0.72						
Weaving and non-weaving speeds, S_i (mi/h)	34.47		41.81						
Number of lanes required for unconstrained operation, N_w					1.25				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					39.99				
Weaving segment density, D (pc/mi/ln)					39.42				
Level of service, LOS					E				
Capacity of base condition, c_b (pc/h)					6665				
Capacity as a 15-minute flow rate, c (veh/h)					6599				
Capacity as a full-hour volume, c_h (veh/h)					5764				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 02/15/12 Analysis Time Period PM					Freeway/Dir of Travel I-87 Southbound Weaving Seg Location Exit 2W on to 2E off Jurisdiction NYSDOT Analysis Year 2016 Diamond				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 810 Terrain Level					Weaving type A Volume ratio, VR 0.19 Weaving ratio, R 0.10				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	3220	0.92	2	0	1.5	1.2	0.990	1.00	3534
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	680	0.92	2	0	1.5	1.2	0.990	1.00	746
V_{w2}	80	0.92	2	0	1.5	1.2	0.990	1.00	87
V_w				833	V_{nw}				3534
V									4367
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	0.92		0.41						
Weaving and non-weaving speeds, S_i (mi/h)	38.98		47.56						
Number of lanes required for unconstrained operation, N_w					1.11				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					45.65				
Weaving segment density, D (pc/mi/ln)					23.92				
Level of service, LOS					C				
Capacity of base condition, c_b (pc/h)					6788				
Capacity as a 15-minute flow rate, c (veh/h)					6721				
Capacity as a full-hour volume, c_h (veh/h)					6183				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 2 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5450* veh/h Peak-Hour Factor, PHF *0.86*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *2134* pc/h/ln
 S *53.1* mi/h
 $D = v_p / S$ *40.2* pc/mi/ln
 LOS *E*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 to Exit 2*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *3950* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1445* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *25.8* pc/mi/ln
 LOS *C*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *4450* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.86*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1742* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *31.1* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2750* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1006* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *18.0* pc/mi/ln
 LOS *B*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 to Exit 5*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5700* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.86*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *2231* pc/h/ln
 S *51.0* mi/h
 $D = v_p / S$ *43.7* pc/mi/ln
 LOS *E*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 5 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *3800* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1391* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *24.8* pc/mi/ln
 LOS *C*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary


N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET																										
			<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Application</th> <th>Input</th> <th>Output</th> </tr> </thead> <tbody> <tr> <td>Operational (LOS)</td> <td>FFS, N, v_p</td> <td>LOS, S, D</td> </tr> <tr> <td>Design (N)</td> <td>FFS, LOS, v_p</td> <td>N, S, D</td> </tr> <tr> <td>Design (v_p)</td> <td>FFS, LOS, N</td> <td>v_p, S, D</td> </tr> <tr> <td>Planning (LOS)</td> <td>FFS, N, AADT</td> <td>LOS, S, D</td> </tr> <tr> <td>Planning (N)</td> <td>FFS, LOS, AADT</td> <td>N, S, D</td> </tr> <tr> <td>Planning (v_p)</td> <td>FFS, LOS, N</td> <td>v_p, S, D</td> </tr> </tbody> </table>			Application	Input	Output	Operational (LOS)	FFS, N, v_p	LOS, S, D	Design (N)	FFS, LOS, v_p	N, S, D	Design (v_p)	FFS, LOS, N	v_p , S, D	Planning (LOS)	FFS, N, AADT	LOS, S, D	Planning (N)	FFS, LOS, AADT	N, S, D	Planning (v_p)	FFS, LOS, N	v_p , S, D
Application	Input	Output																								
Operational (LOS)	FFS, N, v_p	LOS, S, D																								
Design (N)	FFS, LOS, v_p	N, S, D																								
Design (v_p)	FFS, LOS, N	v_p , S, D																								
Planning (LOS)	FFS, N, AADT	LOS, S, D																								
Planning (N)	FFS, LOS, AADT	N, S, D																								
Planning (v_p)	FFS, LOS, N	v_p , S, D																								
General Information			Site Information																							
Analyst		CLD		Highway/Direction of Travel																						
Agency or Company		CHA		Northbound I-87																						
Date Performed		07/30/13		From/To																						
Analysis Time Period		PM		Exit 5 to Exit 6																						
Project Description		Exit 4		Jurisdiction																						
				NYSDOT																						
				Analysis Year																						
				2026 Diamond																						
<input checked="" type="checkbox"/> Oper.(LOS) <input type="checkbox"/> Des.(N) <input type="checkbox"/> Planning Data																										
Flow Inputs																										
Volume, V		5900		veh/h																						
AADT				veh/day																						
Peak-Hr Prop. of AADT, K				Peak-Hour Factor, PHF																						
Peak-Hr Direction Prop, D				0.86																						
DDHV = AADT x K x D				%Trucks and Buses, P_T																						
Driver type adjustment		1.00		2																						
				%RVs, P_R																						
				0																						
				General Terrain:																						
				Level																						
				Grade % Length																						
				mi																						
				Up/Down %																						
Calculate Flow Adjustments																										
f_p		1.00		E_R																						
E_T		1.5		1.2																						
				$f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$																						
				0.990																						
Speed Inputs			Calc Speed Adj and FFS																							
Lane Width		12.0		ft																						
Rt-Shoulder Lat. Clearance		6.0		ft																						
Interchange Density		0.50		l/mi																						
Number of Lanes, N		4																								
FFS (measured)		56.0		mi/h																						
Base free-flow Speed, BFFS				mi/h																						
				FFS																						
				56.0																						
				mi/h																						
LOS and Performance Measures			Design (N)																							
<u>Operational (LOS)</u>			<u>Design (N)</u>																							
$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$			Design LOS																							
1732			$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$																							
pc/h/ln			pc/h																							
S			S																							
56.0			mi/h																							
$D = v_p / S$			$D = v_p / S$																							
30.9			pc/mi/ln																							
LOS			D																							
			Required Number of Lanes, N																							
Glossary			Factor Location																							
N - Number of lanes			S - Speed																							
V - Hourly volume			D - Density																							
v_p - Flow rate			FFS - Free-flow speed																							
LOS - Level of service			BFFS - Base free-flow speed																							
DDHV - Directional design hour volume																										
			E _R - Exhibits 23-8, 23-10																							
			E _T - Exhibits 23-8, 23-10, 23-11																							
			f _p - Page 23-12																							
			LOS, S, FFS, v_p - Exhibits 23-2, 23-3																							
			f _{LW} - Exhibit 23-4																							
			f _{LC} - Exhibit 23-5																							
			f _N - Exhibit 23-6																							
			f _{ID} - Exhibit 23-7																							

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *CLD*
 Agency or Company *CHA*
 Date Performed *07/30/13*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 6 to Exit 5*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *3625* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *4*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *995* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *17.8* pc/mi/ln
 LOS *B*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 2W On-Ramp			
Date Performed		02/15/12		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2026 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1100$ ft $V_u = 840$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4650	0.86	Level	2	0	0.990	1.00	5461	
Ramp	780	0.92	Level	2	0	0.990	1.00	856	
UpStream	840	0.92	Level	2	0	0.990	1.00	922	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 1419.04$ (Equation 25-2 or 25-3) $P_{FM} = 0.581$ using Equation (Exhibit 25-5) $V_{12} = 3173$ pc/h V_3 or $V_{av34} = 2288$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	6317	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	4029	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 31.2$ (pc/mi/ln) LOS = D (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.472$ (Exhibit 25-19) $S_R = 49.4$ mph (Exhibit 25-19) $S_0 = 49.6$ mph (Exhibit 25-19) $S = 49.5$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET													
General Information					Site Information								
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87							
Agency or Company		CHA		Junction		Exit 4 NB Off							
Date Performed		02/15/12		Jurisdiction		NYS DOT							
Analysis Time Period		PM		Analysis Year		2026 Diamond							
Project Description Exit 4													
Inputs													
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1850 ft $V_D =$ 930 veh/h						
Conversion to pc/h Under Base Conditions													
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$					
Freeway	5450	0.86	Level	2	0	0.990	1.00	6401					
Ramp	980	0.86	Level	2	0	0.990	1.00	1151					
UpStream													
DownStream	930	0.88	Level	1	0	0.995	1.00	1062					
Merge Areas					Diverge Areas								
Estimation of v_{12}					Estimation of v_{12}								
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.547 using Equation (Exhibit 25-12) $V_{12} =$ 4023 pc/h V_3 or V_{av34} 2378 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)								
Capacity Checks					Capacity Checks								
		Actual	Capacity		LOS F?								
V_{FO}		Exhibit 25-7					V_F	6401	Exhibit 25-14	6780	No		
							$V_{FO} = V_F - V_R$	5250	Exhibit 25-14	6780	No		
							V_R	1151	Exhibit 25-3	2100	No		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area								
		Actual	Max Desirable		Violation?				Actual	Max Desirable		Violation?	
V_{R12}			Exhibit 25-7				V_{12}		4023	Exhibit 25-14	4400:All	No	
Level of Service Determination (if not F)					Level of Service Determination (if not F)								
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 32.7 (pc/mi/ln) $LOS =$ D (Exhibit 25-4)								
Speed Determination					Speed Determination								
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.467 (Exhibit 25-19) $S_R =$ 49.5 mph (Exhibit 25-19) $S_0 =$ 56.1 mph (Exhibit 25-19) $S =$ 51.7 mph (Exhibit 25-15)								

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 4 NB On-Ramp			
Date Performed		02/15/12		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2026 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1850$ ft $V_u = 980$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4450	0.86	Level	2	0	0.990	1.00	5226	
Ramp	930	0.88	Level	1	0	0.995	1.00	1062	
UpStream	980	0.92	Level	3	0	0.985	1.00	1081	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 1617.07$ (Equation 25-2 or 25-3) $P_{FM} = 0.614$ using Equation (Exhibit 25-5) $V_{12} = 3210$ pc/h V_3 or $V_{av34} = 2016$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	6288	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	4272	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 30.1$ (pc/mi/ln) LOS = D (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.496$ (Exhibit 25-19) $S_R = 49.1$ mph (Exhibit 25-19) $S_0 = 50.5$ mph (Exhibit 25-19) $S = 49.5$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 5 NB Off			
Date Performed		02/15/12		Jurisdiction		NYS DOT			
Analysis Time Period		PM		Analysis Year		2026 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{up} = 7810$ ft $V_u = 930$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 35.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	5700	0.86	Level	2	0	0.990	1.00	6694	
Ramp	420	0.92	Level	3	0	0.985	1.00	463	
UpStream	930	0.88	Level	1	0	0.995	1.00	1062	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} = 5596.13$ (Equation 25-8 or 25-9) $P_{FD} = 0.571$ using Equation (Exhibit 25-12) $V_{12} = 4023$ pc/h V_3 or $V_{av34} = 2671$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	6694	Exhibit 25-14	6780	No
					$V_{FO} = V_F - V_R$	6231	Exhibit 25-14	6780	No
					V_R	463	Exhibit 25-3	2000	No
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	4023	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 36.6$ (pc/mi/ln) $LOS = E$ (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.470$ (Exhibit 25-19) $S_R = 49.4$ mph (Exhibit 25-19) $S_0 = 54.9$ mph (Exhibit 25-19) $S = 51.5$ mph (Exhibit 25-15)				

Generated: 2/16/2012 9:38 AM

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 4 SB Off			
Date Performed		02/15/12		Jurisdiction		NYS DOT			
Analysis Time Period		PM		Analysis Year		2026 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1820 ft $V_D =$ 1310 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	3800	0.92	Level	2	0	0.990	1.00	4172	
Ramp	1040	0.92	Level	2	0	0.990	1.00	1142	
UpStream									
DownStream	1310	0.93	Level	4	0	0.980	1.00	1437	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.603 using Equation (Exhibit 25-12) $V_{12} =$ 2970 pc/h V_3 or V_{av34} 1202 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	4172	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	3030	Exhibit 25-14	6780	No	
				V_R	1142	Exhibit 25-3	2100	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	2970	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 23.5 (pc/mi/ln) $LOS =$ C (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.466 (Exhibit 25-19) $S_R =$ 49.5 mph (Exhibit 25-19) $S_0 =$ 60.6 mph (Exhibit 25-19) $S =$ 52.3 mph (Exhibit 25-15)				


RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 4 SB On-Ramp			
Date Performed		02/15/12		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2026 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1820$ ft $V_u = 1040$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2750	0.92	Level	2	0	0.990	1.00	3019	
Ramp	1310	0.93	Level	4	0	0.980	1.00	1437	
UpStream	1040	0.92	Level	2	0	0.990	1.00	1142	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 1222.80$ (Equation 25-2 or 25-3) $P_{FM} = 0.614$ using Equation (Exhibit 25-5) $V_{12} = 1854$ pc/h V_3 or $V_{av34} = 1165$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	4456	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	3291	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 22.3$ (pc/mi/ln) LOS = C (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.321$ (Exhibit 25-19) $S_R = 51.5$ mph (Exhibit 25-19) $S_0 = 53.6$ mph (Exhibit 25-19) $S = 52.0$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 5 SB On-Ramp			
Date Performed		02/15/12		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2026 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{down} =$ 6100 ft $V_D =$ 1040 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	3150	0.92	Level	2	0	0.990	1.00	3458	
Ramp	670	0.87	Level	1	0	0.995	1.00	774	
UpStream									
DownStream	1040	0.92	Level	2	0	0.990	1.00	1142	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 4591.88$ (Equation 25-2 or 25-3) $P_{FM} = 0.614$ using Equation (Exhibit 25-5) $V_{12} = 2123$ pc/h V_3 or $V_{av34} = 1335$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	4232	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	2897	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 19.6$ (pc/mi/ln) LOS = B (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.288$ (Exhibit 25-19) $S_R = 52.0$ mph (Exhibit 25-19) $S_0 = 53.0$ mph (Exhibit 25-19) $S = 52.3$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 02/15/12 Analysis Time Period PM					Freeway/Dir of Travel I-87 Northbound Weaving Seg Location Exit 2E on to 2W off Jurisdiction NYSDOT Analysis Year 2026 Diamond				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 815 Terrain Level					Weaving type A Volume ratio, VR 0.22 Weaving ratio, R 0.35				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	4200	0.86	2	0	1.5	1.2	0.990	1.00	4932
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	840	0.92	2	0	1.5	1.2	0.990	1.00	922
V_{w2}	450	0.92	2	0	1.5	1.2	0.990	1.00	494
V_w				1416	V_{nw}				4932
V									6348
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	1.39		0.74						
Weaving and non-weaving speeds, S_i (mi/h)	34.22		41.38						
Number of lanes required for unconstrained operation, N_w					1.28				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					39.54				
Weaving segment density, D (pc/mi/ln)					40.14				
Level of service, LOS					E				
Capacity of base condition, c_b (pc/h)					6615				
Capacity as a 15-minute flow rate, c (veh/h)					6550				
Capacity as a full-hour volume, c_h (veh/h)					5725				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 02/15/12 Analysis Time Period PM					Freeway/Dir of Travel I-87 Southbound Weaving Seg Location Exit 2W on to 2E off Jurisdiction NYSDOT Analysis Year 2026 Diamond				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 810 Terrain Level					Weaving type A Volume ratio, VR 0.19 Weaving ratio, R 0.10				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	3320	0.92	2	0	1.5	1.2	0.990	1.00	3644
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	710	0.92	2	0	1.5	1.2	0.990	1.00	779
V_{w2}	80	0.92	2	0	1.5	1.2	0.990	1.00	87
V_w				866	V_{nw}				3644
V									4510
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	0.95		0.43						
Weaving and non-weaving speeds, S_i (mi/h)	38.59		47.12						
Number of lanes required for unconstrained operation, N_w					1.12				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					45.20				
Weaving segment density, D (pc/mi/ln)					24.94				
Level of service, LOS					C				
Capacity of base condition, c_b (pc/h)					6781				
Capacity as a 15-minute flow rate, c (veh/h)					6714				
Capacity as a full-hour volume, c_h (veh/h)					6177				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 2 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5500* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.86*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *2153* pc/h/ln
 S *52.7* mi/h
 $D = v_p / S$ *40.8* pc/mi/ln
 LOS *E*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 to Exit 2*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *4050* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1482* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *26.5* pc/mi/ln
 LOS *D*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *4500* veh/h Peak-Hour Factor, PHF *0.86*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1762* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *31.5* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2800* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1025* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *18.3* pc/mi/ln
 LOS *C*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 to Exit 5*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5750* veh/h Peak-Hour Factor, PHF *0.86*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *2251* pc/h/ln
 S *50.5* mi/h
 $D = v_p / S$ *44.6* pc/mi/ln
 LOS *E*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 5 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *3900* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1427* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *25.5* pc/mi/ln
 LOS *C*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *CLD*
 Agency or Company *CHA*
 Date Performed *07/30/13*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 5 to Exit 6*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *6050* veh/h Peak-Hour Factor, PHF *0.86*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *4*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1776* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *31.7* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *CLD*
 Agency or Company *CHA*
 Date Performed *07/30/13*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 6 to Exit 5*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *3750* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *4*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1029* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *18.4* pc/mi/ln
 LOS *C*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 2W On-Ramp			
Date Performed		02/15/12		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2036 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1100$ ft $V_u = 880$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4700	0.86	Level	2	0	0.990	1.00	5520	
Ramp	780	0.92	Level	2	0	0.990	1.00	856	
UpStream	880	0.92	Level	2	0	0.990	1.00	966	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 1431.66$ (Equation 25-2 or 25-3) $P_{FM} = 0.580$ using Equation (Exhibit 25-5) $V_{12} = 3203$ pc/h V_3 or $V_{av34} = 2317$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	6376	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	4059	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 31.4$ (pc/mi/ln) LOS = D (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.479$ (Exhibit 25-19) $S_R = 49.3$ mph (Exhibit 25-19) $S_0 = 49.4$ mph (Exhibit 25-19) $S = 49.3$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET													
General Information					Site Information								
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87							
Agency or Company		CHA		Junction		Exit 4 NB Off							
Date Performed		02/15/12		Jurisdiction		NYS DOT							
Analysis Time Period		PM		Analysis Year		2036 Diamond							
Project Description Exit 4													
Inputs													
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1850 ft $V_D =$ 980 veh/h						
Conversion to pc/h Under Base Conditions													
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$					
Freeway	5500	0.86	Level	2	0	0.990	1.00	6459					
Ramp	1000	0.86	Level	2	0	0.990	1.00	1174					
UpStream													
DownStream	980	0.88	Level	1	0	0.995	1.00	1119					
Merge Areas					Diverge Areas								
Estimation of v_{12}					Estimation of v_{12}								
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.545 using Equation (Exhibit 25-12) $V_{12} =$ 4052 pc/h V_3 or V_{av34} 2407 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)								
Capacity Checks					Capacity Checks								
		Actual	Capacity		LOS F?								
V_{FO}		Exhibit 25-7					V_F	6459	Exhibit 25-14	6780	No		
							$V_{FO} = V_F - V_R$	5285	Exhibit 25-14	6780	No		
							V_R	1174	Exhibit 25-3	2100	No		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area								
		Actual	Max Desirable		Violation?				Actual	Max Desirable		Violation?	
V_{R12}			Exhibit 25-7				V_{12}	4052	Exhibit 25-14	4400:All	No		
Level of Service Determination (if not F)					Level of Service Determination (if not F)								
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 32.9 (pc/mi/ln) $LOS =$ D (Exhibit 25-4)								
Speed Determination					Speed Determination								
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.469 (Exhibit 25-19) $S_R =$ 49.4 mph (Exhibit 25-19) $S_0 =$ 55.9 mph (Exhibit 25-19) $S =$ 51.7 mph (Exhibit 25-15)								

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 4 NB On-Ramp			
Date Performed		02/15/12		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2036 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1850$ ft $V_u = 1000$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_l)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4500	0.86	Level	2	0	0.990	1.00	5285	
Ramp	980	0.88	Level	1	0	0.995	1.00	1119	
UpStream	1000	0.92	Level	3	0	0.985	1.00	1103	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 1641.90$ (Equation 25-2 or 25-3) $P_{FM} = 0.614$ using Equation (Exhibit 25-5) $V_{12} = 3246$ pc/h V_3 or $V_{av34} = 2039$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	6404	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	4365	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 30.8$ (pc/mi/ln) LOS = D (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.523$ (Exhibit 25-19) $S_R = 48.7$ mph (Exhibit 25-19) $S_0 = 50.5$ mph (Exhibit 25-19) $S = 49.2$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 5 NB Off			
Date Performed		02/15/12		Jurisdiction		NYS DOT			
Analysis Time Period		PM		Analysis Year		2036 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{up} = 7810$ ft $V_u = 980$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 35.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_P)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	5750	0.86	Level	2	0	0.990	1.00	6753	
Ramp	440	0.92	Level	3	0	0.985	1.00	485	
UpStream	980	0.88	Level	1	0	0.995	1.00	1119	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} = 5906.29$ (Equation 25-8 or 25-9) $P_{FD} = 0.569$ using Equation (Exhibit 25-12) $V_{12} = 4051$ pc/h V_3 or $V_{av34} = 2702$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} = 4053$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	6753	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	6268	Exhibit 25-14	6780	No	
				V_R	485	Exhibit 25-3	2000	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	4051	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 36.9$ (pc/mi/ln) $LOS = E$ (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.472$ (Exhibit 25-19) $S_R = 49.4$ mph (Exhibit 25-19) $S_0 = 54.8$ mph (Exhibit 25-19) $S = 51.4$ mph (Exhibit 25-15)				

Generated: 2/17/2012 1:26 PM

RAMPS AND RAMP JUNCTIONS WORKSHEET														
General Information					Site Information									
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87								
Agency or Company		CHA		Junction		Exit 4 SB Off								
Date Performed		02/15/12		Jurisdiction		NYS DOT								
Analysis Time Period		PM		Analysis Year		2036 Diamond								
Project Description Exit 4														
Inputs														
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1820 ft $V_D =$ 1340 veh/h							
Conversion to pc/h Under Base Conditions														
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$						
Freeway	3900	0.92	Level	2	0	0.990	1.00	4282						
Ramp	1110	0.92	Level	2	0	0.990	1.00	1219						
UpStream														
DownStream	1340	0.93	Level	4	0	0.980	1.00	1470						
Merge Areas					Diverge Areas									
Estimation of v_{12}					Estimation of v_{12}									
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ $P_{FD} = 0.597$ using Equation (Exhibit 25-12) $V_{12} = 3047$ pc/h V_3 or V_{av34} 1235 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)									
Capacity Checks					Capacity Checks									
		Actual	Capacity		LOS F?									
V_{FO}							V_F	4282	Exhibit 25-14	6780	No			
			Exhibit 25-7				$V_{FO} = V_F - V_R$	3063	Exhibit 25-14	6780	No			
							V_R	1219	Exhibit 25-3	2100	No			
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area									
		Actual	Max Desirable		Violation?				Actual	Max Desirable		Violation?		
V_{R12}			Exhibit 25-7				V_{12}		3047	Exhibit 25-14		4400:All		No
Level of Service Determination (if not F)					Level of Service Determination (if not F)									
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 24.2$ (pc/mi/ln) $LOS = C$ (Exhibit 25-4)									
Speed Determination					Speed Determination									
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.473$ (Exhibit 25-19) $S_R = 49.4$ mph (Exhibit 25-19) $S_0 = 60.5$ mph (Exhibit 25-19) $S = 52.1$ mph (Exhibit 25-15)									

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 4 SB On-Ramp			
Date Performed		02/15/12		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2036 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1820$ ft $V_u = 1110$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2800	0.92	Level	2	0	0.990	1.00	3074	
Ramp	1340	0.93	Level	4	0	0.980	1.00	1470	
UpStream	1110	0.92	Level	2	0	0.990	1.00	1219	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 1241.64$ (Equation 25-2 or 25-3) $P_{FM} = 0.614$ using Equation (Exhibit 25-5) $V_{12} = 1888$ pc/h V_3 or $V_{av34} = 1186$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	4544	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	3358	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 22.8$ (pc/mi/ln) LOS = C (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.329$ (Exhibit 25-19) $S_R = 51.4$ mph (Exhibit 25-19) $S_0 = 53.5$ mph (Exhibit 25-19) $S = 51.9$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 5 SB On-Ramp			
Date Performed		02/15/12		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2036 Diamond			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{down} =$ 6100 ft $V_D =$ 1110 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	3150	0.92	Level	2	0	0.990	1.00	3458	
Ramp	730	0.87	Level	1	0	0.995	1.00	843	
UpStream									
DownStream	1110	0.92	Level	2	0	0.990	1.00	1219	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 4901.49$ (Equation 25-2 or 25-3) $P_{FM} = 0.614$ using Equation (Exhibit 25-5) $V_{12} = 2123$ pc/h V_3 or $V_{av34} = 1335$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	4301	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	2966	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 20.1$ (pc/mi/ln) LOS = C (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.293$ (Exhibit 25-19) $S_R = 51.9$ mph (Exhibit 25-19) $S_0 = 53.0$ mph (Exhibit 25-19) $S = 52.2$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 02/15/12 Analysis Time Period PM					Freeway/Dir of Travel I-87 Northbound Weaving Seg Location Exit 2E on to 2W off Jurisdiction NYSDOT Analysis Year 2036 Diamond				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 815 Terrain Level					Weaving type A Volume ratio, VR 0.23 Weaving ratio, R 0.34				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	4240	0.86	2	0	1.5	1.2	0.990	1.00	4979
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	880	0.92	2	0	1.5	1.2	0.990	1.00	966
V_{w2}	460	0.92	2	0	1.5	1.2	0.990	1.00	504
V_w				1470	V_{nw}				4979
V									6449
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	1.43		0.77						
Weaving and non-weaving speeds, S_i (mi/h)	33.95		40.97						
Number of lanes required for unconstrained operation, N_w					1.30				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					39.13				
Weaving segment density, D (pc/mi/ln)					41.20				
Level of service, LOS					E				
Capacity of base condition, c_b (pc/h)					6588				
Capacity as a 15-minute flow rate, c (veh/h)					6523				
Capacity as a full-hour volume, c_h (veh/h)					5704				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 02/15/12 Analysis Time Period PM					Freeway/Dir of Travel I-87 Southbound Weaving Seg Location Exit 2W on to 2E off Jurisdiction NYSDOT Analysis Year 2036 Diamond				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 810 Terrain Level					Weaving type A Volume ratio, VR 0.20 Weaving ratio, R 0.11				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	3360	0.92	2	0	1.5	1.2	0.990	1.00	3688
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	750	0.92	2	0	1.5	1.2	0.990	1.00	823
V_{w2}	90	0.92	2	0	1.5	1.2	0.990	1.00	98
V_w				921	V_{nw}				3688
V									4609
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	0.98		0.46						
Weaving and non-weaving speeds, S_i (mi/h)	38.18		46.59						
Number of lanes required for unconstrained operation, N_w					1.15				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					44.63				
Weaving segment density, D (pc/mi/ln)					25.82				
Level of service, LOS					C				
Capacity of base condition, c_b (pc/h)					6736				
Capacity as a 15-minute flow rate, c (veh/h)					6669				
Capacity as a full-hour volume, c_h (veh/h)					6135				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2046 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *4500* veh/h Peak-Hour Factor, PHF *0.86*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1762* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *31.5* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2046 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2750* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.92*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1006* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *18.0* pc/mi/ln
 LOS *B*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 to Exit 5*
 Jurisdiction *NYSDOT*
 Analysis Year *2046 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5800* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.86*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *2271* pc/h/ln
 S mi/h
 $D = v_p / S$ pc/mi/ln
 LOS *F*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/15/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 5 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2046 Diamond*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *3900* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1427* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *25.5* pc/mi/ln
 LOS *C*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary


N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

FLYOVER

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 2 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *3250* veh/h
 AADT *3250* veh/day
 Peak-Hr Prop. of AADT, K *0.92*
 Peak-Hr Direction Prop, D *0*
 DDHV = AADT x K x D *0* veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.92*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS *56.0* mi/h

Calc Speed Adj and FFS

f_{LW} *56.0* mi/h
 f_{LC} *56.0* mi/h
 f_{ID} *56.0* mi/h
 f_N *56.0* mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1189* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *21.2* pc/mi/ln
 LOS *C*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1189* pc/h
 S *56.0* mi/h
 $D = v_p / S$ *21.2* pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 to Exit 2*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5350* veh/h
 AADT *5350* veh/day
 Peak-Hr Prop. of AADT, K *0.92*
 Peak-Hr Direction Prop, D *0*
 DDHV = AADT x K x D *0* veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.92*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS *56.0* mi/h

Calc Speed Adj and FFS

f_{LW} *56.0* mi/h
 f_{LC} *56.0* mi/h
 f_{ID} *56.0* mi/h
 f_N *56.0* mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1958* pc/h/ln
 S *55.3* mi/h
 $D = v_p / S$ *35.4* pc/mi/ln
 LOS *E*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1958* pc/h
 S *55.3* mi/h
 $D = v_p / S$ *35.4* pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2200* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *805* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *14.4* pc/mi/ln
 LOS *B*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 off to Exit 4 off*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2450* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *897* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *16.0* pc/mi/ln
 LOS *B*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *4750* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1738* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *31.0* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 to Exit 5*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2700* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *4*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *741* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *13.2* pc/mi/ln
 LOS *B*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 5 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5300* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1939* pc/h/ln
 S *55.4* mi/h
 $D = v_p / S$ *35.0* pc/mi/ln
 LOS *D*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *CLD*
 Agency or Company *CHA*
 Date Performed *07/30/13*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 5 to Exit 6*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2550* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *4*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *700* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *12.5* pc/mi/ln
 LOS *B*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *CLD*
 Agency or Company *CHA*
 Date Performed *07/30/13*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 6 to Exit 5*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *6000* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.92*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *4*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1647* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *29.4* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 2W On-Ramp			
Date Performed		02/14/12		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2016 Flyover			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1100$ ft $V_u = 660$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2850	0.92	Level	2	0	0.990	1.00	3129	
Ramp	390	0.92	Level	2	0	0.990	1.00	428	
UpStream	660	0.92	Level	2	0	0.990	1.00	725	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 828.40$ (Equation 25-2 or 25-3) $P_{FM} = 0.601$ using Equation (Exhibit 25-5) $V_{12} = 1881$ pc/h V_3 or $V_{av34} = 1248$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	3557	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	2309	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 18.0$ (pc/mi/ln) $LOS = B$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.292$ (Exhibit 25-19) $S_R = 51.9$ mph (Exhibit 25-19) $S_0 = 53.3$ mph (Exhibit 25-19) $S = 52.4$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

Generated: 2/15/2012 2:28 PM

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 4 NB Off to Wolf			
Date Performed		02/14/12		Jurisdiction		NYS DOT			
Analysis Time Period		AM		Analysis Year		2016 Flyover			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 2600$ ft $V_u = 800$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2450	0.92	Level	2	0	0.990	1.00	2690	
Ramp	190	0.82	Level	2	0	0.990	1.00	234	
UpStream	800	0.82	Level	2	0	0.990	1.00	985	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} = 0.682$ using Equation (Exhibit 25-12) $V_{12} = 1909$ pc/h V_3 or V_{av34} 781 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	2690	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	2456	Exhibit 25-14	6780	No	
				V_R	234	Exhibit 25-3	2100	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	1909	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 17.5$ (pc/mi/ln) $LOS = B$ (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.384$ (Exhibit 25-19) $S_R = 50.6$ mph (Exhibit 25-19) $S_0 = 61.4$ mph (Exhibit 25-19) $S = 53.3$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET											
General Information					Site Information						
Analyst		SEB		Freeway/Dir of Travel		Southbound					
Agency or Company		CHA		Junction		Exit 2W Off					
Date Performed		02/14/12		Jurisdiction		NYS DOT					
Analysis Time Period		AM		Analysis Year		2016 Flyover					
Project Description Exit 4											
Inputs											
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1300 ft $V_D =$ 340 veh/h				
Conversion to pc/h Under Base Conditions											
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$			
Freeway	5350	0.92	Level	2	0	0.990	1.00	5873			
Ramp	740	0.92	Level	2	0	0.990	1.00	812			
UpStream											
DownStream	340	0.92	Level	2	0	0.990	1.00	373			
Merge Areas					Diverge Areas						
Estimation of v_{12}					Estimation of v_{12}						
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.576 using Equation (Exhibit 25-12) $V_{12} =$ 3726 pc/h V_3 or V_{av34} 2147 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)						
Capacity Checks					Capacity Checks						
		Actual	Capacity		LOS F?						
V_{FO}							V_F	5873	Exhibit 25-14	6780	No
							$V_{FO} = V_F - V_R$	5061	Exhibit 25-14	6780	No
							V_R	812	Exhibit 25-3	2100	No
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area						
		Actual	Max Desirable		Violation?						
V_{R12}			Exhibit 25-7				V_{12}	3726	Exhibit 25-14 4400:All		No
Level of Service Determination (if not F)					Level of Service Determination (if not F)						
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 33.6 (pc/mi/ln) $LOS =$ D (Exhibit 25-4)						
Speed Determination					Speed Determination						
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.436 (Exhibit 25-19) $S_R =$ 49.9 mph (Exhibit 25-19) $S_0 =$ 57.0 mph (Exhibit 25-19) $S =$ 52.3 mph (Exhibit 25-15)						

RAMPS AND RAMP JUNCTIONS WORKSHEET														
General Information					Site Information									
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87								
Agency or Company		CHA		Junction		Exit 4 SB Off								
Date Performed		02/14/12		Jurisdiction		NYS DOT								
Analysis Time Period		AM		Analysis Year		2016 Flyover								
Project Description Exit 4														
Inputs														
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1585 ft $V_D =$ 600 veh/h							
Conversion to pc/h Under Base Conditions														
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$						
Freeway	5300	0.92	Level	2	0	0.990	1.00	5818						
Ramp	560	0.92	Level	2	0	0.990	1.00	615						
UpStream														
DownStream	600	0.93	Level	5	0	0.976	1.00	661						
Merge Areas					Diverge Areas									
Estimation of v_{12}					Estimation of v_{12}									
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ $P_{FD} = 0.586$ using Equation (Exhibit 25-12) $V_{12} = 3665$ pc/h V_3 or V_{av34} 2153 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)									
Capacity Checks					Capacity Checks									
		Actual	Capacity		LOS F?									
V_{FO}		Exhibit 25-7					V_F	5818	Exhibit 25-14	6780	No			
							$V_{FO} = V_F - V_R$	5203	Exhibit 25-14	6780	No			
							V_R	615	Exhibit 25-3	2100	No			
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area									
		Actual	Max Desirable		Violation?				Actual	Max Desirable		Violation?		
V_{R12}			Exhibit 25-7						V_{12}	3665	Exhibit 25-14		4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)									
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 26.3$ (pc/mi/ln) $LOS = C$ (Exhibit 25-4)									
Speed Determination					Speed Determination									
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.418$ (Exhibit 25-19) $S_R = 50.1$ mph (Exhibit 25-19) $S_0 = 56.9$ mph (Exhibit 25-19) $S = 52.5$ mph (Exhibit 25-15)									

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 4 SB On-Ramp			
Date Performed		02/14/12		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2016 Flyover			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1585$ ft $V_u = 560$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4750	0.92	Level	2	0	0.990	1.00	5215	
Ramp	600	0.93	Level	5	0	0.976	1.00	661	
UpStream	560	0.92	Level	2	0	0.990	1.00	615	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 1531.12$ (Equation 25-2 or 25-3) $P_{FM} = 0.614$ using Equation (Exhibit 25-5) $V_{12} = 3204$ pc/h V_3 or $V_{av34} = 2011$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	5876	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	3865	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 27.1$ (pc/mi/ln) LOS = C (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.402$ (Exhibit 25-19) $S_R = 50.4$ mph (Exhibit 25-19) $S_0 = 50.6$ mph (Exhibit 25-19) $S = 50.4$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 5 SB On-Ramp			
Date Performed		02/14/12		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2016 Flyover			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{down} =$ 4700 ft $V_D =$ 560 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4950	0.92	Level	2	0	0.990	1.00	5434	
Ramp	340	0.93	Level	3	0	0.985	1.00	371	
UpStream									
DownStream	560	0.92	Level	2	0	0.990	1.00	615	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 2472.86$ (Equation 25-2 or 25-3) $P_{FM} = 0.614$ using Equation (Exhibit 25-5) $V_{12} = 3336$ pc/h V_3 or $V_{av34} = 2098$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	5805	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	3707	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 26.1$ (pc/mi/ln) LOS = C (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.376$ (Exhibit 25-19) $S_R = 50.7$ mph (Exhibit 25-19) $S_0 = 50.2$ mph (Exhibit 25-19) $S = 50.6$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst Agency/Company Date Performed Analysis Time Period					SEB CHA 02/14/12 AM				
Freeway/Dir of Travel Weaving Seg Location Jurisdiction Analysis Year					I-87 Northbound Exit 2E on to 2W off NYSDOT 2016 Flyover				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h)					56				
Weaving number of lanes, N					4				
Weaving seg length, L (ft)					815				
Terrain					Level				
Weaving type					A				
Volume ratio, VR					0.27				
Weaving ratio, R					0.31				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	2550	0.92	2	0	1.5	1.2	0.990	1.00	2799
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	660	0.92	2	0	1.5	1.2	0.990	1.00	724
V_{w2}	300	0.92	2	0	1.5	1.2	0.990	1.00	329
V_w				1053	V_{nw}				2799
V									3852
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	0.94		0.46						
Weaving and non-weaving speeds, S_i (mi/h)	38.74		46.59						
Number of lanes required for unconstrained operation, N_w					1.37				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					44.14				
Weaving segment density, D (pc/mi/ln)					21.82				
Level of service, LOS					C				
Capacity of base condition, c_b (pc/h)					6336				
Capacity as a 15-minute flow rate, c (veh/h)					6273				
Capacity as a full-hour volume, c_h (veh/h)					5771				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst Agency/Company Date Performed Analysis Time Period					SEB CHA 02/14/12 AM				
Freeway/Dir of Travel Weaving Seg Location Jurisdiction Analysis Year					I-87 Southbound Exit 2W on to 2E off NYSDOT 2016 Flyover				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h)					56				
Weaving number of lanes, N					4				
Weaving seg length, L (ft)					810				
Terrain					Level				
Weaving type					A				
Volume ratio, VR					0.22				
Weaving ratio, R					0.31				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	3860	0.92	2	0	1.5	1.2	0.990	1.00	4237
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	740	0.92	2	0	1.5	1.2	0.990	1.00	812
V_{w2}	340	0.92	2	0	1.5	1.2	0.990	1.00	373
V_w				1185	V_{nw}				4237
V									5422
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	1.19		0.60						
Weaving and non-weaving speeds, S_i (mi/h)	35.98		43.76						
Number of lanes required for unconstrained operation, N_w					1.24				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					41.79				
Weaving segment density, D (pc/mi/ln)					32.44				
Level of service, LOS					D				
Capacity of base condition, c_b (pc/h)					6633				
Capacity as a 15-minute flow rate, c (veh/h)					6567				
Capacity as a full-hour volume, c_h (veh/h)					6042				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 2 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *3350* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1226* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *21.9* pc/mi/ln
 LOS *C*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 to Exit 2*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5400* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1976* pc/h/ln
 S *55.2* mi/h
 $D = v_p / S$ *35.8* pc/mi/ln
 LOS *E*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2200* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *805* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *14.4* pc/mi/ln
 LOS *B*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 off to Exit 4 off*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2400* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *878* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *15.7* pc/mi/ln
 LOS *B*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *4950* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1811* pc/h/ln
 S *55.9* mi/h
 $D = v_p / S$ *32.4* pc/mi/ln
 LOS *D*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 to Exit 5*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2750* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.92*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *4*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *755* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *13.5* pc/mi/ln
 LOS *B*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 5 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5600* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *2049* pc/h/ln
 S *54.4* mi/h
 $D = v_p / S$ *37.7* pc/mi/ln
 LOS *E*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst CLD
 Agency or Company CHA
 Date Performed 07/30/13
 Analysis Time Period AM

Site Information

Highway/Direction of Travel Northbound I-87
 From/To Exit 5 to Exit 6
 Jurisdiction NYSDOT
 Analysis Year 2026 Flyover

Project Description Exit 4

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V 2600 veh/h Peak-Hour Factor, PHF 0.92
 AADT veh/day %Trucks and Buses, P_T 2
 Peak-Hr Prop. of AADT, K %RVs, P_R 0
 Peak-Hr Direction Prop, D General Terrain: Level
 DDHV = AADT x K x D veh/h Grade % Length mi
 Driver type adjustment 1.00 Up/Down %

Calculate Flow Adjustments

f_p 1.00 E_R 1.2
 E_T 1.5 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ 0.990

Speed Inputs

Lane Width 12.0 ft
 Rt-Shoulder Lat. Clearance 6.0 ft
 Interchange Density 0.50 l/mi
 Number of Lanes, N 4
 FFS (measured) 56.0 mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS 56.0 mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or DDHV}) / (PHF \times N \times f_{HV} \times f_p)$ 714 pc/h/ln
 S 56.0 mi/h
 $D = v_p / S$ 12.8 pc/mi/ln
 LOS B

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or DDHV}) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET																										
			<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Application</th> <th>Input</th> <th>Output</th> </tr> </thead> <tbody> <tr> <td>Operational (LOS)</td> <td>FFS, N, v_p</td> <td>LOS, S, D</td> </tr> <tr> <td>Design (N)</td> <td>FFS, LOS, v_p</td> <td>N, S, D</td> </tr> <tr> <td>Design (v_p)</td> <td>FFS, LOS, N</td> <td>v_p, S, D</td> </tr> <tr> <td>Planning (LOS)</td> <td>FFS, N, AADT</td> <td>LOS, S, D</td> </tr> <tr> <td>Planning (N)</td> <td>FFS, LOS, AADT</td> <td>N, S, D</td> </tr> <tr> <td>Planning (v_p)</td> <td>FFS, LOS, N</td> <td>v_p, S, D</td> </tr> </tbody> </table>			Application	Input	Output	Operational (LOS)	FFS, N, v_p	LOS, S, D	Design (N)	FFS, LOS, v_p	N, S, D	Design (v_p)	FFS, LOS, N	v_p , S, D	Planning (LOS)	FFS, N, AADT	LOS, S, D	Planning (N)	FFS, LOS, AADT	N, S, D	Planning (v_p)	FFS, LOS, N	v_p , S, D
Application	Input	Output																								
Operational (LOS)	FFS, N, v_p	LOS, S, D																								
Design (N)	FFS, LOS, v_p	N, S, D																								
Design (v_p)	FFS, LOS, N	v_p , S, D																								
Planning (LOS)	FFS, N, AADT	LOS, S, D																								
Planning (N)	FFS, LOS, AADT	N, S, D																								
Planning (v_p)	FFS, LOS, N	v_p , S, D																								
General Information			Site Information																							
Analyst		CLD		Highway/Direction of Travel																						
Agency or Company		CHA		From/To																						
Date Performed		07/30/13		Jurisdiction																						
Analysis Time Period		AM		Analysis Year																						
Project Description Exit 4																										
<input checked="" type="checkbox"/> Oper.(LOS) <input type="checkbox"/> Des.(N) <input type="checkbox"/> Planning Data																										
Flow Inputs																										
Volume, V		6100		veh/h																						
AADT				veh/day																						
Peak-Hr Prop. of AADT, K				%																						
Peak-Hr Direction Prop, D				%																						
DDHV = AADT x K x D				veh/h																						
Driver type adjustment		1.00																								
				Up/Down %																						
Calculate Flow Adjustments																										
f_p		1.00		E_R																						
E_T		1.5		$f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$																						
				0.990																						
Speed Inputs			Calc Speed Adj and FFS																							
Lane Width		12.0		ft																						
Rt-Shoulder Lat. Clearance		6.0		ft																						
Interchange Density		0.50		l/mi																						
Number of Lanes, N		4																								
FFS (measured)		56.0		mi/h																						
Base free-flow Speed, BFFS				mi/h																						
				FFS																						
				56.0																						
				mi/h																						
LOS and Performance Measures			Design (N)																							
<u>Operational (LOS)</u>			<u>Design (N)</u>																							
$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$			$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$																							
1674			pc/h/ln																							
S			mi/h																							
56.0			mi/h																							
$D = v_p / S$			$D = v_p / S$																							
29.9			pc/mi/ln																							
LOS			D																							
			Required Number of Lanes, N																							
Glossary			Factor Location																							
N - Number of lanes			S - Speed																							
V - Hourly volume			D - Density																							
v_p - Flow rate			FFS - Free-flow speed																							
LOS - Level of service			BFFS - Base free-flow speed																							
DDHV - Directional design hour volume																										
			E_R - Exhibits 23-8, 23-10																							
			E_T - Exhibits 23-8, 23-10, 23-11																							
			f_p - Page 23-12																							
			LOS, S, FFS, v_p - Exhibits 23-2, 23-3																							
			f_{LW} - Exhibit 23-4																							
			f_{LC} - Exhibit 23-5																							
			f_N - Exhibit 23-6																							
			f_{ID} - Exhibit 23-7																							

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 2W On-Ramp			
Date Performed		02/14/12		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2026 Flyover			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1100$ ft $V_u = 670$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2950	0.92	Level	2	0	0.990	1.00	3239	
Ramp	400	0.92	Level	2	0	0.990	1.00	439	
UpStream	670	0.92	Level	2	0	0.990	1.00	736	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 854.29$ (Equation 25-2 or 25-3) $P_{FM} = 0.601$ using Equation (Exhibit 25-5) $V_{12} = 1948$ pc/h V_3 or $V_{av34} = 1291$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	3678	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	2387	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 18.6$ (pc/mi/ln) LOS = B (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.295$ (Exhibit 25-19) $S_R = 51.9$ mph (Exhibit 25-19) $S_0 = 53.2$ mph (Exhibit 25-19) $S = 52.3$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 4 NB Off to ASR			
Date Performed		02/14/12		Jurisdiction		NYS DOT			
Analysis Time Period		AM		Analysis Year		2026 Flyover			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{down} =$ 2600 ft $V_D =$ 190 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	3350	0.92	Level	2	0	0.990	1.00	3678	
Ramp	910	0.82	Level	2	0	0.990	1.00	1121	
UpStream									
DownStream	190	0.82	Level	2	0	0.990	1.00	234	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ using Equation (Exhibit 25-5) $P_{FM} =$ pc/h $V_{12} =$ pc/h (Equation 25-4 or 25-5) V_3 or V_{av34} pc/h Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ 378.49 (Equation 25-8 or 25-9) $P_{FD} =$ 0.616 using Equation (Exhibit 25-12) $V_{12} =$ 2697 pc/h V_3 or V_{av34} 981 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	3678	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	2557	Exhibit 25-14	6780	No	
				V_R	1121	Exhibit 25-3	2100	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	2697	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 21.1 (pc/mi/ln) $LOS =$ C (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.464 (Exhibit 25-19) $S_R =$ 49.5 mph (Exhibit 25-19) $S_0 =$ 61.4 mph (Exhibit 25-19) $S =$ 52.2 mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 4 NB Off to Wolf			
Date Performed		02/14/12		Jurisdiction		NYS DOT			
Analysis Time Period		AM		Analysis Year		2026 Flyover			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 2600$ ft $V_u = 910$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_P)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2400	0.92	Level	2	0	0.990	1.00	2635	
Ramp	190	0.82	Level	2	0	0.990	1.00	234	
UpStream	910	0.82	Level	2	0	0.990	1.00	1121	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} = 0.683$ using Equation (Exhibit 25-12) $V_{12} = 1875$ pc/h V_3 or $V_{av34} = 760$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	2635	Exhibit 25-14	6780	No
					$V_{FO} = V_F - V_R$	2401	Exhibit 25-14	6780	No
					V_R	234	Exhibit 25-3	2100	No
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	1875	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 17.2$ (pc/mi/ln) $LOS = B$ (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.384$ (Exhibit 25-19) $S_R = 50.6$ mph (Exhibit 25-19) $S_0 = 61.4$ mph (Exhibit 25-19) $S = 53.3$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET													
General Information					Site Information								
Analyst		SEB		Freeway/Dir of Travel		Southbound							
Agency or Company		CHA		Junction		Exit 2W Off							
Date Performed		02/14/12		Jurisdiction		NYS DOT							
Analysis Time Period		AM		Analysis Year		2026 Flyover							
Project Description Exit 4													
Inputs													
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1300 ft $V_D =$ 350 veh/h						
Conversion to pc/h Under Base Conditions													
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$					
Freeway	5400	0.92	Level	2	0	0.990	1.00	5928					
Ramp	760	0.92	Level	2	0	0.990	1.00	834					
UpStream													
DownStream	350	0.92	Level	2	0	0.990	1.00	384					
Merge Areas					Diverge Areas								
Estimation of v_{12}					Estimation of v_{12}								
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.573 using Equation (Exhibit 25-12) $V_{12} =$ 3755 pc/h V_3 or V_{av34} 2173 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)								
Capacity Checks					Capacity Checks								
		Actual	Capacity		LOS F?								
V_{FO}		Exhibit 25-7					V_F	5928	Exhibit 25-14	6780	No		
							$V_{FO} = V_F - V_R$	5094	Exhibit 25-14	6780	No		
							V_R	834	Exhibit 25-3	2100	No		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area								
		Actual	Max Desirable		Violation?				Actual	Max Desirable		Violation?	
V_{R12}			Exhibit 25-7				V_{12}		3755	Exhibit 25-14	4400:All	No	
Level of Service Determination (if not F)					Level of Service Determination (if not F)								
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 33.8 (pc/mi/ln) $LOS =$ D (Exhibit 25-4)								
Speed Determination					Speed Determination								
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.438 (Exhibit 25-19) $S_R =$ 49.9 mph (Exhibit 25-19) $S_0 =$ 56.9 mph (Exhibit 25-19) $S =$ 52.2 mph (Exhibit 25-15)								

RAMPS AND RAMP JUNCTIONS WORKSHEET														
General Information					Site Information									
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87								
Agency or Company		CHA		Junction		Exit 4 SB Off								
Date Performed		02/14/12		Jurisdiction		NYS DOT								
Analysis Time Period		AM		Analysis Year		2026 Flyover								
Project Description Exit 4														
Inputs														
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1585 ft $V_D =$ 650 veh/h							
Conversion to pc/h Under Base Conditions														
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$						
Freeway	5600	0.92	Level	2	0	0.990	1.00	6148						
Ramp	640	0.92	Level	2	0	0.990	1.00	703						
UpStream														
DownStream	650	0.93	Level	5	0	0.976	1.00	716						
Merge Areas					Diverge Areas									
Estimation of v_{12}					Estimation of v_{12}									
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ $P_{FD} = 0.574$ using Equation (Exhibit 25-12) $V_{12} = 3828$ pc/h V_3 or $V_{av34} 2320$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)									
Capacity Checks					Capacity Checks									
		Actual	Capacity		LOS F?									
V_{FO}							V_F	6148	Exhibit 25-14	6780	No			
							$V_{FO} = V_F - V_R$	5445	Exhibit 25-14	6780	No			
							V_R	703	Exhibit 25-3	2100	No			
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area									
		Actual	Max Desirable		Violation?				Actual	Max Desirable		Violation?		
V_{R12}			Exhibit 25-7				V_{12}		3828	Exhibit 25-14		4400:All		No
Level of Service Determination (if not F)					Level of Service Determination (if not F)									
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 27.7$ (pc/mi/ln) $LOS = C$ (Exhibit 25-4)									
Speed Determination					Speed Determination									
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.426$ (Exhibit 25-19) $S_R = 50.0$ mph (Exhibit 25-19) $S_0 = 56.3$ mph (Exhibit 25-19) $S = 52.2$ mph (Exhibit 25-15)									


RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 4 SB On-Ramp			
Date Performed		02/14/12		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2026 Flyover			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1585$ ft $V_u = 640$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4950	0.92	Level	2	0	0.990	1.00	5434	
Ramp	650	0.93	Level	5	0	0.976	1.00	716	
UpStream	640	0.92	Level	2	0	0.990	1.00	703	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 1589.76$ (Equation 25-2 or 25-3) $P_{FM} = 0.614$ using Equation (Exhibit 25-5) $V_{12} = 3336$ pc/h V_3 or $V_{av34} = 2098$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	6150	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	4052	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 28.5$ (pc/mi/ln) LOS = D (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.440$ (Exhibit 25-19) $S_R = 49.8$ mph (Exhibit 25-19) $S_0 = 50.2$ mph (Exhibit 25-19) $S = 50.0$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 5 SB On-Ramp			
Date Performed		02/14/12		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2026 Flyover			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{down} =$ 4700 ft $V_D =$ 640 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	5200	0.92	Level	2	0	0.990	1.00	5709	
Ramp	390	0.93	Level	3	0	0.985	1.00	426	
UpStream									
DownStream	640	0.92	Level	2	0	0.990	1.00	703	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 2826.70$ (Equation 25-2 or 25-3) $P_{FM} = 0.614$ using Equation (Exhibit 25-5) $V_{12} = 3505$ pc/h V_3 or $V_{av34} = 2204$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	6135	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	3931	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 27.8$ (pc/mi/ln) LOS = C (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.416$ (Exhibit 25-19) $S_R = 50.2$ mph (Exhibit 25-19) $S_0 = 49.9$ mph (Exhibit 25-19) $S = 50.1$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 02/14/12 Analysis Time Period AM					Freeway/Dir of Travel I-87 Northbound Weaving Seg Location Exit 2E on to 2W off Jurisdiction NYSDOT Analysis Year 2026 Flyover				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 815 Terrain Level					Weaving type A Volume ratio, VR 0.27 Weaving ratio, R 0.32				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	2640	0.92	2	0	1.5	1.2	0.990	1.00	2898
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	670	0.92	2	0	1.5	1.2	0.990	1.00	735
V_{w2}	310	0.92	2	0	1.5	1.2	0.990	1.00	340
V_w				1075	V_{nw}				2898
V									3973
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	0.96		0.47						
Weaving and non-weaving speeds, S_i (mi/h)	38.45		46.27						
Number of lanes required for unconstrained operation, N_w					1.36				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					43.86				
Weaving segment density, D (pc/mi/ln)					22.65				
Level of service, LOS					C				
Capacity of base condition, c_b (pc/h)					6352				
Capacity as a 15-minute flow rate, c (veh/h)					6289				
Capacity as a full-hour volume, c_h (veh/h)					5786				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 02/14/12 Analysis Time Period AM					Freeway/Dir of Travel I-87 Southbound Weaving Seg Location Exit 2W on to 2E off Jurisdiction NYSDOT Analysis Year 2026 Flyover				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 810 Terrain Level					Weaving type A Volume ratio, VR 0.22 Weaving ratio, R 0.31				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	3880	0.92	2	0	1.5	1.2	0.990	1.00	4259
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	770	0.92	2	0	1.5	1.2	0.990	1.00	845
V_{w2}	350	0.92	2	0	1.5	1.2	0.990	1.00	384
V_w				1229	V_{nw}				4259
V									5488
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	1.22		0.62						
Weaving and non-weaving speeds, S_i (mi/h)	35.74		43.40						
Number of lanes required for unconstrained operation, N_w					1.26				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					41.41				
Weaving segment density, D (pc/mi/ln)					33.13				
Level of service, LOS					D				
Capacity of base condition, c_b (pc/h)					6603				
Capacity as a 15-minute flow rate, c (veh/h)					6538				
Capacity as a full-hour volume, c_h (veh/h)					6015				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 2 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *3500* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1281* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *22.9* pc/mi/ln
 LOS *C*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 to Exit 2*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5450* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.92*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1994* pc/h/ln
 S *55.0* mi/h
 $D = v_p / S$ *36.2* pc/mi/ln
 LOS *E*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2250* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.92*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *823* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *14.7* pc/mi/ln
 LOS *B*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 off to Exit 4 off*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2450* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *897* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *16.0* pc/mi/ln
 LOS *B*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5100* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1866* pc/h/ln
 S *55.8* mi/h
 $D = v_p / S$ *33.4* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 to Exit 5*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2800* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *4*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *768* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *13.7* pc/mi/ln
 LOS *B*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 5 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5850* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *2141* pc/h/ln
 S *53.0* mi/h
 $D = v_p / S$ *40.4* pc/mi/ln
 LOS *E*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *CLD*
 Agency or Company *CHA*
 Date Performed *07/30/13*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 5 to Exit 6*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2650* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *4*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *727* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *13.0* pc/mi/ln
 LOS *B*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *CLD*
 Agency or Company *CHA*
 Date Performed *07/30/13*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 6 to Exit 5*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *6150* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *4*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1688* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *30.1* pc/mi/ln
 LOS *D*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 2W On-Ramp			
Date Performed		02/14/12		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2036 Flyover			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1100$ ft $V_u = 690$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	3100	0.92	Level	2	0	0.990	1.00	3403	
Ramp	420	0.92	Level	2	0	0.990	1.00	461	
UpStream	690	0.92	Level	2	0	0.990	1.00	757	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 894.10$ (Equation 25-2 or 25-3) $P_{FM} = 0.601$ using Equation (Exhibit 25-5) $V_{12} = 2046$ pc/h V_3 or $V_{av34} = 1357$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	3864	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	2507	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 19.5$ (pc/mi/ln) LOS = B (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.301$ (Exhibit 25-19) $S_R = 51.8$ mph (Exhibit 25-19) $S_0 = 52.9$ mph (Exhibit 25-19) $S = 52.2$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 4 NB Off to ASR			
Date Performed		02/14/12		Jurisdiction		NYS DOT			
Analysis Time Period		AM		Analysis Year		2036 Flyover			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{down} =$ 2600 ft $V_D =$ 190 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	3500	0.92	Level	2	0	0.990	1.00	3842	
Ramp	1040	0.82	Level	2	0	0.990	1.00	1281	
UpStream									
DownStream	190	0.82	Level	2	0	0.990	1.00	234	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ using Equation (Exhibit 25-5) $P_{FM} =$ pc/h $V_{12} =$ pc/h (Equation 25-4 or 25-5) V_3 or V_{av34} pc/h Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ 422.43 (Equation 25-8 or 25-9) $P_{FD} =$ 0.605 using Equation (Exhibit 25-12) $V_{12} =$ 2830 pc/h V_3 or V_{av34} 1012 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	3842	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	2561	Exhibit 25-14	6780	No	
				V_R	1281	Exhibit 25-3	2100	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	2830	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 22.3 (pc/mi/ln) $LOS =$ C (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.478 (Exhibit 25-19) $S_R =$ 49.3 mph (Exhibit 25-19) $S_0 =$ 61.4 mph (Exhibit 25-19) $S =$ 52.0 mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 4 NB Off to Wolf			
Date Performed		02/14/12		Jurisdiction		NYS DOT			
Analysis Time Period		AM		Analysis Year		2036 Flyover			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 2600$ ft $V_u = 1040$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2450	0.92	Level	2	0	0.990	1.00	2690	
Ramp	190	0.82	Level	2	0	0.990	1.00	234	
UpStream	1040	0.82	Level	2	0	0.990	1.00	1281	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} = 0.682$ using Equation (Exhibit 25-12) $V_{12} = 1909$ pc/h V_3 or $V_{av34} = 781$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	2690	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	2456	Exhibit 25-14	6780	No	
				V_R	234	Exhibit 25-3	2100	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	1909	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 17.5$ (pc/mi/ln) $LOS = B$ (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.384$ (Exhibit 25-19) $S_R = 50.6$ mph (Exhibit 25-19) $S_0 = 61.4$ mph (Exhibit 25-19) $S = 53.3$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET													
General Information					Site Information								
Analyst		SEB		Freeway/Dir of Travel		Southbound							
Agency or Company		CHA		Junction		Exit 2W Off							
Date Performed		02/14/12		Jurisdiction		NYS DOT							
Analysis Time Period		AM		Analysis Year		2036 Flyover							
Project Description Exit 4													
Inputs													
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1300 ft $V_D =$ 360 veh/h						
Conversion to pc/h Under Base Conditions													
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$					
Freeway	5450	0.92	Level	2	0	0.990	1.00	5983					
Ramp	770	0.92	Level	2	0	0.990	1.00	845					
UpStream													
DownStream	360	0.92	Level	2	0	0.990	1.00	395					
Merge Areas					Diverge Areas								
Estimation of v_{12}					Estimation of v_{12}								
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ $P_{FD} = 0.572$ using Equation (Exhibit 25-12) $V_{12} = 3782$ pc/h V_3 or V_{av34} 2201 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)								
Capacity Checks					Capacity Checks								
		Actual	Capacity		LOS F?								
V_{FO}			Exhibit 25-7				V_F	5983	Exhibit 25-14	6780	No		
							$V_{FO} = V_F - V_R$	5138	Exhibit 25-14	6780	No		
							V_R	845	Exhibit 25-3	2100	No		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area								
		Actual	Max Desirable		Violation?				Actual	Max Desirable		Violation?	
V_{R12}			Exhibit 25-7				V_{12}		3782	Exhibit 25-14	4400:All	No	
Level of Service Determination (if not F)					Level of Service Determination (if not F)								
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 34.1$ (pc/mi/ln) $LOS = D$ (Exhibit 25-4)								
Speed Determination					Speed Determination								
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.439$ (Exhibit 25-19) $S_R = 49.9$ mph (Exhibit 25-19) $S_0 = 56.7$ mph (Exhibit 25-19) $S = 52.2$ mph (Exhibit 25-15)								

RAMPS AND RAMP JUNCTIONS WORKSHEET														
General Information					Site Information									
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87								
Agency or Company		CHA		Junction		Exit 4 SB Off								
Date Performed		02/14/12		Jurisdiction		NYSDOT								
Analysis Time Period		AM		Analysis Year		2036 Flyover								
Project Description Exit 4														
Inputs														
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1585 ft $V_D =$ 700 veh/h							
Conversion to pc/h Under Base Conditions														
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$						
Freeway	5850	0.92	Level	2	0	0.990	1.00	6422						
Ramp	730	0.92	Level	2	0	0.990	1.00	801						
UpStream														
DownStream	700	0.93	Level	5	0	0.976	1.00	772						
Merge Areas					Diverge Areas									
Estimation of v_{12}					Estimation of v_{12}									
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.563 using Equation (Exhibit 25-12) $V_{12} =$ 3963 pc/h V_3 or V_{av34} 2459 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)									
Capacity Checks					Capacity Checks									
		Actual	Capacity		LOS F?									
V_{FO}							V_F	6422	Exhibit 25-14	6780	No			
			Exhibit 25-7				$V_{FO} = V_F - V_R$	5621	Exhibit 25-14	6780	No			
							V_R	801	Exhibit 25-3	2100	No			
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area									
		Actual	Max Desirable		Violation?				Actual	Max Desirable		Violation?		
V_{R12}			Exhibit 25-7				V_{12}		3963	Exhibit 25-14		4400:All		No
Level of Service Determination (if not F)					Level of Service Determination (if not F)									
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 28.9 (pc/mi/ln) $LOS =$ D (Exhibit 25-4)									
Speed Determination					Speed Determination									
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.435 (Exhibit 25-19) $S_R =$ 49.9 mph (Exhibit 25-19) $S_0 =$ 55.7 mph (Exhibit 25-19) $S =$ 52.0 mph (Exhibit 25-15)									


RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 4 SB On-Ramp			
Date Performed		02/14/12		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2036 Flyover			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1585$ ft $V_u = 730$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	5100	0.92	Level	2	0	0.990	1.00	5599	
Ramp	700	0.93	Level	5	0	0.976	1.00	772	
UpStream	730	0.92	Level	2	0	0.990	1.00	801	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 1637.05$ (Equation 25-2 or 25-3) $P_{FM} = 0.611$ using Equation (Exhibit 25-5) $V_{12} = 3420$ pc/h V_3 or $V_{av34} = 2179$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	6371	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	4192	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 29.6$ (pc/mi/ln) LOS = D (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.474$ (Exhibit 25-19) $S_R = 49.4$ mph (Exhibit 25-19) $S_0 = 50.0$ mph (Exhibit 25-19) $S = 49.6$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 5 SB On-Ramp			
Date Performed		02/14/12		Jurisdiction		NYSDOT			
Analysis Time Period		AM		Analysis Year		2036 Flyover			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_I)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{down} =$ 4700 ft $V_D =$ 730 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	5400	0.92	Level	2	0	0.990	1.00	5928	
Ramp	470	0.93	Level	3	0	0.985	1.00	513	
UpStream									
DownStream	730	0.92	Level	2	0	0.990	1.00	801	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 3220.75$ (Equation 25-2 or 25-3) $P_{FM} = 0.614$ using Equation (Exhibit 25-5) $V_{12} = 3639$ pc/h V_3 or $V_{av34} = 2289$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	6441	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	4152	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 29.5$ (pc/mi/ln) LOS = D (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.465$ (Exhibit 25-19) $S_R = 49.5$ mph (Exhibit 25-19) $S_0 = 49.6$ mph (Exhibit 25-19) $S = 49.5$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB					Freeway/Dir of Travel I-87 Northbound				
Agency/Company CHA					Weaving Seg Location Exit 2E on to 2W off				
Date Performed 02/14/12					Jurisdiction NYSDOT				
Analysis Time Period AM					Analysis Year 2036 Flyover				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56					Weaving type A				
Weaving number of lanes, N 4					Volume ratio, VR 0.27				
Weaving seg length, L (ft) 815					Weaving ratio, R 0.32				
Terrain Level									
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	2780	0.92	2	0	1.5	1.2	0.990	1.00	3051
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	690	0.92	2	0	1.5	1.2	0.990	1.00	757
V_{w2}	320	0.92	2	0	1.5	1.2	0.990	1.00	351
V_w				1108	V_{nw}				3051
V									4159
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	1.00		0.49						
Weaving and non-weaving speeds, S_i (mi/h)	38.02		45.81						
Number of lanes required for unconstrained operation, N_w					1.36				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					43.44				
Weaving segment density, D (pc/mi/ln)					23.94				
Level of service, LOS					C				
Capacity of base condition, c_b (pc/h)					6375				
Capacity as a 15-minute flow rate, c (veh/h)					6312				
Capacity as a full-hour volume, c_h (veh/h)					5807				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 02/14/12 Analysis Time Period AM					Freeway/Dir of Travel I-87 Southbound Weaving Seg Location Exit 2W on to 2E off Jurisdiction NYSDOT Analysis Year 2036 Flyover				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 810 Terrain Level					Weaving type A Volume ratio, VR 0.23 Weaving ratio, R 0.31				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	3910	0.92	2	0	1.5	1.2	0.990	1.00	4292
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	790	0.92	2	0	1.5	1.2	0.990	1.00	867
V_{w2}	360	0.92	2	0	1.5	1.2	0.990	1.00	395
V_w				1262	V_{nw}				4292
V									5554
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	1.24		0.64						
Weaving and non-weaving speeds, S_i (mi/h)	35.54		43.11						
Number of lanes required for unconstrained operation, N_w					1.27				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					41.12				
Weaving segment density, D (pc/mi/ln)					33.77				
Level of service, LOS					D				
Capacity of base condition, c_b (pc/h)					6585				
Capacity as a 15-minute flow rate, c (veh/h)					6520				
Capacity as a full-hour volume, c_h (veh/h)					5998				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2046 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2200* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *805* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *14.4* pc/mi/ln
 LOS *B*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 off to Exit 4 off*
 Jurisdiction *NYSDOT*
 Analysis Year *2046 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2450* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *897* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *16.0* pc/mi/ln
 LOS *B*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2046 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5100* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1866* pc/h/ln
 S *55.8* mi/h
 $D = v_p / S$ *33.4* pc/mi/ln
 LOS *D*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 2 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 Flyover*

Project Description *Exit 4*☒ Oper.(LOS)☐ Des.(N)☐ Planning Data

Flow Inputs

Volume, V *5500* veh/h Peak-Hour Factor, PHF *0.86*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *2153* pc/h/ln
 S *52.7* mi/h
 $D = v_p / S$ *40.8* pc/mi/ln
 LOS *E*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 to Exit 2*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *3900* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1427* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *25.5* pc/mi/ln
 LOS *C*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *4300* veh/h Peak-Hour Factor, PHF *0.86*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1683* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *30.1* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 off to Exit 4 off*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *4400* veh/h Peak-Hour Factor, PHF *0.86*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1722* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *30.8* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *2950* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.92*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1080* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *19.3* pc/mi/ln
 LOS *C*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 to Exit 5*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5900* veh/h Peak-Hour Factor, PHF *0.86*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *4*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1732* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *30.9* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 5 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *3650* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1336* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *23.9* pc/mi/ln
 LOS *C*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *CLD*
 Agency or Company *CHA*
 Date Performed *07/30/13*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 5 to Exit 6*
 Jurisdiction *NYSDOT*
 Analysis Year *2016 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *6150* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.86*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *4*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1806* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *32.3* pc/mi/ln
 LOS *D*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET																										
			<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Application</th> <th>Input</th> <th>Output</th> </tr> </thead> <tbody> <tr> <td>Operational (LOS)</td> <td>FFS, N, v_p</td> <td>LOS, S, D</td> </tr> <tr> <td>Design (N)</td> <td>FFS, LOS, v_p</td> <td>N, S, D</td> </tr> <tr> <td>Design (v_p)</td> <td>FFS, LOS, N</td> <td>v_p, S, D</td> </tr> <tr> <td>Planning (LOS)</td> <td>FFS, N, AADT</td> <td>LOS, S, D</td> </tr> <tr> <td>Planning (N)</td> <td>FFS, LOS, AADT</td> <td>N, S, D</td> </tr> <tr> <td>Planning (v_p)</td> <td>FFS, LOS, N</td> <td>v_p, S, D</td> </tr> </tbody> </table>			Application	Input	Output	Operational (LOS)	FFS, N, v_p	LOS, S, D	Design (N)	FFS, LOS, v_p	N, S, D	Design (v_p)	FFS, LOS, N	v_p , S, D	Planning (LOS)	FFS, N, AADT	LOS, S, D	Planning (N)	FFS, LOS, AADT	N, S, D	Planning (v_p)	FFS, LOS, N	v_p , S, D
Application	Input	Output																								
Operational (LOS)	FFS, N, v_p	LOS, S, D																								
Design (N)	FFS, LOS, v_p	N, S, D																								
Design (v_p)	FFS, LOS, N	v_p , S, D																								
Planning (LOS)	FFS, N, AADT	LOS, S, D																								
Planning (N)	FFS, LOS, AADT	N, S, D																								
Planning (v_p)	FFS, LOS, N	v_p , S, D																								
General Information			Site Information																							
Analyst		CLD	Highway/Direction of Travel		Southbound I-87																					
Agency or Company		CHA	From/To		Exit 6 to Exit 5																					
Date Performed		07/30/13	Jurisdiction		NYSDOT																					
Analysis Time Period		PM	Analysis Year		2016 Flyover																					
Project Description Exit 4																										
<input checked="" type="checkbox"/> Oper.(LOS) <input type="checkbox"/> Des.(N) <input type="checkbox"/> Planning Data																										
Flow Inputs																										
Volume, V		3500	veh/h	Peak-Hour Factor, PHF	0.92																					
AADT			veh/day	%Trucks and Buses, P_T	2																					
Peak-Hr Prop. of AADT, K				%RVs, P_R	0																					
Peak-Hr Direction Prop, D				General Terrain:	Level																					
DDHV = AADT x K x D			veh/h	Grade % Length	mi																					
Driver type adjustment		1.00		Up/Down %																						
Calculate Flow Adjustments																										
f_p		1.00		E_R	1.2																					
E_T		1.5		$f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$	0.990																					
Speed Inputs			Calc Speed Adj and FFS																							
Lane Width		12.0	ft	f_{LW}	mi/h																					
Rt-Shoulder Lat. Clearance		6.0	ft	f_{LC}	mi/h																					
Interchange Density		0.50	l/mi	f_{ID}	mi/h																					
Number of Lanes, N		4		f_N	mi/h																					
FFS (measured)		56.0	mi/h	FFS	56.0																					
Base free-flow Speed, BFFS			mi/h																							
LOS and Performance Measures			Design (N)																							
<u>Operational (LOS)</u>			<u>Design (N)</u>																							
$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$		961	pc/h/ln	$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$																						
S		56.0	mi/h	S																						
$D = v_p / S$		17.2	pc/mi/ln	$D = v_p / S$																						
LOS		B		Required Number of Lanes, N																						
Glossary			Factor Location																							
N - Number of lanes		S - Speed	E_R - Exhibits 23-8, 23-10		f_{LW} - Exhibit 23-4																					
V - Hourly volume		D - Density	E_T - Exhibits 23-8, 23-10, 23-11		f_{LC} - Exhibit 23-5																					
v_p - Flow rate		FFS - Free-flow speed	f_p - Page 23-12		f_N - Exhibit 23-6																					
LOS - Level of service		BFFS - Base free-flow speed	LOS, S, FFS, v_p - Exhibits 23-2, 23-3		f_{ID} - Exhibit 23-7																					
DDHV - Directional design hour volume																										

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 2W On-Ramp			
Date Performed		02/14/12		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2016 Flyover			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1100$ ft $V_u = 800$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4650	0.86	Level	2	0	0.990	1.00	5461	
Ramp	870	0.92	Level	2	0	0.990	1.00	955	
UpStream	800	0.92	Level	2	0	0.990	1.00	878	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 1440.22$ (Equation 25-2 or 25-3) $P_{FM} = 0.580$ using Equation (Exhibit 25-5) $V_{12} = 3166$ pc/h V_3 or $V_{av34} = 2295$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	6416	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	4121	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 31.9$ (pc/mi/ln) LOS = D (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.493$ (Exhibit 25-19) $S_R = 49.1$ mph (Exhibit 25-19) $S_0 = 49.5$ mph (Exhibit 25-19) $S = 49.3$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET														
General Information					Site Information									
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87								
Agency or Company		CHA		Junction		Exit 4 NB Off to ASR								
Date Performed		02/14/12		Jurisdiction		NYS DOT								
Analysis Time Period		PM		Analysis Year		2016 Flyover								
Project Description Exit 4														
Inputs														
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{down} =$ 2600 ft $V_D =$ 110 veh/h							
Conversion to pc/h Under Base Conditions														
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$						
Freeway	5500	0.86	Level	2	0	0.990	1.00	6459						
Ramp	1090	0.86	Level	2	0	0.990	1.00	1280						
UpStream														
DownStream	110	0.86	Level	1	0	0.995	1.00	129						
Merge Areas					Diverge Areas									
Estimation of v_{12}					Estimation of v_{12}									
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ using Equation (Exhibit 25-5) $P_{FM} =$ pc/h $V_{12} =$ pc/h (Equation 25-4 or 25-5) V_3 or V_{av34} pc/h Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ 274.30 (Equation 25-8 or 25-9) $P_{FD} =$ 0.540 using Equation (Exhibit 25-12) $V_{12} =$ 4075 pc/h V_3 or V_{av34} 2384 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)									
Capacity Checks					Capacity Checks									
		Actual	Capacity		LOS F?									
V_{FO}		Exhibit 25-7					V_F	6459	Exhibit 25-14	6780	No			
							$V_{FO} = V_F - V_R$	5179	Exhibit 25-14	6780	No			
							V_R	1280	Exhibit 25-3	2100	No			
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area									
		Actual	Max Desirable		Violation?				Actual	Max Desirable		Violation?		
V_{R12}			Exhibit 25-7						V_{12}	4075	Exhibit 25-14		4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)									
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 33.0 (pc/mi/ln) $LOS =$ D (Exhibit 25-4)									
Speed Determination					Speed Determination									
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.478 (Exhibit 25-19) $S_R =$ 49.3 mph (Exhibit 25-19) $S_0 =$ 56.0 mph (Exhibit 25-19) $S =$ 51.6 mph (Exhibit 25-15)									

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 4 NB Off to Wolf			
Date Performed		02/14/12		Jurisdiction		NYS DOT			
Analysis Time Period		PM		Analysis Year		2016 Flyover			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 2600$ ft $V_u = 1090$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4400	0.86	Level	2	0	0.990	1.00	5167	
Ramp	110	0.86	Level	2	0	0.990	1.00	129	
UpStream	1090	0.86	Level	1	0	0.995	1.00	1274	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} = 0.625$ using Equation (Exhibit 25-12) $V_{12} = 3277$ pc/h V_3 or V_{av34} 1890 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	5167	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	5038	Exhibit 25-14	6780	No	
				V_R	129	Exhibit 25-3	2100	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	3277	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 29.3$ (pc/mi/ln) $LOS = D$ (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.375$ (Exhibit 25-19) $S_R = 50.8$ mph (Exhibit 25-19) $S_0 = 58.0$ mph (Exhibit 25-19) $S = 53.2$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET														
General Information					Site Information									
Analyst		SEB		Freeway/Dir of Travel		Southbound								
Agency or Company		CHA		Junction		Exit 2W Off								
Date Performed		02/14/12		Jurisdiction		NYS DOT								
Analysis Time Period		PM		Analysis Year		2016 Flyover								
Project Description Exit 4														
Inputs														
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1300 ft $V_D =$ 800 veh/h							
Conversion to pc/h Under Base Conditions														
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$						
Freeway	3900	0.92	Level	2	0	0.990	1.00	4282						
Ramp	430	0.92	Level	2	0	0.990	1.00	472						
UpStream														
DownStream	800	0.92	Level	2	0	0.990	1.00	878						
Merge Areas					Diverge Areas									
Estimation of v_{12}					Estimation of v_{12}									
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ $P_{FD} = 0.631$ using Equation (Exhibit 25-12) $V_{12} = 2877$ pc/h V_3 or V_{av34} 1405 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)									
Capacity Checks					Capacity Checks									
		Actual	Capacity		LOS F?									
V_{FO}		Exhibit 25-7					V_F	4282	Exhibit 25-14	6780	No			
							$V_{FO} = V_F - V_R$	3810	Exhibit 25-14	6780	No			
							V_R	472	Exhibit 25-3	2100	No			
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area									
		Actual	Max Desirable		Violation?				Actual	Max Desirable		Violation?		
V_{R12}			Exhibit 25-7						V_{12}	2877	Exhibit 25-14		4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)									
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 26.3$ (pc/mi/ln) $LOS = C$ (Exhibit 25-4)									
Speed Determination					Speed Determination									
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.405$ (Exhibit 25-19) $S_R = 50.3$ mph (Exhibit 25-19) $S_0 = 59.9$ mph (Exhibit 25-19) $S = 53.1$ mph (Exhibit 25-15)									

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 4 SB Off			
Date Performed		02/14/12		Jurisdiction		NYS DOT			
Analysis Time Period		PM		Analysis Year		2016 Flyover			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1585 ft $V_D =$ 990 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	3650	0.92	Level	2	0	0.990	1.00	4007	
Ramp	720	0.92	Level	2	0	0.990	1.00	790	
UpStream									
DownStream	990	0.93	Level	4	0	0.980	1.00	1086	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.623 using Equation (Exhibit 25-12) $V_{12} =$ 2796 pc/h V_3 or V_{av34} 1211 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	4007	Exhibit 25-14	6780	No
					$V_{FO} = V_F - V_R$	3217	Exhibit 25-14	6780	No
					V_R	790	Exhibit 25-3	2100	No
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	2796	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 18.8 (pc/mi/ln) $LOS =$ B (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.434 (Exhibit 25-19) $S_R =$ 49.9 mph (Exhibit 25-19) $S_0 =$ 60.6 mph (Exhibit 25-19) $S =$ 52.7 mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 4 SB On-Ramp			
Date Performed		02/14/12		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2016 Flyover			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1585$ ft $V_u = 720$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	2950	0.92	Level	2	0	0.990	1.00	3239	
Ramp	990	0.93	Level	4	0	0.980	1.00	1086	
UpStream	720	0.92	Level	2	0	0.990	1.00	790	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 1199.21$ (Equation 25-2 or 25-3) $P_{FM} = 0.614$ using Equation (Exhibit 25-5) $V_{12} = 1990$ pc/h V_3 or $V_{av34} = 1249$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	4325	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	3076	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 20.7$ (pc/mi/ln) LOS = C (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.300$ (Exhibit 25-19) $S_R = 51.8$ mph (Exhibit 25-19) $S_0 = 53.3$ mph (Exhibit 25-19) $S = 52.2$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 5 SB On-Ramp			
Date Performed		02/14/12		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2016 Flyover			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{down} =$ 4700 ft $V_D =$ 720 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	3050	0.92	Level	2	0	0.990	1.00	3348	
Ramp	610	0.87	Level	1	0	0.995	1.00	705	
UpStream									
DownStream	720	0.92	Level	2	0	0.990	1.00	790	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 3176.52$ (Equation 25-2 or 25-3) $P_{FM} = 0.614$ using Equation (Exhibit 25-5) $V_{12} = 2055$ pc/h V_3 or $V_{av34} = 1293$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	4053	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	2760	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 18.5$ (pc/mi/ln) $LOS = B$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.279$ (Exhibit 25-19) $S_R = 52.1$ mph (Exhibit 25-19) $S_0 = 53.1$ mph (Exhibit 25-19) $S = 52.4$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 02/14/12 Analysis Time Period PM					Freeway/Dir of Travel I-87 Northbound Weaving Seg Location Exit 2E on to 2W off Jurisdiction NYSDOT Analysis Year 2016 Flyover				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 815 Terrain Level					Weaving type A Volume ratio, VR 0.22 Weaving ratio, R 0.36				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	4200	0.86	2	0	1.5	1.2	0.990	1.00	4932
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	800	0.92	2	0	1.5	1.2	0.990	1.00	878
V_{w2}	450	0.92	2	0	1.5	1.2	0.990	1.00	494
V_w				1372	V_{nw}				4932
V									6304
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	1.37		0.72						
Weaving and non-weaving speeds, S_i (mi/h)	34.40		41.69						
Number of lanes required for unconstrained operation, N_w					1.26				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					39.85				
Weaving segment density, D (pc/mi/ln)					39.55				
Level of service, LOS					E				
Capacity of base condition, c_b (pc/h)					6645				
Capacity as a 15-minute flow rate, c (veh/h)					6579				
Capacity as a full-hour volume, c_h (veh/h)					5748				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 02/14/12 Analysis Time Period PM					Freeway/Dir of Travel I-87 Southbound Weaving Seg Location Exit 2W on to 2E off Jurisdiction NYSDOT Analysis Year 2016 Flyover				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 810 Terrain Level					Weaving type A Volume ratio, VR 0.22 Weaving ratio, R 0.15				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	3310	0.92	2	0	1.5	1.2	0.990	1.00	3633
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	800	0.92	2	0	1.5	1.2	0.990	1.00	878
V_{w2}	140	0.92	2	0	1.5	1.2	0.990	1.00	153
V_w				1031	V_{nw}				3633
V									4664
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	1.03		0.50						
Weaving and non-weaving speeds, S_i (mi/h)	37.61		45.73						
Number of lanes required for unconstrained operation, N_w					1.22				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					43.64				
Weaving segment density, D (pc/mi/ln)					26.72				
Level of service, LOS					C				
Capacity of base condition, c_b (pc/h)					6619				
Capacity as a 15-minute flow rate, c (veh/h)					6553				
Capacity as a full-hour volume, c_h (veh/h)					6029				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 2 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5600* veh/h Peak-Hour Factor, PHF *0.86*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *2192* pc/h/ln
 S *51.9* mi/h
 $D = v_p / S$ *42.2* pc/mi/ln
 LOS *E*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 to Exit 2*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *4000* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.92*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1464* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *26.1* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *4350* veh/h Peak-Hour Factor, PHF *0.86*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1703* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *30.4* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 off to Exit 4 off*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *4450* veh/h Peak-Hour Factor, PHF *0.86*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1742* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *31.1* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *3050* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.92*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1116* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *19.9* pc/mi/ln
 LOS *C*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 to Exit 5*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5950* veh/h Peak-Hour Factor, PHF *0.86*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *4*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1747* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *31.2* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 5 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *3800* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.92*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or DDHV}) / (PHF \times N \times f_{HV} \times f_p)$ *1391* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *24.8* pc/mi/ln
 LOS *C*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or DDHV}) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *CLD*
 Agency or Company *CHA*
 Date Performed *07/30/13*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 5 to Exit 6*
 Jurisdiction *NYSDOT*
 Analysis Year *2026 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *6175* veh/h Peak-Hour Factor, PHF *0.86*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *4*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1813* pc/h/ln
 S *55.9* mi/h
 $D = v_p / S$ *32.4* pc/mi/ln
 LOS *D*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET																										
			<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Application</th> <th>Input</th> <th>Output</th> </tr> </thead> <tbody> <tr> <td>Operational (LOS)</td> <td>FFS, N, v_p</td> <td>LOS, S, D</td> </tr> <tr> <td>Design (N)</td> <td>FFS, LOS, v_p</td> <td>N, S, D</td> </tr> <tr> <td>Design (v_p)</td> <td>FFS, LOS, N</td> <td>v_p, S, D</td> </tr> <tr> <td>Planning (LOS)</td> <td>FFS, N, AADT</td> <td>LOS, S, D</td> </tr> <tr> <td>Planning (N)</td> <td>FFS, LOS, AADT</td> <td>N, S, D</td> </tr> <tr> <td>Planning (v_p)</td> <td>FFS, LOS, N</td> <td>v_p, S, D</td> </tr> </tbody> </table>			Application	Input	Output	Operational (LOS)	FFS, N, v_p	LOS, S, D	Design (N)	FFS, LOS, v_p	N, S, D	Design (v_p)	FFS, LOS, N	v_p , S, D	Planning (LOS)	FFS, N, AADT	LOS, S, D	Planning (N)	FFS, LOS, AADT	N, S, D	Planning (v_p)	FFS, LOS, N	v_p , S, D
Application	Input	Output																								
Operational (LOS)	FFS, N, v_p	LOS, S, D																								
Design (N)	FFS, LOS, v_p	N, S, D																								
Design (v_p)	FFS, LOS, N	v_p , S, D																								
Planning (LOS)	FFS, N, AADT	LOS, S, D																								
Planning (N)	FFS, LOS, AADT	N, S, D																								
Planning (v_p)	FFS, LOS, N	v_p , S, D																								
General Information			Site Information																							
Analyst		CLD		Highway/Direction of Travel																						
Agency or Company		CHA		Southbound I-87																						
Date Performed		07/30/13		From/To																						
Analysis Time Period		PM		Exit 6 to Exit 5																						
Jurisdiction		NYSDOT		Analysis Year																						
Analysis Year		2026		Flyover																						
Project Description Exit 4																										
<input checked="" type="checkbox"/> Oper.(LOS) <input type="checkbox"/> Des.(N) <input type="checkbox"/> Planning Data																										
Flow Inputs																										
Volume, V		3650		veh/h																						
AADT				veh/day																						
Peak-Hr Prop. of AADT, K				Peak-Hour Factor, PHF																						
Peak-Hr Direction Prop, D				0.92																						
DDHV = AADT x K x D				%Trucks and Buses, P_T																						
Driver type adjustment		1.00		2																						
				%RVs, P_R																						
				0																						
				General Terrain:																						
				Level																						
				Grade % Length																						
				mi																						
				Up/Down %																						
Calculate Flow Adjustments																										
f_p		1.00		E_R																						
E_T		1.5		1.2																						
				$f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$																						
				0.990																						
Speed Inputs			Calc Speed Adj and FFS																							
Lane Width		12.0		ft																						
Rt-Shoulder Lat. Clearance		6.0		ft																						
Interchange Density		0.50		l/mi																						
Number of Lanes, N		4																								
FFS (measured)		56.0		mi/h																						
Base free-flow Speed, BFFS				mi/h																						
				FFS																						
				56.0																						
				mi/h																						
LOS and Performance Measures			Design (N)																							
<u>Operational (LOS)</u>			<u>Design (N)</u>																							
$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$			Design LOS																							
S			$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$																							
$D = v_p / S$			S																							
LOS			$D = v_p / S$																							
			Required Number of Lanes, N																							
Glossary			Factor Location																							
N - Number of lanes			S - Speed																							
V - Hourly volume			D - Density																							
v_p - Flow rate			FFS - Free-flow speed																							
LOS - Level of service			BFFS - Base free-flow speed																							
DDHV - Directional design hour volume																										
			E_R - Exhibits 23-8, 23-10																							
			E_T - Exhibits 23-8, 23-10, 23-11																							
			f_p - Page 23-12																							
			LOS, S, FFS, v_p - Exhibits 23-2, 23-3																							
			f_{LW} - Exhibit 23-4																							
			f_{LC} - Exhibit 23-5																							
			f_N - Exhibit 23-6																							
			f_{ID} - Exhibit 23-7																							

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 2W On-Ramp			
Date Performed		02/14/12		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2026 Flyover			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1100$ ft $V_u = 840$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4750	0.86	Level	2	0	0.990	1.00	5578	
Ramp	870	0.92	Level	2	0	0.990	1.00	955	
UpStream	840	0.92	Level	2	0	0.990	1.00	922	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 1465.26$ (Equation 25-2 or 25-3) $P_{FM} = 0.578$ using Equation (Exhibit 25-5) $V_{12} = 3225$ pc/h V_3 or $V_{av34} = 2353$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	6533	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	4180	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 32.3$ (pc/mi/ln) LOS = D (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.508$ (Exhibit 25-19) $S_R = 48.9$ mph (Exhibit 25-19) $S_0 = 49.2$ mph (Exhibit 25-19) $S = 49.0$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

Generated: 2/17/2012 1:17 PM

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 4 NB Off to Wolf			
Date Performed		02/14/12		Jurisdiction		NYS DOT			
Analysis Time Period		PM		Analysis Year		2026 Flyover			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 2600$ ft $V_u = 1170$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_P)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4450	0.86	Level	2	0	0.990	1.00	5226	
Ramp	120	0.86	Level	2	0	0.990	1.00	141	
UpStream	1170	0.86	Level	1	0	0.995	1.00	1367	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} = 0.623$ using Equation (Exhibit 25-12) $V_{12} = 3308$ pc/h V_3 or V_{av34} 1918 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	5226	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	5085	Exhibit 25-14	6780	No	
				V_R	141	Exhibit 25-3	2100	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	3308	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 29.6$ (pc/mi/ln) $LOS = D$ (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.376$ (Exhibit 25-19) $S_R = 50.7$ mph (Exhibit 25-19) $S_0 = 57.9$ mph (Exhibit 25-19) $S = 53.1$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET											
General Information					Site Information						
Analyst		SEB		Freeway/Dir of Travel		Southbound					
Agency or Company		CHA		Junction		Exit 2W Off					
Date Performed		02/14/12		Jurisdiction		NYS DOT					
Analysis Time Period		PM		Analysis Year		2026 Flyover					
Project Description Exit 4											
Inputs											
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1300 ft $V_D =$ 840 veh/h				
Conversion to pc/h Under Base Conditions											
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$			
Freeway	4000	0.92	Level	2	0	0.990	1.00	4391			
Ramp	450	0.92	Level	2	0	0.990	1.00	494			
UpStream											
DownStream	840	0.92	Level	2	0	0.990	1.00	922			
Merge Areas					Diverge Areas						
Estimation of v_{12}					Estimation of v_{12}						
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ $P_{FD} = 0.628$ using Equation (Exhibit 25-12) $V_{12} = 2939$ pc/h V_3 or V_{av34} 1452 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)						
Capacity Checks					Capacity Checks						
		Actual	Capacity		LOS F?			Actual	Capacity	LOS F?	
V_{FO}			Exhibit 25-7			V_F		4391	Exhibit 25-14	6780	No
						$V_{FO} = V_F - V_R$		3897	Exhibit 25-14	6780	No
						V_R		494	Exhibit 25-3	2100	No
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area						
		Actual	Max Desirable		Violation?			Actual	Max Desirable		Violation?
V_{R12}			Exhibit 25-7			V_{12}		2939	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)						
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 26.8$ (pc/mi/ln) $LOS = C$ (Exhibit 25-4)						
Speed Determination					Speed Determination						
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.407$ (Exhibit 25-19) $S_R = 50.3$ mph (Exhibit 25-19) $S_0 = 59.7$ mph (Exhibit 25-19) $S = 53.1$ mph (Exhibit 25-15)						

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 4 SB Off			
Date Performed		02/14/12		Jurisdiction		NYS DOT			
Analysis Time Period		PM		Analysis Year		2026 Flyover			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1585 ft $V_D =$ 1010 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	3800	0.92	Level	2	0	0.990	1.00	4172	
Ramp	770	0.92	Level	2	0	0.990	1.00	845	
UpStream									
DownStream	1010	0.93	Level	4	0	0.980	1.00	1108	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $L_{EQ} =$ $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ (Equation 25-8 or 25-9) $L_{EQ} =$ $P_{FD} = 0.617$ using Equation (Exhibit 25-12) $V_{12} = 2897$ pc/h V_3 or V_{av34} 1275 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
		Actual	Capacity		LOS F?				
V_{FO}							V_F	4172	Exhibit 25-14 6780 No
							$V_{FO} = V_F - V_R$	3327	Exhibit 25-14 6780 No
							V_R	845	Exhibit 25-3 2100 No
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
		Actual	Max Desirable		Violation?				
V_{R12}			Exhibit 25-7				V_{12}	2897	Exhibit 25-14 4400:All No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 19.7$ (pc/mi/ln) $LOS = B$ (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.439$ (Exhibit 25-19) $S_R = 49.9$ mph (Exhibit 25-19) $S_0 = 60.4$ mph (Exhibit 25-19) $S = 52.7$ mph (Exhibit 25-15)				


RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 4 SB On-Ramp			
Date Performed		02/14/12		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2026 Flyover			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1585$ ft $V_u = 770$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	3050	0.92	Level	2	0	0.990	1.00	3348	
Ramp	1010	0.93	Level	4	0	0.980	1.00	1108	
UpStream	770	0.92	Level	2	0	0.990	1.00	845	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 1227.24$ (Equation 25-2 or 25-3) $P_{FM} = 0.614$ using Equation (Exhibit 25-5) $V_{12} = 2057$ pc/h V_3 or $V_{av34} = 1291$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	4456	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	3165	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 21.4$ (pc/mi/ln) LOS = C (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.308$ (Exhibit 25-19) $S_R = 51.7$ mph (Exhibit 25-19) $S_0 = 53.2$ mph (Exhibit 25-19) $S = 52.1$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 5 SB On-Ramp			
Date Performed		02/14/12		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2026 Flyover			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{down} =$ 4700 ft $V_D =$ 770 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	3150	0.92	Level	2	0	0.990	1.00	3458	
Ramp	640	0.87	Level	1	0	0.995	1.00	739	
UpStream									
DownStream	770	0.92	Level	2	0	0.990	1.00	845	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 3397.67$ (Equation 25-2 or 25-3) $P_{FM} = 0.614$ using Equation (Exhibit 25-5) $V_{12} = 2123$ pc/h V_3 or $V_{av34} = 1335$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	4197	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	2862	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 19.3$ (pc/mi/ln) LOS = B (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.285$ (Exhibit 25-19) $S_R = 52.0$ mph (Exhibit 25-19) $S_0 = 53.0$ mph (Exhibit 25-19) $S = 52.3$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 02/14/12 Analysis Time Period PM					Freeway/Dir of Travel I-87 Northbound Weaving Seg Location Exit 2E on to 2W off Jurisdiction NYSDOT Analysis Year 2026 Flyover				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 815 Terrain Level					Weaving type A Volume ratio, VR 0.22 Weaving ratio, R 0.36				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	4280	0.86	2	0	1.5	1.2	0.990	1.00	5026
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	840	0.92	2	0	1.5	1.2	0.990	1.00	922
V_{w2}	470	0.92	2	0	1.5	1.2	0.990	1.00	515
V_w				1437	V_{nw}				5026
V									6463
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	1.42		0.76						
Weaving and non-weaving speeds, S_i (mi/h)	34.04		41.15						
Number of lanes required for unconstrained operation, N_w					1.28				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					39.32				
Weaving segment density, D (pc/mi/ln)					41.09				
Level of service, LOS					E				
Capacity of base condition, c_b (pc/h)					6619				
Capacity as a 15-minute flow rate, c (veh/h)					6553				
Capacity as a full-hour volume, c_h (veh/h)					5728				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 02/14/12 Analysis Time Period PM					Freeway/Dir of Travel I-87 Southbound Weaving Seg Location Exit 2W on to 2E off Jurisdiction NYSDOT Analysis Year 2026 Flyover				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 810 Terrain Level					Weaving type A Volume ratio, VR 0.23 Weaving ratio, R 0.14				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	3210	0.92	2	0	1.5	1.2	0.990	1.00	3524
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	840	0.92	2	0	1.5	1.2	0.990	1.00	922
V_{w2}	140	0.92	2	0	1.5	1.2	0.990	1.00	153
V_w				1075	V_{nw}				3524
V									4599
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	1.04		0.51						
Weaving and non-weaving speeds, S_i (mi/h)	37.50		45.49						
Number of lanes required for unconstrained operation, N_w					1.26				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					43.33				
Weaving segment density, D (pc/mi/ln)					26.53				
Level of service, LOS					C				
Capacity of base condition, c_b (pc/h)					6549				
Capacity as a 15-minute flow rate, c (veh/h)					6484				
Capacity as a full-hour volume, c_h (veh/h)					5965				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 2 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5650* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.86*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *2212* pc/h/ln
 S *51.5* mi/h
 $D = v_p / S$ *43.0* pc/mi/ln
 LOS *E*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 to Exit 2*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *4150* veh/h Peak-Hour Factor, PHF *0.92*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1519* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *27.1* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *4300* veh/h Peak-Hour Factor, PHF *0.86*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1683* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *30.1* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 off to Exit 4 off*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *4400* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.86*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1 + P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1722* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *30.8* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *3050* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.92*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1116* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *19.9* pc/mi/ln
 LOS *C*

Design (N)

Design (N)

Design LOS

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 to Exit 5*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5950* veh/h Peak-Hour Factor, PHF *0.86*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *4*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1747* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *31.2* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 5 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *3900* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.92*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1427* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *25.5* pc/mi/ln
 LOS *C*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *CLD*
 Agency or Company *CHA*
 Date Performed *07/30/13*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 5 to Exit 6*
 Jurisdiction *NYSDOT*
 Analysis Year *2036 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *6200* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.86*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *4*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1820* pc/h/ln
 S *55.9* mi/h
 $D = v_p / S$ *32.5* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET																										
			<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Application</th> <th>Input</th> <th>Output</th> </tr> </thead> <tbody> <tr> <td>Operational (LOS)</td> <td>FFS, N, v_p</td> <td>LOS, S, D</td> </tr> <tr> <td>Design (N)</td> <td>FFS, LOS, v_p</td> <td>N, S, D</td> </tr> <tr> <td>Design (v_p)</td> <td>FFS, LOS, N</td> <td>v_p, S, D</td> </tr> <tr> <td>Planning (LOS)</td> <td>FFS, N, AADT</td> <td>LOS, S, D</td> </tr> <tr> <td>Planning (N)</td> <td>FFS, LOS, AADT</td> <td>N, S, D</td> </tr> <tr> <td>Planning (v_p)</td> <td>FFS, LOS, N</td> <td>v_p, S, D</td> </tr> </tbody> </table>			Application	Input	Output	Operational (LOS)	FFS, N, v_p	LOS, S, D	Design (N)	FFS, LOS, v_p	N, S, D	Design (v_p)	FFS, LOS, N	v_p , S, D	Planning (LOS)	FFS, N, AADT	LOS, S, D	Planning (N)	FFS, LOS, AADT	N, S, D	Planning (v_p)	FFS, LOS, N	v_p , S, D
Application	Input	Output																								
Operational (LOS)	FFS, N, v_p	LOS, S, D																								
Design (N)	FFS, LOS, v_p	N, S, D																								
Design (v_p)	FFS, LOS, N	v_p , S, D																								
Planning (LOS)	FFS, N, AADT	LOS, S, D																								
Planning (N)	FFS, LOS, AADT	N, S, D																								
Planning (v_p)	FFS, LOS, N	v_p , S, D																								
General Information			Site Information																							
Analyst		CLD		Highway/Direction of Travel																						
Agency or Company		CHA		Southbound I-87																						
Date Performed		07/30/13		From/To																						
Analysis Time Period		PM		Exit 6 to Exit 5																						
				Jurisdiction																						
				NYSDOT																						
Project Description		Exit 4		Analysis Year																						
				2036 Flyover																						
<input checked="" type="checkbox"/> Oper.(LOS)			<input type="checkbox"/> Des.(N)		<input type="checkbox"/> Planning Data																					
Flow Inputs																										
Volume, V		3800		veh/h																						
AADT				veh/day																						
Peak-Hr Prop. of AADT, K				Peak-Hour Factor, PHF																						
Peak-Hr Direction Prop, D				0.92																						
DDHV = AADT x K x D				%Trucks and Buses, P_T																						
Driver type adjustment		1.00		2																						
				%RVs, P_R																						
				0																						
				General Terrain:																						
				Level																						
				Grade % Length																						
				mi																						
				Up/Down %																						
Calculate Flow Adjustments																										
f_p		1.00		E_R																						
E_T		1.5		1.2																						
				$f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$																						
				0.990																						
Speed Inputs			Calc Speed Adj and FFS																							
Lane Width		12.0		ft																						
Rt-Shoulder Lat. Clearance		6.0		ft																						
Interchange Density		0.50		l/mi																						
Number of Lanes, N		4																								
FFS (measured)		56.0		mi/h																						
Base free-flow Speed, BFFS				mi/h																						
				FFS																						
				56.0																						
				mi/h																						
LOS and Performance Measures			Design (N)																							
<u>Operational (LOS)</u>			<u>Design (N)</u>																							
$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$			Design LOS																							
1043			$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$																							
pc/h/ln			pc/h																							
S			S																							
56.0			mi/h																							
D = v_p / S			D = v_p / S																							
18.6			pc/mi/ln																							
LOS			C																							
			Required Number of Lanes, N																							
Glossary			Factor Location																							
N - Number of lanes			S - Speed																							
V - Hourly volume			D - Density																							
v_p - Flow rate			FFS - Free-flow speed																							
LOS - Level of service			BFFS - Base free-flow speed																							
DDHV - Directional design hour volume																										
			E _R - Exhibits 23-8, 23-10																							
			f _{LW} - Exhibit 23-4																							
			E _T - Exhibits 23-8, 23-10, 23-11																							
			f _{LC} - Exhibit 23-5																							
			f _p - Page 23-12																							
			f _N - Exhibit 23-6																							
			LOS, S, FFS, v_p - Exhibits 23-2, 23-3																							
			f _{ID} - Exhibit 23-7																							

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 2W On-Ramp			
Date Performed		02/14/12		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2036 Flyover			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1100$ ft $V_u = 880$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4750	0.86	Level	2	0	0.990	1.00	5578	
Ramp	880	0.92	Level	2	0	0.990	1.00	966	
UpStream	880	0.92	Level	2	0	0.990	1.00	966	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 1467.62$ (Equation 25-2 or 25-3) $P_{FM} = 0.578$ using Equation (Exhibit 25-5) $V_{12} = 3224$ pc/h V_3 or $V_{av34} = 2354$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	6544	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	4190	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 32.4$ (pc/mi/ln) LOS = D (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.510$ (Exhibit 25-19) $S_R = 48.9$ mph (Exhibit 25-19) $S_0 = 49.1$ mph (Exhibit 25-19) $S = 49.0$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 4 NB Off to ASR			
Date Performed		02/14/12		Jurisdiction		NYS DOT			
Analysis Time Period		PM		Analysis Year		2036 Flyover			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{down} =$ 2600 ft $V_D =$ 120 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	5650	0.86	Level	2	0	0.990	1.00	6635	
Ramp	1260	0.86	Level	2	0	0.990	1.00	1480	
UpStream									
DownStream	120	0.86	Level	1	0	0.995	1.00	140	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ 358.21 (Equation 25-8 or 25-9) $P_{FD} =$ 0.526 using Equation (Exhibit 25-12) $V_{12} =$ 4192 pc/h V_3 or V_{av34} 2443 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	6635	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	5155	Exhibit 25-14	6780	No	
				V_R	1480	Exhibit 25-3	2100	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	4192	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 34.0 (pc/mi/ln) $LOS =$ D (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.496 (Exhibit 25-19) $S_R =$ 49.1 mph (Exhibit 25-19) $S_0 =$ 55.8 mph (Exhibit 25-19) $S =$ 51.3 mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Northbound I-87			
Agency or Company		CHA		Junction		Exit 4 NB Off to Wolf			
Date Performed		02/14/12		Jurisdiction		NYS DOT			
Analysis Time Period		PM		Analysis Year		2036 Flyover			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 2600$ ft $V_u = 1260$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4400	0.86	Level	2	0	0.990	1.00	5167	
Ramp	120	0.86	Level	2	0	0.990	1.00	141	
UpStream	1260	0.86	Level	1	0	0.995	1.00	1472	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} = 0.624$ using Equation (Exhibit 25-12) $V_{12} = 3279$ pc/h V_3 or V_{av34} 1888 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	5167	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	5026	Exhibit 25-14	6780	No	
				V_R	141	Exhibit 25-3	2100	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	3279	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R = 29.3$ (pc/mi/ln) $LOS = D$ (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S = 0.376$ (Exhibit 25-19) $S_R = 50.7$ mph (Exhibit 25-19) $S_0 = 58.0$ mph (Exhibit 25-19) $S = 53.2$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound			
Agency or Company		CHA		Junction		Exit 2W Off			
Date Performed		02/14/12		Jurisdiction		NYS DOT			
Analysis Time Period		PM		Analysis Year		2036 Flyover			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1300 ft $V_D =$ 880 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	4150	0.92	Level	2	0	0.990	1.00	4556	
Ramp	480	0.92	Level	2	0	0.990	1.00	527	
UpStream									
DownStream	880	0.92	Level	2	0	0.990	1.00	966	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.622 using Equation (Exhibit 25-12) $V_{12} =$ 3032 pc/h V_3 or V_{av34} 1524 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}		Exhibit 25-7			V_F	4556	Exhibit 25-14	6780	No
				$V_{FO} = V_F - V_R$	4029	Exhibit 25-14	6780	No	
				V_R	527	Exhibit 25-3	2100	No	
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}		Exhibit 25-7			V_{12}	3032	Exhibit 25-14	4400:All	No
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 27.6 (pc/mi/ln) $LOS =$ C (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.410 (Exhibit 25-19) $S_R =$ 50.3 mph (Exhibit 25-19) $S_0 =$ 59.4 mph (Exhibit 25-19) $S =$ 53.0 mph (Exhibit 25-15)				


RAMPS AND RAMP JUNCTIONS WORKSHEET														
General Information					Site Information									
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87								
Agency or Company		CHA		Junction		Exit 4 SB Off								
Date Performed		02/14/12		Jurisdiction		NYS DOT								
Analysis Time Period		PM		Analysis Year		2036 Flyover								
Project Description Exit 4														
Inputs														
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A, L_D, V_R, V_P)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input checked="" type="checkbox"/> On <input type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ 1585 ft $V_D =$ 1030 veh/h							
Conversion to pc/h Under Base Conditions														
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$						
Freeway	3900	0.92	Level	2	0	0.990	1.00	4282						
Ramp	830	0.92	Level	2	0	0.990	1.00	911						
UpStream														
DownStream	1030	0.93	Level	4	0	0.980	1.00	1130						
Merge Areas					Diverge Areas									
Estimation of v_{12}					Estimation of v_{12}									
$V_{12} = V_F (P_{FM})$ $L_{EQ} =$ (Equation 25-2 or 25-3) $P_{FM} =$ using Equation (Exhibit 25-5) $V_{12} =$ pc/h V_3 or V_{av34} pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ 0.611 using Equation (Exhibit 25-12) $V_{12} =$ 2971 pc/h V_3 or V_{av34} 1311 pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 \times V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)									
Capacity Checks					Capacity Checks									
		Actual	Capacity		LOS F?									
V_{FO}							V_F	4282	Exhibit 25-14	6780	No			
			Exhibit 25-7				$V_{FO} = V_F - V_R$	3371	Exhibit 25-14	6780	No			
							V_R	911	Exhibit 25-3	2100	No			
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area									
		Actual	Max Desirable		Violation?				Actual	Max Desirable		Violation?		
V_{R12}			Exhibit 25-7				V_{12}		2971	Exhibit 25-14		4400:All		No
Level of Service Determination (if not F)					Level of Service Determination (if not F)									
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R =$ (pc/mi/ln) $LOS =$ (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ 20.4 (pc/mi/ln) $LOS =$ C (Exhibit 25-4)									
Speed Determination					Speed Determination									
$M_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-14)					$D_S =$ 0.445 (Exhibit 25-19) $S_R =$ 49.8 mph (Exhibit 25-19) $S_0 =$ 60.2 mph (Exhibit 25-19) $S =$ 52.6 mph (Exhibit 25-15)									

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 4 SB On-Ramp			
Date Performed		02/14/12		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2036 Flyover			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{up} = 1585$ ft $V_u = 830$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{down} =$ ft $V_D =$ veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	3050	0.92	Level	2	0	0.990	1.00	3348	
Ramp	1030	0.93	Level	4	0	0.980	1.00	1130	
UpStream	830	0.92	Level	2	0	0.990	1.00	911	
DownStream									
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 1231.95$ (Equation 25-2 or 25-3) $P_{FM} = 0.614$ using Equation (Exhibit 25-5) $V_{12} = 2057$ pc/h V_3 or $V_{av34} = 1291$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	4478	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	3187	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 21.6$ (pc/mi/ln) LOS = C (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.310$ (Exhibit 25-19) $S_R = 51.7$ mph (Exhibit 25-19) $S_0 = 53.2$ mph (Exhibit 25-19) $S = 52.1$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

RAMPS AND RAMP JUNCTIONS WORKSHEET									
General Information					Site Information				
Analyst		SEB		Freeway/Dir of Travel		Southbound I-87			
Agency or Company		CHA		Junction		Exit 5 SB On-Ramp			
Date Performed		02/14/12		Jurisdiction		NYSDOT			
Analysis Time Period		PM		Analysis Year		2036 Flyover			
Project Description Exit 4									
Inputs									
Upstream Adj Ramp <input type="checkbox"/> Yes <input type="checkbox"/> On <input checked="" type="checkbox"/> No <input type="checkbox"/> Off $L_{up} =$ ft $V_u =$ veh/h			Terrain: Level $S_{FF} = 56.0$ mph $S_{FR} = 40.0$ mph Sketch (show lanes, L_A , L_D , V_R , V_I)				Downstream Adj Ramp <input checked="" type="checkbox"/> Yes <input type="checkbox"/> On <input type="checkbox"/> No <input checked="" type="checkbox"/> Off $L_{down} =$ 4700 ft $V_D =$ 830 veh/h		
Conversion to pc/h Under Base Conditions									
(pc/h)	V (Veh/hr)	PHF	Terrain	%Truck	%Rv	f_{HV}	f_p	$v = V/PHF \times f_{HV} \times f_p$	
Freeway	3250	0.92	Level	2	0	0.990	1.00	3568	
Ramp	670	0.87	Level	1	0	0.995	1.00	774	
UpStream									
DownStream	830	0.92	Level	2	0	0.990	1.00	911	
Merge Areas					Diverge Areas				
Estimation of v_{12}					Estimation of v_{12}				
$V_{12} = V_F (P_{FM})$ $L_{EQ} = 3663.05$ (Equation 25-2 or 25-3) $P_{FM} = 0.614$ using Equation (Exhibit 25-5) $V_{12} = 2190$ pc/h V_3 or $V_{av34} = 1378$ pc/h (Equation 25-4 or 25-5) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-8)					$V_{12} = V_R + (V_F - V_R)P_{FD}$ $L_{EQ} =$ (Equation 25-8 or 25-9) $P_{FD} =$ using Equation (Exhibit 25-12) $V_{12} =$ pc/h V_3 or $V_{av34} =$ pc/h (Equation 25-15 or 25-16) Is V_3 or $V_{av34} > 2,700$ pc/h? <input type="checkbox"/> Yes <input type="checkbox"/> No Is V_3 or $V_{av34} > 1.5 * V_{12}/2$ <input type="checkbox"/> Yes <input type="checkbox"/> No If Yes, $V_{12a} =$ pc/h (Equation 25-18)				
Capacity Checks					Capacity Checks				
	Actual	Capacity		LOS F?		Actual	Capacity		LOS F?
V_{FO}	4342	Exhibit 25-7		No	V_F		Exhibit 25-14		
					$V_{FO} = V_F - V_R$		Exhibit 25-14		
					V_R		Exhibit 25-3		
Flow Entering Merge Influence Area					Flow Entering Diverge Influence Area				
	Actual	Max Desirable		Violation?		Actual	Max Desirable		Violation?
V_{R12}	2964	Exhibit 25-7	4600:All	No	V_{12}		Exhibit 25-14		
Level of Service Determination (if not F)					Level of Service Determination (if not F)				
$D_R = 5.475 + 0.00734 v_R + 0.0078 V_{12} - 0.00627 L_A$ $D_R = 20.1$ (pc/mi/ln) LOS = C (Exhibit 25-4)					$D_R = 4.252 + 0.0086 V_{12} - 0.009 L_D$ $D_R =$ (pc/mi/ln) LOS = (Exhibit 25-4)				
Speed Determination					Speed Determination				
$M_S = 0.293$ (Exhibit 25-19) $S_R = 51.9$ mph (Exhibit 25-19) $S_0 = 52.8$ mph (Exhibit 25-19) $S = 52.2$ mph (Exhibit 25-14)					$D_S =$ (Exhibit 25-19) $S_R =$ mph (Exhibit 25-19) $S_0 =$ mph (Exhibit 25-19) $S =$ mph (Exhibit 25-15)				

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst SEB Agency/Company CHA Date Performed 02/14/12 Analysis Time Period PM					Freeway/Dir of Travel I-87 Northbound Weaving Seg Location Exit 2E on to 2W off Jurisdiction NYSDOT Analysis Year 2036 Flyover				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h) 56 Weaving number of lanes, N 4 Weaving seg length, L (ft) 815 Terrain Level					Weaving type A Volume ratio, VR 0.23 Weaving ratio, R 0.36				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	4260	0.86	2	0	1.5	1.2	0.990	1.00	5003
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	880	0.92	2	0	1.5	1.2	0.990	1.00	966
V_{w2}	490	0.92	2	0	1.5	1.2	0.990	1.00	537
V_w				1503	V_{nw}				5003
V									6506
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	1.45		0.79						
Weaving and non-weaving speeds, S_i (mi/h)	33.79		40.73						
Number of lanes required for unconstrained operation, N_w					1.32				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					38.89				
Weaving segment density, D (pc/mi/ln)					41.83				
Level of service, LOS					E				
Capacity of base condition, c_b (pc/h)					6571				
Capacity as a 15-minute flow rate, c (veh/h)					6506				
Capacity as a full-hour volume, c_h (veh/h)					5690				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *AM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 5 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2046 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *5850* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.92*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *2141* pc/h/ln
 S *53.0* mi/h
 $D = v_p / S$ *40.4* pc/mi/ln
 LOS *E*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary


N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

FREEWAY WEAVING WORKSHEET									
General Information					Site Information				
Analyst Agency/Company Date Performed Analysis Time Period					SEB CHA 02/14/12 PM				
Freeway/Dir of Travel Weaving Seg Location Jurisdiction Analysis Year					I-87 Southbound Exit 2W on to 2E off NYSDOT 2036 Flyover				
Inputs									
Freeway free-flow speed, S_{FF} (mi/h)					56				
Weaving number of lanes, N					4				
Weaving seg length, L (ft)					810				
Terrain					Level				
Weaving type					A				
Volume ratio, VR					0.23				
Weaving ratio, R					0.15				
Conversions to pc/h Under Base Conditions									
(pc/h)	V	PHF	Truck %	RV %	E_T	E_R	f_{HV}	f_p	v
V_{o1}	3500	0.92	2	0	1.5	1.2	0.990	1.00	3842
V_{o2}	0	0.92	2	0	1.5	1.2	0.990	1.00	0
V_{w1}	880	0.92	2	0	1.5	1.2	0.990	1.00	966
V_{w2}	150	0.92	2	0	1.5	1.2	0.990	1.00	164
V_w				1130	V_{nw}				3842
V									4972
Weaving and Non-Weaving Speeds									
	Unconstrained				Constrained				
	Weaving (i = w)		Non-Weaving (i = nw)		Weaving (i = w)		Non-Weaving (= nw)		
a (Exhibit 24-6)	0.15		0.0035						
b (Exhibit 24-6)	2.20		4.00						
c (Exhibit 24-6)	0.97		1.30						
d (Exhibit 24-6)	0.80		0.75						
Weaving intensity factor, W_i	1.11		0.55						
Weaving and non-weaving speeds, S_i (mi/h)	36.77		44.66						
Number of lanes required for unconstrained operation, N_w					1.26				
Maximum number of lanes, N_w (max)					1.40				
<input checked="" type="checkbox"/> If $N_w < N_w(\text{max})$ unconstrained operation					<input type="checkbox"/> if $N_w > N_w(\text{max})$ constrained operation				
Weaving Segment Speed, Density, Level of Service, and Capacity									
Weaving segment speed, S (mi/h)					42.58				
Weaving segment density, D (pc/mi/ln)					29.19				
Level of service, LOS					D				
Capacity of base condition, c_b (pc/h)					6584				
Capacity as a 15-minute flow rate, c (veh/h)					6519				
Capacity as a full-hour volume, c_h (veh/h)					5997				
Notes									
a. Weaving segments longer than 2500 ft. are treated as isolated merge and diverge areas using the procedures of Chapter 25, "Ramps and Ramp Junctions". b. Capacity constrained by basic freeway capacity. c. Capacity occurs under constrained operating conditions. d. Three-lane Type A segments do not operate well at volume ratios greater than 0.45. Poor operations and some local queuing are expected in such cases. e. Four-lane Type A segments do not operate well at volume ratios greater than 0.35. Poor operations and some local queuing are expected in such cases. f. Capacity constrained by maximum allowable weaving flow rate: 2,800 pc/h (Type A), 4,000 (Type B), 3,500 (Type C). g. Five-lane Type A segments do not operate well at volume ratios greater than 0.20. Poor operations and some local queuing are expected in such cases. h. Type B weaving segments do not operate well at volume ratios greater than 0.80. Poor operations and some local queuing are expected in such cases. i. Type C weaving segments do not operate well at volume ratios greater than 0.50. Poor operations and some local queuing are expected in such cases.									

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2046 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *4150* veh/h Peak-Hour Factor, PHF *0.86*
 AADT veh/day %Trucks and Buses, P_T *2*
 Peak-Hr Prop. of AADT, K %RVs, P_R *0*
 Peak-Hr Direction Prop, D General Terrain: *Level*
 DDHV = AADT x K x D veh/h Grade % Length *mi*
 Driver type adjustment *1.00* Up/Down %

Calculate Flow Adjustments

f_p *1.00* E_R *1.2*
 E_T *1.5* $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1625* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *29.0* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p mi/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes S - Speed
 V - Hourly volume D - Density
 v_p - Flow rate FFS - Free-flow speed
 LOS - Level of service BFFS - Base free-flow speed
 DDHV - Directional design hour volume

Factor Location

E_R - Exhibits 23-8, 23-10 f_{LW} - Exhibit 23-4
 E_T - Exhibits 23-8, 23-10, 23-11 f_{LC} - Exhibit 23-5
 f_p - Page 23-12 f_N - Exhibit 23-6
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Northbound I-87*
 From/To *Exit 4 off to Exit 4 off*
 Jurisdiction *NYSDOT*
 Analysis Year *2046 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *4250* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.86*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1664* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *29.7* pc/mi/ln
 LOS *D*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N


Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 5 to Exit 4*
 Jurisdiction *NYSDOT*
 Analysis Year *2046 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *3900* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.92*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1427* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *25.5* pc/mi/ln
 LOS *C*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

BASIC FREEWAY SEGMENTS WORKSHEET



Application	Input	Output
Operational (LOS)	FFS, N, v_p	LOS, S, D
Design (N)	FFS, LOS, v_p	N, S, D
Design (v_p)	FFS, LOS, N	v_p , S, D
Planning (LOS)	FFS, N, AADT	LOS, S, D
Planning (N)	FFS, LOS, AADT	N, S, D
Planning (v_p)	FFS, LOS, N	v_p , S, D

General Information

Analyst *SEB*
 Agency or Company *CHA*
 Date Performed *02/14/12*
 Analysis Time Period *PM*

Site Information

Highway/Direction of Travel *Southbound I-87*
 From/To *Exit 4 off to Exit 4 on*
 Jurisdiction *NYSDOT*
 Analysis Year *2046 Flyover*

Project Description *Exit 4*

☒ Oper.(LOS)

☐ Des.(N)

☐ Planning Data

Flow Inputs

Volume, V *3000* veh/h
 AADT veh/day
 Peak-Hr Prop. of AADT, K
 Peak-Hr Direction Prop, D
 DDHV = AADT x K x D veh/h
 Driver type adjustment *1.00*
 Peak-Hour Factor, PHF *0.92*
 %Trucks and Buses, P_T *2*
 %RVs, P_R *0*
 General Terrain: *Level*
 Grade % Length *mi*
 Up/Down %

Calculate Flow Adjustments

f_p *1.00*
 E_T *1.5*
 E_R *1.2*
 $f_{HV} = 1/[1+P_T(E_T - 1) + P_R(E_R - 1)]$ *0.990*

Speed Inputs

Lane Width *12.0* ft
 Rt-Shoulder Lat. Clearance *6.0* ft
 Interchange Density *0.50* l/mi
 Number of Lanes, N *3*
 FFS (measured) *56.0* mi/h
 Base free-flow Speed, BFFS mi/h

Calc Speed Adj and FFS

f_{LW} mi/h
 f_{LC} mi/h
 f_{ID} mi/h
 f_N mi/h
 FFS *56.0* mi/h

LOS and Performance Measures

Operational (LOS)

$v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ *1098* pc/h/ln
 S *56.0* mi/h
 $D = v_p / S$ *19.6* pc/mi/ln
 LOS *C*

Design (N)

Design (N)
 Design LOS
 $v_p = (V \text{ or } DDHV) / (PHF \times N \times f_{HV} \times f_p)$ pc/h
 f_p
 S mi/h
 $D = v_p / S$ pc/mi/ln
 Required Number of Lanes, N

Glossary

N - Number of lanes
 V - Hourly volume
 v_p - Flow rate
 LOS - Level of service
 DDHV - Directional design hour volume
 S - Speed
 D - Density
 FFS - Free-flow speed
 BFFS - Base free-flow speed

Factor Location

E_R - Exhibits 23-8, 23-10
 E_T - Exhibits 23-8, 23-10, 23-11
 f_p - Page 23-12
 LOS, S, FFS, v_p - Exhibits 23-2, 23-3
 f_{LW} - Exhibit 23-4
 f_{LC} - Exhibit 23-5
 f_N - Exhibit 23-6
 f_{ID} - Exhibit 23-7

**ATTACHMENT F
ACCIDENT ANALYSIS**



MEMORANDUM
DEPARTMENT OF TRANSPORTATION

TO: A. Trichilo, R-1 Design, 3rd floor
FROM: M. Kennedy, R-1 Traffic Engineer, 4th floor
SUBJECT: Updated Accident History for PIN 1721.51
I87 Exits 3/4/5
Town of Colonie, Albany County

DATE: March 3, 2011

Attached please find updated accident data for the subject project, as you requested on 3/23/10. The accident data covers the 3.25 year study period from 1/1/07 to 3/31/10. The current High Accident Location (HAL) period is 11/1/07 to 10/31/09. There were no HALs on the section of I87 from RM 2016 to 2042 studied. NY 910B, Wolf Road, was a Priority Investigation Location from RM 1010 to 1015 and from RM 1016 to 1019. NY 155, Watervliet-Shaker Road, was a Safety Deficient Location from RM 3058 to 3060.

I87, the Northway, is a six lane divided Urban Principal Arterial Interstate highway with full control of access. There were 303 accidents on the section of I87 evaluated during the study period. The accident rate of 0.87 ACC/MVM is less than the expected accident rate of 1.10 ACC/MVM for similar highways statewide. The predominant accident type is rear end accidents. There were 52 accidents during the morning peak from 6 am to 9 am and 105 accidents occurred during the peak evening commute from 3 pm to 6 pm. There was one fatality and no accidents involving pedestrians or bicyclists. Accident summaries and a collision diagram of the southbound Exit5/Exit 4 merge/diverge area service road are provided.

There were 52 accidents in the first section of NY 910B studied and the accident rate is 2.41 ACC/MVM. This rate is less than the expected rate of 3.59 ACC/MVM for four lane divided Urban Principal Arterial highways with free access statewide. The majority of the accidents consisted of rear end and turning accidents due to traffic congestion. There was one accident involving a pedestrian and no accidents involving bicyclists. Of the 53 accidents on this section of highway with pavement condition reported, 14 (26%) occurred on wet pavement and none occurred on snow/ice/slush pavements. There were 7 accidents during the morning peak commute hours from 6 am to 9 am and 16 accidents occurred during the peak evening commute hours from 3 pm to 6 pm. A copy of Highway Safety Investigation report 1-1-0409 is attached.

A. Trichilo, R-1 Design
PIN 1721.5, p. 2 of 3
March 3, 2011

There were 132 accidents in the second section of NY 910B studied and the accident rate is 9.46 ACC/MVM. This rate is greater than the expected accident rate of 3.59 ACC/MVM for four lane divided Urban Principal Arterial highways with free access statewide. The majority of the accidents consisted of rear end and turning accidents due to traffic congestion, particularly at the signalized intersection with Albany County Route 151, Albany-Shaker Road, at the RM 1019. There were no accidents involving pedestrians or bicyclists. Of the 127 accidents on this section of highway with pavement condition reported, 25 (20%) occurred on wet pavement and 5 (4%) occurred on snow/ice/slush pavements. There were 11 accidents during the morning peak commute hours from 6 am to 9 am and 34 accidents occurred during the peak evening commute hours from 3 pm to 6 pm. A signal study, completed 12/28/08, at the intersection with Ulenski Drive at RM 1017 resulted in no safety recommendation. A copy of Highway Safety Investigation report 1-1-0477, which includes the signal study, is attached.

NY 155, Watervliet-Shaker Road, is a four lane undivided Urban Minor Arterial highway with free access. There were 46 accidents on the SDL section of NY 155, from RM 3058 to 3061, evaluated during the period 1/1/07 to 9/30/10. The accident rate of 8.79 ACC/MVM is greater than the expected accident rate of 4.27 ACC/MVM for similar highways statewide. The predominant accident type is rear end accidents. Of the 46 accidents on this section of highway with pavement condition reported, 2 (4%) occurred on wet pavement and 3 (6%) occurred on snow/ice/slush pavements. There were 7 accidents during the morning peak from 6 am to 9 am and 12 accidents occurred during the peak evening commute from 3 pm to 6 pm. There were no accidents involving pedestrians or bicyclists.

Albany County Route 151, Albany-Shaker Road, carries NY Touring Route 155. There were 55 accidents on the section of CR 151 studied, from D'Alessandro Boulevard to Wolf Road. The predominant accident type is rear end accidents. Of the 52 accidents on this section of highway with pavement condition reported, 12 (23%) occurred on wet pavement and 2 (4%) occurred on snow/ice/slush pavements. There were 8 accidents during the morning peak from 6 am to 9 am and 18 accidents occurred during the peak evening commute from 3 pm to 6 pm. There were no accidents involving pedestrians or bicyclists. A signal study, completed 12/22/10, at the signalized intersection with Old Wolf Road and the I87 SB on ramp, resulted in a safety recommendation to refresh the pavement markings. A copy of Highway Safety Investigation report 1-1-0495, which documents the signal study, is attached.

Albany County Route 153, Old Wolf Road, carries NY Touring Route 155. There were 55 accidents on the section of CR 153 studied, from the intersection with AC Rout 151 to Northway Lane, which includes the signalized intersection with the ramp

A. Trichilo, R-1 Design
PIN 1721.5, p. 3 of 3
March 3, 2011

from I87 SB. The predominant accident type is rear end accidents. Of the 28 accidents on this section of highway with pavement condition reported, 7 (25%) occurred on wet pavement and 1 (4%) occurred on snow/ice/slush pavements. There were 6 accidents during the morning peak from 6 am to 9 am and 13 accidents occurred during the peak evening commute from 3 pm to 6 pm. There were no accidents involving pedestrians and one involving a bicyclist. The accidents at the SB ramp junction are plotted on the collision diagram with the ramp accidents.

The majority of the accidents on all the sections of highway reviewed in this study occurred during peak hours and are congestion related. Any project alternative that includes congestion mitigation measures will enhance the overall safety performance, in particular at the signalized junctions with the Exit 4 ramps and Wolf Road. We have no additional safety recommendations to make for the project as a result of our review of this accident history.

If you have any questions concerning this study, please contact Mike Doody of this office at 388-0372.

MJK:MED
Attachments

cc: J. Rutnik, R-1 Traffic, 4th floor

ACCIDENT SUMMARY SHEET

MUNICIPALITY Town of Colonic

COUNTY Albany

LOCATION I87' RM 875-1108-2016 TO 2042

PIN
HSI # 1721.51

TIME PERIOD 1/1/07 TO 3/31/10

NO. OF MONTHS 39

Accident Type No. of Accidents

Right Angle	<u>149</u>
Rear End	<u>57</u>
Overtaking	<u>9</u>
Left Turn Debris	<u>1</u>
Sideswipe/Head-on	<u>5</u>
Right Turn Equipment Malfunction	<u>3</u>
Parked Vehicle	<u> </u>
Pedestrian	<u> </u>
Bicycle	<u> </u>
Animal Deer/Turkey	<u>12</u>
Fixed Object	<u>67</u>
w/Utility Poles	<u>52</u>
w/Guide Rail	<u>7</u>
w/Sign Posts	<u>2</u>
w/Trees	<u>5</u>
w/Ditch-Embank.	<u>1</u>
w/fence	<u> </u>
TOTAL	<u>303</u>

Pavement No. of Accidents

Dry	<u>223</u>
Wet	<u>43</u>
Snow/Ice	<u>35</u>
Unknown	<u>2</u>
TOTAL	<u>303</u>

Weather No. of Accidents

Clear	<u>147</u>
Cloudy	<u>94</u>
Rain	<u>22</u>
Snow	<u>31</u>
Sleet	<u>5</u>
Fog	<u>2</u>
Unknown	<u>2</u>
TOTAL	<u>303</u>

Light Conditions No. of Accidents

Day	<u>221</u>
Night	<u>82</u>
Unknown	<u> </u>
TOTAL	<u>303</u>

Accident Severity No. of Accidents

Fatal	<u>1</u>
Injury	<u>66</u>
Property Damage	<u>236</u>
TOTAL	<u>303</u>

Expected Accident Rates State Highways - 2009

Includes Period from 01-NOV-2007 to 31-OCT-2009

Highway/Intersection

Classification Code: 18 FULL ACCESS, URBAN, DIVIDED, 6 LANE

Classification Type: A = ALL ACCIDENTS

Accident Category	Mean Rate (acc/mvm)	95th Percentile Rate (acc/mvm)
01 OVERALL RATE	1.10	3.29
02 FATAL	.0	.02
03 INJURY	.40	1.26
04 PROPERTY DAMAGE ONLY	.69	2.25
05 NON-REPORTABLE	.01	.04
11 DRY ROAD	.74	2.18
12 WET ROAD	.21	.78
13 SNOW/ICE/SLUSH ROAD	.09	.60
14 ALL OTHER - ROAD SURFACE	.05	.26
21 LEFT-TURN	.01	.05
22 REAR-END	.40	1.29
23 OVERTAKING	.15	.56
24 RIGHT-ANGLE	.02	.09
25 RIGHT-TURN	.0	.02
26 HEAD-ON	.0	.02
27 SIDESWIPE	.0	.03
28 OTHER - MULTI. VEHICLE	.15	.51
41 COLL W/PEDESTRIAN	.01	.03
42 COLL W/BICYCLE	.0	.0
43 COLL W/ANIMAL/TRAIN/OTHER	.05	.28
44 FO:UTILITY/LIGHT POLES	.01	.06
45 FO:RAIL/MBARRIER/CUSHION	.15	.73
46 FO:SIGN/CURB/FENCING	.02	.14
47 FO:DITCH/BRIDGE/CULVERT	.02	.14
48 FO:TREE/HYDRANT/OTHER	.02	.14
49 RUN-OFF-ROAD/OVERTURN	.01	.08
50 NON COLLISION	.02	.12

Accident Severity Summary

Intersection & Non-Intersection Accidents

Complete. Accident Data From NYSDMV Is Only Available thru 30-SEP-2010

Route: 87I Highway Location Ref Mrkr Range: 87I11082016 - 87I11082042

Dates: 01-JAN-2007 thru 31-MAR-2010 Traffic Volume: 108,250

Total of Fatal Accd	Total of Injury Accd	Total of PDO Accd	Total of Non-Reportable	Total Number of Accidents	Accident Rate
1	70	158	73	302	.87

Accident rate for linear section is accidents per million vehicle miles.

NYSDOT Safety Information Management System Summary Report By Segment And/Or Intersection

Intersection & Non-Intersection Accidents

Complete Accident Data From NYSDMV is Only Available thru 30-SEP-2010

ROUTE: 87I		HIGHWAY LOCATION: 87I11082016		- 87I11082042		DATES: 01-JAN-2007		- 31-MAR-2010											
REFERENCE	INT.	DESCRIPTION	TOTAL	FTL	INJ	PDO	N/R	WET ROAD	FIXED OBJ	PED& BIKE	TRUCK ***	NUMBER OF ACCIDENTS				LIGHT CONDITION			
								**	**	**	**	**	**	**	**	**	**	**	
87I 1108 2016		COLONIE VILLAGE/COLONIE TOWN LI	7	0	1	5	1	1	2	0	0	1	3	3					
87I 1108 2017			7	0	1	3	3	2	1	0	1	0	3	4					
87I 1108 2018			8	0	0	4	4	1	0	0	0	1	6	1					
87I 1108 2019			5	0	1	2	2	1	0	0	1	0	3	2					
87I 1108 2020			8	0	1	4	3	1	1	0	0	0	7	1					
87I 1108 2021			10	0	4	4	2	3	3	0	1	0	8	2					
87I 1108 2022			6	0	1	0	5	1	0	0	0	0	6	0					
87I 1108 2023			10	0	1	6	3	0	3	0	0	3	6	1					
87I 1108 2024			12	0	1	7	4	2	4	0	1	1	8	3					
87I 1108 2025			17	0	5	10	2	4	6	0	2	3	12	2					
87I 1108 2026			17	0	5	9	3	1	5	0	2	0	12	5					
87I 1108 2026	09	NB OFF RAMP TO WOLF RD	5	0	2	1	2	1	2	0	0	0	2	2					
87I 1108 2026	10	SB ON RAMP FROM ALBANY SHAKER RD	6	0	3	2	1	2	1	0	1	0	5	1					
87I 1108 2027			16	0	5	8	3	2	2	0	0	2	10	4					
87I 1108 2028			4	0	0	3	1	0	0	0	0	1	3	0					
87I 1108 2029			5	0	2	3	0	0	3	0	1	0	4	1					
87I 1108 2030			7	0	4	2	1	0	2	0	0	0	4	3					
87I 1108 2030	12	SB ON RAMP FROM NY 155	11	0	5	3	3	4	2	0	0	0	10	1					
87I 1108 2031			5	0	2	1	2	0	1	0	1	1	4	0					
87I 1108 2032			12	0	4	5	3	2	0	0	2	1	9	2					
87I 1108 2032	01	NB ON RAMP FROM WOLF RD	5	0	1	4	0	1	0	0	0	0	2	3					
87I 1108 2033			5	0	1	4	0	0	2	0	2	0	4	1					
87I 1108 2034			11	0	1	7	3	1	5	0	0	0	11	0					
87I 1108 2035			6	0	1	3	2	1	2	0	2	0	4	2					
87I 1108 2035	13	SB OFF RAMP TO WOLF RD	22	0	6	12	4	4	2	0	0	0	17	5					
87I 1108 2036			10	0	2	4	4	1	2	0	3	0	5	4					
87I 1108 2037			5	0	2	3	0	0	1	0	0	0	3	1					

NYSDOT Safety Information Management System Summary Report By Segment And/Or Intersection

Date: 02/16/11 12:35
Page: 2

Intersection & Non-Intersection Accidents

Complete Accident Data From NYSDMV Is Only Available thru 30-SEP-2010

ROUTE: 87I		HIGHWAY LOCATION: 87I11082016 - 87I11082042	DATES: 01-JAN-2007 - 31-MAR-2010													
REFERENCE	INT.	DESCRIPTION	TOTAL	FTL	INJ	PDO	N/R	NUMBER OF ACCIDENTS				LIGHT CONDITION				
								WET	FIXED	PED&	TRUCK	DWN/DSK	DAY	NIGHT		
								ROAD	OBJ	BIKE	***	**	**	**	**	
								**	**	**	**	**	**	**	**	
87I 1108 2038			15	0	2	10	3	1	4	0	3	0	13	2		
87I 1108 2038	15	NB OFF RAMP TO NY 155	5	0	1	4	0	0	5	0	0	0	3	2		
87I 1108 2039			11	0	1	7	3	3	1	0	0	0	10	1		
87I 1108 2039	14	SB OFF RAMP TO NY 155	3	0	0	3	0	0	3	0	0	0	0	3		
87I 1108 2040			10	0	1	8	1	1	2	0	1	0	6	4		
87I 1108 2040	16	NB ON RAMP FROM NY 155	2	0	0	2	0	0	0	0	0	0	2	0		
87I 1108 2041			9	1	2	4	2	1	0	0	2	0	8	1		
87I 1108 2042			5	0	1	1	3	1	0	0	1	0	3	2		
ROUTE TOTAL EXCLUDES 999 RMS			302	1	70	158	73	43	67	0	27	14	216	69		

Summary Report By Accident Category

Intersection & Non-Intersection Accidents

Complete Accident Data From NYSDMV Is Only Available thru 30-SEP-2010

ROUTE: 87I HIGHWAY LOCATION 87I 1108 2016 - 87I 1108 2042
DATES: JAN-01-2007 - MAR-31-2010

REPORTABLE ACCIDENTS BY YEAR AND SEVERITY

TIME PERIOD	FATAL	INJURY	P-D-O	NON-REPORTABLE	TOTALS
JAN-01-2007 - DEC-31-2007	0	25	56	30	111
JAN-01-2008 - DEC-31-2008	1	20	45	15	81
JAN-01-2009 - DEC-31-2009	0	20	44	24	88
JAN-01-2010 - MAR-31-2010	0	5	13	4	22
TOTALS	1	70	158	73	302

LOCATION	1.	IDENT. NO.: 1'1'0'1'0'0	STATE OF NEW YORK DEPARTMENT OF TRANSPORTATION TRAFFIC AND SAFETY DIVISION HIGHWAY SAFETY INVESTIGATION REPORT <small>(SEE INSTRUCTIONS ON REVERSE)</small>		MAIN OFFICE USE: DIVISION FILE _____ REVIEWED BY _____ SCHEDULED FOR B&A <input type="checkbox"/>																																
	<input checked="" type="checkbox"/> TOWN <input type="checkbox"/> CITY <input type="checkbox"/> VILLAGE	}	OF <u>Colonie</u>																																		
	ROUTE NO. OR STREET NAME <u>NY 155 / Watervliet-Shaker Rd</u>		STATE HIGHWAY NO. <u>879</u>	FROM OR AT REFERENCE MARKER <div style="display: flex; justify-content: space-between;"> 1'5'5" 1'1'0'1'3'0" </div>																																	
	At Intersection With (If Applicable)	ROUTE NO. OR STREET NAME <u>I 87 Exit 5</u>	STATE HIGHWAY NO.	TO REFERENCE MARKER <div style="display: flex; justify-content: space-between;"> 1'5'5" 1'1'0'1'3'0" </div>																																	
<div style="display: flex;"> <div style="flex: 1;"> <p>2. REASON FOR INVESTIGATION</p> <p><input checked="" type="checkbox"/> (a) IDENTIFIED BY ACCIDENT SURVEILLANCE SYSTEM</p> <p><input type="checkbox"/> (b) POLICE HAZARD REPORT</p> <p><input type="checkbox"/> (c) RESPONSE TO COMPLAINT OR INQUIRY</p> <p><input checked="" type="checkbox"/> (d) REGIONALLY INITIATED <u>PIN 1721.51</u></p> <p><input type="checkbox"/> (e) OTHER (Explain) _____</p> </div> <div style="flex: 1;"> <p>3. RECOMMENDATION</p> <p><input type="checkbox"/> (a) CAPITAL IMPROVEMENT (Initiate Proj. Devel. Study)</p> <p><input type="checkbox"/> (b) TRAFFIC CONTROL IMPROVEMENT</p> <p><input type="checkbox"/> (c) MAINTENANCE IMPROVEMENT</p> <p><input type="checkbox"/> (d) OTHER</p> <p><input checked="" type="checkbox"/> (e) NONE</p> </div> </div>																																					
<p>4. DISCUSSION (Use reverse if additional space is required — check box if reverse is used <input type="checkbox"/>)</p> <p>(a) PROBLEMS IDENTIFIED</p> <div style="text-align: center; font-size: 1.5em; margin-top: 20px;"> See attached Page 2 of 2 </div>																																					
<p>(b) PROPOSED SOLUTION</p> <div style="display: flex; justify-content: space-between; margin-top: 20px;"> <div style="width: 60%;"> <p><u>2009 SDL RM 3058 TO 3060</u></p> </div> <div style="width: 20%;"> <p><u>Reduction Index</u></p> <p><u>7.37</u></p> </div> <div style="width: 20%;"> <p><u>Severity Rat</u></p> <p><u>2.42</u></p> </div> </div>																																					
<p>(c) ACTION TAKEN</p>																																					
<div style="display: flex;"> <div style="flex: 1;"> <p>5. ACCIDENT EXPERIENCE</p> <table border="1" style="width:100%; border-collapse: collapse; text-align: center;"> <thead> <tr> <th rowspan="3">Number of Months</th> <th colspan="2" rowspan="2">PERIOD BEGINNING</th> <th colspan="3">NUMBER OF ACCIDENTS</th> </tr> <tr> <th>Fatal Accidents</th> <th>Injury Accidents</th> <th>Property Damage Accidents</th> </tr> <tr> <th>MONTH</th> <th>YEAR</th> <th></th> <th></th> <th></th> </tr> </thead> <tbody> <tr> <td>1'0</td> <td>0'1</td> <td>0'7</td> <td>0</td> <td>4</td> <td>8</td> </tr> <tr> <td>2'4</td> <td>1'1</td> <td>0'7</td> <td>0</td> <td>9</td> <td>16</td> </tr> <tr> <td>1'1</td> <td>1'1</td> <td>0'9</td> <td>0</td> <td>3</td> <td>6</td> </tr> </tbody> </table> </div> <div style="flex: 1;"> <p>6. BENEFIT/COST ANALYSIS (see instructions)</p> <p>Check box if Benefit/Cost Calculations are attached <input type="checkbox"/></p> <div style="display: flex; justify-content: space-between; margin-top: 10px;"> <div> <p>PRINCIPAL INVESTIGATOR</p> <p><u>[Signature]</u></p> <p>APPROVED BY</p> <p><u>[Signature]</u></p> </div> <div> <p>TITLE</p> <p><u>CET</u></p> <p>DATE</p> <p><u>3/3/11</u></p> </div> </div> </div> </div>						Number of Months	PERIOD BEGINNING		NUMBER OF ACCIDENTS			Fatal Accidents	Injury Accidents	Property Damage Accidents	MONTH	YEAR				1'0	0'1	0'7	0	4	8	2'4	1'1	0'7	0	9	16	1'1	1'1	0'9	0	3	6
Number of Months	PERIOD BEGINNING		NUMBER OF ACCIDENTS																																		
			Fatal Accidents	Injury Accidents	Property Damage Accidents																																
	MONTH	YEAR																																			
1'0	0'1	0'7	0	4	8																																
2'4	1'1	0'7	0	9	16																																
1'1	1'1	0'9	0	3	6																																

Problems Identified

NY Route 155 was identified as a Safety Deficient Location (SDL) from RM 3058 to 3060 based on reportable accidents during the period 11/1/07 to 10/31/09. We evaluated the 0.4 mile section from RM 3058 to 3061 to include all the ramps to and from the Northway Exit 5. This section of NY 155 is a four lane undivided Urban Minor Arterial highway with free access traveling east-west. The highway travel lanes are 12 feet wide and there are 4 foot shoulders. The posted speed limit is 40 MPH. Pavement, pavement markings and signing are satisfactory.

Eastbound NY 155, Watervliet Shaker Road, is intersected from the north by Sherwood Drive in a stop controlled T-intersection at RM 3058. At RM 3059 are the Exit 5 SB on and off ramps. The intersection is controlled with a three color traffic signal. At RM 3060 Old Niskayuna Road, Albany County Route 152, intersects NY 155 from the south in a stop controlled T-intersection. Also at RM 3060 just east of Old Niskayuna Road, is an intersection with Swayzee Drive to the south, Swayzee Drive is one-way SB. At RM 3061 are the I87 Northway Exit 5 NB on and off ramps to the north opposite Holly Lane to the south. The intersection is controlled with a three color traffic signal. Also at RM 3061 just east of the signalized intersection, Feiden Lane intersects NY 155 from the south in a stop controlled T-intersection.

During the 45 month accident study period from 1/1/07 to 9/30/10 there were 46 total accidents. The accident rate was 8.79 ACC/MVM, which is greater than the expected accident rate of 4.27 ACC/MVM for similar highways statewide. Of the 46 accidents with pavement condition reported, there were 2 (4%) wet pavement accidents and 3 (6%) snow/ice pavement accidents. Overall, 23 of the 46 accidents occurred at the two signalized intersections, including 8 rear end accidents, 8 left turn accidents, and 3 right angle accidents. There were 7 accidents during the morning peak from 6 am to 9 am and 12 accidents during the evening peak from 3 pm to 6 pm. There is no apparent treatable pattern of accidents.

Proposed Solution

The scope of PIN 1721.51, I87/NY910B interchange (Exit 4) reconstruction, has been expanded to possibly include work at Exit 5. We have no safety improvements to offer for the project at this time as a result of this review of the accident history.

Actions Taken

Memo to R-1 Design, dated 2/24/11.

Accident Severity Summary

Intersection & Non-Intersection Accidents

Complete Accident Data From NYSDMV Is Only Available thru 30-SEP-2010

Route: 155 Highway Location Ref Mrkr Range: 155 11013058 - 155 11013061

Dates: 01-JAN-2007 thru 30-SEP-2010 Traffic Volume: 9,560

Total of Fatal Accd	Total of Injury Accd	Total of PDO Accd	Total of Non-Reportable	Total Number of Accidents	Accident Rate
0	17	26	3	46	8.79

Accident rate for linear section is accidents per million vehicle miles.

Intersection & Non-Intersection Accidents

155 11013062

ROUTE TOTAL EXCLUDES 999 RMS

*** EXCLUDES PICKUPS & VANS

ACCIDENT SUMMARY SHEET

Case # _____

Municipality Town of Colonie County ALBANYLocation 111 Route 155 - Rm 155-1101-3058 to 3061 HSI # 1-1-0100Time Period 1/1/07 - 11/30/10 No. of Months 47**Accident Type** **No. of Accidents**

Rear End	<u>23</u>
Right Angle	<u>9</u>
Overtaking	<u>2</u>
Left Turn	<u>10</u>
Sideswipe/ Head-on	<u> </u>
Right Turn	<u> </u>
Parked Vehicle	<u> </u>
Debris	<u> </u>
Pedestrian	<u> </u>
Bicycle	<u> </u>
Animal	<u> </u>
Backing	<u> </u>
Fixed Object	<u>3</u>
w/ Utility Poles	<u>1</u>
w/ Guide Rail / Barrier	<u>1</u>
w/ Sign Post	<u> </u>
w/ Trees	<u> </u>
W/ Ditch / Embankment	<u>1</u>
w/	<u> </u>

TOTAL 48**Pavement Condition** **No. of Accidents**

Dry	<u>41</u>
Wet	<u>2</u>
Snow / Ice / Slush	<u>3</u>
Unknown	<u>2</u>

TOTAL 48**Weather** **No. of Accidents**

Clear	<u>29</u>
Cloudy	<u>14</u>
Rain	<u>2</u>
Snow	<u>2</u>
Sleet	<u> </u>
Fog	<u> </u>
Unknown	<u>2</u>

TOTAL 48**Light Conditions** **No. of Accidents**

Day	<u>37</u>
Night	<u>10</u>
Unknown	<u>1</u>

TOTAL 48**Accident Severity** **No. of Accidents**


Property Damage	<u>30</u>
Injury	<u>18</u>
Fatal	<u> </u>

TOTAL 48

NYS DEPARTMENT OF TRANSPORTATION
OFFICE OF TRAFFIC SAFETY & MOBILITY / OFFICE OF MODAL SAFETY & SECURITY
COLLISION DIAGRAM # 3

Sheet 10

Municipality <u>TOWN OF COLONIE</u>	County <u>ALBANY</u>	HSI # <u>1-1-0100</u>	Case # _____
Intersection <u>NY ROUTE 155 RM 155-1101-3058 - RM 3061</u>		File <u>DMV/SIMS/ALIS</u>	
Period <u>4</u> Years <u>0</u> Months	From <u>1/1/07</u>	To <u>12/31/10</u>	By <u>JJC</u> Date <u>1/28/11</u>



SYMBOLS

- | | |
|-----------------------|--------------------|
| ← Moving Vehicle | ← --- Pedestrian |
| ← M Motorcycle | ← B Bicycle |
| ↔ Backing Vehicle | □ Fixed Object |
| ←● Stopped Vehicle | ○ Personal Injury |
| ▢ Parked Vehicle | ● Fatal Injury |

MANNER OF COLLISION

- | | |
|--------------------|-----------------|
| ← ← Rear-end | → → Head-on |
| ← ← Overtaking | → → Left-turn |
| ← ← Out of control | → → Right-angle |
| ← ← Skidding | |
| ← ← Overturned | |

DETAILS OF ACCIDENT HISTORY FOR LOCATION (AS SHOWN ON COLLISION DIAGRAM)

SHEET 2 OF 4DIAGRAM NO. 3

COUNTY <u>ALBANY</u>		P.L.N. OR IDENT.		ROUTE NO. OR STREET NAME		CASE NO.			
TOWN <u>ALBANY</u>		OR IDENT.		AT INTERSECTION WITH/OR BETWEEN		FILE <u>DMV 151ms JAC 15</u>			
CITY						BY <u>SG</u>			
VILLAGE OF <u>COLONIE</u>				Rm 151-1101-3058 - 30601		DATE <u>1/28/11</u>			
TIME PERIOD	FROM	TO	NO. OF VEH.	SEVERITY	ENVIRONMENTAL	LIGHT CONDITIONS	ROADWAY CHARACTER	ROADWAY SURFACE	WEATHER
NUMBER OF MONTHS	DATE	TIME	NO. OF VEH.	SEVERITY	ENVIRONMENTAL	LIGHT CONDITIONS	ROADWAY CHARACTER	ROADWAY SURFACE	WEATHER
4	7	11/30/10	3	PI	1	1	1	1	1
1	3/8/07	0831	3	PI	1	1	1	1	1
2	3/2/07	1955	2	P00	4	1	4	1	1
3	7/20/07	1015	2	P00	1	1	1	1	1
4	11/3/07	1415	2	P00	1	1	1	1	1
5	12/25/07	2307	2	PI	4	1	1	1	1
6	2/8/07	1403	2	P00	1	1	1	1	1
7	2/12/07	1448	2	P00	1	1	1	1	1
8	4/10/07	1613	2	P00	1	1	1	1	1
9	7/10/07	1505	2	P00	1	1	1	1	1
10	7/20/07	2139	2	PI	4	1	1	1	1
11	8/11/07	0848	2	P00	1	1	1	1	1
12	8/28/07	1502	2	PI	1	1	1	1	1
13	10/30/07	2042	4	PI	4	1	1	1	1
14	3/14/08	1624	2	P00	1	1	1	1	1
15	6/2/08	1902	2	PI	1	1	1	1	1
16	6/27/08	2243	2	PI	4	1	1	1	1

Use Codes from MV 104 Police Report
see back of this form for codesAPPARENT
CONTRIBUTING
FACTORS

DESCRIPTION

WB V₃ U₂ STOPPED WAITING FOR UNMOVED V TO TURN
LEFT V₁ R/E V₂ INTO V₃WB V₁ TURNS LEFT IN FRONT OF EB V₂SB V₁ PULLS FROM SHOULDER STRIKING
SB V₂WB V₁ LISTENING TO BACK SEAT PASSENGER
R/E V₂WB V₁ TURNS LEFT IN FRONT OF EB V₂WB V₂ STOPPED WAITING TO TURN, WB V₁ R/E V₂WB V₁ MAKES LEFT TURN, STRIKES STATIONARY
NB V₂NB V₁ R/E NB V₂NB V₁ PULLS OUT - (VIEW OBSTRUCTED BY CONSTRUCTION EQUIP)
STRIKES WB V₂WB V₂ R/E WB V₁NB V₁ R/E NB V₂WB V₁ TURNED LEFT IN FRONT OF
EB V₂WB V₁ (DWI) R/E V₂ INTO V₃ INTO V₄WB V₁ R/E WB V₂WB V₁ TURNING ONTO RAMP W/ GREEN ARROW
EB V₂ (BICYCLE) PASSES THROUGH RED SIGNAL STRUCK BY V₁WB V₁ TURNS LEFT IN FRONT OF EB V₂

DIAGRAM NO. 3

DETAILS OF ACCIDENT HISTORY FOR LOCATION (AS SHOWN IN COLLISION DIAGRAM)

[illegible]

DETAILS OF ACCIDENT HISTORY FOR LOCATION (AS SHOWN ON COLLISION DIAGRAM)

SHEET 4 OF 4DIAGRAM NO. 3

ROUTE NO. OR STREET NAME

PLN-
OR IDENT.

COUNTY

TOWN

CITY

VILLAGE OF

COLUMBIA

TIME PERIOD

NUMBER

FROM

TO

MONTHS

4 7

11/30/10

11/1/07

11/30/10

11/1/07

11/30/10

11/1/07

11/30/10

11/1/07

11/30/10

11/1/07

11/30/10

11/1/07

11/30/10

11/1/07

11/30/10

11/1/07

11/30/10

11/1/07

11/30/10

11/1/07

11/30/10

11/1/07

11/30/10

11/1/07

11/30/10

11/1/07

11/30/10

11/1/07

11/30/10

11/1/07

11/30/10

11/1/07

11/30/10

11/1/07

11/30/10

11/1/07

11/30/10

ENVIRONMENTAL

Use codes from MV 104

(shown at right) for

these categories

(6) (7) (8) (9)

LIGHT

CONDITIONS

ROADWAY

CHARACTER

ROADWAY

SURFACE

CONDITION

WEATHER

(10) APPARENT

CONTRIBUTING

FACTORS

(11) DESCRIPTION

Use Codes from MV 104 Police Report

see back of this form for codes

1. Daylight

2. Dawn

3. Dusk

4. Dark Road Lighted

5. Dark Road Unlighted

6. Curve at Hillcrest

1. Straight and Level

2. Straight and Grade

3. Straight at Hillcrest

4. Curve and Level

5. Curve at Hillcrest

1. Clear

2. Cloudy

3. Rain

4. Snow

5. Sleet/Hail/Freezing Rain

6. Fog/Smog/Smoke

10. Other

1. Daylight

2. Dawn

3. Dusk

4. Dark Road Lighted

5. Dark Road Unlighted

6. Curve at Hillcrest

ROADWAY CHARACTER

1. Straight and Level

2. Straight and Grade

3. Straight at Hillcrest

4. Curve and Level

5. Curve at Hillcrest

ROADWAY SURFACE

1. Dry

2. Wet

3. Muddy

4. Snow/Ice

5. Slush

10. Other

1. Clear

2. Cloudy

3. Rain

4. Snow

5. Sleet/Hail/Freezing Rain

6. Fog/Smog/Smoke

10. Other

1. Clear

2. Cloudy

3. Rain

4. Snow

5. Sleet/Hail/Freezing Rain

6. Fog/Smog/Smoke

10. Other

1. Clear

2. Cloudy

3. Rain

4. Snow

5. Sleet/Hail/Freezing Rain

6. Fog/Smog/Smoke

10. Other

1. Clear

2. Cloudy

3. Rain

4. Snow

5. Sleet/Hail/Freezing Rain

6. Fog/Smog/Smoke

10. Other

1. Clear

2. Cloudy

3. Rain

WEATHER

1. Clear

2. Cloudy

3. Rain

4. Snow

5. Sleet/Hail/Freezing Rain

6. Fog/Smog/Smoke

10. Other

1. Clear

2. Cloudy

3. Rain

4. Snow

5. Sleet/Hail/Freezing Rain

6. Fog/Smog/Smoke

10. Other

1. Clear

2. Cloudy

3. Rain

4. Snow

5. Sleet/Hail/Freezing Rain

6. Fog/Smog/Smoke

10. Other

1. Clear

2. Cloudy

3. Rain

4. Snow

5. Sleet/Hail/Freezing Rain

6. Fog/Smog/Smoke

10. Other

1. Clear

2. Cloudy

3. Rain

4. Snow

5. Sleet/Hail/Freezing Rain

6. Fog/Smog/Smoke

10. Other

1. Clear

2. Cloudy

3. Rain

4. Snow

5. Sleet/Hail/Freezing Rain

6. Fog/Smog/Smoke

10. Other

CASE NO.

FILE

BY

DATE

00151ms/p15

JLC

11/28/10



STATE OF NEW YORK
DEPARTMENT OF TRANSPORTATION - REGION ONE
328 STATE STREET
SCHENECTADY, NEW YORK 12305
www.nysdot.gov

MARY E. IVEY
REGIONAL DIRECTOR

STANLEY GEE
ACTING COMMISSIONER

CASE# 1090278

December 22, 2010

Mr. Mike Greenberg
11 Bittersweet Lane
Slingerlands, New York 12159

Re: Traffic Signal Operational Review
Albany Shaker Road @ Old Wolf Road, Signal #104
Town of Colonie, Albany County

Dear Mr. Greenberg:

This letter is in response to your December 7, 2009 message to NYSDOT.gov in which you express concern for the operation of the traffic signal at the intersection of Route 155 (Old Wolf Road) and Albany-Shaker Road in the Town of Colonie. Your message stated that the stop bar for westbound vehicles on Albany-Shaker Road is pushed into the intersection, which makes it difficult for southbound left turning vehicles on Old Wolf Road to perform their turning maneuver. You suggested the stop bar on Albany-Shaker Road be moved back.

We have completed our study of the intersection. Our investigation included observing the flow of traffic through the area during peak traffic periods, and reviewing the accident records for the intersection. The accident study did not identify a pattern of accidents related to the position of the stop bar, and our observations did not identify any operational issues. Our observations and the data collected during this study do not justify any changes to the stop bar at this time. The dotted 'skip marks' that separate the two southbound left turn lanes were observed to be faded during our field work. These dotted lines delineate the turn lanes and identify the desired turning path for left turning vehicles. A work order was issued in September to re-apply these markings. The work was completed in October.

If you have any questions, please contact Rob Fitch of this office at 388-0380.

Sincerely,

Mark Kennedy
Regional Traffic Engineer

cc: D. Rose, Acting Albany County Resident Engineer
M. Doody, Traffic Engineering and Safety, Region 1

Old Wolf @ ASR

7/8/10

AM Peak Observation - similar to previous observation

Begin 7:20

End 9:20

- WB left turners stop ~ 5-10 feet short of stop bar generally
- Due to the tight geometry, the SB LT is a slow movement - vehicles drive straight into the intersection and then make a slow sharp left turn.
- Lane usage in left-most left turn lane is very light - most vehicles use the right-most lane
- No conflicts observed

PM Peak observations - similar to above

If we were building this intersection today, we would try to widen the exit point (throat) on ASR to facilitate the move. While the geometry does require motorists to be cautious, it has not caused any accident problem operational issues. The cat tracks for the dual lefts were not re-stripped during the last durable markings contract (even though the rest of the intersection was done). I am working w/ Lorenzo to ^{get} them done under the current contract. This should help vehicles align themselves through the intersection.

→ No changes are justified

RFF 9/15/10

The stop bar on ASR is pushed as far west as possible in order to maximize storage (which is severely limited) under the bridge.

CASE #1090278

RESPONSE DUE BY 3/8/10

ROB
12/8/09

From: Mark Pyskadlo
To: mikeyg512@gmail.com
Date: 12/8/2009 2:27 PM
Subject: Re: NYSDOT COMMENT, Albany Shaker Road @ Old Wolf & I-87 Exit 4 SB on ramp, Signal #104, Albany County

Dear Mr. Greenberg:

We will initiate a study of the intersection in response to your concern and respond back to you with the results. It will take approximately 90 days to complete the study.

Sincerely,

Mark A. Pyskadlo, P.E.
Traffic Engineering & Safety
NYSDOT - Region One
328 State Street - 4th Floor
Schenectady, NY 12305
(518) 388-0380, Fax: (518) 388-0379
MPYSKADLO@DOT.STATE.NY.US


>>> no-reply@dot.state.ny.us 12/7/2009 11:21 AM >>>
The following data was entered at NYSDOT.gov

Name - Mike Greenberg
Address - 11 Bittersweet Lane Slingerlands, NY
Email Address - mikeyg512@gmail.com
Comment Topic - NYSDOT COMMENT - Highways/Roads
Question or Comment -

I was turning onto Albany-Shaker Road from Wolf road in order to access the I-87 Southbound ramp. While waiting at the traffic light at Albany-Shaker road and 155 in the left turning lane that would lead me onto the ramp, I notice that the turning lane is pretty far up such that cars turning left from 155 onto Albany-Shaker Road towards wolf road have to use high caution when making that turn so they don't clip the lead car waiting to turn onto I 87. I am wondering if someone could take a look at this and perhaps back up that stop line so that it gives the people turning from 155 onto Albany-Shaker Road more room to turn. Thank you for your time! Page Accessed From:

ACCIDENT DIAGRAM
& OBSERVE


- HDM Chapter 5
- throat width 8-9m
- turning radii



DEPARTMENT OF TRANSPORTATION
 TRAFFIC ENGINEERING AND SAFETY DIVISION
 COLLISION DIAGRAM 3

Sheet 1 of 3

Municipality	TOWN OF COLONIE	County	ALBANY	File	D.M.U.
Intersection	ALBANY SHAKER RD (N.Y. 155) / OLD DOLF RD / E 57th Ave				
Period	3 Years	0 Months	From	1/1/07	To 12/31/09
			By	D.T.W.	Date 1/13/10



SYMBOLS		MANNER OF COLLISION	
← Moving Vehicle	← - - Pedestrian	← ← Rear-end	→ × Head-on
← M Motorcycle	← B Bicycle	← Side-swipe	↘ Left-turn
↔ Backing Vehicle	□ Fixed Object	← Out of control	↓ Right-angle
← Stopped Vehicle	○ Personal Injury	← Skidding	
▢ Parked Vehicle	● Fatal Injury	← Overturned	

DETAILS OF ACCIDENT HISTORY FOR LOCATION (AS SHOWN ON COLLISION DIAGRAM)

SHEET 2 OF 3

DIAGRAM NO. 3

COUNTY ALBANY		ROUTE NO. OR STREET NAME ALBANY SINKER RD (N.Y. 155)		CASE NO. 1090278						
TOWN		AT INTERSECTION WITH/OR BETWEEN OLD WOLF RD. (N.Y. 155) & I-87 S.B. ON RAMP		FILE D.M.V.						
CITY				BY D.T.W.						
VILLAGE OF COLONIE				DATE 4/13/10						
TIME PERIOD NUMBER OF MONTHS	DATE	TIME	NO. OF VEH.	SEVERITY	ENVIRONMENTAL Use codes from MV 104 (shown at right) for these categories	ROADWAY CHARACTER	ROADWAY CONDITION	ROADWAY SURFACE CONDITION	WEATHER	DESCRIPTION
3/6	12/31/09									
1	1/19/07	9:30 AM	2	PDO	1	1	2	4	4	BOTH VEH. S.B. ON OLD WOLF RD. V2 STOPPED, V1 DID NOT (RE.)
2	1/21/07	12:10 AM	2	P.I.	4	1	1	1	7	V1 W.B. ON A.S.R., V2 E.B. V1 TURNED LT. IFO V2 & I-87 (L.T.)
3	1/24/07	7:41 AM	3	PDO	1	1	1	2	66/-1-	V1 S.B. ON OLD WOLF RD., V2 S.W.B. ON A.S.R. IN L.T.L. BEHIND (L.T.)
4	2/5/07	5:36 PM	2	P.I.	4	1	1	2	-17/1B	V1 E.B. ON A.S.R., V2 W.B. V2 TURNED LT. IFO V1 & I-87 (L.T.)
5	3/20/07	2:37 PM	3	P.I.	1	1	2	3	3,66/-	ALL 3 VEH. S.B. ON OLD WOLF RD. V2 & 3 STOPPED FOR TRAFFIC (RE.)
6	4/10/07	4:20 PM	2	PDO	1	1	1	1	1B/1B	BOTH VEH. S.B. ON OLD WOLF RD. V1 STOPPED V2 PUSHED V2 INTO V1. (RE.)
7	5/14/07	P.M.	2	P.I.						BOTH VEH. S.B. ON OLD WOLF RD. V1 STOPPED FOR SIGNAL & A.S.R. (RE.)
8	6/14/07	3:16 PM	2	PDO	1	1	1	1	26,17/-	V1 S.B. ON A.S.R., V2 E.B. V1 TURNED LT. IFO V2 IN CENTER LT. (L.T.)
9	8/18/07	8:01 AM	2	P.I.	1	1	1	1	17/-	V1 S.B. ON OLD WOLF RD., V2 W.B. ON A.S.R. V1 RAN SIGNAL IFO V2 (L.T.)
10	9/20/07	8:10 PM	2	P.I.	1					BOTH VEH. E.B. ON A.S.R. IN R.T.L. BOTH TURNING ONTO I-87 RAMP (RE.)
11	10/10/07	P.M.	2	PDO						V1 STOPPED ALSO WARNING, NO TURN, V2 CAME NOT AROUND VI. (RE.)
12	10/26/07	12:40 PM	2	PDO	1	1	1	1	7/1B	BOTH VEH. E.B. ON A.S.R. V1 STOPPED DESIGNATE, V2 DID NOT. (RE.)
13	12/17/07	3:41 PM	2	P.I.	1	1	2	2	62/-	BOTH VEH. S.B. ON OLD WOLF RD., V2 STOPPED SIGNAL, WITHIN LIGHT TURNED GREEN, V2 STOPPED THEN STOPPED V1 & CAUSE V1 DID NOT STOP (RE.)
14	4/11/08	8:54 AM	3	PDO	1	1	2	3	66/-1-	BOTH VEH. S.B. ON OLD WOLF RD., V2 STOPPED V1 & CAUSE V1 DID NOT STOP (RE.)
15	1/1/08	4:01 AM	2	PDO	1	1	1	1	42/-	BOTH VEH. S.B. ON OLD WOLF RD. V2 STOPPED, V1'S BRIDGES FAILED (RE.)

ACCIDENT SUMMARY SHEET

MUNICIPALITY Town of Colma

COUNTY Albany

LOCATION NY 910B; RM 910B-1101-1016 TO 1019

PIN
~~HST #~~ 1721.51

TIME PERIOD 1/1/07 to 3/31/10

NO. OF MONTHS 39

Accident Type No. of Accidents

Right Angle 17
Rear End 66
Overtaking 14
Left Turn 34
Sideswipe/Head-on
Right Turn 1
Parked Vehicle
Pedestrian
Bicycle
Animal
Fixed Object
 w/Utility Poles
 w/Guide Rail
 w/Sign Posts
 w/Trees
 w/Ditch-Embank.
 w/

TOTAL 132

Pavement

Dry
Wet
Snow/Ice
Unknown

No. of Accidents

97
25 (20% of known
5 (4% of known
5

TOTAL

132

Weather

Clear
Cloudy
Rain
Snow
Sleet
Fog
Unknown

No. of Accidents

68
46
9
3

1
5

TOTAL

132

Light Conditions No. of Accidents

Day 85
Night 46
Unknown 1

TOTAL 132

Accident Severity No. of Accidents

Fatal
Injury 52
Property Damage 80

TOTAL

132

Accident Severity Summary

Intersection & Non-Intersection Accidents

Complete Accident Data From NYSDMV Is Only Available thru 30-SEP-2010

Route: 910B Highway Location Ref Mrkr Range: 910B11011016 - 910B11011019

Dates: 01-JAN-2007 thru 31-MAR-2010 Traffic Volume: 29,180


Total of Fatal Accd	Total of Injury Accd	Total of PDO Accd	Total of Non-Reportable	Total Number of Accidents	Accident Rate
0	59	61	11	131	9.46

Accident rate for linear section is accidents per million vehicle miles.

DEPARTMENT OF TRANSPORTATION
TRAFFIC ENGINEERING AND SAFETY DIVISION
COLLISION DIAGRAM

1080248

Municipality Town of Colton County Albany File _____
 Intersection Wolf Rd @ Ulenski Dr 9108-1101-1017
 Period 3 Years 9 Months From 1/1/05 To 9/28/08 By Pwm Date 10/2/10



SYMBOLS		MANNER OF COLLISION	
← Moving Vehicle	← - - - Pedestrian	← ← Rear-end	→ × Head-on
← M - Motorcycle	← B - Bicycle	← ← Side-swipe	→ ↘ Left-turn
← → → Backing Vehicle	□ Fixed Object	← ~ Out of control	↓ Right-angle
← Stopped Vehicle	○ Personal Injury	← ↘ Skidding	
▢ Parked Vehicle	● Fatal Injury	← o Overturned	

DETAILS OF ACCIDENT HISTORY FOR LOCATION (AS SHOWN ON COLLISION DIAGRAM)

SHEET 2 OF 2

DIAGRAM NO. _____

COUNTY <u>Albany</u>		P.I.N. _____		ROUTE NO. OR STREET NAME <u>Wolf Road</u>		CASE NO. <u>1080248</u>				
TOWN <input checked="" type="checkbox"/>		OR IDENT. _____		AT INTERSECTION WITH/OR BETWEEN <u>Ulensti Dr 9103-1101-1017</u>		FILE BY <u>Baron</u>				
CITY <input type="checkbox"/>		_____		_____		DATE <u>10/2/08</u>				
VILLAGE OF <u>Colonie</u>		_____		_____		_____				
TIME PERIOD NUMBER OF MONTHS	FROM <u>1/1/05</u>	TO <u>9/28/08</u>	④ NO. OF VEH.	⑤ SEVERITY	⑥ LIGHT CONDITIONS	⑦ ROADWAY CHARACTER	⑧ ROADWAY SURFACE CONDITION	⑨ WEATHER	⑩ APPARENT CONTRIBUTING FACTORS	⑪ DESCRIPTION
1	1/7/05	5 ⁵⁸ PM	2	PI	1	1	1	1	9	Stopped in traffic
2	12/23/05	12 ¹⁵ PM	2	PDO	1	1	1	2	7	operator was waved across by uninvolved motorist
3	3/20/06	6 ⁵⁶ PM	2	PI	4	1	1	1	4	pedestrian had just crossed roadway 2 veh in front of
4	3/29/06	1 ²² PM	2	PDO	1	1	1	1	4, 7	
5	4/7/06	5 ¹² PM	2	PDO	1	2	2	3	7, 13	operator waved out by uninvolved motorist, twin lane
6	8/9/06	4 ³¹ PM	3	PDO	1	1	1	1	4	inattention during lane change
7	9/7/06	4 ³⁷ PM	2	PI	1	1	1	1	4	inattention
8	4/17/07	4 ⁴⁷ PM	2	PDO	1	1	1	2	20	
9	9/8/07	8 ⁰⁴ PM	2	PDO	4	1	2	3	7	vision impaired due to heavy rain
10	9/23/07	6 ³⁹ PM	2	PI	3	1	1	1	7	
11	11/26/07	4 ¹⁸ PM	2	PDO	4	1	2	3	4	inattention
12	11/27/07	9 ⁵⁵ AM	2	PDO	1	1	2	2	7	waved out by uninvolved motorist
13	12/2/07	3 ⁰¹ AM	1	PDO	4	1	1	2	2, 19	ALCOHOL

ACCIDENT SUMMARY SHEET

MUNICIPALITY Town of Colma

COUNTY Albany

LOCATION AC Route 153 / Old Wolf Rd

PIN 1721.51
~~HST #~~

TIME PERIOD 1/1/07 TO 3/31/10

NO. OF MONTHS 39

Accident Type No. of Accidents

Right Angle	<u>6</u>
Rear End	<u>12</u>
Overtaking	<u>1</u>
Left Turn	<u>8</u>
Sideswipe/Head-on	<u> </u>
Right Turn	<u> </u>
Parked Vehicle Backing	<u>1</u>
Pedestrian	<u> </u>
Bicycle	<u>1</u>
Animal	<u> </u>
Fixed Object	<u>1</u>
w/Utility Poles-Wires	<u>1</u>
w/Guide Rail	<u> </u>
w/Sign Posts	<u> </u>
w/Trees	<u> </u>
w/Ditch-Embank.	<u> </u>
w/	<u> </u>
TOTAL	<u>30</u>

Pavement No. of Accidents

Dry	<u>20</u>
Wet	<u>7</u>
Snow/Ice	<u>1</u>
Unknown	<u>2</u>
TOTAL	<u>30</u>

Weather No. of Accidents

Clear	<u>19</u>
Cloudy	<u>7</u>
Rain	<u>2</u>
Snow	<u> </u>
Sleet	<u> </u>
Fog	<u> </u>
Unknown	<u>2</u>
TOTAL	<u>30</u>

Light Conditions No. of Accidents

Day	<u>22</u>
Night	<u>7</u>
Unknown	<u>1</u>
TOTAL	<u>30</u>

Accident Severity No. of Accidents

Fatal	<u>0</u>
Injury	<u>13</u>
Property Damage	<u>17</u>
TOTAL	<u>30</u>

DETAILS OF ACCIDENT HISTORY FOR LOCATION (AS SHOWN ON COLLISION DIAGRAM)

SHEET 1 OF 2

DIAGRAM NO. NONE

COUNTY <u>Albany</u>		P.I.N. <u>11721151</u>		ROUTE NO. OR STREET NAME <u>Albany County Route 153/1018 Wolf Rd</u>		CASE NO. FILE <u>AL15</u>					
TOWN <u>Colonia</u>		ORDINANCE		AT INTERSECTION WITH/OR BETWEEN <u>THRM 155-1101-3048 TO 3052</u>		BY <u>MED</u>					
CITY						DATE <u>2/11/11</u>					
VILLAGE OF											
TIME PERIOD NUMBER OF MONTHS	FROM 1/1/07	TO 3/3/10	NO. OF VEH.	SEVERITY	ENVIRONMENTAL Use codes from MV 104 (shown at right) for these categories	ROADWAY CHARACTER	ROADWAY SURFACE	WEATHER	ROADWAY SURFACE CONDITION	WEATHER	
① NO	② DATE	③ TIME	④	⑤	⑥	⑦	⑧	⑨	⑩	⑪	
1	1/2/07	5:18P	2	P00	5	1	1	1	49	3048	REAR END-SB, V-1 STOPPED IN TRAFFIC
2	2/20/07	5:32P	2	P00	4	1	4	1	764	3048	RIGHT ANGLE, V-1 ENTERED TRAFFIC EB, STRUCK SB V-2
3	5/30/07	8:39A	2	PE-2	1	1	1	1	7	3048	RIGHT ANGLE, V-1 ENTERED TRAFFIC EB, STRUCK BY SB V-2
4	8/9/07	5:31P	2	PE-2	1	1	1	1	13	3048	NB V-1 ATTEMPTED LEFT TURN, STRUCK BY SB V-2
5	9/5/07	4:10P	2	PE-2	1	1	1	1	7	3048	RIGHT ANGLE, V-1 ENTERED TRAFFIC EB, STRUCK BY SB V-2
6	10/17/07	4:59P	2	P00	1	1	1	1	4	3048	NB V-1 ATTEMPTED LEFT TURN, STRUCK BY SB V-2
7	12/5/07	1:45P	2	P00	1	1	2	2	420	3048	OVERTAKE-SB, V-1 CHANGED LANES
8	12/19/07	4:12P	2	PE-1	3	1	2	2	7	3049	NB V-1 ATTEMPTED LEFT TURN, STRUCK BY SB V-2
9	2/3/07	10:45A	2	PE-1	1	4	2	1	9	3050	REAR END-WB, V-2 STOPPED IN TRAFFIC AT SIGNAL
10	2/13/07	8:02A	2	P00	1	1	1	2	9	3050	REAR END-WB, HEAVY TRAFFIC ON RAMP SLOWING SIGNAL
11	2/13/07	8:17A	3	P00	1	1	1	2	9	3050	REAR END-WB, HEAVY TRAFFIC ON RAMP SLOWING SIGNAL
12	5/14/07		2	PE-1						3050	REAR END-SB, V-1 STOPPED FOR RED TRAFFIC SIGNAL
13	11/7/07	7:53A	2	PE-1	1	1	1	1	4	3050	REAR END-SB, V-2 STOPPED IN TRAFFIC AT SIGNAL
14	9/10/07	9:18A	2	PE-1	1	1	2	2	3	3052	NB V-1 BACKED-SB, STRUCK V-2 STOPPED NB
15	9/20/07	9:16A	1	P00	1	1	1	1	45	3052	NB V-1 NB W/ DUMP TRUCK, STRUCK UTILITY WIRES
16	1/1/09	5:00P	2	PE-1	1	1	1	1	710	3052	REAR END-SB, V-1 ENTERED TRAFFIC ON RAMP SLOWING SIGNAL

DETAILS OF ACCIDENT HISTORY FOR LOCATION (AS SHOWN ON COLLISION DIAGRAM)

DIAGRAM NO. NONESHEET 2 OF 2

COUNTY <u>Albany</u>		P.I.N. <u>172151</u>		ROUTE NO. OR STREET NAME <u>CR 153 / Old Wolf Rd</u>		CASE NO. FILE <u>ALIS</u>							
TOWN <u>Colonie</u>		OR IDENT: <u>Colonie</u>		AT INTERSECTION WITH/OR BETWEEN <u>TH RM 155-1101-3048 TO 3052</u>		BY <u>MED</u>							
CITY						DATE <u>2/11/11</u>							
VILLAGE OF													
TIME PERIOD NUMBER OF MONTHS	FROM 1/1/07	TO 3/31/10	④ NO. OF VEH.	⑤ SEVERITY	⑥ LIGHT CONDITIONS	⑦ ROADWAY CHARACTER	⑧ ROADWAY SURFACE	⑨ WEATHER	⑩ LIGHT CONDITIONS	⑪ ROADWAY CHARACTER	⑫ ROADWAY SURFACE	⑬ WEATHER	⑭ DESCRIPTION
① NO	② DATE	③ TIME											
17	4/23/08	9:01A	2	PI-1	1	1	1	1	769	3048	RIGHT ANGLE, V-1 ENTERED TRAFFIC EB, STRUCK BY SB V-2		
18	7/10/08	12:31P	2	P00	1	1	1	1	7	3048	NB V-1 ATTEMPTED LEFT TURN, STRUCK BY SB V-2		
19	1/17/08	5:17P	2	P00	3	1	1	2	49	3049	REAR END-SB, V-2 STOPPED IN TRAFFIC		
20	4/30/08	8:06A	2	P00	1	1	1	1	94	3050	REAR END-WB, V-2 SLOWING IN TRAFFIC AT SIGNAL		
21	8/11/08	4:44P	2	P00	1	1	2	3	66	3050	REAR END-WB, V-1 STARTING IN TRAFFIC AT SIGNAL		
22	4/24/09	5:29P	2	PI-2	1	1	1	1	1317	3048	NB V-2 ATTEMPTED LEFT TURN, STRUCK BY SB V-1		
23	6/25/09	5:23P	2	P00	1	1	1	1	7	3048	NB V-1 ATTEMPTED LEFT TURN, STRUCK BY SB V-2		
24	9/2/09	12:56P	2	P00	1	1	1	1	7	3048	NB V-1 ATTEMPTED LEFT TURN, STRUCK BY SB V-2		
25	12/16/09	5:30P	2	P00	4					3048	NB V-1 ATTEMPTED LEFT TURN, STRUCK SB V-2		
26	5/31/09	4:50P	2	P00	1	1	1	1	179	3050	REAR END-SB, V-2 STOPPED AT RED TRAFFIC SIGNAL		
27	8/29/09	6:25P	2	PI-2	3	1	2	2	7	3050	REAR END-WB, V-2 SLOWING IN TRAFFIC AT SIGNAL		
28	9/4/09	10:35A	2	P00	1	1	1	1	264	3050	REAR END-SB, BOTH VEHs PULLING TO SHOULDER FOR EMERGENCY VIEW		
29	4/10/09	6:37P	2	P00	1	1	1	1		3051	RIGHT ANGLE, V-1 ENTERED TRAFFIC EB, STRUCK BY SB V-2		
30	3/22/10	2:20P	1	PI-1	1	1	2	3	10	3048	V-1 STOPPED IN TRAFFIC SB, SB BICYCLIST HAD SEIZURE		

ACCIDENT SUMMARY SHEET

MUNICIPALITY Town of Colma

COUNTY Albany

LOCATION AC Route 151 / Albany-Shaker Rd

PIN 1721.51
~~HST #~~

TIME PERIOD 1/1/07 to 3/31/10

NO. OF MONTHS 39

Accident Type No. of Accidents

Right Angle	<u>8</u>
Rear End	<u>23</u>
Overtaking	<u>10</u>
Left Turn	<u>11</u>
Sideswipe/Head-on	<u>1</u>
Right Turn	<u> </u>
Parked Vehicle	<u> </u>
Pedestrian	<u> </u>
Bicycle	<u> </u>
Animal	<u> </u>
Fixed Object	<u>2</u>
w/Utility Poles	<u> </u>
w/Guide Rail	<u>1</u>
w/Sign Posts	<u>1</u>
w/Trees	<u> </u>
w/Ditch-Embank.	<u> </u>
w/	<u> </u>
TOTAL	<u>55</u>

Pavement

No. of Accidents

Dry	<u>38</u>
Wet	<u>12</u> (23% of known)
Snow/Ice	<u>2</u> (4% of known)
Unknown	<u>3</u>
TOTAL	<u>55</u>

Weather

No. of Accidents

Clear	<u>30</u>
Cloudy	<u>12</u>
Rain	<u>7</u>
Snow	<u>3</u>
Sleet	<u> </u>
Fog	<u> </u>
Unknown	<u>3</u>
TOTAL	<u>55</u>

Light Conditions No. of Accidents

Day	<u>42</u>
Night	<u>12</u>
Unknown	<u>1</u>
TOTAL	<u>55</u>

Accident Severity No. of Accidents

Fatal	<u> </u>
Injury	<u>21</u>
Property Damage	<u>34</u>
TOTAL	<u>55</u>

DETAILS OF ACCIDENT HISTORY FOR LOCATION (AS SHOWN ON COLLISION DIAGRAM)

SHEET 1 OF 4DIAGRAM NO. NONE

COUNTY <u>Albany</u>		P.I.N. <u>172151</u>		ROUTE NO. OR STREET NAME <u>Albany County Route 151 / Albany State Rd</u>		CASE NO. FILE <u>AL15</u>		
TOWN <u>Colonia</u>		OR IDENT.		AT INTERSECTION WITH/OR BETWEEN <u>TH RM 155-1101-3038 TO 3047+</u>		BY <u>MD</u>		
VILLAGE OF <u>Colonia</u>						DATE <u>2/22/11</u>		
TIME PERIOD NUMBER OF MONTHS	FROM 1/1/07 TO 3/31/10	NO. OF VEH.	SEVERITY	ENVIRONMENTAL Use codes from MV 104 (shown at right) for these categories			WEATHER	
				ROADWAY CONDITIONS	ROADWAY CHARACTER	ROADWAY SURFACE CONDITION		
① NO	② DATE	③ TIME	④	⑤	⑥	⑦	⑧	⑨
1	3/12/07	6:07P	2	P00	1	1	2	1
2	6/19/07	6:12P	2	P00	1	1	1	2
3	1/19/07	9:30A	2	P00	1	1	2	4
4	1/21/07	12:00A	2	PL-2	4	1	1	1
5	1/24/07	7:54A	3	P00	1	1	1	2
6	2/5/07	5:36P	2	PL-2	4	1	1	2
7	3/26/07	2:37P	3	PL-1	1	1	2	3
8	4/10/07	4:20P	2	P00	1	1	1	1
9	6/14/07	3:16P	2	P00	1	1	1	1
10	8/18/07	8:01A	2	PL-1	1	1	1	1
11	9/20/07	3:10P	2	PL-1	1			
12	10/7/07	P	2	P00	1	1	1	1
13	10/26/07	12:40P	2	P00	1	1	1	1
14	12/17/07	3:41P	2	PL-1	1	1	2	2
15	1/11/07	5:21P	2	P00	3	1	1	1
11	5/21/10	8:00A	2	P00	1	1	1	1

Use Codes from MV 104 Police Report see back of this form for codes		⑪ DESCRIPTION	
⑩ APPARENT CONTRIBUTING FACTORS	TH KM		
7	3046	WB V-1 ATTEMPTED LEFT TURN, STRUCK BY EB V-2	
18	3046	OVERTAKE - WB, V-1 CHANGED LANES	
4	3047	REAR END - SB, V-2 STOPPED IN TRAFFIC AT SIGNAL	
7	3047	WB V-1 ATTEMPTED LEFT TURN, STRUCK EB V-2 AT SIGNAL	
66	3047	RIGHT ANGLE SB V-1 MAKING LEFT, STRUCK V-2 STOPPED WB	
7, 18	3047	WB V-2 ATTEMPTED LEFT STRUCK BY EB V-1 AT SIGNAL	
9, 66	3047	REAR END - SB, V-3 STOPPED V-2 SLOWING, V-1 STRUCK V-2	
18, 18	3047	OVERTAKE - SB, BOTH VEHICLES MAKING LEFT TURNS	
26, 17	3047	WB V-1 ATTEMPTED LEFT AGAINST SIGNAL, STRUCK BY SB V-2	
17	3047	RIGHT ANGLE, SB V-1 PASSED RED SIGNAL, STRUCK WB V-2	
	3047	REAR END - EB, V-1 SLOWING TO MAKE RIGHT, AT SIGNAL	
	3047	REAR END - EB, V-1 SLOWING IN TRAFFIC AT RED SIGNAL	
	3047	REAR END - SB, V-2 STOPPED IN TRAFFIC AT SIGNAL	
	3047	REAR END - SB, V-2 STOPPED IN TRAFFIC AT SIGNAL	
		REAR END - WB, V-2 SLOWING IN TRAFFIC	
		REAR END - WB, V-2 SLOWING IN TRAFFIC	

DETAILS OF ACCIDENT HISTORY FOR LOCATION (AS SHOWN ON COLLISION DIAGRAM)

DIAGRAM NO. NONECOUNTY Albany P.I.N. 172151 OR IDENT. 1TOWN ☒ Albany
CITY ☐
VILLAGE OF Colonie

ROUTE NO. OR STREET NAME

AC Route 151 / Albany - Shaker Rd

AT INTERSECTION WITH/OR BETWEEN

TH RM 155 - 1101 - 3038 TO 3047+CASE NO. ACISFILE BYDATE 2/22/11SHEET 2 OF 4

TIME PERIOD		NO. OF VEH.	SEVERITY	ENVIRONMENTAL				LIGHT CONDITIONS	ROADWAY CHARACTER	ROADWAY SURFACE	ROADWAY CONDITION	WEATHER
NUMBER OF MONTHS	FROM			TO	(6)	(7)	(8)					
319	1/1/07	2	PDO	1	1	1	1	1	1	1	1	1
320	1/1/07	2	PDO	1	1	1	1	1	1	1	1	1
321	1/1/07	2	PDO	1	1	1	1	1	1	1	1	1
322	1/1/07	2	PDO	1	1	1	1	1	1	1	1	1
323	1/1/07	2	PDO	1	1	1	1	1	1	1	1	1
324	1/1/07	2	PDO	1	1	1	1	1	1	1	1	1
325	1/1/07	2	PDO	1	1	1	1	1	1	1	1	1
326	1/1/07	2	PDO	1	1	1	1	1	1	1	1	1
327	1/1/07	2	PDO	1	1	1	1	1	1	1	1	1
328	1/1/07	2	PDO	1	1	1	1	1	1	1	1	1
329	1/1/07	2	PDO	1	1	1	1	1	1	1	1	1
330	1/1/07	2	PDO	1	1	1	1	1	1	1	1	1
331	1/1/07	2	PDO	1	1	1	1	1	1	1	1	1
332	1/1/07	2	PDO	1	1	1	1	1	1	1	1	1

Use Codes from MV 104 Police Report
see back of this form for codes

APPARENT CONTRIBUTING FACTORS

11

DESCRIPTION

RIGHT ANGLE, V-1 ENTERED TRAFFIC NB, STRUCK BY EB V-2

OVERTAKE-EB, V-1 CHANGED LANES

RIGHT ANGLE, V-1 PULLED SB FROM VIEWING LOT FRO WB V-2

WB V-1 CROSSED CENTERLINE, STRUCK EB V-2 HEAD ON

REAR END- WB, V-2 STOPPED IN TRAFFIC

REAR END- EB, V-2 AND V-3 STOPPED IN TRAFFIC

REAR END- WB, V-2 STOPPED TO MAKE LEFT

REAR END- WB, BOTH VEHICLES SLOWING IN HEAVY TRAFFIC

WB V-1 ATTEMPTED LEFT TURN, STRUCK BY EB V-2

RIGHT ANGLE, V-1 ENTERED TRAFFIC NB, STRUCK BY EB V-2

WB V-1 ATTEMPTED LEFT TURN, STRUCK BY EB V-2

OVERTAKE- WB, V-1 CHANGED LANES TO AVOID UNINVOLVED VEH

OVERTAKE- WB, V-1 CHANGED LANES

OVERTAKE- WB, V-1 CHANGED LANES, STRUCK V-2

OVERTAKE- EB, V-2 CHANGED LANES

DETAILS OF ACCIDENT HISTORY FOR LOCATION (AS SHOWN ON COLLISION DIAGRAM)

DIAGRAM NO. NONE

SHEET 3 OF 4

COUNTY	P.I.N. OR IDENT.	ROUTE NO. OR STREET NAME	CASE NO.
Albany	172151		

COUNTY 7 1
 INCIDENT: 7
 AC Route 151 Albany-Shaker Rd
 CASE NO. ALIS
 FILE FILE

☐ CITY

☐ VILLAGE OF

AT INTERSECTION WITH/OR BETWEEN

BY WED

DATE 2/22/11

VILLAGE OF		TH KM		SS-1101-3038 TO 3047+		DATE		1/28/11	
TIME PERIOD		ENVIRONMENTAL		LIGHT CONDITIONS		POSITIONING		EQUIPMENT	

NUMBER	FROM	TIME PERIOD	ENVIRONMENTAL Use codes from MV 104 (shown at right) for	LIGHT CONDITIONS	ROADWAY CHARACTER	CONDITION	ROADWAY SURFACE	WEATHER
1.				1. Daylight	1. Straight and Level			1. Clear
				2. Dawn	2. Straight and Grade	1. Dry	4. Snow/Ice	2. Cloudy

OF MONTHS

11/01

these categories

(A) (E) (6) (7) (8) (9)

3. Dust
4. Dark Road Lighted
5. Dark Road Unlighted
6. Curve and Grade
7. Straight at Hillcrest
8. Curve and Grade
9. Muddy
10. Other
11. Wet
12. Rain
13. Snow
14. Slush

[illegible]

Use Codes from MV 104 Police Report
see back of this form for codes

NO	DATE	TIME	CONTRIBUTING FACTORS	DESCRIPTION
11				

NO.	TIME	TIME	S	L	C	F	W	FACTORS	DESCRIPTION
32	11:40	11:48	0.00	1	1	1	1	10	0.00 - 0.00

25	6/10/08	4:01	7 PMO	1	1	47	30471	REAR END-SB V-2 STOPPED IN TRAFFIC AT SIGNAL
26								

34	872908	10:10A	2	900	1	1	2	3047 RIGHT ANGLE, SB V-1 MAKING LEFT, STOCK V-2 STOPPED WS AT SIGNAL
----	--------	--------	---	-----	---	---	---	--

35	11/13/08	2	200	1	2	3	2017 REAR END-SS V-1 STOPPED EAR C MEDICAL VEHICLE
----	----------	---	-----	---	---	---	--

[illegible]

26	12-1-71	10-1	7	100	1	4	1	2047	LEAK	END-EB	V-1	STARTED	ROP	STOPPED	AGAIN
----	---------	------	---	-----	---	---	---	------	------	--------	-----	---------	-----	---------	-------

5/	11008	801011	414.9	2 PT-1	2	1	2	20	OVER-TAKE-W/B, V-1 SWERVED TO AVOID UNINVOLVED VEH
----	-------	--------	-------	--------	---	---	---	----	--

38	2/9/88	8:16 P	2800	4	2	3	207	1	OVERVIEW - 6 CHANGED LANES
38	2/9/88	8:16 P	2800	4	2	3	207	1	OVERVIEW - 6 CHANGED LANES

[illegible][illegible]

210	5	20	09	2133P	2	RT-1	1	1	1	3	-	3040	RIGHT ANGLE	V. VALUED SB FROM VIEWING LOT	1FO MB F2
-----	---	----	----	-------	---	------	---	---	---	---	---	------	-------------	-------------------------------	-----------

41	11569	544P2	000	5	4	2	3	4	341	OVERTAKE, EB	1-2 CHANGED LANES
41	11569	544P2	000	5	4	2	3	4	341	OVERTAKE, EB	1-2 CHANGED LANES

42	4/7/6	908	1	1		908	4-1 STANCH V 2 IN STD 20 60 20000
		908	1	1		908	

[illegible]

13	6/10/09	P 17-1	REAR END-EB, V-1 SLOWING IN TRAFFIC
----	---------	--------	-------------------------------------

44	730 09 5:18 P	12-1	1	1	3046	2042 EVO-EB V-2 SLOWING IN TRAFFIC
----	---------------	------	---	---	------	------------------------------------

45	9/8/6	11/8/2	1	1	1	3046	0.0000	1/2	0.0000	11/10/00
46	9/8/6	11/8/2	1	1	1	3046	0.0000	1/2	0.0000	11/10/00

[illegible][illegible][illegible][illegible]

DETAILS OF ACCIDENT HISTORY FOR LOCATION (AS SHOWN ON COLLISION DIAGRAM)

DIAGRAM NO.

NONE

SHEET 4 OF 4

[illegible]

Accident Severity Summary

Intersection & Non-Intersection Accidents

Complete Accident Data From NYSDMV Is Only Available thru 30-SEP-2010

Route: 910B Highway Location Ref Mrkr Range: 910B11011010 - 910B11011015

Dates: 01-JAN-2007 thru 31-MAR-2010 Traffic Volume: 30,260

Total of Fatal Accd	Total of Injury Accd	Total of PDO Accd	Total of Non-Reportable	Total Number of Accidents	Accident Rate
0	21	26	5	52	2.41

Accident rate for linear section is accidents per million vehicle miles.

NYSDOT Safety Information Management System Summary Report By Segment And/Or Intersection

Intersection & Non-Intersection Accidents

Complete Accident Data From NYSDMV Is Only Available thru 30-SEP-2010

ROUTE: 910B		HIGHWAY LOCATION: 910B11011010 - 910B11011015		DATES: 01-JAN-2007 - 31-MAR-2010													
REFERENCE	INT.	DESCRIPTION	TOTAL	FTL	INJ	PDO	N/R	NUMBER OF ACCIDENTS									
								WET	FIXED	PED&	TRUCK	LIGHT	CONDITION	DAY	NIGHT	DAY	NIGHT
910B 1101 1010			7	0	3	4	0	2	0	1	0	0	0	6	1	1	
910B 1101 1010	36	COMPUTER DR	11	0	4	5	2	3	0	0	0	0	0	11	0	0	
910B 1101 1011			7	0	2	4	1	0	0	0	0	0	0	6	1	1	
910B 1101 1011	37	WOLF ROAD SHOPPERS PARK	2	0	1	1	0	0	0	0	0	0	0	1	1	1	
910B 1101 1012			4	0	2	1	1	1	0	0	0	0	0	4	0	0	
910B 1101 1013			6	0	2	4	0	5	0	0	0	0	0	4	1	1	
910B 1101 1013	39	METRO PARK RD	6	0	4	2	0	1	0	0	0	0	0	5	1	1	
910B 1101 1014			2	0	0	2	0	0	0	0	0	0	0	1	1	1	
910B 1101 1014	44	BELTRONE DR	2	0	1	1	0	1	0	0	0	0	0	2	0	0	
910B 1101 1015			4	0	2	2	0	1	0	0	0	0	0	3	1	1	
ROUTE TOTAL EXCLUDES 999 RMS			51	0	21	26	4	14	0	1	0	0	0	43	7	7	

ACCIDENT SUMMARY SHEET

MUNICIPALITY Town of Colmaie COUNTY Albany
 LOCATION NY 910 B; RM 910B - 1101 - 1010 to 1015 ^{P111} ~~HST~~ # 1721.51
 TIME PERIOD 1/1/07 to 3/31/10 NO. OF MONTHS 39

<u>Accident Type</u>	<u>No. of Accidents</u>	<u>Pavement</u>	<u>No. of Accidents</u>
Right Angle	<u>22</u>	Dry	<u>39</u>
Rear End	<u>20</u>	Wet	<u>14</u>
Overtaking	<u>7</u>	Snow/Ice	<u>1</u>
Left Turn	<u>3</u>	Unknown	<u>1</u>
Sideswipe/Head-on	<u>1</u>		
Right Turn	<u> </u>	TOTAL	<u>54</u>
Parked Vehicle	<u> </u>		
Pedestrian	<u>1</u>		
Bicycle	<u> </u>	<u>Weather</u>	<u>No. of Accidents</u>
Animal	<u> </u>	Clear	<u>23</u>
Fixed Object	<u> </u>	Cloudy	<u>20</u>
w/Utility Poles	<u> </u>	Rain	<u>9</u>
w/Guide Rail	<u> </u>	Snow	<u>1</u>
w/Sign Posts	<u> </u>	Sleet	<u> </u>
w/Trees	<u> </u>	Fog	<u> </u>
w/Ditch-Embank.	<u> </u>	Unknown	<u>1</u>
w/	<u> </u>	TOTAL	<u>54</u>
TOTAL	<u>54</u>		

<u>Light Conditions</u>	<u>No. of Accidents</u>	<u>Accident Severity</u>	<u>No. of Accidents</u>
Day	<u>45</u>	Fatal	<u> </u>
Night	<u>9</u>	Injury	<u>20</u>
Unknown	<u> </u>	Property Damage	<u>34</u>
TOTAL	<u>54</u>	TOTAL	<u>54</u>

LOCATION	1.	IDENT. NO.: 1110477	STATE OF NEW YORK DEPARTMENT OF TRANSPORTATION TRAFFIC AND SAFETY DIVISION HIGHWAY SAFETY INVESTIGATION REPORT (SEE INSTRUCTIONS ON REVERSE)		MAIN OFFICE USE: DIVISION FILE _____ REVIEWED BY _____ SCHEDULED FOR B&A <input type="checkbox"/>	
	<input checked="" type="checkbox"/> TOWN <input type="checkbox"/> CITY <input type="checkbox"/> VILLAGE	}	OF <u>Colonie</u>			
	ROUTE NO. OR STREET NAME <u>NY 910B / Wolf Rd</u>		STATE HIGHWAY NO. _____	FROM OR AT REFERENCE MARKER <u>910B 1101101</u>		
	At Intersection With (If Applicable)	ROUTE NO. OR STREET NAME <u>CR 151 / Albany Shaker Road</u>	STATE HIGHWAY NO. _____	TO REFERENCE MARKER <u>910B 1101101</u>		
2. REASON FOR INVESTIGATION <input checked="" type="checkbox"/> (a) IDENTIFIED BY ACCIDENT SURVEILLANCE SYSTEM <input type="checkbox"/> (b) POLICE HAZARD REPORT <input checked="" type="checkbox"/> (c) RESPONSE TO COMPLAINT OR INQUIRY PIN 172151 <input checked="" type="checkbox"/> (d) REGIONALLY INITIATED ARWP <input type="checkbox"/> (e) OTHER (Explain) _____			3. RECOMMENDATION <input type="checkbox"/> (a) CAPITAL IMPROVEMENT (Initiate Proj. Devel. Study) <input type="checkbox"/> (b) TRAFFIC CONTROL IMPROVEMENT <input type="checkbox"/> (c) MAINTENANCE IMPROVEMENT <input type="checkbox"/> (d) OTHER <input checked="" type="checkbox"/> (e) NONE			

complete sections 4 & 8

4. DISCUSSION (Use reverse if additional space is required — check box if reverse is used ☐)
- (a) PROBLEMS IDENTIFIED

See attached Page 2 of 2

(b) PROPOSED SOLUTION	Reduction Index	Severity Rank
2009 PIL RM 1016 TO 1019	66.52	16.00
2009 PIE RM 1019	42.88	42.69

(c) ACTION TAKEN

5. ACCIDENT EXPERIENCE

Number of Months	PERIOD BEGINNING		NUMBER OF ACCIDENTS		
			Fatal Accidents	Injury Accidents	Property Damage Accidents
	MONTH	YEAR			
10	01	07	0	10	10
24	11	07	0	33	57
05	11	09	0	9	13

6. BENEFIT/COST ANALYSIS (see instructions)

Check box if Benefit/Cost Calculations are attached ☐

PRINCIPAL INVESTIGATOR

TITLE

APPROVED BY

DATE

3-3-11

Problems Identified

NY Route 910B, Wolf Road, was identified as a Priority Investigation Location (PIL) from RM 1016 to 1019 and a Priority Investigation Intersection (PII) at RM 1019 based on reportable accidents during the period 11/1/07 to 10/31/09. NY 910B, which travels north-south, is a four lane divided Urban Principal Arterial highway with free access. The travel way is 54 feet wide, which accommodates four lanes and a paved flush median that provides refuge for turning vehicles. This area is commercially developed with various businesses and driveways on both sides of the roadway. Pavement markings and signing are satisfactory. The posted speed limit is 40 MPH.

Northbound, NY 910B is intersected by Marcus Boulevard from the east at RM 1016 in a T-intersection controlled by a three color traffic signal. NY 910B is intersected by Ulenskie Drive from the east at RM 1017 in a stop controlled T-intersection. NY 910B is intersected at RM 1018 by the I87 NB Exit 4 off ramp from the west in a T-intersection controlled by a 3 color traffic signal. NY 910B is intersected by Albany Shaker Road at RM 1019 in an intersection controlled with a fully detected three color traffic signal. NY 910B ends at the intersection and the I87 Exit 4 NB on ramp continues north.

The accident study period was 39 months, 1/1/07 to 3/31/10. Based on the 132 accidents that occurred during the study period the accident rate is 9.46 ACC/MVM. This rate is greater than the expected accident rate of 3.59 ACC/MVM for similar highways statewide. There were 90 accidents during the 2 year HAL period. The majority of the accidents consisted of rear end, overtaking, and turning accidents due to traffic congestion, generally grouped around the intersections. There were no accidents involving pedestrians or bicyclists. Of the 127 accidents on this section of highway with pavement condition reported, 25 (20%) occurred on wet pavement and 5 (4%) on snow/ice/slush pavements. There were 11 accidents during the morning peak from 6 am to 9 am and 34 accidents during the evening peak from 3 pm to 6 pm.

A signal study was recently performed at the intersection with Ulenskie Drive at RM 1017. Case #1080248, completed 12/28/08, resulted in no safety recommendation.

Proposed Solution

There is a project, PIN 1721.51 currently scheduled for letting 11/15/12, to address improvements on the Northway at Exit 4. We have no safety recommendations to offer for the project at this time on this section of highway.

Action Taken

Memo to R-1 Design dated 2/20/11.

Wolf Road @ Ulenki

Case #1080248

Signals on Wolf Road

Central Ave.	1170'
Colonie Center South	1100'
Colonie Center North & DOT	1680'
Sand Creek	1240'
Computer Drive	1750'
Metro Park	1400'
Marcus Blvd	1350'
Exit 4 NB off	490'
Exit 4 NB on & IASR	

Marcus Blvd *Signal	780'
Ulenki Drive	530'
Exit 4 NB off *Signal	

- A 3-color signal @ Ulenki would adversely affect traffic flow on Wolf Road due to its close proximity to the adjacent signals.
- The existing traffic signals on Wolf Road create adequate gaps for vehicles exiting (and making the LT onto) Ulenki Drive.

→ • A 3-color signal should not be considered for Ulenki Drive.

- A 'Do Not Block Side Road' sign already exists.

- no changes are recommended

RFF 12/18/08

Wolf Road @ Ulenki:

Case #10980248

I observed the operation of the intersection on 12/16/08 from 3:00 to 4:00 P.M. I made the following observations:


- A 'Do Not Block Side Road' sign already exists on NB Wolf Road at the intersection.
- ~~Northbound~~ Northbound traffic favors the left lane. Some of this may be due to vehicles trying to avoid the side-friction caused by driveway traffic, but the main reason appears to be that vehicles get in the left lane in order to position themselves for the A-SR intersection.
- The existing signals on Wolf Road created adequate gaps for vehicles exiting Ulenki Drive.
- The existing TWLTL provides adequate refuge for SB vehicles making the LT onto Ulenki.
- No instances were observed where a stopped vehicle on NB Wolf Road 'waved out' a LT'er on Ulenki.
- Occasionally, ^{NB} vehicles in the left lane queued through the Ulenki intersection, but generally they respected the intersection and stopped before it in order to avoid blocking it. The right lane never queued to Ulenki.

RFF 12/18/08

DEPARTMENT OF TRANSPORTATION
TRAFFIC ENGINEERING AND SAFETY DIVISION
COLLISION DIAGRAM 4

Sheet 1 of 10

Municipality <u>Town of Colonie</u>	County <u>Albany</u>	File <u>DMV/SIMS/ALIS</u>
Intersection <u>NY 910B / RM 910B - 1101 - 1016 TO 1019 X</u>		
Period <u>3</u> Years <u>3</u> Months	From <u>1/1/07</u> To <u>3/31/10</u>	By <u>MED</u> Date <u>2/16/11</u>



SYMBOLS

MANNER OF COLLISION

- | | |
|-------------------|-------------------|
| ← Moving Vehicle | ← - - Pedestrian |
| ← M - Motorcycle | ← B - Bicycle |
| ↔ Backing Vehicle | □ Fixed Object |
| ← Stopped Vehicle | ○ Personal Injury |
| ▢ Parked Vehicle | ● Fatal Injury |

- | | |
|--------------------|-----------------|
| ← (3) - Rear-end | → ↔ - Head-on |
| ↔ - Side-swipe | ↘ - Left-turn |
| ⚡ - Out of control | ↓ - Right-angle |
| ↺ - Skidding | |
| ← o - Overturned | |

DETAILS OF ACCIDENT HISTORY FOR LOCATION (AS SHOWN ON COLLISION DIAGRAM)

SHEET 2 OF 10

DIAGRAM NO. 4

COUNTY <u>Albany</u>		ROUTE NO. OR STREET NAME <u>N790B / Wolf Rd</u>		CASE NO. FILE <u>PMJ/HUS/SMS</u>	
TOWN <u>Colonie</u>		AT INTERSECTION WITH/OR BETWEEN <u>Rm 910 B - 1101 - 1016 TO 1019</u>		BY <u>MD</u>	
CITY				DATE <u>1/10/11</u>	
VILLAGE OF					
TIME PERIOD NUMBER OF MONTHS	FROM 1/1/07 TO 3/31/10	ENVIRONMENTAL Use codes from MV 104 (shown at right) for these categories	ROADWAY CHARACTER	ROADWAY SURFACE CONDITION	WEATHER
①	②	③	④	⑤	⑥
NO	DATE	TIME	NO. OF VEH.	SEVERITY	LIGHT CONDITIONS
⑦	⑧	⑨	⑩	⑪	⑫
⑬	⑭	⑮	⑯	⑰	⑱
⑲	⑳	㉑	㉒	㉓	㉔
㉕	㉖	㉗	㉘	㉙	㉚
㉛	㉜	㉝	㉞	㉟	㊱
㊲	㊳	㊴	㊵	㊶	㊷
㊸	㊹	㊺	㊻	㊼	㊽
㊾	㊿	1	2	3	4
5	6	7	8	9	10
11	12	13	14	15	16
17	18	19	20	21	22
23	24	25	26	27	28
29	30	31	32	33	34
35	36	37	38	39	40
41	42	43	44	45	46
47	48	49	50	51	52
53	54	55	56	57	58
59	60	61	62	63	64
65	66	67	68	69	70
71	72	73	74	75	76
77	78	79	80	81	82
83	84	85	86	87	88
89	90	91	92	93	94
95	96	97	98	99	100
101	102	103	104	105	106
107	108	109	110	111	112
113	114	115	116	117	118
119	120	121	122	123	124
125	126	127	128	129	130
131	132	133	134	135	136
137	138	139	140	141	142
143	144	145	146	147	148
149	150	151	152	153	154
155	156	157	158	159	160
161	162	163	164	165	166
167	168	169	170	171	172
173	174	175	176	177	178
179	180	181	182	183	184
185	186	187	188	189	190
191	192	193	194	195	196
197	198	199	200	201	202
203	204	205	206	207	208
209	210	211	212	213	214
215	216	217	218	219	220
221	222	223	224	225	226
227	228	229	230	231	232
233	234	235	236	237	238
239	240	241	242	243	244
245	246	247	248	249	250
251	252	253	254	255	256
257	258	259	260	261	262
263	264	265	266	267	268
269	270	271	272	273	274
275	276	277	278	279	280
281	282	283	284	285	286
287	288	289	290	291	292
293	294	295	296	297	298
299	300	301	302	303	304
305	306	307	308	309	310
311	312	313	314	315	316
317	318	319	320	321	322
323	324	325	326	327	328
329	330	331	332	333	334
335	336	337	338	339	340
341	342	343	344	345	346
347	348	349	350	351	352
353	354	355	356	357	358
359	360	361	362	363	364
365	366	367	368	369	370
371	372	373	374	375	376
377	378	379	380	381	382
383	384	385	386	387	388
389	390	391	392	393	394
395	396	397	398	399	400
401	402	403	404	405	406
407	408	409	410	411	412
413	414	415	416	417	418
419	420	421	422	423	424
425	426	427	428	429	430
431	432	433	434	435	436
437	438	439	440	441	442
443	444	445	446	447	448
449	450	451	452	453	454
455	456	457	458	459	460
461	462	463	464	465	466
467	468	469	470	471	472
473	474	475	476	477	478
479	480	481	482	483	484
485	486	487	488	489	490
491	492	493	494	495	496
497	498	499	500	501	502
503	504	505	506	507	508
509	510	511	512	513	514
515	516	517	518	519	520
521	522	523	524	525	526
527	528	529	530	531	532
533	534	535	536	537	538
539	540	541	542	543	544
545	546	547	548	549	550
551	552	553	554	555	556
557	558	559	560	561	562
563	564	565	566	567	568
569	570	571	572	573	574
575	576	577	578	579	580
581	582	583	584	585	586
587	588	589	590	591	592
593	594	595	596	597	598
599	600	601	602	603	604
605	606	607	608	609	610
611	612	613	614	615	616
617	618	619	620	621	622
623	624	625	626	627	628
629	630	631	632	633	634
635	636	637	638	639	640
641	642	643	644	645	646
647	648	649	650	651	652
653	654	655	656	657	658
659	660	661	662	663	664
665	666	667	668	669	670
671	672	673	674	675	676
677	678	679	680	681	682
683	684	685	686	687	688
689	690	691	692	693	694
695	696	697	698	699	700
701	702	703	704	705	706
707	708	709	710	711	712
713	714	715	716	717	718
719	720	721	722	723	724
725	726	727	728	729	730
731	732	733	734	735	736
737	738	739	740	741	742
743	744	745	746	747	748
749	750	751	752	753	754
755	756	757	758	759	760
761	762	763	764	765	766
767	768	769	770	771	772
773	774	775	776	777	778
779	780	781	782	783	784
785	786	787	788	789	790
791	792	793	794	795	796
797	798	799	800	801	802
803	804	805	806	807	808
809	810	811	812	813	814
815	816	817	818	819	820
821	822	823	824	825	826
827	828	829	830	831	832
833	834	835	836	837	838
839	840	841	842	843	844
845	846	847	848	849	850
851	852	853	854	855	856
857	858	859	860	861	862
863	864	865	866	867	868
869	870	871	872	873	874
875	876	877	878	879	880
881	882	883	884	885	886
887	888	889	890	891	892
893	894	895	896	897	898
899	900	901	902	903	904
905	906	907	908	909	910
911	912	913	914	915	916
917	918	919	920	921	922
923	924	925	926	927	928
929	930	931	932	933	934
935	936	937	938	939	940
941	942	943	944	945	946
947	948	949	950	951	952
953	954	955	956	957	958
959	960	961	962	963	964
965	966	967	968	969	970
971	972	973	974	975	976
977	978	979	980	981	982
983	984	985	986	987	988
989	990	991	992	993	994
995	996	997	998	999	1000

DETAILS OF ACCIDENT HISTORY FOR LOCATION (AS SHOWN ON COLLISION DIAGRAM)

SHEET 3 OF 10DIAGRAM NO. 4

COUNTY <u>Albany</u>		ROUTE NO. OR STREET NAME <u>NY 910B / Wolf Rd</u>		CASE NO. FILE <u>DMV/ALIS/sims</u>	
TOWN <u>Colonie</u>		AT INTERSECTION WITH/OR BETWEEN <u>RM 910B - 1101-1016 TO 1019</u>		BY <u>MEM</u>	
CITY				DATE <u>2/4/11</u>	
VILLAGE OF					
TIME PERIOD NUMBER OF MONTHS	FROM 1/1/07 TO 3/31/10	ENVIRONMENTAL Use codes from MV 104 (shown at right) for these categories	ROADWAY CHARACTER	ROADWAY SURFACE	WEATHER
①	②	③	④	⑤	⑥
NO	DATE	TIME	NO. OF VEH.	SEVERITY	LIGHT CONDITIONS
⑦	⑧	⑨	⑩	⑪	⑫
⑬	⑭	⑮	⑯	⑰	⑱
⑲	⑳	㉑	㉒	㉓	㉔
㉕	㉖	㉗	㉘	㉙	㉚
㉛	㉜	㉝	㉞	㉟	㊱
㊲	㊳	㊴	㊵	㊶	㊷
㊸	㊹	㊺	㊻	㊼	㊽
㊾	㊿	1	2	3	4
5	6	7	8	9	10
11	12	13	14	15	16
17	18	19	20	21	22
23	24	25	26	27	28
29	30	31	32	33	34
35	36	37	38	39	40
41	42	43	44	45	46
47	48	49	50	51	52
53	54	55	56	57	58
59	60	61	62	63	64
65	66	67	68	69	70
71	72	73	74	75	76
77	78	79	80	81	82
83	84	85	86	87	88
89	90	91	92	93	94
95	96	97	98	99	100
101	102	103	104	105	106
107	108	109	110	111	112
113	114	115	116	117	118
119	120	121	122	123	124
125	126	127	128	129	130
131	132	133	134	135	136
137	138	139	140	141	142
143	144	145	146	147	148
149	150	151	152	153	154
155	156	157	158	159	160
161	162	163	164	165	166
167	168	169	170	171	172
173	174	175	176	177	178
179	180	181	182	183	184
185	186	187	188	189	190
191	192	193	194	195	196
197	198	199	200	201	202
203	204	205	206	207	208
209	210	211	212	213	214
215	216	217	218	219	220
221	222	223	224	225	226
227	228	229	230	231	232
233	234	235	236	237	238
239	240	241	242	243	244
245	246	247	248	249	250
251	252	253	254	255	256
257	258	259	260	261	262
263	264	265	266	267	268
269	270	271	272	273	274
275	276	277	278	279	280
281	282	283	284	285	286
287	288	289	290	291	292
293	294	295	296	297	298
299	300	301	302	303	304
305	306	307	308	309	310
311	312	313	314	315	316
317	318	319	320	321	322
323	324	325	326	327	328
329	330	331	332	333	334
335	336	337	338	339	340
341	342	343	344	345	346
347	348	349	350	351	352
353	354	355	356	357	358
359	360	361	362	363	364
365	366	367	368	369	370
371	372	373	374	375	376
377	378	379	380	381	382
383	384	385	386	387	388
389	390	391	392	393	394
395	396	397	398	399	400
401	402	403	404	405	406
407	408	409	410	411	412
413	414	415	416	417	418
419	420	421	422	423	424
425	426	427	428	429	430
431	432	433	434	435	436
437	438	439	440	441	442
443	444	445	446	447	448
449	450	451	452	453	454
455	456	457	458	459	460
461	462	463	464	465	466
467	468	469	470	471	472
473	474	475	476	477	478
479	480	481	482	483	484
485	486	487	488	489	490
491	492	493	494	495	496
497	498	499	500	501	502
503	504	505	506	507	508
509	510	511	512	513	514
515	516	517	518	519	520
521	522	523	524	525	526
527	528	529	530	531	532
533	534	535	536	537	538
539	540	541	542	543	544
545	546	547	548	549	550
551	552	553	554	555	556
557	558	559	560	561	562
563	564	565	566	567	568
569	570	571	572	573	574
575	576	577	578	579	580
581	582	583	584	585	586
587	588	589	590	591	592
593	594	595	596	597	598
599	600	601	602	603	604
605	606	607	608	609	610
611	612	613	614	615	616
617	618	619	620	621	622
623	624	625	626	627	628
629	630	631	632	633	634
635	636	637	638	639	640
641	642	643	644	645	646
647	648	649	650	651	652
653	654	655	656	657	658
659	660	661	662	663	664
665	666	667	668	669	670
671	672	673	674	675	676
677	678	679	680	681	682
683	684	685	686	687	688
689	690	691	692	693	694
695	696	697	698	699	700
701	702	703	704	705	706
707	708	709	710	711	712
713	714	715	716	717	718
719	720	721	722	723	724
725	726	727	728	729	730
731	732	733	734	735	736
737	738	739	740	741	742
743	744	745	746	747	748
749	750	751	752	753	754
755	756	757	758	759	760
761	762	763	764	765	766
767	768	769	770	771	772
773	774	775	776	777	778
779	780	781	782	783	784
785	786	787	788	789	790
791	792	793	794	795	796
797	798	799	800	801	802
803	804	805	806	807	808
809	810	811	812	813	814
815	816	817	818	819	820
821	822	823	824	825	826
827	828	829	830	831	832
833	834	835	836	837	838
839	840	841	842	843	844
845	846	847	848	849	850
851	852	853	854	855	856
857	858	859	860	861	862
863	864	865	866	867	868
869	870	871	872	873	874
875	876	877	878	879	880
881	882	883	884	885	886
887	888	889	890	891	892
893	894	895	896	897	898
899	900	901	902	903	904
905	906	907	908	909	910
911	912	913	914	915	916
917	918	919	920	921	922
923	924	925	926	927	928
929	930	931	932	933	934
935	936	937	938	939	940
941	942	943	944	945	946
947	948	949	950	951	952
953	954	955	956	957	958
959	960	961	962	963	964
965	966	967	968	969	970
971	972	973	974	975	976
977	978	979	980	981	982
983	984	985	986	987	988
989	990	991	992	993	994
995	996	997	998	999	1000

DETAILS OF ACCIDENT HISTORY FOR LOCATION (AS SHOWN ON COLLISION DIAGRAM)

SHEET 4 OF 10DIAGRAM NO. 4

COUNTY <u>Albany</u>		ROUTE NO. OR STREET NAME <u>NY 910B / Wolf Rd</u>		CASE NO. FILE <u>DMV 1015 / SIMS</u>	
TOWN <u>Colonie</u>		AT INTERSECTION WITH/OR BETWEEN <u>RM 910B - 1101 - 1016 TO 1019</u>		BY <u>MEG</u>	
CITY				DATE <u>2/4/11</u>	
VILLAGE OF					
TIME PERIOD NUMBER OF MONTHS	FROM TO	ENVIRONMENTAL Use codes from MV 104 (shown at right) for these categories	ROADWAY CHARACTER CONDITIONS	ROADWAY SURFACE CONDITION	WEATHER
319	3/31/10	(6) (7) (8) (9)	(5)	(4)	(3)
①	②	③	④	⑤	⑥
NO	DATE	TIME	NO. OF VEH.	SEVERITY	DESCRIPTION
33	6/13/08	5:56P	2	P00	1017 REAR END-NB V-2 STOPPED IN TRAFFIC
34	12/3/08	7:30P	2	P00	1017 OVERTAKE-NB V-2 CHANGED LANES
35	1/22/08	4:30P	2	P00	1018 OVERTAKE-EB, BOTH VEHAS MAKING LEFT TURNS
36	8/30/08	1:18A	2	P00	1018 OVERTAKE-SB, NB V-1 MADE RIGHT, EB V-2 MADE LEFT
37	9/17/08	A	2	P00	1018 REAR END-SB, V-1 STOPPED AT RED TRAFFIC SIGNAL
38	10/3/08	9:37P	2	P00	1018 SB V-1 ATTEMPTED LEFT TURN, STRUCK BY NB V-2
39	12/4/08	12:26P	2	P00	1018 OVERTAKE-EB V-1 LOST CONTROL EXITING
40	1/4/08	6:03P	2	P52	1019 REAR END-NB, V-1 STOPPED, STARTED ROL, STOPPED AGAIN
41	1/6/08	5:30P	2	P00	1019 WB V-1 ATTEMPTED LEFT TURN, STRUCK BY EB V-2
42	1/8/08	3:07P	2	P53	1019 EB V-1 ATTEMPTED LEFT TURN, STRUCK BY WB V-2
43	1/15/08	2:00P	2	P00	1019 REAR END-NB, V-1 SLOWING IN TRAFFIC AT SIGNAL
44	2/6/08	2:07P	2	P51	1019 REAR END-EB, BOTH VEHICLES STARTING IN TRAFFIC
45	2/19/08	9:21P	2	P00	1019 WB V-1 ATTEMPTED LEFT TURN, STRUCK BY EB V-2
46	3/28/08	9:56A	2	P00	1019 WB V-1 ATTEMPTED LEFT TURN, STRUCK BY EB V-2
47	4/17/08	5:56P	2	P00	1019 CRASH AT ANGLE V-1 WB IN INTERSECTION, NB V-2 JUMPED ON GREEN

DETAILS OF ACCIDENT HISTORY FOR LOCATION (AS SHOWN ON COLLISION DIAGRAM)

SHEET 5 OF 10DIAGRAM NO. 4

COUNTY <u>Albany</u>		P.O. NO. <u>110477</u>		ROUTE NO. OR STREET NAME <u>NY 910 B / Wolf Rd</u>		CASE NO. FILE <u>DMV / AUS / SIMS</u>								
TOWN <u>Colonie</u>		OR IDENT.		AT INTERSECTION WITH/OR BETWEEN		BY <u>MED</u>								
VILLAGE OF <u>Colonie</u>				<u>RM 910 B - 1101-1016 TO 1019</u>		DATE <u>2/8/11</u>								
TIME PERIOD NUMBER OF MONTHS	FROM <u>1/1/07</u>	TO <u>3/31/10</u>	④ NO. OF VEH.	⑤ SEVERITY	⑥ LIGHT CONDITIONS	⑦ ROADWAY CHARACTER	⑧ ROADWAY SURFACE CONDITION	⑨ WEATHER	⑩ LIGHT CONDITIONS	⑪ ROADWAY CHARACTER	⑫ ROADWAY SURFACE CONDITION	⑬ WEATHER	⑭ APPARENT CONTRIBUTING FACTORS	⑮ DESCRIPTION
3/9														
49	4/25/08	11:42A	2	PDO	1	5	1	1	1019	REAR END-NB, BOTH VEHICLES STARTING IN TRAFFIC				
50	5/1/08	8:36A	2	PT-1	1	1	1	1	1019	REAR END-NB, V-2 STOPPED, STARTED, STOPPED AGAIN				
51	5/8/08	6:10P	2	PDO	1	1	1	1	1019	NB V-1 ATTEMPTED LEFT TURN, STRUCK BY EB V-2				
52	6/1/08	12:01P	2	PT-1	1				1019	REAR END-WB, V-2 STOPPED AT RED TRAFFIC SIGNAL				
53	6/12/08	5:00P	2	PT-1	1	1	1	1	1019	REAR END-NB, V-1 STOPPED IN TRAFFIC AT SIGNAL				
54	6/14/08		2	PDO	1	1	2	3	1019	REAR END-NB, V-1 STOPPED IN TRAFFIC AT SIGNAL				
55	7/7/08	12:15P	2	PDO	1	1	1	1	1019	REAR END-EB, BOTH VEH STOPPED, OP-2 FOOT SLIPPED BEHIND				
56	7/19/08	6:29P	2	PT-1	1	1	1	1	1019	REAR END-EB, V-2 SLOWING TO TURN				
57	7/28/08	3:00P	2	PDO	1				1019	REAR END-NB, V-2 STOPPED, STOPPED AGAIN				
58	7/29/08	10:23A	2	PDO	1	1	1	1	1019	EB V-2 ATTEMPTED LEFT TURN, STRUCK BY WB V-1				
59	7/29/08	1:27P	2	PT-1	1	1	1	1	1019	REAR END-WB, V-2 STOPPED IN TRAFFIC AT SIGNAL				
60	8/12/08	6:55P	2	PDO	3	1	1	1	1019	RIGHT ANGLE, NB V-1 STRUCK WB V-2, BOTH CLAIM GREEN				
61	9/2/08	1:37P	2	PDO	1	1	1	1	1019	REAR END-NB, V-1 STOPPED BEHIND UNINVOLVED VEH				
62	9/3/08	11:56P	2	PDO	4	1	1	2	1019	RIGHT ANGLE, EB V-1 PASSED RED SIGNAL, STRUCK NB V-2				
63	9/10/08	8:52A	2	PDO	1	1	1	1	1019	RIGHT ANGLE, EB V-1 PASSED RED SIGNAL, STRUCK NB V-2				

DETAILS OF ACCIDENT HISTORY FOR LOCATION (AS SHOWN ON COLLISION DIAGRAM)

SHEET 6 OF 10

DIAGRAM NO. 4

COUNTY <u>Albany</u>		ROUTE NO. OR STREET NAME <u>NY 910 E / Wolf Rd</u>		CASE NO. FILE <u>DMV/ALBIS/SIMS</u>					
TOWN <u>Colonie</u>		AT INTERSECTION WITH/OR BETWEEN		BY <u>MED</u>					
CITY				DATE <u>2/8/11</u>					
VILLAGE OF									
TIME PERIOD NUMBER OF MONTHS	FROM 1/1/07	TO 3/31/10	ENVIRONMENTAL Use codes from MV 104 (shown at right) for these categories	LIGHT CONDITIONS	ROADWAY CHARACTER	ROADWAY SURFACE	WEATHER	APPARENT CONTRIBUTING FACTORS	DESCRIPTION
319			(6) (7) (8) (9)	(5) SEVERITY	(4) NO. OF VEH.				
① NO	② DATE	③ TIME							
65	10/5/08	8:10P	4 1 1 1	2 P00	2	1019	1	1019	EB V-1 ATTEMPTED LEFT TURN, STRUCK BY WB V-2
66	10/8/08	5:15P	1 1 1 2	2 P1-1	2	1019	2	1019	REAR END-NB V-2 SLOWING AT SIGNAL, OP-1 LOOKING LEFT
67	10/15/08	A	4 4 1 1	2 P00	1	1019	1	1019	OVERTAKE-NB V-2 ATTEMPTED LEFT FROM RIGHT LANE
68	10/16/08	6:44P	4 1 1 1	3 P1-1	3	1019	1	1019	WB V-1 ATTEMPTED LEFT TURN, STRUCK BY EB V-7
69	11/21/08	6:19P	4 1 1 1	2 P00	2	1019	1	1019	EB V-1 ATTEMPTED LEFT TURN, STRUCK BY WB V-2
70	11/25/08	1:22P	1 1 2 3	2 P00	2	1019	3	1019	RIGHT ANGLE, NB V-1 PASSED RED SIGNAL, STRUCK WB V-2
71	12/10/08	8:18A	1 1 2 3	2 P00	2	1019	3	1019	OVERTAKE-SB EB V-2 MADE RIGHT TURN, WB V-1 MADE LEFT
72	12/10/08	12:39P	1 1 2 3	2 P00	2	1019	4	1019	REAR END-WB V-1 STOPPED IN TRAFFIC AT SIGNAL
73	4/24/09	7:29A	1 1 1 1	2 P00	2	1016	9.26	1016	REAR END-SB V-2 BRAKED ABRUPTLY BEHIND UNINVOLVED VEH
74	11/12/09	4:15P	1 1 1 1	2 P1-1	2	1017	4	1017	REAR END-NB V-2 STOPPED IN TRAFFIC
75	11/16/09	5:17P	4 1 1 1	2 P1-2	2	1017	4	1017	REAR END-NB V-2 STOPPED IN TRAFFIC
76	12/13/09	5:26P	4 1 1 2	3 P1-2	3	1017	4	1017	REAR END-NB V-2 & V-3 STOPPED IN TRAFFIC
77	12/15/09	4:39P	4 1 1 1	2 P00	2	1017	4	1017	REAR END-NB V-2 STOPPED IN TRAFFIC
78	7/27/09	6:56A	1 1 1 2	2 P00	2	1018	4	1018	REAR END-NB V-2 STOPPED IN TRAFFIC AT SIGNAL
79	10/16/09	2:04P	1 1 1 1	2 P1-2	2	1018	9	1018	REAR END-NB V-2 STOPPED IN TRAFFIC

DIAGRAM NO. 4

DETAILS OF ACCIDENT HISTORY FOR LOCATION (AS SHOWN ON COLLISION DIAGRAM)

SHEET 7 OF 10

COUNTY <u>Albany</u>		ROUTE NO. OR STREET NAME <u>NY 910B / Wolf Rd</u>		CASE NO. FILE <u>DMV / ALBIS / 51005</u>						
TOWN <u>Colome</u>		AT INTERSECTION WITH/OR BETWEEN <u>RM 910B - 1101-1016 TO 1019</u>		BY <u>MD</u>						
CITY				DATE <u>2/9/11</u>						
VILLAGE OF										
TIME PERIOD NUMBER OF MONTHS	FROM 1/1/07 TO 3/31/10	ENVIRONMENTAL Use codes from MV 104 (shown at right) for these categories	ROADWAY CHARACTER 1. Straight and Level 2. Straight at Hillcrest 3. Straight at Hillcrest 4. Curve and Level 5. Curve and Grade 6. Curve at Hillcrest	ROADWAY SURFACE CONDITION 1. Dry 2. Wet 3. Muddy 4. Snow/Ice 5. Slush 10. Other	WEATHER 1. Clear 2. Cloudy 3. Rain 4. Snow 5. Sleet/Hail/Freezing Rain 6. Fog/Smog/Smoke 10. Other					
① NO	② DATE	③ TIME	④ NO. OF VEH.	⑤ SEVERITY	⑥ LIGHT CONDITIONS	⑦ ROADWAY CHARACTER	⑧ ROADWAY SURFACE CONDITION	⑨ WEATHER	⑩ APPARENT CONTRIBUTING FACTORS	⑪ DESCRIPTION
81	1/19/09	1:22P	2	P00	1	1	2	2	9	1018 REAR END-NB, V-1 SLOWING IN TRAFFIC
82	2/15/09	3:34P	2	P00	1	2	1	1	7	1018 REAR END-EB, V-2 STOPPED IN TRAFFIC AT SIGNAL
83	2/24/09	1:17P	2	P00	1	1	1	1	74	1018 RIGHT ANGLE, V-1 ENTERED TRAFFIC EB, STRUCK BY SB V-2
84	4/10/09	6:37P	2	P00	1	1	1	1	74	1018 RIGHT ANGLE, V-2 ENTERED TRAFFIC EB, STRUCK BY SB V-1
85	5/15/09	A 3	3	P00					1018 REAR END-NB, V-1 & V-2 STOPPED IN TRAFFIC, V-2 STRUCK V-1	
86	6/6/09	9:12P	2	P00	3	2	1	1	9, 2	1018 REAR END-EB, V-1 STOPPED AT RED TRAFFIC SIGNAL
87	6/11/09	2:55P	2	P00	1	1	1	2	7	1018 RIGHT TURN, SB V-1 MAKING RIGHT, STRUCK V-2 STOPPED EB
88	11/19/09	11:54A	2	P5-1	1	1	1	1	9	1018 REAR END-NB, V-2 STOPPED IN TRAFFIC
89	12/22/09	5:05P	2	P5-1	4	1	1	1	7, 7	1018 OVERTAKE-EB, BOTH VEHICLES MAKING LEFT TURNS
90	12/30/09	3:37P	2	P00	1	1	1	2	7, 18	1018 SB V-1 ATTEMPTED LEFT TURN, STRUCK BY NB V-2
91	1/24/09	4:31P	2	P5-1	1	1	1	1	4	1019 REAR END-NB, V-2 STOPPED FOR RED TRAFFIC SIGNAL
92	2/22/09	9:00P	2	P5-1	4	1	2	1	4	1019 REAR END-NB, BOTH VEHICLES STOPPED, OP-1 FOOT SLIPPED ^{FROM} _{BRAKE}
93	3/13/09	5:00P	2	P5-2	1	1	1	1	4	1019 REAR END-NB, V-2 STARTED RUC, STOPPED FOR EB TRAFFIC
94	3/21/09	4:45P	2	P5-2	1	1	1	1	4	1019 REAR END-NB, V-2 STARTED RUC, STOPPED OP-1 LOOKING LEFT
95	3/30/09	2:59P	2	P00	1	1	1	2	17	1019 RIGHT ANGLE, NB V-1 PASSED RED SIGNAL, STRUCK EB V-2

DETAILS OF ACCIDENT HISTORY FOR LOCATION (AS SHOWN ON COLLISION DIAGRAM)

SHEET 8 OF 10

DIAGRAM NO. 4

COUNTY <u>Albany</u> OR IDENT. <u>110477</u>		ROUTE NO. OR STREET NAME <u>NY 910B / Wolf Rd</u>		CASE NO. FILE <u>DMV/MIS/SIMS</u> BY <u>MEB</u> DATE <u>2/9/11</u>								
TOWN <input checked="" type="checkbox"/> CITY <input type="checkbox"/> VILLAGE OF <u>Colonie</u>		AT INTERSECTION WITH/OR BETWEEN <u>RM 910B - 1101 - 1016 TO 1019</u>										
TIME PERIOD NUMBER OF MONTHS 3/9	FROM 1/1/07 TO 3/31/10	④ NO. OF VEH.	⑤ SEVERITY	ENVIRONMENTAL Use codes from MV 104 (shown at right) for these categories			⑧ ROADWAY SURFACE CONDITION	⑨ WEATHER	⑩ LIGHT CONDITIONS	ROADWAY CHARACTER 1. Straight and Level 2. Straight at Grade 3. Straight at Hillcrest 4. Curve and Level 5. Curve at Hillcrest	ROADWAY SURFACE CONDITION 1. Dry 2. Wet 3. Muddy 4. Snow/Ice 5. Slush 10. Other	WEATHER 1. Clear 2. Cloudy 3. Rain 4. Snow 5. Sleet/Hail/Freezing Rain 6. Fog/Smog/Smoke 10. Other
				⑥ ROADWAY CONDITIONS	⑦ ROADWAY CHARACTER	⑧ ROADWAY SURFACE CONDITION						
① NO	② DATE	③ TIME	⑪ DESCRIPTION Use Codes from MV 104 Police Report see back of this form for codes									
97	4/22/09	6:54P	2	PI-2	1	1	1	2	177	1019	RIGHT ANGLE, WB V-1 PASSED RED SIGNAL, STRUCK BY NB V-2	
98	4/29/09	9:05P	2	PS-2	4	1	1	1	7	1019	EB V-1 ATTEMPTED LEFT TURN, STRUCK BY WB V-2	
99	5/3/09	9:35A	2	PI-1	1				1019	REAR END-NB, V-1 STOPPED AT RED TRAFFIC SIGNAL		
100	6/6/09	4:55P	2	PDO	1				7:18	1019	OVERTAKE-SB, WB V-1 MADE LEFT, EB V-2 MADE RIGHT	
101	6/10/09	8:09P	2	PI-1	1	1	1	1	7	1019	EB V-1 ATTEMPTED LEFT TURN, STRUCK BY WB V-2	
102	6/15/09	9:51A	2	PDO	1	1	1	2	7	1019	EB V-1 ATTEMPTED LEFT TURN, STRUCK BY WB V-2	
103	6/20/09	12:57P	2	PDO	1	1	1	2	7	1019	WB V-1 ATTEMPTED LEFT TURN, STRUCK BY EB V-2	
104	6/24/09	9:08A	2	PDO	1	1	1	1	7	1019	WB V-1 ATTEMPTED LEFT TURN, STRUCK BY EB V-2	
105	6/27/09	11:35A	2	PI-1	1	1	1	2	4	1019	REAR END-NB, V-1 STOPPED IN TRAFFIC AT SIGNAL	
106	6/28/09	3:28P	2	PS-4	1	1	1	1	17	1019	RIGHT ANGLE, NB V-1 PASSED RED SIGNAL, STRUCK BY EB V-2	
107	7/11/09	1:51P	2	PI-1	1	1	1	2	4	1019	REAR END-NB, BOTH VEHICLES STOPPED, V-1 JUMPED ON GREEN	
108	7/16/09	1:05P	2	PDO	1	1	1	1		1019	REAR END-NB, V-2 STOPPED, STARTED ROR, STOPPED AGAIN	
109	9/9/09	2:58P	2	PDO	1	1	1	1	9	1019	REAR END-NB, V-1 SLOWING TO MAKE RIGHT TURN	
110	9/12/09	12:46P	2	PDO	1	1	1	2	4	1019	REAR END-NB, V-1 STOPPED AT RED SIGNAL, OP-2 LOOKING LEFT	
111	9/16/09	2:05P	2	PS-1	1	1	1	2	7:4	1019	RIGHT ANGLE, NB EMT V-1 W/ LIGHTS & SIREN, STRUCK BY EB V-2	

DETAILS OF ACCIDENT HISTORY FOR LOCATION (AS SHOWN ON COLLISION DIAGRAM)

DIAGRAM NO. 4PREF. OR IDENT. 110477ROUTE NO. OR STREET NAME
NY 910B / Wolf RdCASE NO. DMV/ALIS/simsFILE MDBY MDDATE 2/10/11SHEET 9 OF 10

COUNTY <u>Albany</u>		TOWN <u>Colonie</u>		CITY <u>Colonie</u>		VILLAGE OF <u>Colonie</u>		ROUTE NO. OR STREET NAME <u>NY 910B / Wolf Rd</u>		CASE NO. <u>DMV/ALIS/sims</u>	
TIME PERIOD FROM <u>1/1/07</u> TO <u>3/31/10</u>		NO. OF VEH.		SEVERITY		ENVIRONMENTAL Use codes from MV 104 (shown at right) for these categories		LIGHT CONDITIONS		ROADWAY CHARACTER	
NUMBER OF MONTHS <u>39</u>		DATE		TIME		ROADWAY CHARACTER		ROADWAY SURFACE		WEATHER	
NO		DATE		TIME		ROADWAY CHARACTER		ROADWAY SURFACE		WEATHER	
113	10/7/09	4:23P	2	P00	1	1	1	1	1	1	1
114	10/15/09	12:44P	2	P5-2	1	1	1	1	1	1	1
115	10/26/09	2:01P	2	P00	1	1	1	1	1	1	1
116	11/2/09	7:01P	2	P00	5	1	1	1	1	1	1
117	11/28/09	6:00P	2	P5-1	4	1	1	1	1	1	1
118	12/6/09	P	2	P00	1	1	1	1	1	1	1
119	12/16/09	7:59P	2	P00	4	1	1	1	1	1	1
120	12/17/09	7:01P	2	P00	4	1	1	1	1	1	1
121	12/22/09	1:13P	2	P00	1	1	1	1	1	1	1
122	12/31/09	3:28P	2	P5-1	1	1	1	1	1	1	1
123	1/9/10	3:56P	2	P5-2	1	1	1	1	1	1	1
124	1/13/10	8:44A	2	P00	1	1	1	1	1	1	1
125	3/18/10	3:56P	2	P00	1	1	1	1	1	1	1
126	1/14/10	7:43A	2	P5-1	1	1	1	1	1	1	1
127	1/7/10	4:17P	3	P00	3	1	1	1	1	1	1
128	1/1/10	5:00P	2	P00	1	1	1	1	1	1	1

Use codes from MV 104 Police Report
see back of this form for codes

APPARENT CONTRIBUTING FACTORS

11 DESCRIPTION

113 NB V-1 ATTEMPTED LEFT TURN, STRUCK BY EB V-2

114 RIGHT ANGLE; EB V-1 PASSED RED SIGNAL, STRUCK NB V-2

115 WB V-1 ATTEMPTED LEFT TURN, STRUCK BY EB V-2

116 REAR END-NB V-2 STOPPED IN TRAFFIC AT SIGNAL

117 WB V-1 ATTEMPTED LEFT TURN, STRUCK BY EB V-2

118 REAR END-NB V-1 STOPPED, STARTED ROR, STOPPED AGAIN

119 OVERTAKE-SB, WB V-1 MAKING LEFT, EB V-2 MAKING RIGHT

120 WB V-1 ATTEMPTED LEFT TURN, STRUCK BY EB V-2

121 WB V-1 ATTEMPTED LEFT TURN, STRUCK BY EB V-2

122 REAR END NB V-2 STARTED ROR, STOPPED, OPV-1 LOOKING LEFT

123 REAR END-SB, V-2 STOPPED IN TRAFFIC AT SIGNAL

124 OVERTAKE-NB, V-1 CHANGED LANES

125 SB V-1 ATTEMPTED LEFT TURN, STRUCK BY NB V-2

126 SB V-1 ATTEMPTED LEFT TURN, STRUCK BY NB V-2

127 REAR END-NB, ALL VEHICLES STOPPED, OP-3 FOOT SLIPPED

128 FROM REAR

DIAGRAM NO.

SHEET 10 OF 10

COUNTY <u>Albany</u>		PLN- <u>1110477</u>		ROUTE NO. OR STREET NAME <u>NY 9105 / Wolf Rd</u>		CASE NO. <u>DMV/ALIS/SIMS</u>	
<input checked="" type="checkbox"/> TOWN		OR IDENT.		AT INTERSECTION WITH/OR BETWEEN <u>RM 9105 - 1101 - 1016 TO 1019</u>		FILE <u>MED</u>	
<input type="checkbox"/> CITY						BY <u>2/10/11</u>	
<input type="checkbox"/> VILLAGE OF <u>Colonie</u>						DATE <u>2/10/11</u>	
TIME PERIOD NUMBER OF MONTHS <u>3/9</u>		FROM <u>1/1/07</u>		TO <u>3/31/10</u>		WEATHER 1. Clear 2. Cloudy 3. Rain 4. Snow 5. Sleet/Hail/Freezing Rain 6. Fog/Smog/Smoke 10. Other	
NO. OF VEH.		SEVERITY		LIGHT CONDITIONS		ENVIRONMENTAL Use codes from MV 104 (shown at right) for these categories	
④		⑤		⑥		⑦	
③		②		①		⑧	
TIME		DATE		ROADWAY CHARACTER		ROADWAY SURFACE CONDITION	
③		②		①		⑧	
①		②		③		④	
NO		DATE		ROADWAY CHARACTER		ROADWAY SURFACE CONDITION	
①		②		③		④	
⑤		④		③		②	
④		③		②		①	
③		②		①		⑧	
②		①		⑦		⑥	
①		⑧		⑦		⑥	
⑧		⑦		⑥		⑤	
⑦		⑥		⑤		④	
⑥		⑤		④		③	
⑤		④		③		②	
④		③		②		①	
③		②		①		⑧	
②		①		⑦		⑥	
①		⑧		⑦		⑥	
⑧		⑦		⑥		⑤	
⑦		⑥		⑤		④	
⑥		⑤		④		③	
⑤		④		③		②	
④		③		②		①	
③		②		①		⑧	
②		①		⑦		⑥	
①		⑧		⑦		⑥	
⑧		⑦		⑥		⑤	
⑦		⑥		⑤		④	
⑥		⑤		④		③	
⑤		④		③		②	
④		③		②		①	
③		②		①		⑧	
②		①		⑦		⑥	
①		⑧		⑦		⑥	
⑧		⑦		⑥		⑤	
⑦		⑥		⑤		④	
⑥		⑤		④		③	
⑤		④		③		②	
④		③		②		①	
③		②		①		⑧	
②		①		⑦		⑥	
①		⑧		⑦		⑥	
⑧		⑦		⑥		⑤	
⑦		⑥		⑤		④	
⑥		⑤		④		③	
⑤		④		③		②	
④		③		②		①	
③		②		①		⑧	
②		①		⑦		⑥	
①		⑧		⑦		⑥	
⑧		⑦		⑥		⑤	
⑦		⑥		⑤		④	
⑥		⑤		④		③	
⑤		④		③		②	
④		③		②		①	
③		②		①		⑧	
②		①		⑦		⑥	
①		⑧		⑦		⑥	
⑧		⑦		⑥		⑤	
⑦		⑥		⑤		④	
⑥		⑤		④		③	
⑤		④		③		②	
④		③		②		①	
③		②		①		⑧	
②		①		⑦		⑥	
①		⑧		⑦		⑥	
⑧		⑦		⑥		⑤	
⑦		⑥		⑤		④	
⑥		⑤		④		③	
⑤		④		③		②	
④		③		②		①	
③		②		①		⑧	
②		①		⑦		⑥	
①		⑧		⑦		⑥	
⑧		⑦		⑥		⑤	
⑦		⑥		⑤		④	
⑥		⑤		④		③	
⑤		④		③		②	
④		③		②		①	
③		②					

ACCIDENT SUMMARY SHEET

Case # _____

Municipality TOWN OF COLONIE

County

ALBANY

Location 87E EX. 4 ROUTE 155

PIN
~~HSI #~~

1721.51

Time Period 11/1/07 - 2/28/10

No. of Months 38

Accident Type No. of Accidents

Rear End	<u>39</u>
Right Angle	<u> </u>
Overtaking	<u>3</u>
Left Turn	<u> </u>
Sideswipe/ Head-on	<u> </u>
Right Turn	<u> </u>
Parked Vehicle	<u>1</u>
Debris	<u> </u>
Pedestrian	<u> </u>
Bicycle	<u> </u>
Animal	<u> </u>
Backing	<u> </u>
Fixed Object	<u>7</u>
w/ Utility Poles	<u> </u>
w/ Guide Rail / Barrier	<u>5</u>
w/ Sign Post	<u>1</u>
w/ Trees	<u> </u>
W/ Ditch / Embankment	<u>1</u>
w/	<u> </u>

TOTAL 50

Pavement Condition No. of Accidents

Dry	<u>33</u>
Wet	<u>13</u>
Snow / Ice / Slush	<u>3</u>
Unknown	<u>1</u>

TOTAL 50

Weather No. of Accidents

Clear	<u>21</u>
Cloudy	<u>19</u>
Rain	<u>5</u>
Snow	<u>3</u>
Sleet	<u> </u>
Fog	<u>1</u>
Unknown	<u>1</u>

TOTAL 50

Light Conditions No. of Accidents

Day	<u>40</u>
Night	<u>9</u>
Unknown	<u>1</u>

TOTAL 50

Accident Severity No. of Accidents


Property Damage	<u>33</u>
Injury	<u>17</u>
Fatal	<u> </u>

TOTAL 50

NYS DEPARTMENT OF TRANSPORTATION
OFFICE OF TRAFFIC SAFETY & MOBILITY / OFFICE OF MODAL SAFETY & SECURITY
COLLISION DIAGRAM # 1

1 OF 2

Municipality <u>TOWN OF COLONIE</u>	County <u>ALBANY</u>	HSI # _____	Case # _____
Intersection: <u>87I @ EXIT 4 RAMP</u>		File _____	
Period <u>3</u> Years <u>2</u> Months	From <u>1/1/07</u>	To <u>2/28/10</u>	By <u>JJC</u> Date <u>2/23/11</u>




NYS DEPARTMENT OF TRANSPORTATION
OFFICE OF TRAFFIC SAFETY & MOBILITY / OFFICE OF MODAL SAFETY & SECURITY
COLLISION DIAGRAM # 2

2 of 2

Municipality TOWN OF COLONIE County ALBANY
Intersection 87I & EXIT 4 RAMP
Period 3 Years 2 Months From 1/1/07 To 2/28/10

HSI # _____ Case # _____
File _____
By JJC Date 2/23/11



DETAILS OF ACCIDENT HISTORY FOR LOCATION (AS SHOWN ON COLLISION DIAGRAM)

COUNTY <u>Alameda</u>		P.I.N. _____ OR IDENT. _____		ROUTE NO. OR STREET NAME		CASE NO. _____				
<input checked="" type="checkbox"/> TOWN				871 EXIT 4 RAMP		FILE _____				
<input type="checkbox"/> CITY				AT INTERSECTION WITH/OR BETWEEN		BY <u>JLC</u>				
<input type="checkbox"/> VILLAGE OF <u>Colony</u>				<u>Route 155 / Old Wolf Rd.</u>		DATE <u>2/23/00</u>				
TIME PERIOD NUMBER OF MONTHS	FROM TO	NO. OF VEH.	SEVERITY	ENVIRONMENTAL Use codes from MV 104 (shown at right) for these categories			LIGHT CONDITIONS	ROADWAY CHARACTER 1. Straight and Level 2. Straight at Grade 3. Straight at Hillcrest 4. Curve and Level 5. Curve at Hillcrest	ROADWAY SURFACE CONDITION 1. Dry 2. Wet 3. Muddy 4. Snow/Ice 5. Slush 10. Other	WEATHER 1. Clear 2. Cloudy 3. Rain 4. Snow 5. Sleet/Hail/Freezing Rain 6. Fog/Smog/Smoke 10. Other
				(6) LIGHT	(7) ROADWAY CHARACTER	(8) ROADWAY SURFACE CONDITION				
① NO	② DATE	③ TIME	④	⑤	⑥	⑦	⑧	⑨	⑩ APPARENT CONTRIBUTING FACTORS Use Codes from MV 104 Police Report see back of this form for codes	⑪ DESCRIPTION
17	2/13/07	0817	3	P00	1	1	1	2	9	WB V, R/E WB V ₂ INTO WB V ₃
18	5/14/07	2	2	PI						WB V, R/E WB V ₂
19	11/7/07	0753	2	PI	1	1	1	1	4	WB V, R/E WB V ₂
20	5/16/08	0401	2	PI	5	1	1	2	7, 20	SB V, MISC. IN 40 TO 9TH STRIKES SB V ₂ WHICH IS ON 871
21	8/5/08	0805	2	PI	1	1	1	1	9	SB V, MOTORCYCLE R/E SB V ₂
22	1/2/08	1459	2	P00	1	1	2	2	9, 66	SB V, R/E SB V ₂
23	4/30/08	0754	3	PI	1	1	1	1	9, 19	SB V, R/E SB V ₂
24	4/30/08	0755	2	P00	1	1	1	1	9	SB V, R/E SB V ₂
25	6/25/08	0236	1	PI	4	1	1	2	2, 19	SB V, MOTORCYCLE TRAVELING @ HIGH RATE OF SPEED MISSES TURN GOES INTO MEDIAN OVERTURN
26	9/10/08	0742	2	P00	1	1	1	1	9	SB V, R/E SB V ₂
27	9/26/08	1900	2	P00	5	1	2	3	9	SB V, R/E SB V ₂
28	12/23/08	1350	2	P00	1	1	1	2	9, 19	SB V, R/E SB V ₂
29	2/12/08	2138	1	P00	4	1	4	4	19, 66	SB V, Loses Control on Snow for bumper
30	12/17/08	0357	1	P00	5	1	4	4	19, 66	SB V, Loses Control on Snow HITS Concrete
31	4/30/08	0800	2	P00	1	1	1	1	9, 4	SB V, R/E SB V ₂
32	8/10/08	1644	2	P00	1	1	2	3	66	WB V ₂ R/E WB V ₁

DIAGRAM NO. 122

COUNTY <u>Alameda</u>		P.I.N. OR IDENT.		ROUTE NO. OR STREET NAME		CASE NO.		
TOWN <u>EXIT 4 RAMP</u>						FILE <u>JLC</u>		
CITY <u>Colony</u>				AT INTERSECTION WITH/OR BETWEEN		BY <u>JLC</u>		
VILLAGE OF <u>Colony</u>				<u>Route 151 / 100 West Rd.</u>		DATE <u>2/23/10</u>		
TIME PERIOD NUMBER OF MONTHS	FROM TO	④ NO. OF VEH.	⑤ SEVERITY	ENVIRONMENTAL Use codes from MV 104 (shown at right) for these categories			⑩ APPARENT CONTRIBUTING FACTORS	⑪ DESCRIPTION
				⑥ LIGHT CONDITIONS	⑦ ROADWAY CHARACTER	⑧ ROADWAY SURFACE CONDITION		
3	1/1/07 TO 2/28/10							
33	7/3/09 1710	1	P00	1	5	2	19	SB U, ENTERING 87Z LOSES CONTROL, CROSSES 87Z STRIKES GUIDE RAIL
34	6/21/09 1046	3	PI	1	5	1	9, 20	SB U, V2, U2 ENTERING 87Z SB V3 R/E U2 OVERTURNING IT WHICH R/E V1
35	7/3/09 1417	1	P00	1	2	1	4, 19	SB U, READING MAP STRIKES GUIDE RAIL
36	7/26/09 0221	2	P20	4	1	2	2, 28	SB U, PULSED BY POLICE (U2) U, SWERVES RIGHT INTO U2
37	7/26/09 0221	2	P20	5	1	2	2, 28	SEE ABOVE U, SWERVED LEFT INTO U2
38	1/15/09 0757	2	PI	1	1	1	9	SB U, R/E SB U2
39	1/22/09 0750	2	P00	1	1	1	9	SB U, R/E SB U2
40	1/22/09 0825	3	P00	1	1	1	19, 9	SB U, R/E SB U2 INTO SB U3
41	4/23/09 0847	4	P00	1	1	1	9	SB U, R/E SB U2 INTO SB U3 INTO SB U4
42	5/15/09 0748	3	P00	1	1	1	20	SB U, R/E SB U2 INTO SB U3
43	9/17/09 0809	2	P20	1	1	1	9	SB U, R/E SB U2
44	11/29/09 1040	1	PI	5	4	1	20, 17	SB U, UNSAFELY CHANGES LANES, LOSES CONTROL STRIKES CONSTRUCTION EQUIP
45	12/15/09 1722	2	P20	5	1	1	9	SB U, R/E SB U2
46	1/13/09 0505	1	P00	5	1	1	20	SB U, ATTEMPTS LANE CHANGE LOSES CONTROL STRIKES GUIDE RAIL
47	5/31/09 1650	2	P00	1	1	1	17, 9	SB U, R/E SB U2
48	8/29/09 1925	2	PI	3	1	2	7	SB U, R/E SB U2

DIAGRAM NO. 1

DETAILS OF ACCIDENT HISTORY FOR LOCATION (AS SHOWN IN COLLISION DIAGRAM)

SHEET 4 OF 4

[illegible]

LOCATION	1.	IDENT. NO.: <u>11'0'40'9</u>	STATE OF NEW YORK DEPARTMENT OF TRANSPORTATION TRAFFIC AND SAFETY DIVISION HIGHWAY SAFETY INVESTIGATION REPORT (SEE INSTRUCTIONS ON REVERSE)		MAIN OFFICE USE: DIVISION FILE _____ REVIEWED BY _____ SCHEDULED FOR B&A <input type="checkbox"/>		
	<input checked="" type="checkbox"/> TOWN <input type="checkbox"/> CITY <input type="checkbox"/> VILLAGE } OF <u>Colonie</u>						
	ROUTE NO. OR STREET NAME <u>NY 910B (Wolf Rd)</u>		STATE HIGHWAY NO. <u>69-1</u>	FROM OR AT REFERENCE MARKER <u>910'B 11'0' 11'0'</u>			
	At Intersection With (If Applicable)		ROUTE NO. OR STREET NAME	STATE HIGHWAY NO.	TO REFERENCE MARKER <u>910'B 11'0' 11'0'</u>		
		2. REASON FOR INVESTIGATION <input checked="" type="checkbox"/> (a) IDENTIFIED BY ACCIDENT SURVEILLANCE SYSTEM <input type="checkbox"/> (b) POLICE HAZARD REPORT <input checked="" type="checkbox"/> (c) RESPONSE TO COMPLAINT OR INQUIRY <input checked="" type="checkbox"/> (d) REGIONALLY INITIATED <u>PIN 1721.51</u> <input type="checkbox"/> (e) OTHER (Explain) _____		3. RECOMMENDATION <input type="checkbox"/> (a) CAPITAL IMPROVEMENT (Initiate Proj. Devel. Study) <input type="checkbox"/> (b) TRAFFIC CONTROL IMPROVEMENT <input type="checkbox"/> (c) MAINTENANCE IMPROVEMENT <input type="checkbox"/> (d) OTHER <input checked="" type="checkbox"/> (e) NONE } complete sections 4 &			
4. DISCUSSION (Use reverse if additional space is required — check box if reverse is used <input type="checkbox"/>) (a) PROBLEMS IDENTIFIED <div style="text-align: center; font-size: 1.2em; margin-top: 20px;">See attached Page 2 of 2</div>							
(b) PROPOSED SOLUTION							
(c) ACTION TAKEN							
5. ACCIDENT EXPERIENCE						6. BENEFIT/COST ANALYSIS (see instructions)	
Number of Months	PERIOD BEGINNING		NUMBER OF ACCIDENTS			Check box if Benefit/Cost Calculations are attached <input type="checkbox"/>	
	MONTH	YEAR	Fatal Accidents	Injury Accidents	Property Damage Accidents		
10	01	07	0	5	10	PRINCIPAL INVESTIGATOR <u>Michael E. Dordy</u> TITLE <u>CE-II</u> APPROVED BY <u>[Signature]</u> DATE <u>3-3-11</u>	
24	11	07	0	10	18		
05	11	09	0	5	6		

NY 910B, RM 910B-1101-1010 to 1015
Town of Colonie, Albany County

Problems Identified

NY Route 910B, Wolf Road, was identified as a Priority Investigation Location (PIL) from RM 1010 to 1015 based on reportable accidents during the period 11/1/07 to 10/31/09. NY 910B, which travels north-south, is a four lane divided Urban Principal Arterial highway with free access. The travel way is 54 feet wide, which accommodates four lanes and a paved flush median that provides refuge for turning movements. This area is commercially developed with various businesses and driveways on both sides of the roadway. Pavement markings and signing are satisfactory. The posted speed limit is 40 MPH.

NY 910B is intersected by Computer Drive at RM 1010. The intersection is controlled by a three color traffic signal. NY 910B is intersected by the Wolf Road Shoppers Park drive from the east at RM 1011 in a stop controlled T-intersection. NY 910B is intersected by Cerone Commercial Drive from the west at RM 1012 in a stop controlled T-intersection. NY 910B is intersected by Metro Park Road from the east at RM 1013 in a T-intersection. The intersection is controlled by a three color traffic signal. NY 910B is intersected by Beltrone Drive from the east at RM 1014 in a stop controlled T-intersection.

The accident study period was 39 months, 1/1/07 to 3/31/10. Based on the 54 accidents that occurred during the study period the accident rate is 2.50 ACC/MVM. This rate is less than the expected accident rate of 3.59 ACC/MVM for similar highways statewide. There were 28 accidents during the 2 year HAL period. The majority of the accidents consisted of rear end, overtaking, and turning accidents due to traffic congestion, generally grouped at the driveways and intersections. There was one accident involving a pedestrian and no accidents involving bicyclists. Of the 53 accidents on this section of highway with pavement condition reported, 14 (26%) occurred on wet pavement and no accidents occurred on snow/ice/slush pavements. There were 7 accidents during the morning commute hours from 6 am to 9 am and 16 accidents occurred during the peak evening commute from 3 pm to 6 pm.

Proposed Solution

There is a project, PIN 1721.51 currently scheduled for letting 11/15/12, to address improvements on the Northway at Exit 4. We have no safety recommendations to offer for the project at this time as a result of this review of the accident history.

Action Taken

Memo to R-1 Design dated 2/16/11.

LOCATION	1.	IDENT. NO.:	11'04'9'5			STATE OF NEW YORK DEPARTMENT OF TRANSPORTATION TRAFFIC AND SAFETY DIVISION HIGHWAY SAFETY INVESTIGATION REPORT (SEE INSTRUCTIONS ON REVERSE)			MAIN OFFICE USE: DIVISION FILE _____ REVIEWED BY _____ SCHEDULED FOR B&A <input type="checkbox"/>			
	<input checked="" type="checkbox"/> TOWN <input type="checkbox"/> CITY <input type="checkbox"/> VILLAGE		}			OF <u>Colonie</u>						
	ROUTE NO. OR STREET NAME					STATE HIGHWAY NO.		FROM OR AT REFERENCE MARKER				
	ACR 151 / Albany Shaker Rd							1'55' 1'1'0' 3'0'4				
		At Intersection With (If Applicable)	ROUTE NO. OR STREET NAME			STATE HIGHWAY NO.		TO REFERENCE MARKER				
			ACR 153 / Old Wolf Rd									
2. REASON FOR INVESTIGATION											3. RECOMMENDATION	
<input checked="" type="checkbox"/> (a) IDENTIFIED BY ACCIDENT SURVEILLANCE SYSTEM <input type="checkbox"/> (b) POLICE HAZARD REPORT <input checked="" type="checkbox"/> (c) RESPONSE TO COMPLAINT OR INQUIRY <u>PIN 172151</u> <input checked="" type="checkbox"/> (d) REGIONALLY INITIATED <u>ARWP</u> <input checked="" type="checkbox"/> (e) OTHER (Explain) _____											<input type="checkbox"/> (a) CAPITAL IMPROVEMENT (Initiate Proj. Devel. Study) <input type="checkbox"/> (b) TRAFFIC CONTROL IMPROVEMENT <input checked="" type="checkbox"/> (c) MAINTENANCE IMPROVEMENT <input type="checkbox"/> (d) OTHER <u>Refresh Striping</u> <input type="checkbox"/> (e) NONE	
2008 PIL; Red Index = 18.11; Ser Rank = 15.09											complete sections 4 &	
4. DISCUSSION (Use reverse if additional space is required — check box if reverse is used <input type="checkbox"/>)												
(a) PROBLEMS IDENTIFIED												
(b) PROPOSED SOLUTION												
(c) ACTION TAKEN												
5. ACCIDENT EXPERIENCE						6. BENEFIT/COST ANALYSIS (see instructions)						
Number of Months	PERIOD BEGINNING		NUMBER OF ACCIDENTS			Check box if Benefit/Cost Calculations are attached <input type="checkbox"/>						
	MONTH	YEAR	Fatal Accidents	Injury Accidents	Property Damage Accidents							
1'2	0'1	0'7	0	7	6	PRINCIPAL INVESTIGATOR <u>[Signature]</u> TITLE _____ APPROVED BY <u>[Signature]</u> DATE <u>3-3-11</u>						
1'2	0'1	0'8	0	0	4							
1'2	0'1	0'9	0	1	3							

HSI # 1-0495
NY 155, RM 155-1101-3047
Town of Colonie, Albany County

Page 2 of 2

Problems Identified

NY Route 155 identified as a Priority Investigation at TH RM 3047 based on reportable accidents during the period 1/1/07 to 12/31/08.

This section of NY Touring Route 155 is the intersection of Albany County Route 151, Albany Shaker Road, traveling east-west with Albany County Route 153, Old Wolf Road, carrying Touring Route 155 north from the intersection, and the southbound on ramp to I87, the Northway, south from the intersection. The intersection is controlled with a 3 color traffic signal.

During the 36 month accident study period from 1/1/07 to 12/31/09 there were 21 total accidents. Of the 18 accidents with highway surface condition reported there were 5 (28%) wet pavement accidents and 2 (11%) snow/ice pavement accidents. There were 11 rear end accidents at the signal, including 7 SB. There is no apparent treatable pattern of accidents.

Proposed Solution

The dotted "skip marks" that separate the 2 SB left turn lanes were observed to be faded during the field review. These pavement markings were refreshed in October 2010.


Actions Taken

Letter to complainant, dated 12/22/10.

DEPARTMENT OF TRANSPORTATION
TRAFFIC ENGINEERING AND SAFETY DIVISION
COLLISION DIAGRAM #2

Sheet 1 of 1

Municipality Town of Colonie County Albany File DMV/ALIS/SIMS
Intersection NY 910B; RM 910B - 1101-1010 TO 1015
Period 3 Years 3 Months From 1/1/07 To 3/31/10 By MED Date 2/14/11



SYMBOLS

- | | |
|-------------------|-------------------|
| ← Moving Vehicle | ← - - Pedestrian |
| ← M - Motorcycle | ← B - Bicycle |
| ↔ Backing Vehicle | □ Fixed Object |
| ← Stopped Vehicle | ○ Personal Injury |
| ▢ Parked Vehicle | ● Fatal Injury |

MANNER OF COLLISION

- | | |
|------------------|---------------|
| ← - - Rear-end | → - - Head-on |
| ↔ Side-swipe | ↘ Left-turn |
| ⚡ Out of control | ↓ Right-angle |
| ↖ Skidding | |
| ↺ Overturned | |

Not all features shown
Not to scale

DETAILS OF ACCIDENT HISTORY FOR LOCATION (AS SHOWN ON COLLISION DIAGRAM)

DIAGRAM NO. 2SHEET 2 OF 5

COUNTY <u>Albany</u>		ROUTE NO. OR STREET NAME <u>NY 910 B / Wolf Rd</u>		CASE NO. FILE <u>DMV/H113/51115</u>							
TOWN <u>Colonie</u>		AT INTERSECTION WITH/OR BETWEEN <u>RM 910 B - 1101-1010 TO 1015</u>		BY <u>MD</u>							
CITY				DATE <u>11/10/11</u>							
VILLAGE OF											
TIME PERIOD NUMBER OF MONTHS	FROM DATE	TO DATE	NO. OF VEH.	SEVERITY	ENVIRONMENTAL Use codes from MV 104 (shown at right) for these categories	LIGHT CONDITIONS	ROADWAY CHARACTER	ROADWAY SURFACE	WEATHER	APPARENT CONTRIBUTING FACTORS	DESCRIPTION
319	3/31/10										
1	1/2/07	2:30P	2	P00						7,17	1010 RIGHT ANGLE, EB V-2 MADE RIGHT ON RED, STRUCK SB V-1
2	2/18/07	12:31P	2	PE-1						4,17	1010 RIGHT ANGLE, SB V-1 RAN RED, STRUCK EB V-2
3	5/8/07	1:30P	2	PE-1						9,4	1010 OVERTAKE-SB, V-1 CHANGED LANES
4	5/19/07	5:43P	2	P00						4	1010 REAR END-NB, OP V-2 FOOT SLIPPED FROM BRAKE
5	6/15/07	12:32P	2	PE-3						4	1010 REAR END-NB, V-2 STARTING TO GO ON GREEN
6	6/25/07	3:58P	1	PE-1						14	1010 NB V-1 MAKING LEFT INTO DRIVE, PED STEPPED BACK INTO PATH OF V-1
7	9/21/07	8:02A	2	P00						4	1010 REAR END-NB, V-1 SLOWING TO MAKE TURN
8	10/26/07	10:03P	2	P00						3,9	1010 OVERTAKE-NB, V-1 CHANGED LANES
9	11/18/07	11:26A	2	P00						6,8	1010 RIGHT ANGLE, EB V-1 STRUCK BY SB V-2, SIGNAL NOT WORKING
10	1/12/07	3:27P	2	P00						7	1011 RIGHT ANGLE, V-1 ENTERED TRAFFIC WB, STRUCK NB V-2
11	5/29/07	9:40A	2	PE-1						7	1012 RIGHT ANGLE, V-1 ENTERED TRAFFIC WB, STRUCK BY NB V-2
12	6/7/07	4:45P	2	P00						7,13	1012 RIGHT ANGLE, V-1 WAVED INTO TRAFFIC WB, STRUCK BY NB V-2
13	1/12/07	8:41P	2	P00						9	1013 REAR END-SB, V-2 SLOWING IN TRAFFIC
14	1/13/07		2	P00							1013 REAR END-NB, V-2 SLOWING IN TRAFFIC
15	7/23/07	3:47P	2	P00						9,6,26	1013 REAR END-SB, V-2 BEALED ABRUPTLY BEHIND UNINVOLVED VEH

DETAILS OF ACCIDENT HISTORY FOR LOCATION (AS SHOWN ON COLLISION DIAGRAM)

SHEET 3 OF 5DIAGRAM NO. 2

COUNTY <u>Albany</u>		TOWN <u>Colonie</u>		ROUTE NO. OR STREET NAME <u>NY 910 3/WOLF RD</u>		CASE NO. FILE <u>DMV/A615/SIMS</u>				
CITY <input type="checkbox"/>		VILLAGE OF <u>Colonie</u>		AT INTERSECTION WITH/OR BETWEEN <u>RM 910 B-1101-1010 TO 1015</u>		BY <u>MED</u>				
DATE <u>1/14/11</u>		DATE <u>1/14/11</u>		DATE <u>1/14/11</u>		DATE <u>1/14/11</u>				
TIME PERIOD NUMBER OF MONTHS	FROM <u>11/1/07</u>	TO <u>3/31/10</u>	④ NO. OF VEH.	⑤ SEVERITY	⑥ LIGHT CONDITIONS (shown at right) for these categories	⑦ ROADWAY CHARACTER	⑧ ROADWAY SURFACE	⑨ WEATHER	⑩ APPARENT CONTRIBUTING FACTORS	⑪ DESCRIPTION
17	12/22/07	4:04P	2	P00	4	1	1	2	7	1014 RIGHT ANGLE, V-1 ENTERED TRAFFIC WB, STRUCK BY SBV2
18	5/30/07	5:04P	2	P00	1	1	1	1	7/13	1015 RIGHT ANGLE, V-1 ENTERED TRAFFIC WB, STRUCK BY NB V2
19	5/3/08	8:00A	3	PT-2	1	1	2	3	7	1010 NB V1 ATTEMPTED LEFT TURN, STRUCK BY SB V-2
20	5/28/08	5:40P	3	P00	1	1	1	1	4	1010 REAR END- NB, V-2 + V-3 STOPPED IN TRAFFIC AT SIGNAL
21	7/7/08	12:15P	2	P00	1	1	2	2	1010	1010 REAR END- SB, V-1 STOPPED AT RED TRAFFIC SIGNAL
22	10/6/08	8:33A	2	P00	1	1	2	3	4	1010 REAR END- NB, V-2 STOPPED IN TRAFFIC AT SIGNAL
23	1/17/08	6:44P	2	P00	4	1	1	1	4	1011 OVERTAKE- SB, V-1 CHANGED LANES
24	2/29/08	1:15P	2	P00	1	1	1	2	17.7	1011 RIGHT ANGLE, V-1 ENTERED TRAFFIC WB, STRUCK BY NB V-2
25	7/14/08	3:49P	2	PT-1	1	1	1	1	7	1011 RIGHT ANGLE, V-1 ENTERED TRAFFIC WB, STRUCK BY NB V-2
26	1/15/08	3:19P	2	P00	1	1	2	4	7	1012 REAR END- EB, V-2 SLOWING IN TRAFFIC
27	6/28/08	5:19P	3	P00	1	1	1	1	20.9	1012 OVERTAKE- SB, V-1 CHANGED LANES
28	5/9/08	7:22P	2	P00	1	1	1	1	4	1013 OVERTAKE- NB, V-1 CHANGED LANES
29	9/2/08	5:14P	2	P00	1	1	1	1	4	1013 REAR END- NB, V-1 STOPPED AT RED TRAFFIC SIGNAL
30	11/13/08	8:59A	3	PT-1	1	1	2	2	7	1013 RIGHT ANGLE, V-1 ENTERED TRAFFIC EB, STRUCK BY SB V-2
31	11/14/08	9:18A	2	PT-1	1	1	2	2	7	1013 SB V-2 MAKING LEFT TURN, NB V-1 PASSED RED SIGNAL

DETAILS OF ACCIDENT HISTORY FOR LOCATION (AS SHOWN ON COLLISION DIAGRAM)

DIAGRAM NO. 2SHEET 4 OF 5

COUNTY <u>Albany</u>		P-I-N- OR IDENT. <u>110909</u>		ROUTE NO. OR STREET NAME <u>NY 910B / Wolf Rd</u>		CASE NO. FILE <u>DMV / AUS / SIMS</u>				
TOWN <u>Colome</u>				AT INTERSECTION WITH/OR BETWEEN <u>RM 910B - 1101-1010 TO 1015</u>		BY <u>MD</u>				
CITY						DATE <u>2/4/11</u>				
VILLAGE OF										
TIME PERIOD NUMBER OF MONTHS	FROM 1/1/07	TO 3/31/10	④ NO. OF VEH.	⑤ SEVERITY	⑥ LIGHT CONDITIONS (shown at right) for these categories	⑦ ROADWAY CHARACTER	⑧ ROADWAY SURFACE CONDITION	⑨ WEATHER	⑩ APPARENT CONTRIBUTING FACTORS	⑪ DESCRIPTION
33	10/17/08	9:21A	2	P00	1	1	1	1	1820	1015 OVERTAKE-NB, V-1 CHANGED LANES
34	11/3/09	7:43A	2	P00	1	1	1	1	4	1010 REAR END-SB, BOTH VEHICLES STARTING IN TRAFFIC AT SIGNAL
35	11/12/09	11:21A	2	P00	1	1	1	1	9	1010 REAR END-NB, V-2 SLOWING IN TRAFFIC
36	11/12/09	11:28A	2	PI-1	1	1	1	2	9	1010 REAR END-NB, V-2 SLOWING IN TRAFFIC FOR #35 ABOVE
37	12/10/09	12:1P	2	P00	1	1	1	2	726	1010 RIGHT ANGLE, V-1 ENTERED TRAFFIC NB, STRUCK BY NB V-2
38	9/18/09	1:02P	3	P00	1	1	1	2	9	1011 REAR END-SB, V-2 AND V-3 STOPPED IN TRAFFIC
39	9/18/09	1:04P	2	PI-1	1	1	1	1	7	1011 RIGHT ANGLE, V-1 ENTERED TRAFFIC WB, STRUCK BY NB V-2
40	10/19/09	12:30P	2	P00	1	1	1	1	7	1011 RIGHT ANGLE, WB V-2 MADE RIGHT IFO, NB V-1
41	12/11/09	1:30P	2	P00	1	1	1	1	26	1012 REAR END-SB, V-1 STOPPED IN TRAFFIC
42	1/19/09	2:45P	2	P00	1	1	2	2	47	1013 RIGHT ANGLE, V-1 ENTERED TRAFFIC WB, STRUCK BY NB V-2
43	7/1/09	7:12P	2	PI-2	1	1	2	3	7	1013 RIGHT ANGLE, V-1 ENTERED TRAFFIC EB, STRUCK BY SB V-2
44	7/24/09	12:55P	2	P00	1	1	1	2	227	1013 HEAD ON - V-2 STOPPED AT SIGNAL SB, NB V-1 VEERED OVER C
45	11/27/09	10:20P	2	P00	4	1	1	2	7	1013 OVERTAKE-SB, V-1 ATTEMPTED LEFT TURN FROM RIGHT LANE
46	12/2/09	8:47A	2	PI-2	1	1	1	1	177	1013 RIGHT ANGLE, V-1 ENTERED TRAFFIC EB, STRUCK SB V-2
47	2/27/09	5:58P	3	PI-1	1	1	2	3	4	1014 REAR END-SB, V-2 SLOWING AT SIGNAL, V-2 STRUCK NB V-3

COUNTY <u>Albany</u>		ROUTE NO. OR STREET NAME <u>NY 910B / Wolf Rd</u>		CASE NO. <u>DMV 1215/51MS</u>	
<input checked="" type="checkbox"/> TOWN		AT INTERSECTION WITH/OR BETWEEN <u>RM 910B - 1101-1010 TO 1015</u>		FILE BY <u>MEP</u>	
<input type="checkbox"/> CITY				DATE <u>2/9/11</u>	
<input type="checkbox"/> VILLAGE OF <u>Colonie</u>					
TIME PERIOD NUMBER OF MONTHS <u>319</u>		FROM <u>1/1/07</u> TO <u>3/31/10</u>		WEATHER 1. Clear 2. Cloudy 3. Rain 4. Snow 5. Sleet/Hail/Freezing Rain 6. Fog/Smog/Smoke 10. Other	
① NO		② DATE		③ TIME	
④ NO. OF VEH.		⑤ SEVERITY		⑥ LIGHT CONDITIONS Use codes from MV 104 (shown at right) for these categories	
⑦ ROADWAY CHARACTER		⑧ ROADWAY SURFACE		⑨ WEATHER	
⑩ APPARENT CONTRIBUTING FACTORS (M)		⑪ DESCRIPTION		⑫ ROADWAY CHARACTER 1. Straight and Level 2. Straight and Grade 3. Straight at Hillcrest 4. Curve and Level 5. Curve and Grade 6. Curve at Hillcrest	
⑬ ROADWAY SURFACE 1. Dry 2. Wet 3. Muddy 4. Snow/Ice 5. Slush 10. Other		⑭ LIGHT CONDITIONS 1. Daylight 2. Dawn 3. Dusk 4. Dark Road Lighted 5. Dark Road Unlighted		⑮ CASE NO. <u>DMV 1215/51MS</u>	
⑯ CASE NO. <u>DMV 1215/51MS</u>		⑰ FILE BY <u>MEP</u>		⑱ DATE <u>2/9/11</u>	
⑳ CASE NO. <u>DMV 1215/51MS</u>		㉑ FILE BY <u>MEP</u>		㉒ DATE <u>2/9/11</u>	
㉓ CASE NO. <u>DMV 1215/51MS</u>		㉔ FILE BY <u>MEP</u>		㉕ DATE <u>2/9/11</u>	
㉖ CASE NO. <u>DMV 1215/51MS</u>		㉗ FILE BY <u>MEP</u>		㉘ DATE <u>2/9/11</u>	
㉙ CASE NO. <u>DMV 1215/51MS</u>		㉚ FILE BY <u>MEP</u>		㉛ DATE <u>2/9/11</u>	
㉜ CASE NO. <u>DMV 1215/51MS</u>		㉝ FILE BY <u>MEP</u>		㉞ DATE <u>2/9/11</u>	
㉟ CASE NO. <u>DMV 1215/51MS</u>		㊱ FILE BY <u>MEP</u>		㊲ DATE <u>2/9/11</u>	
㊳ CASE NO. <u>DMV 1215/51MS</u>		㊴ FILE BY <u>MEP</u>		㊵ DATE <u>2/9/11</u>	
㊶ CASE NO. <u>DMV 1215/51MS</u>		㊷ FILE BY <u>MEP</u>		㊸ DATE <u>2/9/11</u>	
㊹ CASE NO. <u>DMV 1215/51MS</u>		㊺ FILE BY <u>MEP</u>		㊻ DATE <u>2/9/11</u>	
㊼ CASE NO. <u>DMV 1215/51MS</u>		㊽ FILE BY <u>MEP</u>		㊾ DATE <u>2/9/11</u>	
㊿ CASE NO. <u>DMV 1215/51MS</u>		1 FILE BY <u>MEP</u>		2 DATE <u>2/9/11</u>	
3 CASE NO. <u>DMV 1215/51MS</u>		4 FILE BY <u>MEP</u>		5 DATE <u>2/9/11</u>	
6 CASE NO. <u>DMV 1215/51MS</u>		7 FILE BY <u>MEP</u>		8 DATE <u>2/9/11</u>	
9 CASE NO. <u>DMV 1215/51MS</u>		10 FILE BY <u>MEP</u>		11 DATE <u>2/9/11</u>	
12 CASE NO. <u>DMV 1215/51MS</u>		13 FILE BY <u>MEP</u>		14 DATE <u>2/9/11</u>	
15 CASE NO. <u>DMV 1215/51MS</u>		16 FILE BY <u>MEP</u>		17 DATE <u>2/9/11</u>	
18 CASE NO. <u>DMV 1215/51MS</u>		19 FILE BY <u>MEP</u>		20 DATE <u>2/9/11</u>	
21 CASE NO. <u>DMV 1215/51MS</u>		22 FILE BY <u>MEP</u>		23 DATE <u>2/9/11</u>	
24 CASE NO. <u>DMV 1215/51MS</u>		25 FILE BY <u>MEP</u>		26 DATE <u>2/9/11</u>	
27 CASE NO. <u>DMV 1215/51MS</u>		28 FILE BY <u>MEP</u>		29 DATE <u>2/9/11</u>	
30 CASE NO. <u>DMV 1215/51MS</u>		31 FILE BY <u>MEP</u>		32 DATE <u>2/9/11</u>	
33 CASE NO. <u>DMV 1215/51MS</u>		34 FILE BY <u>MEP</u>		35 DATE <u>2/9/11</u>	
36 CASE NO. <u>DMV 1215/51MS</u>		37 FILE BY <u>MEP</u>		38 DATE <u>2/9/11</u>	
39 CASE NO. <u>DMV 1215/51MS</u>		38 FILE BY <u>MEP</u>		39 DATE <u>2/9/11</u>	
40 CASE NO. <u>DMV 1215/51MS</u>		39 FILE BY <u>MEP</u>		40 DATE <u>2/9/11</u>	
41 CASE NO. <u>DMV 1215/51MS</u>		40 FILE BY <u>MEP</u>		41 DATE <u>2/9/11</u>	
42 CASE NO. <u>DMV 1215/51MS</u>		41 FILE BY <u>MEP</u>		42 DATE <u>2/9/11</u>	
43 CASE NO. <u>DMV 1215/51MS</u>		42 FILE BY <u>MEP</u>		43 DATE <u>2/9/11</u>	
44 CASE NO. <u>DMV 1215/51MS</u>		43 FILE BY <u>MEP</u>		44 DATE <u>2/9/11</u>	
45 CASE NO. <u>DMV 1215/51MS</u>		44 FILE BY <u>MEP</u>		45 DATE <u>2/9/11</u>	
46 CASE NO. <u>DMV 1215/51MS</u>		45 FILE BY <u>MEP</u>		46 DATE <u>2/9/11</u>	
47 CASE NO. <u>DMV 1215/51MS</u>		46 FILE BY <u>MEP</u>		47 DATE <u>2/9/11</u>	
48 CASE NO. <u>DMV 1215/51MS</u>		47 FILE BY <u>MEP</u>		48 DATE <u>2/9/11</u>	
49 CASE NO. <u>DMV 1215/51MS</u>		48 FILE BY <u>MEP</u>		49 DATE <u>2/9/11</u>	
50 CASE NO. <u>DMV 1215/51MS</u>		49 FILE BY <u>MEP</u>		50 DATE <u>2/9/11</u>	
51 CASE NO. <u>DMV 1215/51MS</u>		50 FILE BY <u>MEP</u>		51 DATE <u>2/9/11</u>	
52 CASE NO. <u>DMV 1215/51MS</u>		51 FILE BY <u>MEP</u>		52 DATE <u>2/9/11</u>	
53 CASE NO. <u>DMV 1215/51MS</u>		52 FILE BY <u>MEP</u>		53 DATE <u>2/9/11</u>	
54 CASE NO. <u>DMV 1215/51MS</u>		53 FILE BY <u>MEP</u>		54 DATE <u>2/9/11</u>	
55 CASE NO. <u>DMV 1215/51MS</u>		54 FILE BY <u>MEP</u>		55 DATE <u>2/9/11</u>	
56 CASE NO. <u>DMV 1215/51MS</u>		55 FILE BY <u>MEP</u>		56 DATE <u>2/9/11</u>	
57 CASE NO. <u>DMV 1215/51MS</u>		56 FILE BY <u>MEP</u>		57 DATE <u>2/9/11</u>	
58 CASE NO. <u>DMV 1215/51MS</u>		57 FILE BY <u>MEP</u>		58 DATE <u>2/9/11</u>	
59 CASE NO. <u>DMV 1215/51MS</u>		58 FILE BY <u>MEP</u>		59 DATE <u>2/9/11</u>	
60					



MEMORANDUM
DEPARTMENT OF TRANSPORTATION

TO: A. Trichilo, R-1 Design, 3rd floor

FROM: M.J. Kennedy, R-1 Traffic Engineer, 4th floor *M.J. Kennedy*

SUBJECT: PIN 1721.51: I87 Exits 3/4
Updated Accident Data
Town of Colonie, Albany County

DATE: May 11, 2010

Attached please find the updated Verbal Description Reports for the subject project as you requested on 3/23/10. The accident data covers the 3 year period from 1/1/07 to 12/31/09.

The Northway, I87, is a six lane divided Urban Principal Arterial Interstate highway with full control of access. There were no High Accident Locations (HALs) on the section of highway from RM 2018 to 2042 based on accident data between 11/1/07 and 10/31/09. There were 262 total accidents on this segment of I87 during the study period. The accident rate was 0.90 ACC/MVM which is less than the expected accident rate of 1.10 ACC/MVM for similar highways statewide. There were no accidents involving pedestrians or bicyclists.

NY 910B, Wolf Road, is a four lane divided Urban Principal Arterial highway with free access. Wolf Road is a Priority Investigation Location (PIL) from RM 1010 to 1015 and from RM 1016 to 1019 based on accident data between 11/1/07 and 10/31/09. There were 166 total accidents on this segment of Wolf Road during the study period. The accident rate was 4.60 ACC/MVM which is greater than the expected accident rate of 3.59 ACC/MVM for similar highways statewide. There was one accident involving a pedestrian and no accidents involving bicyclists. These locations have been added to the program for Highway Safety Investigations. HSI reports will be forwarded when completed.

NY 155, Watervliet Shaker Road, is a two lane divided Urban Minor Arterial highway with free access. Watervliet Shaker Road is a Safety Deficient Location (SDL) from RM 3058 to 3061 based on accident data between 11/1/07 and 10/31/09. There were 35 total accidents on this segment of Watervliet Shaker Road during the study period. The accident rate was 7.99 ACC/MVM which is greater than the expected accident rate of 3.94 ACC/MVM for similar highways statewide. There was one accident involving a pedestrian and no accidents involving bicyclists. This location has been added to the program for a Highway Safety Investigation. A HSI report

A. Trichilo, R-1 Design

PIN 1721.51

P. 2 of 2

will be forwarded when completed.

Accident data is attached for Albany County Route 151, Albany Shaker Road, from Wolf Road to Dalessandro Boulevard. There were 118 accidents on this segment of Albany Shaker Road during the study period. A signal study at the intersection of CR 151 with Old Wolf Road (CR 153) and the Exit 4 SB on ramp is underway. A HSI report will be forwarded when completed.

Accident data is attached for Albany County Route 153, Old Wolf Road, from Albany Shaker Road to the Exit 4 SB off ramp. There were 43 accidents on this segment of Old Wolf Road during the study period.

Accident data is attached for the I87 SB Exit 5/Exit 4 Merge Diverge Area service road. There were 19 accidents on the various ramp segments during the study period.

Please be advised that accident data at intersections and ramps will appear on both roadways in the summaries. We have no safety recommendations to make as a result of our initial review of this accident history. If you have any questions concerning the data provided, please contact Mike Doody of this office at 388-0372.

MJK:MED

Attachments

cc: J. Rutnik, Traffic 4th floor

ATTACHMENT G
PEDESTRIAN GENERATOR CHECKLIST

<p align="center">PIN: 1721.51 DESCRIPTION: Exit 3/4 Access Improvements MUNICIPALITY/COUNTY: Town of Colonie / Albany County PEDESTRIAN GENERATOR CHECKLIST DATE: 07/30/12 PREPARED BY: LMW REVIEWED BY:</p>		
<p><i>Note: The term "generator" in this document refers to both pedestrian generators (where pedestrians originate) and destinations (where pedestrians travel to). A check of yes indicates a potential need to accommodate pedestrians and coordination with the Regional Bicycle and Pedestrian Coordinator is necessary during project scoping. Answers to the following questions should be checked with the local municipality to ensure accuracy.</i></p>		
1.	<p>Is there an existing or planned sidewalk, trail, or pedestrian crossing facility? Comments: Wolf Rd is part of CDTC's Proposed Priority Bicycle/Pedestrian Network and improving system connecting between the existing pedestrian/bicycle facilities on Wolf Rd and those constructed as part of the Albany-Shaker/Watervliet-Shaker Rd project is a secondary objecting of the proposed project.</p>	YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>
2.	<p>Are there bus stops, transit stations or depots/terminals located in or within 800m of the project area? Comments: CDTA currently provides service along I-87, Albany-Shaker Rd and Wolf Rd within the project study area.</p>	YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>
3.	<p>Is there more than occasional pedestrian activity? Evidence of pedestrian activity may include a worn path. Comments: Moderate to high pedestrian activity was observed along the existing sidewalks within the project corridor. In addition, there is evidence of pedestrian activity on Albany-Shaker Rd west of Wolf Rd.</p>	YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>
4.	<p>Are there existing or approved plans for generators of pedestrian activity in or within 800m of the project that promote or have the potential to promote pedestrian traffic in the project area, such as schools, parks, playgrounds, places of employment, places of worship, post offices, municipal buildings, restaurants, shopping centers or other commercial areas, or shared-use paths? Comments: There are several generators of pedestrian activity within and around the proposed project area. Retail establishments, hotels, the Albany International Airport, office space, Ann Lee Pond Nature and Historic Preserve and the Crossings at Colonie are all located in or adjacent to the project study area and have potential to promote pedestrian activity.</p>	YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>
5.	<p>Are there existing or approved plans for seasonal generators of pedestrian activity in or within 800m of the project that promote or have the potential to promote pedestrian traffic in the project area, such as ski resorts, state parks, camps, amusement parks? Comments: Ann Lee Pond Nature and Historic Preserve, the Crossings at Colonie, and the Shaker Historic site are all located adjacent to the project study area and have potential to promote seasonal pedestrian activity.</p>	YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>
6.	<p>Is the project located in a residential area within 800m of existing or planned pedestrian generators such as those listed in #4? Comments: Residential areas are located along Wolf Rd, Sand Creek Rd, Albany-Shaker Rd, and Watervliet-Shaker Rd. Although there are not many residential areas located within the project study area, several are located adjacent to the project study area within 2,500 ft of the pedestrian generators listed above.</p>	YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>
7.	<p>From record plans, were pedestrian facilities removed during a previous highway reconstruction project? Comments: Pedestrian Facilities have not been removed during previous highway reconstruction projects.</p>	YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>
8.	<p>Did a study of secondary impacts indicate that the project promotes or is likely to promote commercial and/or residential development within the intended life cycle of the project? Comments: The project is not likely to promote commercial and/or residential development within the intended life cycle of the project.</p>	YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>
9.	<p>Does the community's comprehensive plan call for development of pedestrian facilities in the area? Comments: Wolf Road is part of CDTC's Proposed Priority Bicycle / Pedestrian Network and improving system connectivity between the existing pedestrian/bicycle facilities on Wolf Rd and the facilities constructed as part of the Albany-Shaker/Watervliet-Shaker Rd project is a secondary objective of the proposed project.</p>	YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>
10.	<p>Based on the ability of students to walk and bicycle to school, would the project benefit from engineering measures under the Safe-Routes-To-School-Program? Eligible infrastructure-related improvements must be within a 3.2km radius of the project. Comments: Several schools within the North and South Colonie Central School Districts are located within 2 miles of the project study area, the immediate project area would not benefit from engineering measures under the Safe-Routes-To-School Program.</p>	YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>
<p>ADDITIONAL COMMENTS: <i>Include comment on exceptional circumstances from EI 04-011 if pedestrian accommodations are warranted but not provided.</i></p>		

Note: <i>This checklist should be revisited due to a project delay or if site conditions or local planning changes during the project development process.</i>